

INTERNATIONAL LIBRARY OF TECHNOLOGY

A SERIES OF TEXTBOOKS FOR PERSONS ENGAGED IN THE ENGINEERING PROFESSIONS AND TRADES OR FOR THOSE WHO DESIRE INFORMATION CONCERNING THEM. FULLY ILLUSTRATED AND CONTAINING NUMEROUS PRACTICAL EXAMPLES AND THEIR SOLUTIONS

ELECTRIC RAILWAY SYSTEMS
ELECTRIC-RAILWAY LINE CONSTRUCTION
TRACK CONSTRUCTION
ELECTRIC-RAILWAY CALCULATIONS
RAILWAY MOTORS
ELECTRIC-CAR EQUIPMENT
SPEED CONTROL
EFFICIENCY TESTS
SWITCHGEAR
ELECTRIC STATIONS
ELECTRIC SUBSTATIONS
OPERATION OF ELECTRICAL MACHINERY

SCRANTON
INTERNATIONAL TEXTBOOK COMPANY
136

Electric Railway Systems: Copyright, 1915, by INTERNATIONAL TEXTBOOK COMPANY.

Electric-Railway Line Construction: Copyright, 1915, by INTERNATIONAL TEXTBOOK COMPANY.

Track Construction: Copyright, 1915, by INTERNATIONAL TEXTBOOK COMPANY.

Electric-Railway Calculations: Copyright, 1915, by INTERNATIONAL TEXTBOOK COMPANY.

Railway Motors: Copyright, 1915, by INTERNATIONAL TEXTBOOK COMPANY.

Electric-Car Equipment: Copyright, 1915, by INTERNATIONAL TEXTBOOK COMPANY.

Speed Control: Copyright, 1915, by INTERNATIONAL TEXTBOOK COMPANY.

Efficiency Tests: Copyright, 1915, by INTERNATIONAL TEXTBOOK COMPANY.

Switchgear: Copyright, 1915, by INTERNATIONAL TEXTBOOK COMPANY.

Electric Stations: Copyright, 1915, by INTERNATIONAL TEXTBOOK COMPANY.

Electric Substations: Copyright, 1915, by INTERNATIONAL TEXTBOOK COMPANY.

Operation of Electrical Machinery, Parts 1 and 2: Copyright, 1915, by INTERNATIONAL TEXTBOOK COMPANY.

Copyright in Great Britain.

All rights reserved.

PRESS OF
INTERNATIONAL TEXTBOOK COMPANY
SCRANTON, PA.

70186

205471
AUG 24 1916
SB
.IN82
136

PREFACE

The volumes of the International Library of Technology are made up of Instruction Papers, or Sections, comprising the various courses of instruction for students of the International Correspondence Schools. The original manuscript for each Instruction Paper is prepared by a person thoroughly qualified, both technically and by experience, to write with authority on his subject. In many cases the writer is regularly employed elsewhere in practical work and writes for us during spare time. The manuscripts are then carefully edited to make them suitable for correspondence work.

The only qualification for enrolment as a student in these Schools is the ability to read English and to write intelligibly the answers to the Examination Questions. Hence, our students are of all grades of education, and our Instruction Papers are, therefore, written in the simplest possible language so as to make them readily understood by all students. If technical expressions are essential to a thorough understanding of the subject, they are clearly explained when first introduced.

The great majority of our students wish to prepare themselves for advancement in their vocations or to qualify for other and more congenial occupations. Their time for study is usually after the day's work is done and is limited to a few hours each day. Therefore, every effort is made to give them practical and accurate information in clear, concise form, and to make this information include all of the essentials but none of the non-essentials. To effect this result derivations of rules and formulas are usually omitted, but thorough and complete instructions are given regarding how, when, and under what conditions any particular rule, formula, or process should be

applied. Whenever possible one or more examples, such as would be likely to arise in actual practice, together with their solutions, are given for illustration.

As the best way to make a statement, explanation, or description clear is to give a picture or a diagram in connection with it, illustrations are very freely used. These illustrations are especially made by our own Illustrating Department in order to adapt them fully to the requirements of the text. Projection drawings, sectional drawings, outline drawings, perspective drawings, partly shaded or full shaded, are employed, according to which will best produce the desired result. Halftone engravings are used only in those cases where the general effect is desired rather than the actual details.

In the table of contents that immediately follows are given the titles of the Sections included in this volume, and under each title is listed the main topics discussed. At the end of the volume will be found a complete index, so that quick reference can be made to any subject treated.

INTERNATIONAL TEXTBOOK COMPANY

CONTENTS

ELECTRIC RAILWAY SYSTEMS	Section	Page
Introduction	17	1
Direct-Current Railway Systems	17	2
Current-Collection Systems	17	2
Energy Distribution Systems for Direct-Current Operation	17	6
Alternating-Current Railway Systems	17	23
Energy Distribution Systems for Alternating-Current Operation	17	23
Energy Calculations	17	27
General Consideration	17	27
Passenger Factor and Length of Track	17	28
Number of Cars	17	29
Size and Weight of Cars	17	30
Tractive-Effort Formulas	17	31
Power Formulas	17	43
Energy Tests	17	47
Location of Power House	17	54
Energy Costs	17	57
ELECTRIC-RAILWAY LINE CONSTRUCTION		
Overhead Systems	18	1
Line Poles	18	1
Feeders	18	6
Trolley Wires	18	13
Line Lightning Arresters	18	30
Catenary Line Construction	18	30
Third-Rail Systems	18	49
Conduit Systems	18	57

	Section	Page
TRACK CONSTRUCTION		
Roadbeds	19	1
Hints on Construction	19	1
Typical Roadbeds	19	3
The Track	19	6
Ties	19	6
Rail and Tie Accessories	19	9
Rails	19	12
Rail Joints	19	18
Rail Bonds	19	26
Special Work	19	32
Maintenance of Track	19	39
ELECTRIC-RAILWAY CALCULATIONS		
Line Calculations	20	1
Conditions Affecting the Size of Feeders	20	1
Feeder Formulas	20	3
Track Resistance	20	5
Feeder Problems	20	11
Importance of Low-Voltage Drop	20	25
Line Tests	20	26
Bond Tests	20	26
Feeder and Track-Return Tests	20	32
General Engineering Features	20	33
Rail Calculations	20	33
Curve Calculations	20	34
Grade Calculations	20	38
Track Tests	20	38
Electrolysis	20	40
RAILWAY MOTORS		
Preliminary Considerations	21	1
Operating Requirements	21	1
Gear Reduction	21	2
Motor Rating	21	4
Direct-Current Motors	21	4
Description of Motor	21	4
Features of Construction	21	7
Alternating-Current Motors	21	12

RAILWAY MOTORS—*Continued*	*Section*	*Page*
Description of Motor	21	12
Features of Operation	21	14
Motor Characteristics	21	17
Motor Installation and Maintenance	21	20
ELECTRIC-CAR EQUIPMENT		
Motor-Circuit and Auxiliary Apparatus	22	1
Trunk Connections	22	1
Lightning Arresters	22	16
Lighting, Heating, and Auxiliary Apparatus	22	19
Electric-Car Lighting	22	19
Electric Car Heating	22	27
Auxiliary Car Devices	22	34
Car House	22	56
Pit Room	22	57
Repair Shop	22	58
SPEED CONTROL		
Methods of Speed Control	23	1
Rheostatic Control	23	2
Series-Parallel Cylinder Control	23	3
Series-Parallel Multiple-Unit Hand Control	23	12
Series-Parallel Multiple-Unit Automatic Control	23	20
Single-Phase Speed Control	23	28
Control for Storage-Battery Car	23	34
Control for Gasoline-Electric Car	23	35
EFFICIENCY TESTS		
Comparison of Methods	52	1
Losses	52	2
Direct-Current Machines	52	4
Resistance Measurements	52	4
Running-Light Test	52	8
Generator Test	52	8
Motor Test	52	17
Loading-Back Test	52	19
Series-Motor Test	52	25

EFFICIENCY TESTS—*Continued*	*Section*	*Page*
Alternating-Current Machines	52	28
Alternator Running-Light Test	52	28
Synchronous-Motor Running-Light Test	52	31
Alternator Test With Auxiliary Motor	52	31
Induction-Motor Test	52	37
Transformer Test	52	40
SWITCHGEAR		
Requirements of Switchgear Construction	53	1
General Classifications	53	3
Direct-Current Switchgear	53	3
Circuit-Opening Devices	53	3
Direct-Current Regulating Devices	53	14
Lightning Arresters for Direct-Current Circuits	53	20
Alternating-Current Switchgear	53	23
Circuit-Opening Devices	53	23
Alternating-Current Regulating Devices	53	35
Lightning Arresters for Alternating-Current Circuits	53	35
The Assembled Switchboard	53	39
Definition and General Requirements	53	39
Pressure Wiring	53	40
Direct-Current Switchboards	53	40
Alternating-Current Switchboards	53	43
ELECTRIC STATIONS		
Number and Capacities of Units	54	1
Conductors and Current Densities	54	3
Direct-Current Generating Stations	54	4
Railway Stations	54	4
Direct-Current Light and Power Stations	54	14
Alternating-Current Stations	54	28
Parallel Operation of Alternators	54	28
Synchronizing Circuits	54	29
Small Alternating-Current Stations	54	38
Medium-Size Alternating-Current Stations	54	45
Large Alternating-Current Stations	54	50

ELECTRIC SUBSTATIONS	Section	Page
Purpose of Substations	55	1
Similarity Between Substations and Generating Stations	55	3
Direct-Current Substations	55	4
Miscellaneous Equipment	55	6
Transformers	55	9
Choice Between Synchronous Converters and Motor-Generators	55	13
Motor-Generator Substations With Induction Motors	55	15
Motor-Generator Substations With Synchronous Motors	55	23
Synchronous-Converter Substations for Railways	55	26
Synchronous-Converter Stations for Light and Power	55	38
Synchronizing Circuits for Rotary Converters	55	50
Automatic Synchronous-Converter Substations	55	52
Alternating-Current Substations	55	54
Frequency-Changer Substations	55	54
Transformer Substations	55	57
OPERATION OF ELECTRICAL MACHINERY		
Safe Operating Temperatures	56	1
Operation of Electric Motors	56	4
Direct-Current Motors	56	4
Alternating-Current Motors	56	10
Operation of Direct-Current Generators	56	16
Preliminary Inspection	56	16
Shunt Generators	56	16
Compound Generators	56	22
Series Generators	56	24
Field Circuits of Direct-Current Generators	56	26
Edison Three-Wire System	56	27
Tirrill Regulators With Direct-Current Generators	56	28

OPERATION OF ELECTRICAL MACHINERY—*Continued*

	Section	Page
Routine Care and Inspection	56	30
Operation of Alternating-Current Generators	56	31
Preliminary Inspection	56	31
Operation of Single Alternator	56	32
Series Operation	56	33
Parallel Operation	56	33
Tirrill Regulators With Alternators	56	39
Operating Troubles of Alternators	56	43
Operation of Motor-Generators and Synchronous Converters	57	1
Motor-Generators for Current Conversion	57	1
Induction-Motor-Driven Frequency Changers	57	4
Synchronous - Motor - Driven Frequency Changers	57	4
Synchronous Converters	57	18
Miscellaneous Equipment	57	29
Storage Batteries	57	29
Series Booster Generators	57	35
Transformers	57	36
Potential Regulators on Distributing Circuits	57	36
Care and Maintenance of Electrical Machinery	57	37
General Instructions	57	37
Troubles of Direct-Current Machines	57	41
Troubles of Alternating-Current Machines	57	52
Dangers of Physical Injury	57	54
Tests for Faults in Electrical Circuits	57	57
Classification	57	57
Qualitative Tests	57	57
Quantitative Tests	57	64

ELECTRIC RAILWAY SYSTEMS

INTRODUCTION

1. A number of railway systems have been developed in which electric motors installed on the cars are utilized to drive the cars and trains. Electric energy for the operation of these motors is generated at one or more main stations and, for the larger systems, is distributed through substations to conductors leading to the moving cars.

The larger number of electric cars are propelled by direct-current, or continuous-current, energy. In large systems alternating-current energy is usually supplied by the main stations to the substations, where it is converted by rotary converters or motor-generators into direct-current energy for the car motors.

Alternating-current motors are also used to propel the cars in some railway systems; in such cases, the rotary-converter substation is not required. Alternating-current energy is generated in the main station and utilized on the moving cars.

2. Electric railway systems are broadly classified according to the kind of electric energy supplied to the motors on the cars, as *direct-current* or *alternating-current systems*. Further classification is based on the method of current collection or supply used on the moving cars, as *trolley*, *third-rail*, *slot*, *storage-battery car*, and *gasoline-electric car systems*. The most generally used is the the direct-current, trolley system. The other systems mentioned have been adopted where other methods of current distribution and collection must be employed to meet operating conditions or comply with city laws.

COPYRIGHTED BY INTERNATIONAL TEXTBOOK COMPANY. ALL RIGHTS RESERVED

DIRECT-CURRENT RAILWAY SYSTEMS

CURRENT-COLLECTION SYSTEMS

TROLLEY SYSTEM

3. The methods of supplying current to the cars usually depend on the local conditions affecting operation of the system. In most of the city and suburban roads, the trolley system is employed because of its reasonable cost of installation and the small liability of people or vehicles coming in contact with the *trolley wire*, which is a bare conductor sus-



FIG. 1

pended over the center of the tracks. This wire is connected at intervals with large conductors, called *feeders*, which are often mounted on the poles supporting the trolley wire. The feeders are connected to the positive terminals of the main generators or of the rotary converters. Each car is provided with a device called a *trolley*. This consists of a pole mounted on the roof

of the car and having at its upper end a wheel that runs in contact with the lower surface of the trolley wire. Current passes through the wheel and pole to the motors on the car and thence to the rails. The rails are connected through the earth or through copper conductors to the negative terminals of the generators or rotary converters. A complete electric circuit is thus formed.

4. Fig. 1 shows the more important current-collection features of a trolley system. All cars are in parallel between the trolley wire and the ground; therefore, the operation of any car is independent of all others that are in normal condition. An accident to one car cannot prevent the others from operating unless the line is short-circuited by the accident.

5. A trolley system using a single trolley wire is called a *ground-return system*, because the ground forms at least a part of the negative side of the circuit, the rails being in contact with the earth. In some early systems, two trolley wires placed side by side were used. One wire was connected to the positive bus-bars and the other wire to the negative bus-bars at the station. Such a system is a *metallic-return system*, because both sides of the circuit are metallic conductors; the rails and earth do not form a part of the circuit. Two trolleys on each car must be used and the overhead wiring in the streets is complicated.

THIRD-RAIL SYSTEM

6. The **third-rail system** is electrically the same as the trolley system. The trolley wire is replaced by a third rail, which is usually mounted on insulators to one side of the track and a little above the level of the track rails. The current passes to the car circuits through shoes that slide on the contact rail and returns to the station through the track rails. In a few cases, both positive and negative conductor rails have been used, the track rails in such cases not being used as a return circuit.

Fig. 2 shows the collecting-shoe arrangement for third-rail equipment. The third rail *a* is of standard **T** section and is supported on insulators *b* resting on every fifth tie, which is extended for this purpose. The link-suspended cast-iron shoe *c*

has a limited vertical movement and the whole collecting device is mounted on a wooden beam *d* supported by the truck. A



FIG. 2

cable *e* leads to the controlling devices on the car and connection is made to the shoe through a bare, flexible, copper cable *f* which is called the *shoe shunt* because it shunts the

current around the link-pin connections, thereby preventing their becoming blistered by the current crossing their comparatively poor contacts. In some cases a *shoe fuse* is connected in the circuit at *g* to cut off the current in case of a short circuit; the fuse may be of either the enclosed or open type. The third-rail construction is much used for heavy-traffic, high-speed service over private right of way where the live rail is not a menace to persons and cattle. As the cross-section of the contact rail has a large copper equivalent, long stretches of track can be supplied with current without using feeders.

SLOT SYSTEM

7. The *slot system*, or *open-conduit system*, Figs. 3 and 4, is used only in large cities where heavy traffic warrants the great



FIG. 3

expense of installation and city ordinances prohibit overhead trolley wires and feeders. Two conductor rails *a*, one positive

and the other negative, are mounted in the conduit and are connected through feeders run in adjacent ducts to the positive and negative terminals of the generators at the station, thus forming a metallic-return system. At the top of the conduit is a $\frac{5}{8}$-inch slot between rails *e*, through which passes a plow, suspended from the car truck. Flat steel springs *b* press two cast-iron or soft-steel shoes *s*, mounted on the lower part of the plow, against the conductor rails. Flexible cables *c* extend through the body of the plow and connect through fuses, or shoe shunts, *d*, Fig. 4, to the plow shoes. The upper ends of cables *c*, Fig. 3, connect to the car circuit.



FIG. 4

ENERGY DISTRIBUTION SYSTEMS FOR DIRECT-CURRENT OPERATION

8. The term **energy distribution systems** as here used applies to the arrangement of conductors by which electric energy is transmitted from the main station, either directly or through substations to the trolley wire or third rail, from which the current for the car is taken. Systems using direct-current motors on the cars are here considered; of these there are two main divisions: (1) Direct-current generation and supply to the cars; (2) alternating-current generation and direct-current supply to the cars.

DIRECT-CURRENT GENERATION AND SUPPLY

9. 550-Volt System.—The simplest method of supplying energy to cars is by direct current transmitted from the generators in the main station to the trolley wire without any

intervening transforming devices. The voltage between the positive and negative bus-bars is generally from 500 to 600 volts;



FIG. 5

the latter voltage is the later development. This system is adapted to operation in sections of dense population where the distances are not too great; it is not adapted to economical

transmission of large amounts of energy over long distances, because at low voltage the current required is very large and the line losses excessive. Efforts to decrease these losses by greatly increasing the copper result unprofitably.

10. Fig. 5 indicates the more important connections of the parts of a railway system of this simple type. An engine S drives a direct-current generator D, which is connected with the switchboard K; this is connected with the trolley and rails forming a current path as indicated by the arrowheads.

11. Each car requires a current proportional to the power necessary to operate it. The sum of the currents taken by the cars forms the load on the station. The total current is indicated by the ammeter connected to the negative bus-bar, as in Fig. 5.

In a very small system, the trolley wire, if only in one section, may be connected directly to the positive bus-bar without the use of feeder cables. In large systems, the trolley wire is usually in sections and is too small to carry all the current; feeder cables are then provided to connect the positive bus-bar directly with the more distant trolley wire sections.

12. Return cables connecting points on the track to the negative bus-bars are installed in some systems. The conductivity of the track-return portion of the circuit is thus improved and the liability of damage to iron pipes, due to the pipes forming part of the current-return system, is lessened.

13. The maximum distance it is economical to operate cars with direct-current energy generation at a voltage of from 500 to 600 depends on the character of the traffic and on the frequency of the service; the limiting distance has been often stated in round numbers, as 7 miles. Many roads operate over greater distances, but it is probable that operation would be improved if the voltage were raised. By using boosters in the station or storage batteries on distant parts of the line, the permissible limit of economical operation is appreciably increased. Most medium-sized roads are operated over a radius of 6 to 8 miles without using alternating-current energy.

14. High-Voltage Bus-Bars.—Usually the heavier traffic is confined to a comparatively small area, the traffic on lines running to remote points being light; by raising the voltage of the feeders running to these distant sections, normal voltage at the cars can be maintained. Assuming voltages of 550 and 650 to be available at the station, feeders to the near sections could be connected to the 550-volt bus-bars and the long feeders of distant sections to the 650-volt bus-bars, thereby providing a permissible extra voltage drop of 100 volts. The radius of operation can thus be extended 3 or 4 miles.

15. Fig. 6 shows the connections for both high- and low-voltage bus-bars. The negative terminals of compound-wound generators *1*, *2*, and *3* are connected to the ground bus, while each positive terminal is connected through a main switch, the shunt of ammeter *A*, and the circuit-breaker, to the middle of a single-pole double-throw switch. By means of this switch, the positive side of the generator can be connected to either the upper or the lower bus-bar.

Generators *1* and *2* are shown connected to the lower bus-bar and operating in parallel, their equalizing switches being closed. Generator *3* is shown connected to the upper bus-bar and its equalizer switch is open. Most standard railway generators will generate 650 volts on full series field; generator *3* is assumed to generate 650 volts and generators *1* and *2*, 550 volts. Any machine, however, can be connected to either bus-bar. The feeders have single-pole double-throw switches for connection to either bus-bar. If feeders *A* and *B* are supplying near sections or if their loads are light, they can be connected to the 550-volt bus-bar; feeder *C* on a distant or heavily loaded section can be thrown on to the 650-volt bus-bar. By this arrangement, a fairly uniform voltage can be maintained at the cars under widely varying load and transmission conditions. In Fig. 6, the generators are shown equalized on the negative side; this connection is the prevailing practice in railway plants. The main and equalizer switches are mounted side by side near the machine and the negative leads are carried directly to the rail bus-bar.

16. Installation of Boosters.—On sections distant from the station, overcompounding of the generators may be inadequate to compensate for the feeder drop; in such cases *boosters* may be used in connection with the main generators in order to obtain high voltage at the distant section of the road. A **booster** is a generator connected in series with the feeder or



FIG. 6

feeders, the voltage of which is to be raised, so that the booster voltage is added to that of the main generators.

In Fig. 7, *a* represents the armature of a station generator, and *b*, the armature of a booster. Short feeders connect the positive bus-bar of the generator with near-by sections of the trolley wire; the circuits of long feeders include the booster, which in this case is assumed to generate 200 volts.

Railway boosters are generally of the *series type;* that is, the field winding is in series with the armature so that the voltage generated increases in proportion to the booster current. When the feeder load is light, the booster voltage is low because its field is weak; a heavy load increases the booster voltage and compensates for the drop in the boosted feeders. This automatic voltage regulation is indispensable, for were the booster to generate constant voltage regardless of the value of the feeder current, then at light loads with negligible line drop, the voltage applied to the cars would be excessive; this would be a tax on the motors and would cause continuous trouble with lights, heaters, and other auxiliary devices on the cars.

17. Street-railway boosters are driven at constant speed, generally by shunt-wound motors, though other constant-speed



FIG. 7

drive can be used. Fig. 8 shows a booster set consisting of a shunt-wound motor *M* coupled to a series-wound booster *B*. Boosters do not differ in their general construction from standard generators except that their commutators may be larger owing to their comparatively large current rating. Recent types of booster are equipped with commutating poles to give perfect commutation without brush shifting.

18. Booster Rating.—Booster output in watts is the product of the booster amperes by the booster volts. If a booster carries 600 amperes and boosts this current 200 volts, the booster output is $600 \times 200 = 120{,}000$ watts or 120 kilowatts. A decrease of current to 300 amperes would lower the booster voltage to 100 if the voltage varies directly with the current, that is in a straight line, and the output in this case



FIG. 8

Digitized by Google

would be $300 \times 100 = 30{,}000$ watts or 30 kilowatts. At zero booster current, the booster output would be zero, but its voltage would be 25 or 30 volts due to residual magnetism. Booster voltage rarely varies in an absolutely straight line, and the amount by which the variation departs from the straight-line variation is important, because too much departure will result in trouble with lamps and other devices designed for rated voltage.



FIG. 9

In Fig. 9 the straight line shows voltage variation of a booster in which the change of voltage per ampere is constant. When the amperes are 500, the booster voltage is 400 and when the amperes are 250, the booster voltage is 200; this proportion is maintained over the current range. A booster with such a perfect characteristic would cost a prohibitive amount of money, and such perfection is unnecessary. The curved line illustrates more nearly the actual manner in which booster voltage varies with the booster current. Here, at 500 amperes the booster voltage is 400 as before, but at 250 amperes the voltage is 240,

or 40 volts high, and at no point on the curve does the same proportion between voltage and current exist. This variation is satisfactory, provided the departure is within safe limits, which are given in Table I.

TABLE I

BOOSTER VOLTAGE VARIATIONS

Full-Load Voltages of Boosters	Allowable Maximum Variation of Full-Load Voltage at Partial Load Per Cent.
50 to 100	20
100 to 150	15
150 to 250	12½
250 to 500	10

19. The rating of a booster required for a given case depends on the drop in the feeders to be boosted, but the drop in the trolley-wire section is not usually considered as there are ordinarily but few cars per section in the outlying districts. The resistance of the feeder and the maximum current to be transmitted are usually known or may be calculated and the size of the booster is determined by an application of Ohm's law.

Suppose that the feeder has a resistance of .3 ohm and carries a maximum current of 600 amperes. The drop is $600 \times .3 = 180$ volts and for the same current the drop will be the same whether the feeder voltage is boosted or not; therefore, the correct rating for the booster in such a case will be 600 amperes at 180 volts. The output is then $600 \times 180 = 108$ kilowatts.

A size found well adapted to average railway service has an output of 120 kilowatts or 600 amperes at 200 volts. For smaller roads an output of 60 kilowatts or 600 amperes at 100 volts is convenient. To adapt boosters to a variety of conditions, it is customary to provide the series-field winding with taps, so that the number of active turns can be changed to suit existing conditions; or to furnish a variable shunt by means of which some of the current can be diverted from the series-field

winding. Where a shunt is used, it should be of the inductive type; otherwise, the booster is apt to respond sluggishly to sudden changes in the load. The objection to a non-inductive shunt is that when the current increases suddenly, most of the increase at first will pass through the shunt and but little through the series-field in parallel with it.



FIG. 10

20. Booster Connections.—The connections of the booster are such that the booster voltage is added to that of the main generators. The booster negative terminal is connected to the positive generator bus-bar, as shown in Fig. 10. The main generators *1*, *2*, and *3* connect to the positive bus-bar,

which connects to the negative booster bus-bar through a switch *a*. Each feeder includes a double-throw single-pole switch *b*, with which to connect it either to the main positive bus-bar or to the positive bus-bar of the booster. As indicated by the dotted lines, the long feeders *A* and *B* are shown connected to the booster, while the short feeder *C* is connected directly to the main generator bus-bar. In order that feeder *C* will have the same voltage impressed on it as the feeders *A* and *B*, the right-hand feeder switch *b* should be thrown to its upper position. The booster is driven by a shunt motor operated from the main generators and equipped with a circuit-breaker and starting rheostat. The booster is connected to the booster bus-bars through an ammeter *A*, circuit-breaker *d*, and a double-pole main switch. The connections of Fig. 10 are equivalent to those of Fig. 7. All current supplied to feeders *A* and *B*, Fig. 10, passes through the booster and the feeder voltage is increased by an amount proportional to the current. The motor circuit-breaker should be so arranged that on opening it trips the booster circuit-breaker. A simple way to do this is to mount the two circuit-breakers *d* and *e* side by side and interlock them. They should also be so arranged that the booster circuit cannot be closed until after the motor has been started. If current were cut off the motor but not off the booster, the latter would be driven as a series motor reversed in direction of rotation, because series generators and motors run in opposite directions for given connections.

21. At times, it is desirable to use a small 550-volt generator as a booster. This can be done by connecting the armature and series coil of the generator in series with the feeder to be boosted and adjusting the excitation of the shunt coils to that necessary to give the desired electromotive force. This adjustment is sometimes made by connecting the shunt-field coils in parallel and then connecting the group of coils in parallel with a length of feeder in which the drop is sufficient to give the desired exciting electromotive force. This makes the shunt-field excitation of the booster proportional to the voltage drop in the feeder.

22. Location of Booster.—The location of the booster is preferably in the power station, where no extra attendant is required; if a motor-driven booster is located out on the line, its operating current must be transmitted from the station and the line loss is therefore increased. Boosters driven from some other source of power, such as a steam or gas engine, are free from this objection but the cost of attendance remains.

23. Economy of Boosters.—Booster practice represents an excess of electric energy generated in order that a sufficient amount may reach the locality of useful consumption, and all that does not reach that locality is wasted; but the real difference in the economies of boosters and of high-tension alternating-current transmission is not so great as the apparent difference. Boosters cause heavy losses only when the load is heavy, and this is a comparatively small part of the total time. With alternating-current transmission, certain transforming losses are constant irrespective of the useful load, and the annual cost of substation attendance may cause the total expense of losses and attendance to exceed those incident to booster operation. Boosters permit line extensions without expensive changes in station equipment or excessive outlay for copper. These advantages are more fully realized if storage batteries are installed out on the line. The battery will charge from the booster when the load is light and discharge when it is heavy, thereby keeping a fairly uniform load on the feeder and working it to best advantage.

The annual cost of operation, under certain conditions, with boosters may be less than that with alternating-current transmission. The system to adopt can be decided only by comparing their costs of operation. There are roads on which cars are operated over a radius exceeding 20 miles with the aid of boosters and storage batteries; these roads give satisfactory service, are as economical in operation as similar roads for which alternating-current transmission is used, and are less liable to interruptions from breakdowns that characterize transforming appliances necessary with alternating-current transmission and direct-current distribution.

24. Storage-Battery Auxiliaries.—On systems dependent entirely on direct current, the storage-battery auxiliary may be in the form of a portable substation, which is a motor-driven car loaded with batteries and which can be used where most needed; or it may be in the form of a permanently located battery that *floats* on the line. In the first case, the batteries are charged from the line during the periods of light load and then dicharged into the line when help is required on heavy loads. The disadvantage of this system is that it requires an attendant during the charging period, unless the charging is done at the station. The advantage of the system is that the car can be placed at the point where it is most needed and thereby meet overload shifts due to attractions at different terminals.

25. A floating battery is connected permanently across trolley and ground on some distant line section and, by properly proportioning the number of cells connected in series, charge and discharge currents may be made approximately the same. The automatic operation of the set depends on the drop in the line. A heavy load on the line causes sufficient line drop to allow the battery to discharge and help the station; when the line load is light, the line drop is small and the line voltage at the battery is sufficient to charge the battery.

ALTERNATING-CURRENT GENERATION AND DIRECT-CURRENT SUPPLY

26. Electric energy can be economically transmitted at greater distance by alternating current than by direct current, and is more economically generated in one large station than in several small ones. Therefore, where many cars are to be operated by direct current over a large area, it is the practice to concentrate generation in one or two large stations equipped with polyphase alternators and transformers and to transmit the energy to centrally located substations equipped with transformers and rotary converters or motor-generators, which supply direct-current energy of the desired voltage to the cars.



FIG. 11

In the main station, the alternators are of the rotary-field type, because this construction places the high-voltage conductors on the stator of the machines which affords more room for insulation and effective ventilation. In the substations, six-phase converters are often used because their capacity is nearly twice that of an ordinary generator of the same weight. Where considerable direct-current energy is required near the main station, a substation is frequently installed in the same building.

27. 600-Volt Supply. Fig. 11 shows the general features of the electric-energy distribution system of a large railway system. Alternating-current energy is generated in a main station, the voltage raised by transformers for the transmission lines, and the energy transmitted to substations where transformers and rotary converters supply direct-current energy to the cars at approximately 600 volts.

28. 1,200- to 1,500-Volt Supply.—In order to transmit direct-current energy economically over

very considerable distances, the voltage of the direct-current supply lines in some systems is 1,200 volts or more. The development of the direct-current commutating-pole motor, which allows a high electromotive force to be impressed safely on its terminals, made possible the successful development of the 1,200-volt system. This high-tension system is especially adapted for extensions to 600-volt systems and for interurban roads.



FIG. 12

29. Fig. 12 shows the more important connections of a substation designed to supply direct-current energy at 1,200 volts. The two rotary converters are supplied with alternating-current energy from two separate secondaries of the transformer, in order to prevent circulation of current between the alternating-current ends, which might occur if both rotaries were connected to one secondary. The direct-current ends of the two rotaries are connected in series to produce the 1,200 volts required.

In some cases, one or more 1,200-volt rotaries are used instead of sets consisting of two 600-volt rotaries in series. Motor-generator sets are also used in some systems. The motor drives either two 600-volt direct-current generators connected in series or one 1,200-volt generator. If there are four motors on a car, two groups are formed, each of two motors connected permanently in series. For low speeds the groups are connected in series, and for high speeds the groups are connected in parallel by means of the control apparatus on the car. A maximum electromotive force of about 600 volts is impressed across the terminals of each motor. Motors have been developed intended for an impressed electromotive force of 1,200 volts on their terminals.

Current collection by trolley wire is usually employed in these high-tension systems, but the third-rail method has also been used successfully.

30. 2,400-Volt Supply.—In the 2,400-volt, direct-current, supply system, motor-generator sets in the substation are used. An alternating-current motor drives two 1,200-volt, direct-current generators, which are connected in series.

The locomotives are equipped with four 1,200-volt motors. For low speed the four motors are in series, and for high speed the motors are arranged in two pair so that only two motors are in series across the 2,400-volt circuit in each current path.

31. Portable Substation.—On large railway systems, events are likely to occur that attract unusual travel in certain directions at irregular intervals. It is not often advisable to install direct-current feeders to meet these temporary conditions, but the application of a portable substation consisting of a rotary converter and its auxiliary apparatus, a motor-generator, or a storage battery will often solve the problem.

The necessary apparatus is mounted on a car, moved to a central position on the loaded section, and connected to the alternating-current and direct-current feeders if a rotary or motor-generator is used, or if a storage battery is used, it is connected across the direct-current feeder or trolley circuit. In some cases, the transformer and high-tension switches are

mounted on a steel tower erected near the car. By this means, the temporary load may be carried satisfactorily with little if any change in the regular energy distribution system. It may be necessary to run an alternating-current feeder circuit to the portable converter substation, but the circuit wires would be comparatively small.

INDEPENDENT ENERGY SYSTEMS

32. Storage-Battery Cars.—Improvements in both the lead storage cell and the Edison storage cell and in the construction of the cars on which a battery is installed for motive purposes have adapted storage-battery cars for special classes of railway service, among which are: (1) Steam-road branch lines in suburban service and in local service where the population is sparse. (2) At steam-road terminals in the larger cities and in tunnels to avoid the smoke nuisance. (3) For construction and emergency cars on lines on which breakdowns may be such as to interrupt the energy transmission lines. (4) As "trippers" to be charged during hours of comparatively light station load and to be operated during morning and evening rush hours. (5) As "night hawks" to be operated at night, thereby permitting the power station to be shut down. (6) On new extensions of all kinds to develop traffic. (7) In small towns of 7,500 inhabitants and more. (8) As independent railways of light construction to serve agricultural interests as feeders to standard steam trunk lines.

33. The storage battery that furnishes energy for propulsion can be charged while in position on the car or after removal; in the latter case, another battery is substituted if the car is to continue in service. The car is usually able to travel from 80 to 100 miles on a single charge. The voltage of the battery depends on the kind and number of cells connected in series; in some cars 88 lead cells in series are used and the discharge is at an average voltage of 173. As the car carries its own source of electric energy, it can be operated over any tracks of suitable gauge independent of feeder or trolley installation. The control apparatus on the car serves to vary

the portion of the battery electromotive force that is applied to the motors in such manner as to start and to regulate the car speed, as explained in another Section.

34. Gasoline-Electric Cars.—A gasoline-electric car is equipped with a gasoline engine mechanically connected to a direct-current generator, which in turn is electrically connected through speed-control apparatus to motors used for propelling the car. This type of car was developed to provide frequent single-car service on short railroad lines and to replace trains operated by steam locomotives at infrequent intervals. The operation of the speed control for these cars is explained in another Section.

ALTERNATING-CURRENT RAILWAY SYSTEMS

ENERGY DISTRIBUTION SYSTEMS FOR ALTERNATING-CURRENT OPERATION

SINGLE-PHASE GENERATION AND SUPPLY

35. The development of a successful single-phase alternating-current, railway motor, lead to the construction of many electric-railway systems in which alternating-current is generated in the stations and utilized to propel the cars. In the United States, the development has been mostly on the single-phase system using a series-wound commutator motor.

Single-phase generators may be installed at the power station, but three-phase generators are often employed; only one or two of the windings are however used to supply energy for car propulsion. All three phases of these generators are, in some cases, used to supply energy to the railway shops.

In some systems, transformer substations are installed, as indicated in Fig. 13, to reduce the transmission line voltage to that desired for the trolley system. In other systems, the voltage of the high-tension generators is applied through feeders


Single-Phase, High-Tension Transmission Line
POWER STATION
Steam Turbine
Alternating-Current Generator
Raising Transformer
SUBSTATION
Lowering Transformer
Single Trolley Line

FIG. 13


Single Trolley Line
POWER STATION
Steam Turbine
Alternating-Current Generator

FIG. 14



FIG. 15

to the trolley and rail without transformation of any kind, as indicated in Fig. 14.

Various voltages between trolley and rail have been employed on alternating-current roads. Among these values are 11,000 volts and 6,600 volts. A transformer on the car reduces the voltage to that suitable for the motors. The trolley system of current collection is usually employed. The trolley wire is installed with particular attention to its insulation and the high-speed service to which it is subjected.

THREE-PHASE GENERATION AND SUPPLY

36. The use of three-phase railway motors is rare in the United States. It is customary in systems of this kind to install two trolley wires over each track and to use the track rails for the third conductor of the three-phase energy-supply system, as indicated in Fig. 15.

In one installation of this kind, three-phase energy is generated at the station and the voltage stepped up by

transformers for transmission to the substation. The transformers there installed reduce the voltage of the energy for the trolley and rail supply to 6,600 volts. Three-phase transformers on the locomotive further reduce the voltage to a value suitable for the three-phase induction motors, approximately 500 volts. Taps at different points on the secondaries of the transformers and adjustable resistances in the rotor circuits of the motors serve to start the motors without taking excessive current from the supply system. The motors run, however, at approximately constant speed for all loads and grades.

Motors of this kind are better fitted for railroad work in which infrequent stops are made and the speed desired is nearly constant, as they are essentially constant-speed motors.

Two or more speeds may be obtained from three-phase induction motors by changing the connections of the coils on the stators so as to produce a different number of poles, and by the cascade system of connecting two motors. In the cascade system, the rotors of the two motors are provided with windings connected to slip rings. The stator of No. 1 motor is connected to the three-phase line wires; the rotor of this motor is connected to the stator of the No. 2 motor, the rotor of which is connected to Y-connected resistors. The combination will run at such speed that the frequency of the current in the No. 1 rotor is of the proper value to drive the rotor of the No. 2 motor at the combination speed. Both motors must rotate at the same speed if they are connected to the same size of driving wheels. If the motors have the same number of poles, the combination speed is about half the speed of each motor when connected separately to the line wires.

ENERGY CALCULATIONS

GENERAL CONSIDERATION

37. The station-generator capacity required to support a given schedule on a given road depends on the number of cars and their schedule speed, the weight per car, topography of the road, character of traffic, and manner of handling equipment, and the condition of the line and of the track return. In new developments it is fair to assume that the condition of line and of track return is good. On large systems, it is usual to assume that the saving of power due to cars coasting down grades offsets the extra power demand of cars ascending grades. On small systems, however, where the average and maximum demands on the station are so widely different, the acceleration of one loaded car on a grade may easily treble the existing current demand on the station.

The maximum demand, hence maximum capacity, of a station can be greatly reduced by the installation of current-limiting devices upon the cars and by the enforcement of a rule requiring cars to be operated up grades on the series-notches of the controllers.

On a small road the energy required for lighting cars is inconsiderable, but on all roads the energy consumed by electric heaters may exceed 20 per cent. of the total energy required, because the heaters draw current continuously while the motors do not. The probability of snow equipment being in operation at the same time as schedule cars must also be considered.

A relation that works out satisfactorily on large and average-sized roads is that, assuming 25 per cent. of the station output to be consumed in transmission and conversion, the total kilowatt capacity of the station must equal the total horsepower capacity of all car motors likely to be in operation at the same

time; to this, assuming that the summer and winter schedules are the same, must be added the extra capacity required by electric heaters.

Car speeds are largely fixed by the character of the service. City cars may not average more than 10 miles per hour, while interurban cars may average 40 to 50 miles per hour, according to the number of stops. The number of cars required depend on the length of line, frequency of service and schedule speed. To determine the best schedule speed and frequency of service for any proposed road requires a close study of dependent conditions, such as probable traffic and returns therefrom, competition, etc. In all cases, traffic estimates should consider traffic growth.

PASSENGER FACTOR AND LENGTH OF TRACK

38. The length of the proposed road depends largely on the population to be served and its distribution. The curves in Fig. 16 show what may generally be expected; they are plotted from data obtained under average conditions in cities and towns. The curve marked *passenger factor p* shows approximately the number of rides to be expected each year per inhabitant of the territory to be served by the system. This includes the center of population and the suburban sections reached by the road. With a population of 1,500,000, for example, there may be expected a passenger factor of 240. With a population of 250,000, the passenger factor expected is 190.

The curve marked *track factor t* shows the number of miles of single track to each 1,000 inhabitants. With a population of 375,000, the miles of single track for each 1,000 inhabitants is .61 mile, approximately. With a population of 1,500,000, the track factor is .49, approximately.

Let l = length of single track, in miles;
n = population to be served, say 10 years from time of building road;
t = track factor.

Then,
$$l = \frac{n\,t}{1{,}000}$$

For example, if the population of a territory in 10 years will be 1,000,000 and the track factor t, Fig. 16, is .51, the length of



FIG. 16

single track required to serve this population is $l = \frac{1{,}000{,}000 \times .51}{1{,}000}$ = 510 miles.

NUMBER OF CARS

39. Knowing the number of contributing inhabitants, the fare per ride, and the probable number of rides each year per inhabitant, Fig. 16, the annual income in dollars can be computed. The average income for each car per mile of run, or as it is expressed per car-mile, is 21.56 cents on seventeen representative New York State roads; and the income on sixteen

roads in various portions of the country is 27.31 cents per car-mile. Call the average for the thirty-three roads 24 cents. If the estimated annual income of the proposed road is divided by an assumed income per car-mile, the result will be the number of car-miles that must be made in a year to realize the estimated income; this, divided by the total number of hours that cars must run each year, gives the necessary number of car-miles each hour; and this divided by the schedule speed, in miles per hour, gives the number of cars required.

The annual income is equal to the product of the contributing population, n; the passenger factor p, Fig. 16; and the single fare, f, expressed in dollars. The number of cars c required is equal to the total annual income $n\,p\,f$ divided by the product of 365 (the days in a year); the operating hours per day, h; the schedule car speed in miles per hour, v; and the income per car-mile, r, expressed in dollars.

$$c = \frac{n\,p\,f}{365\,h\,v\,r}$$

EXAMPLE.—The following estimates are made for a proposed railway system to serve a population of 250,000: The single fare is to be 5 cents; the cars are to operate, 19 hours a day at an average speed of 10 miles per hour; and the income per car-mile is estimated as 24 cents. How many cars are required?

SOLUTION.—The passenger factor p, Fig. 16, for the population n of 250,000 is 190; f is \$.05; h is 19 hr.; v is 10 mi. per hr.; and r is \$.24. The number of cars

$$c = \frac{250{,}000 \times 190 \times .05}{365 \times 19 \times 10 \times .24} = 143 \text{ cars.} \quad \text{Ans.}$$

SIZE AND WEIGHT OF CARS

SIZE

40. The size of the cars to be used on any one continuous line of a railway system depends on the number of passengers to be transported each day on that line and the number of cars available for the service. An approximate estimate of the passenger capacity of any one of these cars may be made as

follows: The estimated number of passengers per day divided by the number of cars on the line gives the passengers per car per day. The schedule speed in miles per hour multiplied by the number of hours' operation of the car each day gives the total distance that the car travels during the day; and this divided by the length of the line gives the number of single trips made each day by the car. The average number of passengers per trip is equal to the number per day divided by the number of trips made by the car. The average ride of a passenger in city work is estimated as 3 miles; therefore, the capacity of the car may be considered as equal to the passengers per trip divided by one-third of the number of miles length of the line.

CAR WEIGHTS

41. The weight of cars depends on the nature of the traffic in which they are engaged. Interurban cars are heavier than city cars and frequently approach in size and weight those used on steam roads. Many complete double-truck trolley cars of older design but now in service weigh about 1,000 pounds per seated passenger and single-truck trolley cars about 800 pounds. Some of the more recent interurban cars weigh as low as 900 pounds, but most of them average about 1,250 pounds per seated passenger. The weight of ordinary trolley cars has been reduced 25 per cent.

These figures are, of course, only approximately correct, because the weight of trucks, car bodies, motors, and auxiliary devices vary greatly.

To the dead weight of the car should be added the live weight of the passengers estimated as 150 pounds per passenger. The live weight seldom exceeds 10 or 15 per cent. of the dead weight.

TRACTIVE-EFFORT FORMULAS

42. The following formulas for calculating the tractive force required by electric cars are only of approximate accuracy because of the many factors that modify the running conditions, among which are the conditions of the running gear, the roadbed, the wind, and the weather.

43. Tractive effort, or tractive force, refers to the force applied to a car to keep it in motion. On motor-driven cars this force is applied at the rim of the wheel. The resistance to motion, which the tractive effort must overcome, is due to four causes: *Train resistance*, which includes the resistances due to bearing friction, rolling friction, flange friction, and wind pressure; *grades*, which require that the car or train be lifted gradually at a rate depending on the steepness of the grade; *curves*, which increase the flange friction; *acceleration*, because all bodies at rest or in a certain condition of motion resist any effort to change that condition, therefore force must be used to overcome this resistance.

44. Train Resistance.—Were it not for train resistance, a car once in motion at a certain speed on a straight, level, rigid track would stay in motion without decrease of speed and without application of any force. All train-resistance formulas assume good condition of track and bearings and freedom from wind pressure, except that due to the train motion.

Let T_r = train resistance, or its equivalent, the tractive effort required to overcome it, in pounds;
w = weight of car, in tons;
v = car speed, in miles per hour;
s = number of square feet of head-end surface area of car.

Then,
$$T_r = 50\sqrt{w} + \frac{w\,v}{25} + \frac{s\,v^2}{400}$$

The first two elements of the right-hand side of the formula relate to the mechanical friction; the last element relates to the air friction.

EXAMPLE.—What is the tractive effort required to overcome the train resistance of a 16-ton car operating at 16 miles per hour on straight level track, the head end area of the car being 80 square feet?

SOLUTION.—Here $w = 16$ tons; $v = 16$ mi. per hr.; and $s = 80$ sq. ft. Substituting these values in the formula, gives

$$T_r = 50 \times \sqrt{16} + \frac{16 \times 16}{25} + \frac{80 \times 16 \times 16}{400} = 261 \text{ lb.} \quad \text{Ans.}$$

45. Effect of Grades.—When a car is traveling a 1-per-cent., a 2-per-cent., or a 3-per-cent. grade, the car is lifted vertically 1, 2, or 3 feet, respectively, for every 100 feet of distance traveled along the track. For the comparatively small grades usually met in railway practice, it is sufficiently accurate to consider the 100-foot section as measured along the rail, because the horizontal distance moved over, on which the percentage of grade is really based, is practically the same as the rail distance.

Any body on a grade has a tendency to move down the grade and, neglecting friction, a force must be applied to the body in a direction parallel to the rail to overcome this tendency. This force depends on the weight of the body and the grades. For small grades, the force is one one-hundredth of the weight of the body for every per cent. grade.

Assuming a weight of 1 ton, or 2,000 pounds, and a grade of 1 per cent., the force acting parallel to the rail is $2{,}000 \times \frac{1}{100} = 20$ pounds. The work done by a force of 20 pounds acting through a distance of 100 feet is equivalent to the force of 2,000 pounds acting through a vertical distance of 1 foot, which is the distance that the body rises for every 100 feet of rail at 1-per-cent. grade.

The extra tractive effort T_g, required on account of the grade of the tracks, is equal to 20 pounds for each ton of weight and for each per cent. grade.

Let w = weight of car, in tons;

g = per cent. grade, expressed as a whole number.

Then, $$T_g = 20\, w\, g$$

EXAMPLE.—What is the extra tractive effort required to force a 16-ton car up a 3-per-cent. grade?

SOLUTION.—In the formula $w = 16$ and $g = 3$.

$$T_g = 20 \times 16 \times 3 = 960 \text{ lb.} \quad \text{Ans.}$$

46. Effect of Curves.—When a car is passing around a curve, the flanges of the wheels rub against the side of the rail head, thus causing friction and thereby increasing the necessary tractive effort over that required to overcome train resistance and grade. Curves are usually estimated to add to the

tractive effort ½ pound per ton of train weight for each degree of curvature. The degree of curvature of a railway curve is the angle of an arc of that curve between two points 100 feet apart.

If c = number of degrees curvature;
w = weight of train, in tons;
T_c = extra tractive effort required to overcome resistance of curve, in pounds.

Then, $$T_c = \frac{w\,c}{2}$$

EXAMPLE.—What is the extra tractive effort required to force a 16-ton car around a 3° curve?

SOLUTION.—In the formula $w = 16$ and $c = 3$; therefore,

$$T_c = \frac{16 \times 3}{2} = 24 \text{ lb.} \quad \text{Ans.}$$

47. Acceleration.—So far, uniform car motion has been assumed. It takes more energy to start a car than it takes to keep it moving at the speed acquired. Car-motor capacity based on assumptions of uniform motion will be insufficient unless the station stops are very infrequent. To start a car from rest and accelerate it to a given speed, energy must be expended in excess of that required to balance train resistance and the resistances of grades and curves; this extra energy is stored in the car by virtue of its weight and motion and it must be dissipated as heat when the car is stopped with the brakes. The extra tractive effort required to accelerate a car depends on the weight of the car and on the rate at which it is accelerated. In car-operation problems, the rate of speed increase (acceleration) or speed decrease (retardation or deceleration) is expressed in miles per hour per second. For example, an acceleration of 1¼ miles per hour per second, means that during each second, the car speed is increased 1¼ miles per hour; a car started from rest will, at the end of the first second, be moving at the rate of 1¼ miles per hour; at the end of the second second, 2½ miles per hour, and so on. Again, if it takes a car 16 seconds to accelerate from rest to a speed of 16 miles per hour, its acceleration will be 1 mile per hour per second.

In general, if the difference in the two speeds, expressed in miles per hour, is divided by the seconds taken to accelerate from one speed to the other, the quotient is the average acceleration in miles per hour per second.

If a = acceleration, in miles per hour per second;
w = weight of the train, in tons;
T_a = extra tractive effort required for acceleration, in pounds.

Then, $$T_a = 100\ w\ a$$

EXAMPLE.—What is the extra tractive effort required to accelerate a 16-ton car from rest to a speed of 16 miles per hour at the rate of 1 mile per hour per second?

SOLUTION.—In the formula $w = 16$ and $a = 1$; therefore, $T_a = 100 \times 16 \times 1 = 1{,}600$ lb. Ans.

48. Total Tractive Effort.—The total tractive effort T, taking into consideration the resistances offered by train resistance, grades, curves, and acceleration, may be expressed by a formula combining the right-hand members of the formulas in Arts. 44 to 47.

$$T = 50\sqrt{w} + \frac{w\,v}{25} + \frac{s\,v^2}{400} + 20\ w\ g + \frac{w\,c}{2} + 100\ w\ a$$

substituting the values of T_r, T_g, T_c, and T_a in the examples under the preceding formulas, $T = 261 + 960 + 24 + 1{,}600 = 2{,}845$ pounds.

This is the total tractive effort required to accelerate a 16-ton car at the rate of 1 mile per hour per second on a 3-per-cent. grade and in a 3° curve. This is a possible condition. With a straight level track $20\ w\ g + \frac{w\,c}{2}$ will become zero and the total tractive effort required to accelerate the car against train resistance and inertia will be $T = 261 + 1{,}600 = 1{,}861$ pounds.

49. Tractive Effort Per Ton.—If the tractive effort per ton is desired, the right-hand members of the formulas for T_r, T_g, T_c, T_a, and T should be divided by w, the weight in tons of the car. Thus, in the example in Art. 44 the tractive effort per ton t_r required to overcome train resistance is

$$t_r = \frac{50}{\sqrt{w}} + \frac{v}{25} + \frac{s\,v^2}{400\,w} = 12\tfrac{1}{2} + \tfrac{1}{2}\tfrac{6}{5} + \tfrac{1}{6}\tfrac{6}{5}$$

$$= 16 \text{ pounds, approximately} \qquad (1)$$

The combined tractive effort per ton, Art. 48, is

$$t = \frac{50}{\sqrt{w}} + \frac{v}{25} + \frac{s\,v^2}{400\,w} + 20\,g + \frac{c}{2} + 100\,a \qquad (2)$$

Substituting the values given in the examples, $t = 12\tfrac{1}{2} + \tfrac{1}{2}\tfrac{6}{5} + \tfrac{1}{6}\tfrac{6}{5} + 60 + \tfrac{3}{2} + 100 = 178$ pounds.

50. Limit of Adhesion.—The pressure of the brake shoes against the car wheels tends to stop their rotating, but the pressure of the car wheels on the rails tends to keep the wheels rolling; the most effective pressure will prevail. This means, that, when braking, if the braking pressure is excessive, the car wheels will stop rotating, but the car will still move; also, when accelerating, if the tractive effort tending to rotate the wheels exceeds the tendency of the wheel-rail friction, called *adhesion*, to prevent wheel slippage, the wheels will rotate, but the car may not move. The rate at which a car can be accelerated, or the steepness of the grade that it can ascend, is limited by the rail-wheel adhesion, which depends on the weight on the drivers and on the coefficient of friction between wheel and rail. The latter is lower for street railways, where the rails are liable to be dirty and slippery, than it is for elevated, subway, or interurban roads, where the rails are clean.

Table II gives *coefficients of adhesion* for rails under different conditions and assumes uniform tractive effort applied to the wheels. The **coefficient of adhesion** expresses the ratio between the tractive effort that will just slip the wheels and the weight on the rails directly under the driving wheels. The application of sand increases adhesion.

The coefficient of adhesion of 30 per cent. is the maximum value given in the table, but tests with electric locomotives have recorded as high a coefficient as 35 to 40 per cent. under favorable conditions. Except in infrequent-stop, high-speed service, where lower rates of acceleration prevail, it is customary to provide sufficient motive power to slip the wheels on dry

rail; in high-speed service, this practice is not observed because high-speed equipments are not intended for high rates of acceleration and efforts to qualify them as such result in enormous currents and unnecessarily high cost of equipment.

51. On interurban or elevated roads, the adhesive force may be safely taken as 15 per cent. of the weight on the rails under the drivers; on city street railways, a safe value is 12 per cent. of the weight on the rails under the drivers; this gives $2{,}000 \times .15 = 300$ pounds per ton for elevated and interurban service and $2{,}000 \times .12 = 240$ pounds per ton in city trolley service.

TABLE II
COEFFICIENTS OF ADHESION

Condition of Rail	Without Sand Per Cent.	With Sand Per Cent.
Clean dry rail	30	
Wet rail	18	22
Rail covered with sleet	15	20
Rail covered with dry snow	10	15

On single-truck, two-motor cars, all wheels are drivers and the weight on the rails under the drivers equals the total weight of the car. This style of equipment is well adapted to hill climbing and to operation under unfavorable rail conditions.

On double-truck, two-motor cars, from 55 to 70 per cent. of the total weight rests on the rails under the drivers, thus limiting the tractive effort to from 165 to 210 pounds per ton weight of car at 15 per cent. adhesive force.

On four-motor, double-truck cars, all weight is on the rails under the drivers; these equipments are desirable for roads operating double-truck cars in hilly localities.

52. Limiting Grades.—The car wheels on separate axles are usually not rigidly connected together, therefore, on grades, where weight is transferred from the forward to the rear drivers, less tractive effort can be applied than is the case on a level,

because of the tendency of the forward wheels to slip. The motors are usually started while connected in series and, if the wheels connected to one motor slip, the high counter electromotive force of the spinning motor reduces the current through both motors to an insufficient value for satisfactory operation.

If t_s = tractive effort required to start car on level, in pounds per ton;
g = grade, expressed as a percentage;
w = car weight, in tons;
p = per cent. of total weight on rails under drivers, expressed as a decimal;
r = coefficient of adhesion, expressed as a decimal.

Then,

Weight on rails under drivers, in pounds $= 2{,}000\ w\ p$
Adhesive force, in pounds $= 2{,}000\ w\ p\ r$
Force required to start car on grade g $= w\ t_s + 20\ w\ g$

Each per cent. of grade requires 20 pounds per ton additional tractive effort over that required on a level. When the grade is such that the tractive effort required to start on it is just sufficient to cause wheel slippage; then,

$$g = \frac{2{,}000\ w\ p\ r - w\ t_s}{20\ w} = \frac{2{,}000\ p\ r - t_s}{20}$$

EXAMPLE.—If 65 per cent. of the weight of a car rests on the rails under the drivers and if the coefficient of adhesion is 15 per cent., what is the maximum grade that the car can start on without wheel slippage, assuming that it requires a tractive effort of 70 pounds per ton weight of car to start on the level?

SOLUTION.—In the formula, $p = .65$; $r = .15$; and $t_s = 70$; therefore,

$$g = \frac{2{,}000 \times .65 \times .15 - 70}{20} = 6.25 \text{ per cent.} \quad \text{Ans.}$$

The wheels will slip if the car is started on a grade exceeding this percentage, assuming the conditions stated in the example.

53. Acceleration Curve.—Fig. 17 shows typical curves for an electric train equipped for rapid acceleration. Curve A shows the relation between speed and time, curve B shows the

total current supplied, and curve *C* shows the voltage. Starting from rest, the speed increases almost uniformly up to 25 miles per hour; the speed curve then bends over, thereby indicating decrease in acceleration; at 37½ miles per hour, the curve has become almost horizontal; the speed is then nearly uniform and the acceleration has become practically zero. After 93 seconds, the current is shut off; the train then coasts by virtue of the energy stored in it and the speed is gradually decreased because this stored energy has to overcome train



FIG. 17

resistance. Later, the brakes are applied and the train retarded, as indicated by the straight sloping line at the right, and finally brought to a stop. With all starting resistance in series, the total current is about 1,100 amperes; and as the resistance is cut out, the current varies as indicated by the notches in the curve during the first 10 seconds. The motors are then thrown into parallel and the total current rises to about 2,400 amperes, after which it further increases to 3,200 amperes, as the resistance on the parallel notches is cut out. Up to this point the

current through each motor and the tractive effort have remained practically constant, since the motors of each car are first in series and then in parallel. As the train resistance remains almost constant for moderate speeds, the speed is accelerated during the first 20 seconds almost uniformly from 0 to 25 miles per hour. The average acceleration during this interval is 1.25 miles per hour per second. Beyond 25 miles per hour, the current and tractive effort diminish, thereby decreasing the rate of acceleration; and when the current has dropped to about 650 amperes, the speed has become nearly uniform. The tractive effort is then wholly utilized in overcoming train resistance; during acceleration, a large part of the total effort is used to increase the speed and thereby store energy in the train, the remainder being used to overcome train resistance.

54. Tractive Effort for Trains.—When trains are composed of two or more cars, the tractive effort per ton of train is less than for single-car operation because, while the head-end air resistance remains the same in the two cases, for given speed, the weight of a long train is greater than that of a single car so that the tractive effort per ton required by head-end air resistance is correspondingly less. Each car added, however, increases the amount of surface exposed to side friction, also adding a certain amount of air friction where the cars couple together. The latter effect can be largely eliminated by solidly vestibuling the coaches in a manner to present a smooth surface where they join. The total air resistance of a train is, therefore, much less than the air resistance of one car multiplied by the number of cars. The effect of head-end air resistance can be much decreased by so shaping the head end of the train as to cleave the air and turn it off to the side.

A corrective factor of $1+\frac{n-1}{10}$, where n is the number of cars in the train, is applied to the third element of the right-hand side of the formula for the total tractive effort when train operation is to be considered. This element relates to air friction. The formula then becomes:

$$T = 50\sqrt{w} + \frac{w\,v}{25} + \frac{s\,v^2}{400}\left(1 + \frac{n-1}{10}\right) + 20\,w\,g + \frac{w\,c}{2} + 100\,w\,a$$

EXAMPLE.—A 400-ton, eight-car train operates at 60 miles per hour on a straight level track. The surface area of the head end of the train is 120 square feet. (*a*) What is the total tractive effort? (*b*) What is the tractive effort per ton weight of train?

SOLUTION.—(*a*) In the formula $w = 400$; $v = 60$; $s = 120$; and $n = 8$. As the train is operating on a straight level track at constant speed, the last three elements of the formula, which relates to grades, curves, and acceleration are eliminated. The total tractive effort

$$T = 50 \times \sqrt{400} + \frac{400 \times 60}{25} + \frac{120 \times 60 \times 60}{400} \times \left(1 + \frac{8-1}{10}\right)$$

$$= 1{,}000 + 960 + 1{,}836 = 3{,}796 \text{ lb.} \quad \text{Ans.}$$

(*b*) $3{,}796 \div 400 = 9.49$ lb. per ton. Ans.

55. It should be noted that the tractive effort, 1,836 pounds, required to overcome air resistance almost equals the effort required, 1,960 pounds, to overcome all mechanical resistance. At very low speeds, train resistance decreases as the speed increases, reaching a minimum around 5 miles per hour; the speed corresponding to minimum train resistance, however, varies and depends on the condition of the cars and track. As the speed further increases the train resistance increases rapidly, due to the rate at which air resistance increases. Head-on high winds can easily double the train resistance, while high winds from the rear have the opposite effect. The shorter a train is, the lower is the speed at which the air resistance becomes equal to the mechanical resistance, because the larger portion of the resistance due to air friction is caused by the surface at the head end of the train, and this remains the same whatever the number of cars

TABLE III

RELATION OF WEIGHT OF CAR TO SURFACE AT END

Weight of Car Tons	Area of Surface at One End Square Feet
20	90
30	100
40	110
50	120
60	120

may be, while the weight of the train, and consequently the mechanical resistance, is greatly lessened by decreasing the number of cars.

The more frequent are the stops, the greater is the percentage of total train energy input expended on acceleration; therefore, in low-speed, frequent-stop service, the trains should be light, while in high-speed service, with few stops, light weight is not so important.



FIG. 18

The approximate relation between the weight of a car and the area of the surface at one end is shown in Table III.

56. Train Resistance Curves for Single Cars and Trains.—Fig. 18 indicates the train resistance per ton for single cars of different weights; Fig. 19 gives train resistance per ton for five-car trains composed of cars of similar weights to those of Fig. 18. For example, the train resistance per ton of a single 20-ton car, Fig. 18, operating at 25 miles per hour is 17½ pounds per ton; that of a train of five 20-ton cars, Fig. 19,

at the same speed is about 7½ pounds per ton. The train resistance per ton of a single 60-ton car, Fig. 18, operating at



FIG. 19

60 miles per hour, is 22½ pounds per ton; for a train of five such cars, Fig. 19, it is about 9½ pounds per ton.

POWER FORMULAS

57. By **horsepower of operation** is meant the power required to operate a car of given weight and with certain assumptions in regard to train resistance, grades, and acceleration. The effects of curves on power requirements can usually be ignored; because, if the curves are of long radius the power is negligible, and if the curves are of short radius, not only is the speed reduced, but the headway of the car helps it to round the curve. The power may be expressed either as horsepower or kilowatts.

58. Kilowatt Input for Train Resistance.—The kilowatt input to a car operating at uniform speed on level track can be calculated from the following formula:

Let p = kilowatt input;
t_r = train resistance, or tractive effort required to overcome it, in pounds per ton;
w = weight of car, in tons;
v = speed, in miles per hour;
e = full-speed efficiency of motor equipment, expressed as a decimal.

$$p = \frac{2\, t_r\, w\, v}{1{,}000\, e}$$

EXAMPLE.—(*a*) A 16-ton car runs at a uniform speed of 16 miles an hour on level track against a train resistance of 17 pounds per ton. Assuming the efficiency of the motor equipment at full speed to be 70 per cent., what is: (*a*) the kilowatt input? (*b*) the horsepower input? One kilowatt equals 1.34 horsepower.

SOLUTION.—(*a*) In the formula $t_r = 17$, $w = 16$, $v = 16$, and $e = .7$. Substituting these values,

$$p = \frac{2 \times 17 \times 16 \times 16}{1{,}000 \times .7} = 12.4 \text{ K. W.} \quad \text{Ans.}$$

(*b*) H. P. $= 12.4 \times 1.34 = 16.62$ H. P. Ans.

59. Total Kilowatt Input for Train Resistance and Grades.—The combined tractive efforts per ton for train resistance and grade is $t_r + t_g$. The kilowatt input of a car operating at uniform speed on a grade can be calculated by means of the following formula:

$$p_{rg} = \frac{2(t_r + t_g)\, w\, v}{1{,}000\, e}$$

EXAMPLE.—A 16-ton car moves at a uniform speed of 16 miles per hour against a train resistance of 17 pounds per ton up a 3-per-cent. grade. The efficiency of the motor equipment at full speed is assumed to be 70 per cent. (*a*) What is the input in kilowatts? (*b*) What is the input in horsepower?

SOLUTION.—(*a*) In the formula, $t_r = 17$, $t_g = 3 \times 20 = 60$ (Arts. **45** and **49**), $t_r + t_g = 17 + 60 = 77$, $w = 16$, $v = 16$, and $e = .7$. Substituting these values,

$$p_{rg} = \frac{2 \times 77 \times 16 \times 16}{1{,}000 \times .7} = 56.3 \text{ K. W.} \quad \text{Ans.}$$

(*b*) 56.3 K. W. $\times 1.34 = 75.4$ H. P. Ans.


Tractive Effort lbs
4 Mile per Hour
6
8
10
12
14
16
20
25
30
35
40
Total H.P.
10% Grade
8%
6%
4%
3%
2%
1%
Level
Weight of Car-Tons
a
b
c
d
e

FIG. 20

60. Tractive Effort and Horsepower-Output Curves. The curves of Fig. 20 show approximately the tractive effort and the horsepower output of the motors required to operate a car under given conditions. The train resistance on a level track is assumed to be 20 pounds per ton, which is a safe figure for city operation. An example will serve to illustrate the use of the curves.

EXAMPLE.—What is: (*a*) the tractive effort, and (*b*) the output of the motors required to move a 16-ton car up a 3-per-cent. grade at the rate of 10 miles per hour?

SOLUTION.—(*a*) First find the point *a* on the weight data line corresponding to 16 tons; proceed vertically upwards to point *b* on the 3-per-cent. line; then horizontally to the right to point *c* on the tractive effort line; and read 1,280 pounds. Ans.

(*b*) From point *c* continue horizontally to the right to point *d* on the line marked 10 (mi. per hr.) and then vertically downwards to point *e* on the total-horse power line and read 34.1 H. P. Ans.

NOTE.—The movements for this particular solution are indicated in Fig. 20 by dotted lines.

To obtain the horsepower input, the horsepower output derived from the curves must be divided by the efficiency of the motors under running conditions selected.

61. Kilowatt Input for Acceleration.—Calculations relating to the kilowatt input for acceleration are only of approximate accuracy because they involve changing conditions of the tractive efforts during acceleration, the energy expended in the starting resistances or other speed regulating devices, and the efficiency of the motors. If the acceleration is uniform, the average speed may be taken as one-half of the final speed.

If the tractive force T_a in pounds and the average speed v in miles per hour are known and a value of the combined efficiency e of the starting apparatus and motors is assumed, the approximate value of the kilowatt input for acceleration is

$$p_a = \frac{T_a v}{503\, e}, \text{ or approximately } \frac{.002\, T_a v}{e}$$

EXAMPLE.—A 16-ton car is accelerated from rest to a speed of 16 miles per hour in 16 seconds with a tractive force of 1,600 pounds. The

combined efficiency of the starting apparatus and motors is assumed to be 60 per cent. What is the kilowatt input required for acceleration?

SOLUTION.—In the formula, the tractive force $T_a = 1{,}600$ and the average speed $v = 16 \div 2 = 8$; $e = .6$. Substituting these values,

$$p_a = \frac{.002 \times 1{,}600 \times 8}{.6} = 42.7 \text{ K. W.} \quad \text{Ans.}$$

ENERGY TESTS

INTERURBAN ROADS

62. Tests made on cars in every-day operation afford reliable data for estimating the probable energy required for a given service; such tests include observations of power, speed, time, voltage, current, grades, curves, and everything else likely to affect the energy consumption. The following figures are taken from the record of tests made with 40-foot cars each weighing 63,000 pounds complete and each equipped with two 150-horsepower motors mounted on the forward truck. The energy consumption was measured for both limited and local service so that the effect of stops could be determined.

In local service, the average speed for the whole run of 56.5 miles was 22.6 miles per hour, but part of the run was at reduced rates through cities; outside of the cities, the local-service speed averaged 26.6 miles per hour.

In limited service, the speed averaged 28.3 miles per hour for the whole run and 35.3 miles per hour, exclusive of slow running, in the cities. The speed between stations frequently rose to 40 and 45 miles per hour and on one part of the road reached 60 miles per hour. Most of the grades were less than 2 per cent., but a few short ones were as high as 3 per cent. The weight of the car with passengers was usually from 34 to 34.5 tons. The energy consumption, as indicated by the average of a large number of watt-hour-meter readings, is given in Table IV. From these figures it would be safe in making a preliminary estimate on a similar road, to allow from 70 to 75 watt-hours input per ton-mile for limited service and 85 to

90 watt-hours input per ton-mile for local service. The energy consumption in local service runs higher than in the limited service at moderate speeds because of the greater number of stops. Each stop is followed by a start with heavy accelerating current, which is required to overcome the inertia of the car weight. If the limited service had been at very high continuous speed, the energy consumption in watt-hours per ton-mile would probably exceed that for the local service because of the great effect of air resistance at the higher speeds.

TABLE IV

ENERGY CONSUMPTION OF INTERURBAN CARS

Class of Service	Kilowatt-Hours per Car-Mile	Watt-Hours per Ton-Mile
Local service, outgoing trips	2.24 to 2.78	66.7 to 81
Local service, return trips	2.62 to 3.05	77 to 89.5
Local service, average for six round trips	2.62	76.6
Limited service, outgoing trips	2.10	58.7
Limited service, return trips	2.31	71.6
Limited service, average for round trips	2.20	65.1

63. Tests made with 25-ton cars give results quite consistent with those of Table IV. The average energy consumption for regular trips at speeds varying from 8 to 29 miles per hour was 2.16 kilowatt-hours per car-mile, or 86.4 watt-hours per ton-mile. The average consumption for test runs made with speeds varying from 19 to 27.5 miles per hour, was 1.96 kilowatt-hours per car-mile, or 78.4 watt-hours per ton-mile. The greatest consumption was for a short run of 1.46 miles at a low speed of 8 miles per hour; here the energy consumption was 3.7 kilowatt-hours per car-mile, or 148 watt-hours per ton-mile.

64. A 7-ton, storage-battery car in regular service over grades ranging from 3.8 to 4.5 per cent., at 22 miles per hour schedule speed, including five stops per mile, required 63.4 watt-hours per ton-mile for a daily mileage of 110 miles with an average of seven passengers per car-mile.

65. The application of the preceding data is illustrated in the following example:

EXAMPLE.—An interurban electric road is to operate ten cars, each weighing 30 tons when loaded; six are for local and four for limited service. Local cars are to average 20 miles per hour and limited cars, 32 miles per hour. Estimate the approximate station capacity, assuming the total loss between generators and cars to be 18 per cent. of the delivered energy at the cars.

SOLUTION.—The average energy consumption, in watt-hours per ton-mile, may be taken at 72.5 for the limited cars and 87.5 for the local service. (See Art. **62.**) In 1 hr. the total number of watt-hours supplied would be:

For local service, 6 cars × 30 tons × 20 mi.	
×87.5 watt-hours.....	=315,000 watt-hours
For limited service, 4 cars × 30 tons	
×32 mi.×72.5 watt-hours.....	=278,400 watt-hours
	593,400 watt-hours

As the energy supplied to the cars in 1 hr. is 593,400 watt-hours, the power is 593,400÷1=593,400 watts=593.4 K. W. The loss in lines, working conductor, rotaries, and transformers, is 593.4×.18=106.8 K. W. The average station output must be 593.4+106.8=700.2 K. W. On an interurban system where comparatively few cars are operated, the local fluctuations are great and the maximum load may be twice the average; also, considerable energy is required for lighting and heating. In the present case, the station should be capable of furnishing at least 1,000 K. W. and to insure against shut-downs, two 1,000 K.-W. generators would be advisable; or at least three generators of 500 K. W. each, one, two, or three being operated, as occasion might require; by thus operating generators only when needed and then at or near full load, a high-load factor and greater efficiency is maintained.

CITY ROADS

66. The energy consumption per ton-mile is greater for city service than for interurban, because the cars are lighter, the tractive effort per ton greater, the stops more frequent, and, as a rule, the surface of the track is not in as good condition. In frequent-stop service, much energy is wasted in the starting rheostats. The average energy consumption per ton-mile is seldom less than 90 watt-hours and often is more.

Table V gives data of tests made on cars equipped with motors of the sizes ordinarily used in city and suburban work.

TABLE V
ENERGY CONSUMPTION OF CITY CARS

Weight of Car Tons	Horsepower per Motor	Number of Motors per Car	Kilowatt-Hours per Car-Mile	Watt-Hours per Ton-Mile
19.25	35	2	1.67	87.0
16.64	40	2	1.58	94.9
24.35	38	4	2.78	114.0
21.65	40	4	2.58	119.0
19.12	35	4	2.38	124.0
21.65	38	4	2.83	131.0
19.92	40	4	2.85	143.0
22.80	35	4	3.26	143.0
21.73	40	4	3.12	144.0
21.80	50	4	3.29	152.0
21.04	38	4	3.32	157.0
21.19	40	4	4.12	193.0

EXAMPLES FOR PRACTICE

1. If 750 pounds is required to propel a 30-ton car on a level track, what total force must be applied to propel the car up a 2-per-cent. grade?

Ans. 1,950 lb.

2. (*a*) If a car weighs 25 tons, what force must be applied to produce an acceleration of 1.25 miles per hour per second? (*b*) What must be the total force applied to produce the acceleration and overcome the train resistance as well, assuming that the latter amounts to 20 pounds per ton weight of car?

Ans. { (*a*) 3,125 lb. (*b*) 3,625 lb.

3. A certain car has 60 per cent. of its weight resting on the driving wheels and the adhesive force between track and rail is 15 per cent. of the weight on the drivers. A force of 75 pounds per ton weight of car is necessary to start the car from rest. What is the steepest grade on which the car can be started without slippage of the wheels on the tracks?

Ans. 5.25 per cent.

4. If a force of 20 pounds per ton is required to propel a 25-ton car on a level track at the rate of 15 miles per hour, the motor efficiency at that speed being 70 per cent., what is the input, in kilowatts, for the car?

Ans. 21 K. W.

METHOD OF MAKING ENERGY TEST

67. The simplest method of running an energy test on a car is to connect a watt-hour meter into the motor circuit, note the reading at the beginning of a regular run and the reading at the end of the run and take the difference, which will be the watt-hours consumed during the run. This method automatically averages the products of the volts and amperes and multiplies the result by the time in hours; but it gives no information in regard to maximum, average, and minimum volts and amperes. When such information is wanted, or when a watt-hour meter of sufficient capacity is not available, a test can be made with a voltmeter and an ammeter, the first being connected across trolley and ground and the second in the main motor circuit. Where the car equipment includes heaters, compressor, governor, electric headlights and car lights, and only a record of the energy consumption of the motor circuit is desired, either these other circuits must be kept open, or the ammeter or the current coil of the watt-hour meter must be connected only in the motor circuit.

68. The voltmeter-ammeter test consists in taking a series of simultaneous voltage and ampere readings at a certain number of seconds apart; each voltage reading is afterwards multiplied by its corresponding amperage reading and the product, watts, placed opposite in a third column of the record sheet. The sum of the voltage readings divided by their number, gives the average voltage during the test; the sum of the current readings divided by their number gives the average current during the test; and the sum of the watt readings, divided by their number gives the average watts required during the test. Table VI gives 27 of the 426 readings taken during such a test.

The following data are based on the full record of readings: Maximum voltage, 625; maximum current, 355 amperes; maximum power, 189,750 watts; maximum voltage and current readings did not occur at the same time; minimum voltage, 360; minimum current, 0 amperes; average voltage from all readings, 511; average current from all readings, 87 amperes:

TABLE VI

RESULT OF AMMETER-VOLTMETER TEST

Volts	Amperes	Watts	Volts	Amperes	Watts	Volts	Amperes	Watts
520			525	169	88,725	500	280	140,000
510			505	123	62,115	500		
480	212	101,760	475	109	51,775	540	74	39,960
515			500	98	49,000	475		
480	315	151,200	520			510		
490	175	85,750	460	154	70,840	525		
500	170	85,000	490			500	164	82,000
450	130	58,500	475	206	97,850	500		
500	84	42,000	475	107	50,825	490	150	73,500

average power, 43,112 watts, found by taking the average of all of the watt values in the complete record sheet; average of current readings, not considering the zero readings, 149 amperes; average power, considering only readings when electricity flows, 74,445 watts; duration of test, 1.7 hours; energy to drive car during complete test $= \frac{43{,}112}{1{,}000} \times 1.7 = 73.29$ kilowatt-hours; energy per hour is equal to the average kilowatts = 43.112 kilowatt-hours; weight of car, 21.19 tons; energy per ton-hour $= 43.112 \div 21.19 = 2.03$ kilowatt-hours; length of run 17.78 miles; average speed, 10.46 miles per hour; energy per car-mile $= 43.112 \div 10.46 = 4.12$ kilowatt-hours; energy per ton-mile $= 2.03 \div 10.46 = .193$ kilowatt-hour, or 193 watt-hours.

RELATION OF MAXIMUM AND AVERAGE CURRENTS

69. The maximum current taken by a car during a run depends on the manner in which the motorman handles the controller; if he moves the handle too quickly, the current may be excessive.

The average current depends on the number of times that the car must be started from rest, on the voltage, the weight of the car, grades, curves, gear ratio, and track conditions. A great number of tests under widely different conditions indicate that the maximum current is from three to five times the average current when the latter is based on all test readings, including the periods of coasting and stops.

When the energy test is made with a watt-hour meter, the result obtained directly will be the watt-hours of energy expended on the car during the test trip. If the watt-hours are divided by the time, in hours, of the trip, the result is the average power in watts. If the average watts is divided by the average voltage (ascertained by voltmeter readings or assumed), the result is the average current.

LOCATION OF POWER HOUSE

GENERAL CONSIDERATIONS

70. Purely electrical considerations would place the power-house as nearly as practicable to the center of the system in order to minimize the transmission losses. The location of water-driven stations, however, is dictated by the location of the dam, and the ideal central location of steam-driven stations is often influenced by other features that may be more important than is transmission loss. For example: The best electric location might fall in a section where office buildings would pay better dividends than many well-managed railroads. Again, the load center might fall where coal would have to be hauled at great expense or where there would be lack of water for boilers and condensers. The final selection of a power station site is a compromise of several sites governed by conflicting conditions, each of which must be considered from the point of view of its advantages and disadvantages expressed in dollars.

CENTER OF SYSTEM

71. By **center of system** is meant the center of load or traffic. A portion of the energy transmitted from the station to the distribution points is lost in the distributing system. If the conductors are too small, the loss will be excessive and the voltage at the end of the line low; the loss depends on the line resistance and on the current transmitted. The load center and geographical center seldom coincide; the location of the latter depends on the number of miles of track and on their disposition; the location of the former depends on how the load is distributed.

In Fig. 21, $A\ B$ represents 10 miles of straight level track on which 14 similar cars operate at regular intervals. The geographical, or mileage, center, is located at P as there is

5 miles of track on each side of it. Assuming equal power requirements for the cars *1* to *7* on each side of the center line *c l* the load center is also at *P*. An absolutely even distribution of load is improbable, however, due to grades, directions in which the passenger loads travel, and density of population at different points on the line. For example, heavier grades and denser traffic near *A* would bring the load center between *A* and *P*.

72. When locating a station site future extension and traffic growth should be considered. The station should be situated at a point that will be at approximately the load center of the



FIG. 21

future enlarged system, even if this location is some distance from the central position under present conditions.

73. The load center of any system can be located with sufficient accuracy for practical purposes by considering the system in sections, each with fairly uniform load distribution, and assuming that the load on each section is concentrated at its geographical center. For example, a system may consist of two lines merging at a point, as represented by Fig. 22, and the load may not be uniform on all parts of the system. The load, being fairly uniform over section *a b*, may be considered as concentrated at its central point *c*; a heavier load distributed over section *b d* is concentrated at *e*; and the uniform load of section *d f*, at *g*.

The concentrated loads should be estimated from the number of cars operating on the section and the energy requirements of each car. The loads can be expressed in horsepower, kilowatts, or in kilowatt-hours, but all must be in the same units. The relation between the loads should be noted. For instance, if load c is taken as 1 and load e is four times as great, it is called 4; and if load g is five times as great as c, it is called 5. The load center for the length of road $a\,d$ is first determined. Suppose that the distance L between c and e is 7 miles, and the distance between the center of load h and e is l miles. The



FIG. 22

center is located at such a point that the product of the lesser load 1 and the longer distance $L-l$ is equal to the product of the larger load 4 and the shorter distance l.

$1\times(L-l)=4\,l$, or $L=5\,l$; as $L=7$, $5\,l=7$ and $l=1\frac{2}{5}$ miles

The center of the concentrated load $1+4=5$ for the portion of the road $a\,d$ is at h between e and c and $1\frac{2}{5}$ miles from e.

The problem is now to find the final center of load of the whole system, which will lie between h and g. By consulting a map on which the route of the proposed road is traced, the distance between h and g may be estimated. In this case both loads

g and h have the value 5; therefore, the center of load will be at i midway on a line between h and g. If loads h and g are not equal the center of load is determined in the manner explained for determining h.

Considerations of the price of real estate, coal haulage, and water supply may cause the station to be located at other than the theoretical load center.

ENERGY COSTS

74. The cost of generating electric energy varies, because it includes items subject to wide fluctuations; in the same station the cost will be higher during some months than during others, because the load will vary both in amount and in the manner in which it is distributed throughout the 24 hours of a day. The ideal load condition would be the full station capacity, 24 hours per day 365 days in the year, and without material fluctuation. This is, of course, impracticable because of the comparatively limited demand for lights in the daytime and for power at night; conditions are considerably helped by carrying a mixed light and power load, because their maximums do not coincide. A station must be prepared to meet the maximum demand upon it. The maximum demand, however, may be active only a few hours of the twenty-four; during the time that the demand is below the station capacity, expensive machinery is absorbing interest on idle investment, and the costs of attendance and fixed charges are going on.

The *load factor*, or ratio of the average load to the maximum load, materially affects the cost of power, as shown by Table VII, giving cost per kilowatt-hour. The table is based on the following assumptions: Steam power plant of 10,000 kilowatts capacity; cost per kilowatt installed complete, $100; coal containing 12,000 heat units per pound of combustible, $2 per ton of 2,000 pounds; fixed charges for interest, depreciation, and taxes, 12 per cent. per year. This table shows that the cost per kilowatt-hour, including all charges except that of real estate, varies from 2¼ cents when the station operates with a

load factor of 10 per cent. to .6 cent when the load factor is 100 per cent. It will be noted that in all cases the cost of coal is a large percentage of the total cost.

75. The cost per kilowatt-hour, not including interest and depreciation, will lie between .65 cent and 1 cent for many steam stations; in others the total cost, including interest, etc., will lie between 1 and 2 cents per kilowatt-hour. In the largest plants the cost, including interest, etc., may be considerably below 1 cent per kilowatt-hour.

When energy is sold to one railroad company by another, a common charge is 3 cents per kilowatt-hour. Assuming that

TABLE VII

COSTS PER KILOWATT-HOUR

Load Factor Per Cent.	Cost of Coal Cent	Cost of Labor Cent	Other Items Cent	Operating Charges Cent	Fixed Charges Cents	Total Cost per Kilowatt-Hour Cents
10	.60	.13	.12	.85	1.41	2.25
25	.45	.07	.08	.60	.56	1.16
50	.40	.05	.07	.52	.28	.80
75	.38	.04	.07	.49	.21	.70
100	.36	.03	.07	.46	.14	.60

a station is equipped with the highest grade generating and economizing devices, the cost of power is strongly affected by the distance of the station from the coal mine and by labor charges.

76. In order that the total cost of generating power in a station may be analyzed and money leaks checked before they become serious, a complete record of the various costs and of the station output must be kept. To this end, every station switchboard should be equipped with at least one recording watt-hour meter for registering the station output, and it is well to provide two such meters so that one can operate while

the other is being calibrated. In case only one instrument is available, it should be checked at frequent intervals to insure correct records of energy consumption. By dividing the total cost of operation per day by the total output in kilowatt-hours, as gotten from the recording instruments, the operating cost per kilowatt-hour is obtained.

77. The fixed charges entering into the cost of generating energy consists of depreciation, interest on investment, insurance, and taxes. The depreciation in value of electric machinery depends on many conditions such as length of service, care, obsolescence, which is the quality of becoming out of date, change in load conditions making the capacity of a machine

TABLE VIII

COST OF STEAM POWER PLANTS AND EQUIPMENT

Capacity of Plant Kilowatts	Cost per Kilowatt	Capacity of Plant Kilowatts	Cost per Kilowatt
100,000	$ 60	10,000	$ 90
40,000	70	5,000	100
20,000	80	2,500	140

too great or too small, etc. Many ways of calculating depreciation are in use, the most common being to make a yearly allowance of a fixed per cent. of the first cost. The rate of depreciation is not the same for all parts of a power plant, but for practical purposes in determining the cost of energy an allowance of 5 per cent. for depreciation, 5 per cent. for interest, and 2 per cent. for taxes and insurance will generally give results approximately correct.

In estimating the first cost of a plant the figures in Table VIII will serve as a guide. These costs are fair averages for complete installations exclusive of land and buildings, for which from $10 to $20 per kilowatt must be added.

ELECTRIC-RAILWAY LINE CONSTRUCTION

OVERHEAD SYSTEMS

LINE POLES

WOODEN POLES

1. The term **line construction** as used here relates to the system of conductors and their supports installed on electric railroads for the purpose of transmitting electric energy from the substations or the low-voltage main stations to the cars. On the larger number of electric roads this system consists of some form of trolley wire supported by poles on one or both sides of the street or right of way.

2. Selection.—Wooden poles are used extensively for supporting the trolley wire and feeders on suburban, interurban, and some city roads. Poles with tops less than 24 inches in circumference should not be used except for very light work. The best poles are cut when the sap is down; to secure these, some managers send inspectors to the woods to mark consignments. Redwood is much used in the West; elsewhere cedar and chestnut, preferably second growth, are used in their natural condition. Octagonal poles are generally of hard pine; sawed poles have a better appearance than round ones in natural condition, but their life is shorter. Frequent paintings improve appearances and prolong life by keeping water out of

COPYRIGHTED BY INTERNATIONAL TEXTBOOK COMPANY. ALL RIGHTS RESERVED

checks and climber holes. Decay is further retarded by coating the ground end of the poles with coal tar or other preservative. The bases of the poles are left untreated, in order that they may absorb moisture and prevent dry rot. Creosote is commonly used as a preservative; but whatever is used, the treatment should extend above the ground line where the tendency to decay is most active.

Poles, when received, should be sorted and the best used on curves and as anchors. Table I gives data on weights and limiting dimensions of wooden poles.

3. Installation.—Wooden poles need not be set in concrete except when the soil is yielding. For poles from 25 to

TABLE I

WOODEN POLES

Length Feet	Net Weight Pounds	Minimum Circumference at Top Inches	Minimum Circumference 6 Feet From Butt Inches
25	325	24	38
30	460	24	38
35	600	24	42
40	710	24	45
45	1,075	24	48
50	1,375	24	51

50 feet long, the holes should be from 5 to 7 feet deep depending on the nature of the ground. In construction where a span wire stretched between poles on opposite sides of the street supports the trolley wire, two or three stones jammed against the pole butt on the side away from the track and two or three more near the mouth of the hole on the side next to the track, will keep the span wires from pulling the tops of the poles together. A piece of timber 8 inches by 8 inches by 3 feet may be used instead of the stones on the track side. The filler should be well tamped around the pole

during the filling, and the span wire should not be attached until the pole is firmly secured in position. On straight track and where side brackets on the poles support the trolley wire, poles should have a backward rake of 2 or 3 inches. With span-wire construction in yielding soil, the rake should be from 8 to 12 inches, according to the kind of pole foundation. To get equal rakes on all poles, a plumb or level must be used. In city work, poles are placed 100 to 125 feet apart.

METAL POLES

4. Construction.—The metal poles used in city work are usually made of three sizes of pipe telescoped together and welded, although poles made of seamless steel tube, pressed-steel parts riveted together, and latticework built up of struc-

TABLE II

METAL POLES

Style of Pipe	Diameter of Sections			Length Feet	Weight Pounds
	Bottom Inches	Middle Inches	Top Inches		
Standard.....	5	4	3	27	350
Extra heavy...	5	4	3	27	500
Standard.....	6	5	4	28	475
Extra heavy...	6	5	4	28	700
Standard.....	7	6	5	30	600
Extra heavy...	7	6	5	30	1,000
Standard.....	8	7	6	30	825
Extra heavy...	8	7	6	30	1,300

tural steel are also used. Fig. 1 shows a tubular steel pole adapted to the three types of construction. That shown in (*a*) is suitable for side-bracket work, that in (*b*) for center-pole, and that in (*c*) for span-wire construction. The method of attaching the span wire to the pole is shown in the detail





(d)

FIG. 1

sketch. Feeders are carried on iron cross-arms bolted to the pole, as in (*c*). An enlarged view of the top of the center pole is shown in (*d*). The trolley-wire hanger is flexibly supported from a short span wire stretched between brackets. Span wires are usually $\frac{5}{16}$-inch stranded steel cable. Table II gives data relating to metal poles.

5. Installation.—Metal poles are always set in concrete, for which the following is a suitable composition: Portland cement, 1 part; clean sharp sand, 2 parts; clean broken stone, 3 parts. The concrete lagging should be brought above the ground line, rounded off to shed water, and its contact surface with the pole well tarred.



FIG. 2

CONCRETE POLES

6. Construction and Installation.—Poles made of concrete reinforced by metal rods are used on some roads. They are formed by placing in a mold long iron bars separated by spacing pieces and then pouring in the concrete. These iron rods greatly strengthen the pole. Some poles are made with the mold in a horizontal position and are thoroughly dried before being placed in the hole. Others are made with the mold in a vertical position over the hole; some form of elevating device is then necessary to lift the concrete to the top of the mold. Concrete poles have a long life and withstand weather conditions better than wooden poles.

Fig. 2 shows a typical concrete pole of hollow cross-section; it is 7 inches square at the top, 14 inches square at the bottom,

and is 35 feet in length, 6 feet of which is in the ground. In the sectional view, the long reinforcing rods are indicated by circles and the spacing pieces are shown connecting them. These pieces are placed at intervals along the pole. The weight without fixtures is approximately 2,700 pounds. The concrete mixture is cement, 1 part; sand, 2 parts; crushed stone (not too large to pass through a ¾-inch screen), 3 or 4 parts.

REPAIRS AND RENEWALS

7. Repairs.—The life of tubular steel poles is not definitely known and their repair is practically limited to the results of collisions. They are exceedingly tough and difficult to bend and if bent, they are difficult to straighten. If badly bent the best procedure is to replace them. Cracked wooden poles may be sufficiently strengthened by binding with telegraph wire, the turns of which are held at intervals with staples. Another method of repairing wooden poles consists in forming around the affected length a concrete sleeve reinforced with steel rods.

8. Renewals.—Both metal and wooden poles are replaced without interruption to circuits or service by first installing, alongside the one to be replaced, another pole with cross-arms and insulators to which the wires can be conveniently transferred; the old fixtures and pole can then be removed.

FEEDERS

MATERIAL

9. Feeders serve to transmit electric energy to the different sections of the trolley wire, which is sometimes called the *working conductor*. Sizes 0000 B. S. and smaller feeders are usually of solid wire, but the larger feeders are of stranded wire. Either copper or aluminum cables bare, or with weather-proof braided insulation, are used. The bare aluminum wire

has the property of shedding sleet. Feeders, when installed in ducts, are usually in the form of stranded cables, insulated and provided with an outside covering of lead.

TYPICAL FEEDER LAYOUTS

10. The simplest feeder layout is a single wire serving both as trolley wire and feeder. With this arrangement and a heavy load, the voltage at the end of the line will probably be low. On some roads, a cable is run parallel to the trolley wire and tapped to it at intervals. Both trolley wire and feeder then serve as outgoing conductors.

When the trolley wire is divided into sections insulated from one another, an independent feeder for each section is



FIG. 3

sometimes run from the station; in other cases, several feeders are used and taps from each feeder are tied into one or more of the trolley-wire sections. An insulator directly connected to the ends of the two trolley wires serves to separate the section. The shape of this insulator is such that the trolley wheel may pass smoothly under it from one trolley wire to

the other. In such cases, if trouble occurs on a trolley section or on a feeder, only a portion of the system need be cut out of service while repairs are being made.

Switches in the feeder circuits and switches at the ends of the trolley-wire sections allow considerable flexibility in routing the current from one section of the road to another section. In case of trouble at one substation, the feeders and trolleys normally fed by that substation may be supplied with energy from the feeders and trolleys of the adjacent section of the road, which are fed by another substation.

11. In Fig. 3 is shown the general layout of substations, feeders, and trolleys for a 1,200-volt, direct-current, interurban road. The portion of the system represented by the horizontal lines of feeders and trolleys is a two-track road with two trolley wires. The portion represented by the vertical lines of trolley and feeder is a single-track road with one trolley wire. By means of the trolley switches and the feeder switches at the ends of the sections, the sections may be disconnected from each other or tied together as desired. With this arrangement, if one substation is disabled, the trolley may be supplied with current from another substation.

FEEDER SECTION SWITCHES

12. Feeder Tap Switch.—Fig. 4 shows a section switch of a type that is sometimes used to connect a feeder with a trolley section. The hinge clip of the switch is connected to the trolley wire. Opening the switch cuts the trolley section out of circuit. A fuse is sometimes installed in the switch box as shown. The box is usually mounted on a pole near the tap point of the feeder.

13. Feeder Automatic Sectionalizing Switch.—Independent feeder construction has the advantage that sections are isolated in time of trouble. Construction in which all of the feeders are connected together out on the line has the advantage that the full current-carrying capacity of all feeders is utilized so that less feeder conductor is required and

overloaded feeders are helped by the lighter loaded ones. By means of *automatic sectionalizing switches* connected to adjacent ends of trolley sections the full advantages of both systems are realized.



FIG. 4

Fig. 5 shows a layout for three feeders, in which one automatic switch is shown developed and another outlined. Trolley sections *a*, *b*, and *c* are fed from feeders controlled by switches and circuit-breakers *d*, *e*, and *f* in the power house. When circuit-breaker *f* and its switch are closed, the operating coil *g* of the relay is energized through the path including the right-hand switch blade *h* and the ground; the relay then operates and connects together the two contacts below it. When circuit-breaker *e* and its switch are closed, the operating coil *i* of the switch that bridges the line insulator is energized; the switch contacts shown below coil *i* then close and a conducting path is formed around the



FIG. 5

insulator between the ends of the trolley sections. Current may then pass from one trolley section to the next.

The current path of coil *i* includes the contacts under coil *g*; therefore, if either coil *i* or *g* is deenergized, the switch under *i* is operated and the trolley sections are separated. If a short circuit occurs on any of these sections, all of the circuit-breakers will open because the sections are tied together, and all the automatic switches immediately open and separate the trolley sections. If the trouble is in section *a*, circuit-breaker *d* will not stay closed, but the other circuit-breakers, such as *e* and *f*, may be closed. With *e* and *f* closed, the automatic switch shown on the right becomes active and joins section *b* and *c*, but the automatic switch indicated at the left is not active, because the left-hand operating coil corresponding to coil *i* of that switch does not receive current when circuit-breaker *d* is open. The automatic switch to the left of section *a* (not shown) is also inactive because the right-hand operating coil corresponding to coil *g* of that switch is deenergized; therefore, trolley section *a* is cut out of circuit.

When repairs are made and circuit-breaker *d* is closed, the automatic switches to the right and left of section *a* are closed and all of the trolley sections are again tied together.

SPLICING FEEDERS

14. Copper Wires.—Small feeders of solid wire may be joined by some form of Western Union joint as shown in Fig. 6. The wires are twisted together, soldered, and insulated with tape. A solution of resin in alcohol makes a good soldering flux for this purpose.

Large stranded copper cables may be joined by weaving the strands together as indicated in Fig. 7 (*a*) and (*b*). The copper joint should be soldered by pouring melted solder over and through it. In some cases the joints are made by soldering the ends of the cables into a copper sleeve. All splices should be taped to give insulation equivalent to that of the regular insulation on the wire. The tape covering should be painted with water-proof paint.

FIG. 6

15. Aluminum Wires.—Stranded aluminum feeders may also be joined by the method indicated in Fig. 7, except



FIG. 7

soldering is not required. The joint is made as follows: Remove the insulation from 2 feet of the ends to be spliced; open out the wires; clean and straighten them; cut out a few of the inner strands so that the final joint will not be too bulky; place the cables together as shown in Fig. 7 (*a*); then wrap all of the strands one at a time around the wires forming the core, the wires of the two cables being wrapped in opposite directions; tape and paint the joint.

16. The McIntyre joint shown in Fig. 8 is much used on aluminum wires or cables not exceeding No. 0000 B. S. in size. The ends of the wires to be joined are inserted side by side into an aluminum tube and gripped by a special tool having a groove of the same shape as the tube; the tube and contained wires are then given from $2\frac{1}{2}$ to 4 complete twists.



FIG. 8

The joint is easily and quickly made and its mechanical strength and electric conductivity are good.

17. On account of the stiffness of large aluminum cables, joints of the compression type, one form of which is shown in Fig. 9, are often used. The ends of the cable are inserted



FIG. 9

into a cast aluminum sleeve of proper size, the ends butting together in the center of the sleeve. The sleeve with its cables is then inserted between dies in a portable hydraulic jack, and sufficient pressure is applied to the dies to cause the metal of the sleeve and the metal of the cables to flow together into a solid, homogeneous mass. When tested, the cable will be pulled in two instead of the ends of the cables pulling out of the sleeve.

A modified form of the joint just described is shown in Fig. 10. Terminal pieces of aluminum are compressed on

FIG. 10

the ends of the cables at the factory. One terminal has a right-hand thread and the other terminal a left-hand thread. The ends of two cables are joined by screwing into the two terminals a right-and-left-hand threaded stud *a*, which draws the terminals into firm contact with the stud.

FEEDER INSULATORS

18. Glass insulators may be used for feeders of ordinary size. Fig. 11 shows one that is adapted for either top or side tying. The top groove is usually employed for straight-line construction and the side groove for curves and corners where the stresses that tend to break the insulator are greater.

For large feeders, insulators of the type shown in Fig. 12 are sometimes used. These are provided with metal clips

that are bent over the wire, thus holding it in position. The insulator is made of molded compound insulation, the clip



FIG. 11



FIG. 12

FIG. 13

forming part of a metal shell mounted on the top portion.

Fig. 13 shows a type of insulator used for corners only. The top part is covered by a metal shell and the cable lies in the groove at the lower portion of this cap.

TROLLEY WIRES

MATERIAL

19. Trolley wire is usually of hard-drawn copper, but tough composition wire is sometimes used on curves where the wear is heavy. The size is seldom less than No. 0 B. & S.; a few roads use No. 000 or 0000 B. & S., but No. 00 is the most common size.

Hard-drawn copper has greater tensile strength, better wearing qualities, and slightly higher resistance than soft copper; with a good feeder system the trolley carries current such short distances that the effect of higher resistance is negligible.

At curves and at other places where there is heavy wear and stresses, phono-electric wire is frequently used. This is an alloy wire; its tensile strength is 40 per cent. greater than that of hard-drawn copper wire; and its conductivity is 50 per cent. of that of pure copper.

CROSS-SECTIONS OF TROLLEY WIRES

20. Trolley wire for moderate car speeds is usually of round cross-section, Fig. 14 (*a*). An ear, forming part of a hanger used to support the wire, is either clamped or soldered to the trolley wire. With round wires there is some possibility of the trolley wheel striking the edges of the ear and temporarily separating the wheel and wire, thus causing sparking and final destruction of the hanger. By careful installation, however, the obstruction to the passage of the wheel is comparatively slight.



FIG. 14

For high-speed service, the under portion of the trolley wire should offer a perfectly smooth surface for the wheel to run on. Fig. 14 (*b*) shows a cross-section of a wire sometimes used. The upper part of the wire is gripped by the clamp ears *a*, leaving the lower part *b* unobstructed.

Fig. 14 (*c*) shows a standard form of grooved trolley wire for high-speed work. It is supported by clamp ears *a* that fit into grooves *b*. The under portion of the wire is unobstructed and the trolley wheel passes smoothly under the hanger.

SPLICING TROLLEY WIRES

21. Trolley-wire splices must be strong enough to stand heavy mechanical stresses and must offer minimum obstruction to the passage of the trolley wheels. The most common

FIG. 15

form of splice, Fig. 15, is made with a tapered tinned brass sleeve; the wires enter at each end and are bent up through

the openings *a*; the remaining space is then sweated full of solder and the ends of the wires trimmed.

Fig. 16 shows a form of mechanical splicing sleeve especially adapted to temporary or emergency work. The wires are held by the steel wedges *a*. This sleeve has requisite strength and conductivity, but offers more obstruction to the under running

FIG. 16

trolley wheel than does the soldered splice. The sleeve splice may be made anywhere on the wire circuit.

Some forms of hanger ears that are used to support the wire also serve to connect the ends of two adjacent pieces of trolley wire as explained later. This form of splicing device is used only at the point of support of the wire.

TYPES OF TROLLEY-WIRE SUSPENSION

22. Span-Wire Construction.—In Fig. 17 is shown a form of suspension known as the **span-wire construction.**



FIG. 17

Steel span wires are supported from poles located on opposite sides of the roadbed, or street, and the trolley wire is suspended from the span wires by means of insulated hangers. In case

of double track, two hangers on the same span wire are used; each hanger supports a wire over the center of its track. Feeder cables are often supported on cross-arms placed on the poles as indicated in Fig. 17.

23. Center-Pole Construction.—Center-pole construction is adapted to wide streets where the poles will not interfere



FIG. 18

with traffic; it is much used on interurban roads. Fig. 18 shows one type of center-pole construction, in which yellow-pine octagonal poles are set in concrete and a No. 000 trolley wire is suspended 20 feet above the center of each track. The hangers are attached to small, stranded-steel, span wires, which make the suspensions flexible and receive the blows of the trolley wheel as it passes under the hangers; the life of the overhead rigging is thus extended.


Local Feeder
Feeder for Distant Section
½" Truss Rod 10'-6" Long
5"
4"
24"
29"
4½"x3" Eye Bolt
1¼" Tubing
⅝" Strand
No 00 Trolley Wires
5'-6½"
16"
19'-0"
Center Line Gauge and Trolley
Cedar Pole
19'-0"
20'-0"
30'-0"
4'-8½"
4'-0"
¾" Tinned Bond
8' Oak Tie
Broken Stone Ballast
5'-6"

FIG. 19

24. Side-Bracket Construction.—Side-bracket construction is often used when the track is on one side of the street. Fig. 19 shows one type of side-bracket construction. In this case two trolley wires are used. Cars going in one direction use one wire and in the opposite direction, the other wire. At a *turnout*, which is a short length of double-track construction, one of the two wires is led to a position over one track and the other wire to a corresponding position over the other track. Feeders are carried on cross-arms and the local feeder is tapped to the trolley wires by the conductor *a*. A lightning arrester *b* is provided at intervals and is connected between the feeder tap and the ground wire *c*. Telephone wires are installed on brackets *d*.

TROLLEY-WIRE ERECTION

25. When a dead trolley wire is to be erected, it is generally unreeled under the span wires in the middle of the track and tied with temporary tie wires to the span wire. The wire is then put under tension and permanently fastened to the hangers.

When a live trolley wire is to be erected, the reel is often mounted on a flat car pushed ahead of the construction car. The wire, which is put under tension by means of the forward



FIG. 20

movement and by brakes on the reel, is immediately fastened permanently to the suspension insulators on the span wire.

26. Typical Tangent Construction.—Fig. 20 shows a common arrangement of span wires and trolley wires for a double-track road. The poles *p* are spaced about 125 feet apart along the road and between opposite poles are stretched the span wires *s*. Anchor wires *a* are provided at intervals of

about 500 feet on straight track and at the approach of curves, to hold the trolley wire in place and to prevent tearing it from the hangers if it breaks. The trouble due to the break



FIG. 21

will be localized to the length of trolley wire between the two adjacent anchor points, as the trolley wires to the other sides of these points remain firmly supported.

27. Typical Curve Construction.—Fig. 21 shows methods of securing the trolley wire at curves. In (*a*) is

shown an arrangement of guy wires *g*, called *pull-over* wires, from a single pole *p* to the trolley wire *t*. Strain insulators are shown at *k*. The straight portion of the wire at the ends of the curve is held in place by anchor wires *a*.

In (*b*) is shown a flexible method of suspension. A large span wire *s* supports the guy wires; this construction tends to equalize the stresses on the span wires and it is quite generally adopted.

A method of suspension for a double curve is shown in (*c*). In (*d*) is shown a method of suspension used for the two trolley wires of a two-track construction. The pull-over wires are connected to two heavy span wires and the pulls are made nearly at right angles to the trolley wires.



FIG. 22

28. Offset in Trolley Wire at Curves.—In rounding a curve, the trolley wire does not follow the track center line but is shifted toward the inside rail of the curve; the distance depends on the radius of the curve. The offset from the track center line is indicated in Fig. 22, in which the curve *r* is the track center line and *t* the path of the trolley wire. A set of values for the offset, indicated in Fig. 22 by the distance between the arrows, and measured at the middle of a curve of 90° arc, is given in Table III. These values may be modified to suit operating conditions.

The offset allows the trolley wheel to follow better the curve of the trolley wire than it would be if the wire followed the track center line. This feature decreases the amount of wear on the trolley wheel and the wire at curves and the tendency of the wheel to climb off the wire.

29. Trolley-Wire Tension.—Wire strung in hot weather must be allowed more sag than wire strung in cold weather, otherwise, contraction may break the wire or strain the whole overhead construction. A range of 80° F. between summer and winter temperatures corresponds to a variation of nearly

4 feet a mile in the length of the trolley wire. For a 125-foot span of No. 0 wire installed with a tension of 2,000 pounds, the sag at the center of the span should be 3.8 inches; for a

TABLE III

OFFSET IN TROLLEY WIRE

Radius of Curve Feet	Offset Inches	Radius of Curve Feet	Offset Inches
40	16	100	6
50	13	120	5
60	12	150	4
80	8	200	3

tension of 1,500 pounds, 5 inches; for 750 pounds, 9.5 inches; for 500 pounds, 15 inches. It has been recommended that for localities where the temperature does not fall below −20° F., the sag should equal three-fourths of 1 per cent. of the length of the span when the wire is strung at the ordinary temperature of 60° to 65° F. Experience has shown that for a 125-foot span if a sag of $125 \times 12 \times .0075 = 11\frac{1}{4}$ inches is allowed, the sag in the warmest weather will not exceed 15 inches.

30. Span Wires.—Span wire is usually of galvanized iron or of steel; a common size is $\frac{5}{16}$ inch in diameter and composed of seven strands of No. 12 B. W. G. In heavier construction, $\frac{3}{8}$-inch cable composed of seven strands of No. 11



FIG. 23

B. W. G. is used. Solid span wire is not recommended, but if used, should in no case be smaller than No. 1 B. & S. for No. 0 trolley wire. Span wires should be so placed that the trolley

wire will be from 19 to 20 feet above the top of the track rails. At steam-railroad crossings it may be necessary to place it higher and under elevated structures, lower than 19 feet.

31. Guard Wires.—When guard wires are used, they are generally in pairs suspended from a separate span wire; each guard wire is located about 18 inches above and to one side of the trolley wire, as shown in Fig. 23, to prevent telephone and other wires from falling on the trolley wire. No. 6 or No. 8 B. W. G. wire with weather-proof insulation is commonly used for this purpose. The installation of guard wires has ceased to be standard practice except in special cases such, for example, as at the crossing of high-tension wires over the trolley wire, because their expense is out of proportion to their utility, except under special conditions.

AUXILIARY TROLLEY-WIRE DEVICES

32. Span-Wire Insulators.—The trolley hangers are so made as to provide insulation between span wire and trolley wire, except when the hanger itself forms part of a tap circuit from feeder to trolley. With wooden poles, the hanger insulation is sufficient; with iron poles, one and sometimes two



(a) FIG. 24 (b)

span-wire insulators are usually connected to the span wire between each iron pole and the hanger, in order to improve the insulation of the circuit.

Fig. 24 illustrates a **span-wire insulator,** which is commonly known in the trade as a **strain insulator,** view (*a*) showing the exterior and view (*b*) the interior construction. The span wires are attached to metal eyes *a*, and these are insulated from each other by sheet mica and by the molded

insulation which covers all of the device except the eyes. The metal parts within the insulation are so interlocked as to withstand the stress to which they are subjected by the span wire without pulling apart.



FIG. 25

Fig. 25 shows an insulated turnbuckle that may be used to tighten and to insulate the span wire for construction using iron poles. Fig. 17 shows two of these turnbuckles in place on the span wire.



FIG. 26

33. Suspensions.—In general, **suspensions, or hangers,** consist of a body casting, which is attached to the span wire, an ear, which grips or is soldered to the trolley wire, and insulation between the ear and the body casting. Fig. 26 shows a common form of suspension with the ear removed. The body casting is shown at *a*, a screw cap that holds the insulated bolt in position at *b*, the insulated bolt that holds the ear at *c*, and the grooved arms that hold the hanger in place on the span wire at *d*.



FIG. 27

Fig. 27 is a sectional view of a body casting of a suspension very similar to Fig. 26. The insulated bolt *a* is provided



FIG. 28

with molded insulation *b*, and is held in place by the cap *c*; the bolt may be removed by taking off the cap.

34. The ears are made in many forms to suit the special work for which they are intended. Fig. 28 shows a few of

these forms. The *plain ear*, Fig. 28 (*a*), is used for straight, or *tangent*, work; the *strain ear*, (*b*), to take anchor wires from both directions as in Fig. 20; the *strain ear*, (*c*), to take anchor wires from one direction as in Fig. 21 (*a*); the *feeder ear*, (*d*), to take the tap wire from the feeder to the trolley hanger; the *splicing ear*, (*e*), to serve simultaneously as a hanger and splice in which the abutting ends of the two trolley wires pass up through the openings and are bent back; the *clamp ear*, (*f*), to clamp the trolley wire and hold it without the use of solder. All of the ears shown, except (*f*), are to be soldered to the trolley wire.



FIG. 29



FIG. 30

35. When constructing a curve, suspensions of the type shown in Figs. 29 and 30 are used; the first for construction with a single trolley wire, and the second for construction with two trolley



FIG. 31

wires in cases where a span wire or a pull-over wire must be attached to each side of the suspension. Methods of using suspensions of this type are indicated in Fig. 21.



FIG. 32

The metal castings for hangers may be of malleable iron or of brass; soldered ears are of brass; and clamp ears are usually of malleable iron, but may be stampings.

36. Frogs.—Where a line branches or at draw bridges, overhead switches or **frogs** are used to guide the trolley wheel from one trolley wire to another. Fig. 31 shows the under side of a two-way **V** frog and Fig. 32, a frog of the



FIG. 33

V type in its proper position. The span wires are attached at *a* and the trolley wires are held by clamps *b*. Frogs are also made for a right- or a left-hand turnout from a continuous straight track.

Fig. 33 shows a form of frog used at drawbridges. When the bridge is closed, a rib on the underside of the frog is in line with a similar rib on the adjacent frog, and large contact surfaces on the two frogs engage and complete the circuit.

Mechanical fastenings for the trolley wires are desirable, because they allow the frogs to be adjusted by trial for proper position. If a frog is level, the wheel will probably follow the car; if the frog sags to one side, the wheel is liable to be thrown off the wire.



FIG. 34

37. Locating a Frog.—A method for determining the position of a frog in the overhead work, indicated in Fig. 34, is as follows: From switch point *a* draw a line to the center point *b* of frog distance *c d*, and from switch point *c*, draw a line to the center point *e* on arc *a e d*. The intersection of these two lines at *f* indicates the location of the trolley frog. The lines may be laid out on the ground, the intersection

found, and a plumb-bob used to locate the frog on the wire above the intersection. Slight adjustment of the position of the frog may be made by the turnbuckles on the span wires.

38. Crossings.—At the intersection of two trolley lines, a device called a **crossing**, or **cross-over**, is installed. Fig. 35



FIG. 35

shows two forms, (*a*) for a right-angle crossing and (*b*) an adjustable crossing for any angle between 30° and 90°. Fig. 36 shows a right-angle crossing in which the conducting circuits are insulated by hardwood; this crossing is used where the two circuits are to be kept electrically separate.

39. Section Insulators.—Section insulators are placed between two trolley wire sections that are fed by separate



FIG. 36

feeders or from separate taps of the same feeder; they are also called line **circuit-breakers** or **line breakers.**

Fig. 37 shows a type of line breaker suitable for attachment to the body casting of a hanger that is connected to the span

wire. The direct line of the trolley wire is maintained by a hardwood runway, which also serves to insulate the two trolley wire sections.

40. Requirements of Line Devices.—The main requirements of all line devices are durability, simplicity, and strength. The line and its devices must be capable of withstanding

FIG. 37

violent blows from trolley poles that may fly off under a tension of 20 to 30 pounds when the cars are going 25 to 40 miles per hour. All insulation must be good, for while the leakage current over one insulator may be small, that over hundreds may be considerable and the higher the voltage the greater the energy loss corresponding to a given leakage current. The lines should be systematically inspected for minor faults, which can be remedied before they become serious.

TAPPING IN FEEDERS

41. Copper Feeders.—Fig. 38 shows a method commonly used to connect a copper feeder to the trolley wire. One end of a piece of solid or stranded weather-proof wire (No. 00 to 0000) is tapped on to the feeder, and the other end is passed through the eye of strain insulator *a*, given a few



FIG. 38

turns around itself, and attached to one end of strain insulator *b*. Insulator *b* is always placed far enough from the trolley hanger to escape blows in case the trolley wheel flies off the wire, and in some cases is placed near the pole on the opposite side of the street from the feeder. When placed as shown in Fig. 38,

ordinary steel wire is used for the balance of the span from *b*. The insulation is removed from the feed-wire at the point where the trolley-wire hanger is attached. The hanger has no insulation between the body casting and the ear and is soldered to the copper span wire. Sometimes an insulated hanger is used and the tap is connected to an ear of the form shown in Fig. 28 (*d*). The feeder and trolley wire are thus electrically connected.



FIG. 39

For connecting the tap wire to the copper feeder, any one of a number of tap joints may be used. In Fig. 39 (*a*) and (*b*), the tap wire is skinned, the strands straightened, cleaned,


FIG. 40

halved, and the two groups of wires wound in opposite directions around the feeder. In Fig. 40, the strands of the tap


FIG. 41

wire are not separated and are wound on the feeder. In Fig. 41, the tap wire is bound to the feeder by a wrapping

wire. The last two methods may be applied to either solid or stranded conductors. In all cases, the joint is soldered, trimmed, tinned, taped, and given a thick coat of weatherproof varnish.



FIG. 42

42. Aluminum Feeders. Copper tap wires are usually employed for aluminum feeders, and are soldered or clamped to them. When soldering, the feeder cable should be kept warm and its surface brightened by scratching.

Fig. 42 shows a form of clamp used to connect an aluminum feeder to a tap wire. All parts are of aluminum and the lug into which the copper tap wire is soldered, or in some cases clamped, forms a part of the clamp.

LINE LIGHTNING ARRESTERS

43. The overhead distributing system of an electric railway should be protected by lightning arresters disposed at least five to the mile and effectively grounded to the rails. Line arresters are similar to those used in station work, except that they must either be housed or adapted to exposure. The connections of a line arrester are indicated in Fig. 19 near *b*.

CATENARY LINE CONSTRUCTION

44. For high-speed, high-potential, railway work, the ordinary overhead construction is not suitable. In such construction, the trolley wire sags between supports and is lifted and bent as the trolley passes under it. Moreover, the insulation of 500- or 600-volt line construction is insufficient for the high voltages sometimes used in alternating-current railway work. To meet the requirement of high-speed railroading and high-voltage insulation, the *catenary line-construction system* was introduced.

SINGLE-CATENARY CONSTRUCTION

45. In the **single-catenary construction,** shown in Fig. 43, a $\frac{7}{16}$-inch, seven-stranded, galvanized-steel cable *a*, called a ***messenger cable***, is supported by bracket construction from poles on one side of the track or from span wires between poles on opposite sides of the track. The trolley wire *b* is suspended from the messenger cable by means of iron hangers *c*



FIG. 43

of proper lengths to maintain the wire at a uniform height above the track. The contact shoe of the pantagraph trolley attached to the roof of the car or the locomotive slides smoothly under the wire and will cause it to move but slightly. Either wheel trolleys or sliding contact shoes are used in this system of overhead construction. The messenger cable, being connected electrically as well as mechanically to the trolley wire,

serves as an auxiliary conductor. Both the cable and the trolley wire are insulated from the brackets and poles by means of either porcelain or wooden insulators.

Distances of from 125 to 175 feet between supporting poles are permissible with this type of trolley-wire suspension. In case the trolley wire breaks, it cannot fall to the ground because of the short distance between hangers.

Fig. 44 shows one form of hanger, three or more of which are commonly used between pole supports on single-catenary construction. The bronze ear is clinched on the grooved trolley wire; the hanger rod, which is screwed into the ear, has its upper portion formed into a loop through which the messenger wire passes. When the trolley of a car moves under the hanger, the trolley wire and hanger may move upwards a short distance without lifting the messenger wire. Tendency to bend the trolley wire close to the hangers is thereby lessened.



FIG. 44

46. Bracket Construction.—A bracket for straight single track is shown in Fig. 45, in which a bracket arm *a* carries an insulator *b* on which is a messenger wire *c* that supports the trolley wire *d* by means of hangers *e*.

The messenger wire sags between the supporting poles, but the trolley wire, being supported by the hangers, maintains almost the same height above the track throughout its length. The trolley wire is supported about 17 inches below the messenger cable at the poles, and the distance between the messenger cable and the trolley wire gradually decreases toward the center of the span between the poles.

47. Single brackets for curves on single track with the poles on the inside of the curves are shown in Fig. 46. Extensions of the bracket arms support a span wire called a *backbone wire*, to which *pull-off bridles* attached to the top and



FIG. 45



FIG. 46



FIG. 47

bottom of the hangers are fastened. The trolley and messenger wires are thus made to conform approximately to the curve of the track.

When the poles are on the outside of the curve, the span wire is supported by the poles, the bracket extensions are omitted, and the pull-off bridles are connected between the hangers and the span wire.

Fig. 47 shows a method of construction for a double-track curve with double brackets provided with extensions at one end that support a backbone wire to which the pull-off bridles from both sets of trolley and messenger wires are attached.

On curves of large radius, and at intervals of about 440 feet on a straight track, a supplemental rod made of hardwood is attached to the bracket arm at one end and to a clamp secured to the trolley wire at the other end, as shown in Fig. 48, thus serving to keep the catenary structure in an upright position. A bracket thus equipped is called a **steady-strain bracket.**

Fig. 49 shows another method of holding the messenger wire and trolley wire in the same vertical plane. The messenger wire *a* is supported on an insulator mounted on the bracket. The

trolley wire *b* is supported on a short span wire between the pole and the end of the bracket arm.

48. Feeder Tap for Bracket Construction.—Fig. 50 shows a method of connecting the feeder tap. One end of



FIG. 48

the tap wire is connected to the feeder, the wire supported by insulators on the pole and bracket arm, and its other end connected to a clamp on the trolley wire.



FIG. 49



FIG. 50



FIG. 51



49. Bracket Anchor Construction.—Both messenger and trolley wires should be anchored every ½ mile for straight track and at all approaches to curves. Fig. 51 shows one method of anchoring for bracket construction. Anchor bridles, attached to the end of a bracket but insulated from it, are clamped to both the trolley wire and the messenger wire, and the bracket is guyed to adjacent poles each way. In some cases, these bridles are fastened to pull-off hangers instead of to separate clamps.



FIG. 53

50. Span-Wire Construction and Anchorage on Straight Track.—Fig. 52 shows a method of span-wire construction and anchorage used for straight tracks. The messenger wire is supported by a loop at the lower end of an insulated hanger, one type of which is shown in Fig. 53. The trolley wire is supported by hangers from the messenger wire as shown in Fig. 52. The method of anchoring the wires is shown near the middle pair of poles, Fig. 52.

In order to preserve the alinement of the messenger and trolley wires, bridles, Fig. 54, are connected at intervals between backbone wires and the top and bottom of pull-off hangers. The backbone wires are connected between adjacent poles.

51. Span-Wire Construction on Curved Track. Fig. 55 shows span-wire construction for curved double tracks.



FIG. 54

The poles to which the backbone wires are connected are on the outside of the curve and are guyed, in order to withstand better the stresses of the pull-off bridles.

52. Span-Wire Construction With Bridges on Curved Tracks.—Span-wire construction for curved double tracks where bridges are used instead of poles is shown in Fig. 56. The upper of the two messenger wires for each trolley wire is supported on insulators at the top of the bridges



FIG. 55

and is clamped to the lower messenger wire. The trolley wire is supported by span wires at the bridges and by hangers from the lower messenger wire between the bridges. The pull-off bridles are connected to lattice poles placed at points between the bridges and on the outside of the curve.

DOUBLE-CATENARY CONSTRUCTION

53. A form of double-catenary construction is used to a limited extent, notably on a portion of the main line of the New York, New Haven, and Hartford Railroad. It is more expensive to install than the single-catenary system, but holds the trolley wire from swaying better than the single-messenger



FIG. 56

wire construction. Steel bridges spanning the tracks, or a form of substantial span construction from lattice poles on the sides of the roadbeds, support the messenger wires *a*, Fig. 57. Triangular hangers support conductor *b*, and to this is connected the trolley wire *c* by means of short hangers *d*. The hangers *d* are placed midway between the hangers supporting wire *b*, thus allowing a slight vertical movement of the wires *b* and *c* with but little change in position of the catenary system as a whole.

54. Adjacent to and under low bridges, double-arm clips connected to the lower hangers support the two conductors *b*



FIG. 57

and *c* of Fig. 57 in the same horizontal plane, as shown in Fig. 58.

At intervals are provided anchor bridges to which the ends of the messenger cables are securely fastened through massive insulators.

55. At the ends of trolley sections, the two trolley wires, about 16 inches apart, are run parallel for a short distance, but are insulated from each other. The broad sliding shoe on the type of trolley used makes contact with the wire of one section before breaking contact with that of the other section.

56. To insure that the sliding trolley shoe will pass smoothly over the junction of the main trolley wire and turnout trolley wire, *deflector wires* are placed in the angle formed by the two wires, as shown in Fig. 59, in which the two trolley wires



FIG. 58

are shown at *a* and the deflector wires at *b*. The illustration shows the junction of the trolley wires of a single- and a double-



FIG. 59

catenary system. When wheel trolleys are used exclusively, the deflector wires are unnecessary.

HINTS ON INSTALLATION

57. When wheel trolleys are used and the speed of the car is from 40 to 50 miles per hour, three hangers between messenger-wire supports usually result in satisfactory service. The number of hangers may, however, be from two to eleven according to the length of the span, the weight of wire to be

supported, the kind of trolley used, and the speed of the car. The greater the number of hangers, the less the sag in the trolley wire, and the straighter the trolley wire for a given tension applied to it.

58. Tension of Wires.—If the messenger and trolley wires in the single-catenary construction are installed with correct tensions, the wires tend to keep in the same vertical plane. With insufficient messenger tension, the upward pressure of the trolley wheel acting through the trolley wire and the hangers

TABLE IV

MESSENGER AND TROLLEY-WIRE TENSIONS

Temperature Degrees F.	Messenger-Wire Tension Pounds	Trolley-Wire Tension Pounds
10	3,400	3,620
20	3,160	3,360
30	2,930	3,100
40	2,680	2,850
50	2,400	2,600
60	2,200	2,340
70	2,000	2,100
80	1,890	1,840
90	1,780	1,600
100	1,690	1,340

will force the messenger wire to one side, thereby allowing an increase in the upward deflection of the trolley wire and making the wheel liable to strike an ear. This may also occur when the trolley wire is too slack, for then the upward pressure of the wheel rotates the trolley wire around the messenger as a center.

Correct tension for messenger and trolley wires, to obtain proper sag in the messenger wire, has been determined for the usual temperature variations and span lengths. Table IV gives data for a 150-foot span and for No. 0000 grooved trolley wire hung from $\frac{7}{16}$-inch steel messenger cable.

59. Lengths of Hangers.—The messenger cable should be installed with uniform tension throughout its length, therefore the short span should have less sag than the long ones. For this reason definite line-pole spacings have been adopted and the lengths of the hangers proportioned accordingly.

Fig. 60 indicates the hanger lengths used in three-point construction for spans varying from 80 to 150 feet. These lengths are based on the assumption that the maximum distance between the messenger cable *c* and the trolley wire *d*, Fig. 45, is 22 inches at the point where the messenger-wire insulator *b* supports the messenger wire.



FIG. 60

For shorter spans two-point construction is used and the length of the hangers proportioned to suit the span. For a 70-foot span and two-point suspension, two 20½-inch hangers would be used.

When the standard hangers prescribed for given span lengths are used and the messenger wire adjusted to hold the trolley wire at a uniform distance above the track, the messenger cable will have the correct tension.

60. Size of Wires.—The trolley wires in common use are Nos. 00000 and 0000. For ordinary conditions, the messenger wire is $\frac{7}{16}$-inch, extra-galvanized, steel cable; the anchor wires, $\frac{3}{8}$-inch steel cable; and the pull-off wires, $\frac{1}{4}$-inch steel cable.

61. Insulation of Wires.—Voltages from 600 to 11,000 are employed on roads equipped with the catenary trolley construction. The messenger cable must, therefore, be very thoroughly insulated from the supporting poles or bridges, and

massive insulators are used for this purpose. Smaller insulators are used with the span wires, anchor wires, guy wire, etc. Both porcelain insulators and wooden rods are employed for insulating purposes.

62. Installing the Wires.—The bracket arm should be located 18 inches above the desired position of the trolley wire in single-track construction, and 16 inches above the trolley in double-track construction; the additional 2 inches for the single bracket is allowed for sag of the end of the bracket due to the yielding of the pole when the bracket is loaded.

Generally, this construction does not require back guys on straight work; but on curves and at all anchor points, all



FIG. 61

poles should be guyed. It is recommended that strain insulators be used in all guy wires.

With brackets and messenger insulators in place, the trolley and messenger wires are both run out and hung over the brackets, except at curves where the messenger wire is run over the bracket arms and the trolley wire supported below them; the trolley is then pulled tight and temporarily anchored.

It is generally inconvenient to measure the tension of the trolley wire in course of installation. The desired tension of about 1,000 pounds for 0000 wire can be secured if the pull is made with a pair of three-sheave blocks, Fig. 61, and a "luff," or purchase, with a pair of two-sheave blocks. Two strong men can pull the wire to about the right tension with this arrangement of blocks. The messenger wire should next be adjusted for tension to give the sag *a*, Fig. 62, of 9 inches at 30° F.; 10 inches at 60° F.; and 11 inches at 85° F.; after which it may be lifted on to the messenger insulators and tied. The trolley wire should then be dropped off the ends of the

bracket arms and temporarily supported by hooks from the brackets and from the messenger wire at the center of the span; the line will then be ready for the hangers to be installed. Both messenger and trolley wires should be anchored every ½ mile on straight track and at all approaches to curves. Sufficient slack should be left in the curves to allow the messenger and trolley wires to be pulled to proper position over the track. Where bridles for pull offs and anchor wires are used, care should be taken to see that no wires are allowed within a space 6 inches above the horizontal plane of the



FIG. 62

trolley wire at a distance of 3 feet either side; this clearance is necessary to avoid interference should sliding contacts be used.

63. In span construction, the span wire should be so installed that when the weight of the messenger and trolley is put on it, there will be a sag of about 1 foot for each 20 feet of span. The back guy wires that run from the tops of the poles to the ground, thus preventing the tops from being pulled toward each other, should be insulated for the full line potential. After the poles are guyed and the spans are in place, the messenger and trolley wires are run out and are hung temporarily from the span wires by hooks. Tension is then applied to the trolley and messenger wires and the installation of the hangers may then proceed as in bracket construction.

THIRD-RAIL SYSTEMS

64. Rail Location.—The conductor, called the *third rail*, or the *contact rail*, from which current is taken for the cars in the third-rail system, is an iron rail mounted a short distance from the ground and to one side of the track rails. A **T** rail is commonly used, but rectangular and **U**-shaped rails are employed to a limited extent.

At grade crossings, the third rail is omitted, as the momentum of the car is sufficient to carry it over the gap in the conductor rail. In the case of a train, the shoes on the first car will make contact with the forward section of the third rail before the shoes on the rear cars have left contact with the other section of the rail.

On double-track roads, the two contact, or third, rails are usually placed between the tracks; on single-track roads the third rail may be placed first on one side and then on the other of the track, according to convenience; since all cars have collector shoes on both sides this is permissible. The relative position of track and third rail is largely determined by the clearance required by rolling stock. Where steam locomotives also operate on the road, their cylinders govern the limiting clearances. One recommendation for position is that the vertical center line of the third rail and the gauge line of the nearest track rail, which is a vertical line drawn on the inside edge of the head of the rail, should be 2 feet 3 inches apart and that the top of the third rail should be $3\frac{1}{2}$ inches above the plane of the tops of the two track rails. These relations are, however, not always observed.

Fig. 63 shows a typical third-rail construction. A plan view is shown in (*a*), an end view in (*b*), and a side view in (*c*). The third rail *r* is, in this case, an ordinary **T** rail weighing 80 pounds per yard. It is supported on reconstructed granite insulators *a* located on every fifth tie, which is about 2 feet longer than the other ties.

65. Rail Weights.—The weight per yard and the contact surface of the third rail depend somewhat on the current to be collected. Weights of less than 60 pounds per yard are seldom used except for light traffic; more often the weight of the conductor rail is about the same as that of the track



FIG. 63

rails. Third rails are often made in 60-foot lengths, in order to lessen the number of bonded joints that are required.

66. Rail Insulators.—The third rail is supported on insulators that allow for expansion or contraction of the rail. Specially treated wooden blocks provided with iron caps to hold the rail have been used, but in the best construction reconstructed granite or porcelain has been adopted.

Fig. 64 shows three granite insulators; in (*a*) and (*b*), the rail rests on an iron cap and is held by the lugs; in (*c*), it rests on the granite block and is kept alined by special castings held by a bolt passing through the granite body. The castings should allow some vertical play to avoid undue stresses on the

insulators. Third rails for 1,200-volt, direct-current, railway systems require better insulation and protection, but in general the method of mounting is similar to the ordinary construction.



FIG. 64

67. Rail Protection.—On many roads the third rail is exposed, but the present trend is toward protection that will prevent accidental contact between the third rail and ground or track rails and at the same time prevent the accumulation of snow or sleet on the rail.

Fig. 65 shows a method that has been used on elevated roads; planks parallel to the rail and projecting about 2 inches above it, prevent contact by anything accidentally dropped across it; but this arrangement does not prevent accumulation of sleet and snow.

In Fig. 66 is shown a type of substantial third-rail protection that is sometimes used in subways.

The type of protected third rail used in the electric zones of some large steam railroads is shown in Fig. 67. The rail is of the bullhead, under-running type. The car shoes are pressed upwards against the lower surface of the rail by shoe springs.



FIG. 65

The method of supporting the third rail is shown in greater detail in Fig. 68. The iron bracket *a*, located at intervals of 10 feet, supports the semiporcelain insulator blocks *b* that fit around the third rail *c*. A steel hook bolt *d* passes around the insulator and through a lug on the top of the bracket. Lugs on both the bolt and the bracket fit into vertical and horizontal grooves in the insulator blocks and thus hold these blocks in position.

The rail between the brackets is first covered with flexible-fiber sheathing and further protected by means of a top strip and two side strips of yellow-pine boards. With this thorough protection, there is but slight chance of an accidental connection between the third rail and the ground or the track rail. The rail is also protected from snow and sleet.

The third rail is anchored at frequent intervals by means of bolts, Fig. 69, that pass through the rail and wooden insulator blocks mounted on each side of a regular semiporcelain insulator, similar to *b*, Fig. 68.


FIG. 66

68. Connections of Third Rails at Highway Crossings.—At public highway grade crossings and at turnouts in the track system, the line of contact rail must be broken and connections must be arranged between the two sections of rail thus formed by means of either an

overhead or an underground cable, usually called a **jumper.** The connection is nearly always made by means of an under-



FIG. 67

ground cable, which can be made short and direct. Fig. 70 shows a typical crossing. The contact rail *a* is provided with



FIG. 68

cast steel, inclined approach blocks *b* that allow the shoes to glide on to the rails without shock. A cable is attached to



FIG. 69

the rail at *c*, and it is carried underground to *d*, where it connects to the rail again, thus preserving the continuity of the

conducting system. The cable should have a cross-section equivalent, in carrying capacity, to that of the rail. For this purpose, 1,000,000-circular-mil, lead-covered, paper-insulated cable is often used.

69. The jumper cable must be thoroughly insulated from the ground, in order to prevent leakage current. There are various methods of installing jumpers, one of which is shown in Figs. 71 and 72. In this case the cable is drawn into a



FIG. 70

black, bituminized, fiber tube, which is laid in solid concrete. A concrete or a terra-cotta cap protects the top of the cable, and flexible leads connect the cable to the third rail. In case it is desired to have independent jumper cables for the two sets of third rails on a double-track road, another cable can be installed in the second fiber tube, Fig. 71.

70. Sleet Troubles.—When sleet gathers on the third rail or when rain freezes as it strikes the cold rail, there is formed on the surface a non-conducting film of ice that often

results in delays in the operating schedule. The sleet is difficult to remove, but is easy to prevent if rail cleaning devices are



FIG. 71

promptly applied. At complicated special work, it is customary to use salt freely, and in some cases large special blow torches burning crude oil have been used to heat the rail; on straight rail some form of sleet brush hung from the car trucks is depended on to keep the rail surface clean. At the least prospect of trouble, the rail should be swept frequently, even if extra cars must be run. Fig. 73 shows one type of sleet-cutting device. It is fastened to an extension of the collecting-shoe beam; the cutter consists of steel plates *a*



FIG. 72

cast into a block *b*, and set at an angle so that they will slide over projections at joints. A flat spring *c* presses the cutter against the rail and a cam *d* operated by lever *e* holds the shoe up when it is not in use; by moving lever *e* to one side the shoe can be lowered by the motorman.

71. Third-Rail Leakage.—The current leakage per mile of rail is negligible where precautions are taken to avoid it; the leakage from a poorly insulated underground cable at a crossing may easily exceed that of several miles of third rail.



FIG. 73

Tests on a section of third rail disconnected from all crossing cables showed leakage varying from .057 ampere per mile, after a 20-hour rain, to .023 ampere per mile in hard freezing weather with a light snow on the track. Tests of the whole road, including crossing cables, showed an average leakage of about .5 ampere per mile, and an investigation located the greater part of this in defective insulation of crossing cables. The third-rail insulators in the case under test were of specially prepared wood with iron caps.

CONDUIT SYSTEMS

72. Construction.—Owing to their great first cost, conduit systems are installed only where city ordinances prohibit any other form of construction. Theoretically, both sides of the line are insulated from the ground; as a matter of fact, one side of the line or the other is generally grounded enough to nullify this advantage.

Fig. 74 shows the conduit construction used in New York, which may be taken as typical of this class of construction. The rails are supported on heavy cast-iron yokes *a* spaced 5 feet apart; every third yoke has handholes and carries the insulators *b* that support the conductor rails *c* every 15 feet.

Fig. 75 shows a section through one of the handhole yokes and illustrates the method of supporting the conductor rails. The conduit between yokes is made of concrete filled in around a sheet-iron form that is afterwards removed. The conduit may be lined with steel plates or may be constructed of concrete alone. Each manhole connects to the sewer through a 6-inch drain pipe. The outgoing and return feeders are run in terra-cotta ducts *d*, Fig. 74. To facilitate the installation of new feeders or the repair of old ones, duct manholes are provided every 400 feet. The yokes are designed to stand the pressure of the earth (packed down by the heavy traffic) and also the pressure due to freezing of the soil in cold climates. Cast-iron, steel, and wrought iron have been used, but cast iron is the most common. Light-weight yokes gave much trouble from breakage, so castings weighing from 200 to 400 pounds have been adopted. In some cases, the metal yokes have been replaced with concrete, but the best construction calls for the heavy metal yokes.

73. Operating Features.—Mud accumulates in the main conduit, which must be cleaned about once a month in the summer and oftener in the winter. With special scrapers the





Half Section through Hand-hole Yoke.



Section between Yokes.

FIG. 74

mud is drawn into the yoke manholes from which it is removed. The conductor rails are divided into insulated sections about 1 mile long and each section has its own feeder, so that trouble on one section does not interfere with traffic on others. As each feeder includes its own switch and automatic circuit-breaker, if two grounds occur in a section, its circuit-breaker opens and the power-house attendant can locate the defective section. Separate sections supplied by individual feeders have the advantage that in case of a block on the road, the simultaneous efforts of all motormen to start their cars cannot overload the station, because the switchboard attendant has all sections under his control and can compel the starting of the cars one section at a time.



FIG. 75

TRACK CONSTRUCTION

ROADBEDS

HINTS ON CONSTRUCTION

1. Definitions.—A **railroad** consists of the *foundation*, the *ballast*, and the *track*. The foundation consists of the earth support, the top of which is called the *subgrade*. The ballast rests on the subgrade and consists of broken stone, gravel, sand, cinders, or slag. The ballast serves to hold the ties, rails, and connecting-rods that constitute the track in position and helps to drain the moisture from the surface of the roadbed. The name *roadbed* is given to the arrangement of ballast, concrete, paving blocks, etc. that is built on the subgrade and holds the track.

2. City Roads.—Through improved city districts, the location of the roadbed is fixed by street limits and city ordinances. The tracks should be so located that the maximum car overhang on straight track or on curves will not cause interference between cars or with any fixed object near the tracks.

On paved streets the rails are generally supported by wooden ties though metal ties are sometimes used, and in rare cases ties are omitted and the rails supported along their length by stringers of wood or of concrete.

3. Interurban Roads.—On interurban roads in undeveloped districts, steam-railroad construction of the roadbed

COPYRIGHTED BY INTERNATIONAL TEXTBOOK COMPANY. ALL RIGHTS RESERVED

can be followed closely. Some roads require very expensive construction and others, on account of natural conditions, may be spared most of this expense. When crossing swamps and marshes, it may be necessary to effect thorough drainage in order to obtain a solid foundation that will not yield under heavy cars; on a yielding track a heavy car pushes a wave of rail ahead of it, thereby increasing the resistance to train motion. Before building across marshes or lowlands, soundings should be taken to determine whether the foundation must be supported on piles. In general, where the subsoil is yielding, the substructure must be more substantial and have more area exposed to subsoil. In steam-road construction, instances are recorded in which sections of improperly constructed road disappeared under water.



FIG. 1

The subgrades should be crowned, or graded downwards from the center to the sides, to help drainage, and should be sufficiently wide at the top to support ballast around the ends of the ties. The lines of the grades in undeveloped districts in the suburbs of cities should be given by the city engineers, to avoid the expense of later raising or lowering the tracks.

In allowing clearances between the cars and the walls and roof of tunnels and bridges, the height of the car, including trolley stands, ventilators, and stove pipes must be considered; and where margins are close, measurements must allow for possible increase in the sizes of car wheels to be used. Failure to consider such points may cause great expense for later changes.

TYPICAL ROADBEDS

INTERURBAN ROAD

4. In Fig. 1 is shown a cross-section of a roadbed construction for an interurban double-track road. The right-hand half of the figure represents the construction used for a cut or on the side of a hill. The construction for an embankment is shown at the left. The subgrade is crowned to promote drainage, and ample provision for ballast is provided at the ends of the wooden ties. Most of the measurements refer to the center line of the double roadbed.

CITY ROADS

5. For city construction, a trench is excavated in the street wide enough for the single or double track. In the construction shown in Fig. 2, only one-half of a double-track roadbed is



FIG. 2

indicated. The trench for both tracks is 18 feet wide and 23 inches deep. The bottom is rolled and the trench partly filled with 2-inch broken stone; soft spots in the rolled surface are dug out and also filled with stone or other solid material. The stone is rolled until it is firm at a depth of 8 inches. On this ballast are laid the wooden ties, 6 in. × 7 in. × 7 ft. 6 in., a little less than 2 feet between centers, except at the rail joints, which are supported by three ties about 15 inches between centers; 60-foot rails are then laid on the ties, ends butted and joints staggered; before joining, the ends of the rails and the

joint plates are well cleaned. The rails are then coupled, the plates bolted tight, brace plates installed every other tie, the ties lined up and spiked to the rail. The track is then lined and surfaced and the space between the ties filled with broken stone well tamped to the top of the tie. The rail is then finally lined, the joints secured, and the broken stone or concrete brought up to the proper surface for the asphalt pave.



FIG. 3

6. Fig. 3 shows a roadbed construction for a weak subsoil. A trench 36 inches deep and the width of the tracks is dug and filled to a depth of 29 inches with successive layers of 12 inches of hard earth and rock well beaten down; 10 inches of earth, pebbles, clay, sand, and rocks, well tamped, and 7 inches of concrete. Hard pine ties 6 in. × 8 in. × 8 ft., treated with asphalt, are laid on the concrete, and these support 80-pound T rails. More concrete is then added to form the surface for the asphalt pave.

7. Fig. 4 shows a roadbed construction in which granite blocks are used for the street surface. The wooden ties, spaced 3 feet between centers, are embedded in concrete. A layer of sand on the concrete serves as a bed for the granite paving



FIG. 5

blocks. The spaces near the web of the rails are filled with cement mortar.


10'-2" Track Centers
4'-8½" Gauge
5'-5½"
4'-8½" Gauge
Paving to be ½" Below Head of Rail
City Paving Grade Line
Paving to be ½" Above Lip of Rail
Grade
Standard Tie Rod 2"X⅞"X15'-0"
Paving at Rail to be ½" Below Head of Rail.
½" Crown
Sand
Cement Mortar Portland Cement 1 Part Torpedo Sand 3 Parts
Grade
Grade Line
Concrete
Tie 6"X8"X7'-0"
7'-4"
1'-5"
1'-5"
3'-8"
4'-3"
9'-4"
9'-4"
SECTION A-A
CROSS-SECTION
SECTION B-B
Concrete. Portland Cement 1 Part Torpedo Sand 3 Parts Crushed Stone 6 Parts
Granite Blocks
Sand
Concrete
3'
LONGITUDINAL SECTION C-C

FIG. 4

In other construction, bricks or blocks are shaped so that they fit against the web and lie partly under the head of the rail. Cement mortar is poured over the brick or block paving to hold all parts together.

Fig. 5 shows a construction in which steel ties are used. Concrete is used under the ends of the ties but is not necessary under their middle portions.

THE TRACK

TIES

8. Wooden Ties.—Ties are the wooden or metal supports to which both rails of a track are fastened. The ties are laid at right angles to the rails. Wooden ties are shown and their position indicated in Fig. 4. The woods most used for ties are block locust, red cedar, cypress, oak, chestnut, pine, hemlock, and spruce, here given approximately in the order of their life untreated and under average conditions. The life of untreated ties varies from 4 to 10 years according to the wood and climatic conditions.

Ties for standard gauge road (4 feet 8½ inches) are usually 6 in. × 8 in. × 8 ft.; in third-rail construction, the insulator ties are about 2 feet longer. Wooden ties are generally spaced from 2 to 3 feet between centers. Heavy T-rail construction requires the closer spacing and roads designed for light traffic the wider spacing. Economy in tie spacing, however, may under some conditions be false economy because of excessive wear and tear on rails and rolling stock. Completely embedded ties deteriorate more rapidly than ties partly exposed. If stone ballasted, their life is longer than when buried in soil, because of better drainage.

9. Preservation of Wooden Ties.—The life of a tie can be prolonged by treatment with preservatives applied by dipping, boiling, or vacuum impregnating; in any case the tie should be heated before being treated, to dry it and to expel

part of the air. Zinc chloride or creosote are the preservatives generally used.

One method of impregnating ties with creosote is as follows: The ties are placed in an iron tank, from which the air is then partly exhausted by means of a vacuum pump, thus withdrawing air from the pores of the ties. When the gauge shows a constant degree of vacuum, creosote is admitted to the tank. The creosote fills the empty pores and penetrates the wood, the distance depending on the hardness and condition of the ties, but always far enough to do much good. The process is helped if a pressure of 50 to 100 pounds per square inch is applied after the creosote is admitted to the tank. The pores being filled, moisture is excluded from the wood, and decay is thus retarded.

10. Steel Ties.—Increasing scarcity and the cost of suitable timber for cross-ties has led to many experiments with concrete, concrete and metal, and all-metal ties. Steel ties have proved most satisfactory and many miles of track with such ties have been installed. Among the advantages of steel ties are:

1. Ability to maintain correct track gauge. Steel ties can be punched accurately, and bolt clips hold the rails permanently in place, provided the nuts on the bolts are tightened occasionally. With wooden ties, frequent spiking is necessary to prevent rail spreading.

2. The useful life of steel ties is nearly three times that of wooden ties; renewals, including new ties and disturbance of the roadbed to place them are correspondingly less frequent.

3. Steel ties and rails are practically integral and the lower tie flanges are sometimes crimped so as to minimize creeping of tracks.

4. After serving approximately three times the useful life of wooden ties, steel ties have a scrap value of from 40 to 50 per cent. of their original value, resulting in some financial gain by the use of steel ties.

5. Uniformity of spans of rails between steel ties equalizes rail deflections, resulting in smoother riding than with the unequal spans over wooden rails.

11. Steel ties are made of open-hearth steel of about structural-steel grade. They can be obtained of manufacturers



FIG. 6

who furnish the ties in any lengths, accurately punched to gauge if desired, and also dipped in coal tar to prevent rusting if such treatment is deemed advisable.

Fig. 6 shows a steel tie punched to support an 80- or a 100-pound rail; the inner pair of holes is forthe lighter weight rail, and the outer pair for the heavier. The left-hand section is taken through the part of the tie where the lower flange is straight, and the right-hand section through the part where the lower flange is crimped. The crimped portion in conjunction with the ballast tends to prevent the rails and ties from creeping. Under heavy traffic conditions and on grades, the tracks used by the descending trains should be equipped with the crimped ties, since when the brakes are applied, the moving train tends to drag the track along with it.



FIG. 7

12. Methods of Fastening Rails and Steel Ties. Fig. 7 shows the fastening devices for intermediate ties, and

Fig. 8 those for ties near a joint. Similar letters refer to corresponding parts in the figures. The shoulders on steel clips *a* bear against the rail *b* and the clips are secured to the tie *c* by bolts *d*, lock washers *e*, and nuts *f*.

In Fig. 8, the two splice bars that fasten the ends of the rails together are shown at *g*. Some types of splice bars are stengthened by a projection under the rail beneath the joint, as shown by the dotted lines in view (*a*). In order to avoid drilling special bolt holes in the ties near rail joints, slots are provided in the splice bars permitting the clips to be placed the same as on intermediate ties between joints; these slots aid in preventing creepage of the rails. In the absence of such slots, special clips more widely spaced than normal may be used to hold the joints in position on the adjacent tie.



FIG. 8

RAIL AND TIE ACCESSORIES

13. Tie-Plates.—Pounding, expansion, contraction, and creeping of rails tend to wear wooden ties immediately under the rail. As tie-plates increase the wearing surfaces and decrease the wear, thereby adding to the life of the tie and to the permanency of the track, they are desirable, especially for comparatively soft-wood ties. Fig. 9 shows a common form of plain tie-plate and also shows its position on the rail.

14. Tie-Rods.—Tie-rods are used to hold the two rails of a track to gauge. The method of installing them is indicated in Fig. 5. In some cases, a tie-rod is placed every 4 feet of single track and in other cases the tie-rods are 10 feet or more

apart, depending on the type of roadbed. In general, the farther apart the ties are, the closer should be the tie-rods.



FIG. 9

The shoulders of the tie-rods are such a distance from the ends that the rods may be placed in the holes in the rails after the rails are spiked in position, and nuts are then tightened against each side of the web of each rail.

15. Rail Chairs.—In some cases, rails that are too low to accommodate paving are raised to the desired height by rail chairs, one type of which is shown in Fig. 10; the chairs are spiked to the ties.



FIG. 10

16. Brace Tie-Plate. Another device to keep the rails to gauge, especially on curves, is the brace tie-plate, types of which are shown in Fig. 11. View (*a*) shows a brace for one side of the rail, (*b*) shows a double brace, and (*c*) shows types designed for T rails. Since the top of the braces bears against the head of the rail, the effect of any force tending to turn the rail is lessened.



FIG. 11

TABLE I

MODIFYING CONSTITUENTS OF STEEL RAILS

	Rails Weighing From 50 to 60 Pounds a Yard	Rails Weighing From 61 to 70 Pounds a Yard	Rails Weighing From 71 to 80 Pounds a Yard	Rails Weighing From 81 to 90 Pounds a Yard	Rails Weighing From 91 to 100 Pounds a Yard
Carbon	.35 to .45	.35 to .45	.40 to .50	.43 to .53	.45 to .55
Phosphorus, not over	.10	.10	.10	.10	.10
Silicon, not over	.20	.20	.20	.20	.20
Manganese	.70 to 1.00	.70 to 1.00	.75 to 1.05	.80 to 1.10	.84 to 1.14

RAILS

RAIL COMPOSITION

17. Track rails are of mild steel that contains low percentages of carbon, manganese, and silicon and lower percentages of sulphur and phosphorus. If the percentages of carbon and manganese are too low, the rails are soft and of poor wearing quality; if too high, the rails are brittle and their electric conductivity low. The percentages as used by a large steel company for rails intended for electric service are indicated in Table I.

DROP TEST

18. Sections of rail made from a given lot of steel and not less than 4 feet or more than 6 feet in length are in some cases subjected to the drop test. The rails are placed head upwards on supports 3 feet apart and a weight of 22,000 pounds with a 5-inch face allowed to fall on them. The temperature of the test pieces should not be lower than

60° F. nor higher than 120° F. The distance, in feet, that the weight drops is 16 feet for 61- to 80-pound rails; 17 feet for 81- to 90-pound rails; and 18 feet for 91- to 100-pound rails. If the falling weight breaks the rail, tests on two additional pieces are made from the same lot of steel. If either of these rails breaks, all of the rails made of that lot of steel are usually rejected. If the two rails pass the test satisfactorily, the lot of rails is usually accepted as far as this test feature is concerned.

RAIL WEIGHT

19. Rails are made in many sizes to suit widely differing operating conditions, but all are rated in pounds per yard of rail. For electric service, rail weights generally range from 60 pounds to 141 pounds per yard; 129-pound rails are used in Chicago, Illinois, and 141-pound rails in Columbus, Ohio.

RAIL SECTIONS

20. Rails for electric service are rolled in many shapes, but may be divided into three general classes: The T rail, Fig. 12 (*a*); the *girder* rail, view (*b*); and the *groove* rail, view (*c*).



FIG. 12

The names *head*, *web*, *base*, *tram*, *groove*, *lip*, and *neck* have been given to the different parts of the rails as indicated in the three views. The gauge of the track is measured from the inside

edge *a* of the head of each rail, called the *gauge line.* The tendency in electric-railway practice is to use long rails in order to reduce the number of joints. Ordinarily, rails are 30 feet in length, but some roads use 60-foot rails.

21. T Sections.—T rails of much the same sections as used on steam roads are employed on the unpaved portions of suburban and interurban railroads. Somewhat higher sections are quite frequently used on paved streets for city roads. Fig. 13 shows a section that has a wider than normal tread in order that interurban cars with 3-inch wheel tread may operate on city streets without interference with the paving. The splice bars are shown unshaded.



FIG. 13

The T section gives maximum strength and stiffness with minimum weight and has no groove nor tram to collect dirt; the head remains clean, thus lessening the power required to propel cars. T rails are cheaper than groove or tram rails, are easier to lay and have as good, and in some cases better running qualities. An old objection to their use was the difficulty in paving to their head in a manner to keep the street surface unbroken; with the special paving blocks and bricks now used, this objection does not exist, and T sections, as listed in Table II, are advocated by good authorities.

22. Girder and Groove Sections.—Rails with either a tram or a groove offer minimum interference with wagon traffic. The groove rail leaves the street surface near the track practically level. The tram of the girder rail offers a good path for vehicle wheels which results in a very considerable wear of the rails; also, wagons have difficulty in turning out from such a rail; therefore, in places of dense traffic, groove rails or T rails with special paving blocks are usually to be preferred.

To obtain satisfactory service with a groove rail, dirt must not be allowed to accumulate in the groove because of the danger of derailment. With some sections of groove rail the lip is ½ inch lower than the head and the groove so shaped that the flange of the wheels tends to push the dirt out of the groove.

There is always a given shape of car-wheel flange best suited to a groove of given form. In buying car wheels the shape of

TABLE II

WEIGHTS AND DIMENSIONS OF STANDARD T RAILS

(A. S. C. E. Sections)

Weight per Yard Pounds	Area of Cross-Section Square Inches	Width of Base and Height Inches	Thickness of Web Inch	Width of Head Inches
100	9.8	$5\frac{3}{4}$	$\frac{9}{16}$	$2\frac{3}{4}$
95	9.3	$5\frac{9}{16}$	$\frac{9}{16}$	$2\frac{11}{16}$
90	8.8	$5\frac{3}{8}$	$\frac{9}{16}$	$2\frac{5}{8}$
85	8.3	$5\frac{3}{16}$	$\frac{9}{16}$	$2\frac{9}{16}$
80	7.8	5	$\frac{35}{64}$	$2\frac{1}{2}$
75	7.4	$4\frac{13}{16}$	$\frac{17}{32}$	$2\frac{15}{32}$
70	6.9	$4\frac{5}{8}$	$\frac{33}{64}$	$2\frac{7}{16}$
65	6.4	$4\frac{7}{16}$	$\frac{1}{2}$	$2\frac{13}{32}$
60	5.9	$4\frac{1}{4}$	$\frac{31}{64}$	$2\frac{3}{8}$
55	5.4	$4\frac{1}{16}$	$\frac{15}{32}$	$2\frac{1}{4}$
50	4.9	$3\frac{7}{8}$	$\frac{7}{16}$	$2\frac{1}{8}$
45	4.4	$3\frac{11}{16}$	$\frac{27}{64}$	2

groove in the rail on which they are to operate should be considered in order to lessen the wear on both the flange and the groove.

Groove rails must be kept accurately to gauge in order to prevent the wheel flange from binding on the rail head or lip when the car is operating on a straight section of track or when the car is rounding a curve. The groove must also be of sufficient depth so that the wheel flange will not ride on the rail.

TRACK AND WHEEL GAUGES

23. The standard track gauge in the United States is 4 feet 8½ inches. There are, however, many roads with a track gauge other than standard. The device for testing the distance apart of the rails is also called a *track gauge;* one of these is indicated in Fig. 14 (*a*). When in service, the shoulders should engage the rail heads at the gauge line on each rail when the testing device is laid at right angles to the track.



FIG. 14

The car wheels are pressed on the axle so that the outside of the wheel flanges are 4 feet 8¼ inches apart, this distance being tested by a device called a *wheel gauge* shown in Fig. 14 (*b*). This gauge should fit over the flanges so that if one end is held pivoted over the flange, the other end may be moved laterally about 2½ inches.

RAILS WITH CONICAL TREAD

24. Car-wheel tread diameters are greater next to the flange than they are at the outside edges, thus permitting the car to center itself on the track when the two wheels on the same axle differ slightly in diameter. This so-called *coning* of the treads can satisfactorily perform its service when the difference in the diameters of the two wheels on the same axle is not enough to cause differences of more than ⅜ inch in the circumferences of the two wheels. It was formerly customary to make the rail top level; under this condition, until there is some wear in either the rail tread or in the wheel tread, the


(a) FIG. 15 (b)

bearing surface between the two is practically a line, as shown by Fig. 15 (*a*).

Girder and groove rails are now rolled with a conical tread, as in Fig. 15 (*b*), thus providing good traction surface between wheel and rail and increasing the life of both. T rails are coned in both directions from the center and to such an extent that when a fair life has been realized from one side of the rail head, the rails can be turned end for end and the other side of the head used.

GUARD-RAILS

25. When a car rounds a curve, the flange of the forward outer wheel presses against the gauge line of the outer rail. The contact of these two surfaces guides the car around the curve and causes a tendency for a wheel to climb the rail; the sharper the curve and the higher the speed, the greater is the climbing tendency, which may be dangerously aggravated by chipped wheel flanges or open rail joints. To prevent climbing, curves are laid with a *guard* feature which may be either a part of the running rail itself or a separate rail laid alongside the running rail. In some cases both running rails are provided with guards, but this practice increases the cost as well as the amount of power required to propel the car against the increased friction. The best authorities are agreed that a guard to the inner rail of the curve affords ample protection. The groove rail guard is generally a part of the running rail itself, as indicated in Fig. 16; this rail is similar to a groove rail except that the guard lip is heavier and extends above the rail tread. The dotted line indicates the contour to which the guard wears in time.



FIG. 16

T-guard rails for city work are usually fastened to the T rail as indicated in Fig. 17 (*a*) for high rails and in (*b*) for low rails.

In open-country work, a second line of T rails is sometimes



(*a*) FIG. 17 (*b*)

laid near the inner rail of the curve and between the two track rails. On bridges, a guard-rail is laid near each track rail and between them.

RAIL JOINTS

26. Necessity of Good Joints.—Substantially constructed rail joints are essential on any railroad, and especially on electric roads, in order to obtain durability of track and rolling stock and to maintain good conductance of track circuit. A portion of the weight of the car motors is supported directly by the car axle without the intervention of springs, so if the rail ends are slightly uneven or loose, the car wheels strike them a heavy blow thus tending to flatten the heads of the rails. The blows become heavier as the rail heads flatten, and unless the joints are promptly made even and secure, they soon get in such bad condition as to decrease greatly the conductance of the track and to rack the rolling stock. The remedies are to cut off the damaged ends of the rails, or if the rails are not too much damaged, to grind the rail treads so as to slope the flat back some distance from the joint. The better plan is to make the joints perfect and rigidly secure when the track is laid. A few of the bolted joints will be described.

27. Standard Channel-Plate Joint.—All forms of bolted joints depend for their fastening and stiffening on the *channel plates*, sometimes called *fish-plates*, *splice bars*, or *joint*



FIG. 18

plates. The most common form of bolted joint is made by bolting a channel plate on each side of the rail. The holes in the channel plates are oblong as are also a portion of the shanks of the button-headed bolts so that the bolts cannot turn when they are being tightened.

Fig. 18 shows a standard twelve-bolt joint made with two channel plates; the plates have projecting ribs *O*, to prevent buckling when the bolts are tightened. The channel-plate flanges bear against the under side of the rail head and tram and the upper side of the rail foot, thereby stiffening the joint.

In Fig. 18 the bolts have hexagon heads; ordinarily, square-headed nuts are to be preferred, but with girder rails and high T rails where two rows of bolts are used in the plates and it is desirable to have the bolts close to the edges of the plate, the hexagon headed nuts are used because they are easier to get at with wrenches. Square-headed nuts have more bearing surface on the rail.



FIG. 19



FIG. 20

28. Continuous Joints.—Fig. 19 shows a form of continuous rail joint made of sections so shaped that a flange projects under the foot of the rail from each side. The abutting rail ends are thus held firmly in line. The slots, Fig. 19, in the splice bars made for the rail spikes or bolts also serve to prevent rail creeping, as explained in Art. **12.** In another form of base-supporting joint, the under portions are bolted together below the rail.

Fig. 20 shows a base-supporting joint made up of two channel plates, a block of wood, and a rolled angle of steel, all of which are bolted to the two abutting rail ends.



FIG. 21

29. Joining Rails of Different Sections.—For joining rails of unlike sections, combination joints can be made with

special splice bars that directly connect the rail ends together, or special sections of cast-steel rails may be used and these joined to the two rail ends by ordinary splices. Fig. 21 shows four combination joints made with special splice bars and Fig. 22 shows a form of rail casting that may be inserted in the line to join a groove rail to a T rail.

30. Use of Welded Joints.—Rails laid to their full depth in paving expand and contract but little with ordinary changes of atmospheric temperature, because the paving tends to equalize the temperature of the rail and the earth. The joints of such rails can therefore be welded so as to form a long length of rail and no allowance need be made for expansion and contraction.



FIG. 22

If the rails are exposed, as in open-country work and on elevated structures, they may be welded together if joints that allow a slight movement of one rail toward or away from the other rail are installed at intervals of about 1,000 feet on straight track and at the ends of curves.

31. Lorain Welded Joint.—In the Lorain method, mild-steel plates are electrically welded to each side of the webs of the two abutting rails by passing a very large current through the plates and the rails.

The welding outfit consists of a sand blast, a synchronous converter, a transformer, a welder, and grinding apparatus, all mounted on four cars. The surfaces to be welded are cleaned by directing a blast of sand against them. The converter serves to change direct current from the trolley circuit to alternating current and the transformer provides the proper

value of voltage for the welder. The tops of the rails at the welded joint are smoothed by the grinder.

Fig. 23 shows a splice plate, one of which is welded to each



FIG. 23



FIG. 24

side of the rail web as shown in Fig. 24. Each plate is welded at points *a*, *b*, and *c*, Fig. 23, the total area affected being about 10½ square inches on each plate.



FIG. 25

32. The welder is shown in Fig. 25 and is suspended by a crane from the front of one of the cars so that it can easily be placed in position on either rail of the track. After cleaning the rail surfaces, the splice bars *a* are clamped in position on the rails *b*. The terminals *c* and *d* of the welding transformer *e* are pressed against the plates over the portions to be welded by means of levers *f* and *g* operated by pistons in a hydraulic cylinder *h*. The primary coil of the welding transformer *e* is supplied with alternating current. The secondary circuit of this transformer consists of a single loop of very large conductor and includes in the circuit, plates *a* and rails *b*. A secondary current of about 25,000 amperes at 7 volts melts

the surfaces to be welded; the current is then cut off and the surfaces firmly pressed together and the joint allowed to cool. The central weld of the joint is made first, followed by the welds at the ends of the plates.

33. Fig. 26 (*a*) shows a horizontal section through a completed joint; (*b*) a section of the center weld; and (*c*) of an end weld. The resistance of a joint of this kind is less than the corresponding length of rail.

For welds on old rails, a special section of plate on the tread side of the joint is sometimes used; this section is provided with a lug that fits under the rail head, and the small space between



FIG. 26

the lug and the rail head is poured full of melted zinc, thus improving the support of the rail head.

34. Arc Welded Joint.—The welding of rail joints by the arc method is accomplished by clamping plates on each side of the webs of the rails and then causing metal to flow from a soft-steel electrode along the junction of the plates and the rails. The steel electrode is a rod about $\frac{1}{4}$ inch in diameter and 30 inches long and is connected through an adjustable rheostat with the trolley wire. The rail forms the negative side of the circuit. When the electrode is touched and then withdrawn from the plates, or rail, an arc is formed and the melted steel from the rod lodges against the rail and welds the edges of the plates to the rails.

35. Cast Welded Joint.—Cast welded joints are made by pouring molten iron into a cast-iron mold placed around the abutting rail ends, which are first sand-blasted for a distance of 6 or 8 inches from the center of the joint.



FIG. 27

Fig. 27 shows a cast-iron weld. The added iron which is indicated at *l* may weigh from 75 to 225 pounds, depending on the shape of the joint. The apparatus used with this method consists of a sand-blast machine for cleaning the rails, rail molds, and a portable cupola for melting the iron.

36. Thermit Joint. Thermit is a powdered mixture consisting mostly of finely divided iron oxide and aluminum. The mixture is placed in a crucible over the joint. The metal aluminum has a great affinity for oxygen, and if the mixture is suddenly heated by burning some ignition powder on its surface, a very rapid chemical action takes place that melts



FIG. 28



FIG. 29

the whole mass in the crucible. The iron oxide and other ingredients are reduced into steel and this is poured into molds attached to the rail ends. The melted metal is so hot that it

welds itself into the structure of the rails. A scratch brush is used to clean the rails before making the joint.

Fig. 28 shows a thermit joint and Fig. 29 the molds. The sheet-iron case (*b*) is placed over a model of the joint and tamped full of China clay and loam. The molds for the two sides of the rail thus formed are shown at (*a*) and (*c*) and these are clamped to the rails.

37. Zinc Joint.—Fig. 30 shows a type of zinc joint. The rails are sand-blasted and the rolled joint plates are riveted to the rails. There are open spaces left at the top of the plates and around the foot of the rail. The whole joint is heated to a temperature of 300° or 400° F. by means of portable oil burners and molten zinc is then poured in the spaces near the foot of the rail and between the plates and head of the rail. The zinc fills all irregularities of the surfaces of plates and rails and offers a firm support for the joint.

FIG. 30

38. Expansion Joint.—In exposed rails with welded joints, expansion joints are usually installed at intervals of 800 to 1,000 feet on straight track and at the approaches of curves. Each expansion joint allows slight endwise movements of one of the rails, and thus lessens the danger of the rails breaking or the curves being distorted due to changes in length of the rail caused by temperature changes.

Fig. 31 shows one type of expansion joint with the rails in the positions assumed in warm weather. Rail *a* is fixed to the base *b* which is spiked to the ties. Rail *c* is free to move endwise to the right through the guides *d* as the rail contracts as the result of cold weather. Rail *a* is the movable rail at the next expansion joint on the left.

The extent of rail movement depends on conditions such as the amount of temperature change and of rail surface exposed.

39. Disposition of Joints.—Some engineers advocate placing the joints in the two rails of a track opposite each



FIG. 31

other, while others prefer to locate the joint in one rail opposite the center of the rail length on the other side of the track. In the first method, the track is said to be *even jointed* and in the second method it is said to be *broken jointed.*

When the track is so laid that the ends of the rails meet on a tie, the joints are called *supported joints;* when the rails meet between ties, the joints are called *suspended joints.* Both methods are in general use.

RAIL BONDS

40. Use of Rail Bonds.—Rail bonds usually consist of large bare copper conductors, the terminals of which are firmly attached to points near the ends of the abutting rails of a joint. As the sole purpose of rail bonds is to improve the track conductance they are not usually employed with rails having the joints welded; the chief use of bonds is with bolted joints, where loosening bolts and rusting surfaces would otherwise reduce conductance.

No matter what type of bond is used, the conductance of the joint depends on the mechanical excellence of the bolted connections and of the contacts between the bond and the rails, because continual movement of the rails is likely to loosen the bond contacts and increase the resistance of the joint. It is highly important, therefore, that the track should be inspected systematically and that the joints be kept tightly bolted.

41. The maintenance of high rail conductance keeps the energy loss low and helps in maintaining good car operation.



(*a*)

(*b*)

(*c*)

FIG. 32

High track conductance also minimizes leakage of the return current to adjacent pipes with possible resulting damage to them.

Bonds placed between the channel plates and the rail to protect them from mechanical injury and from thieves are known as **protected bonds**; those not so covered are known as **unprotected bonds.** Fig. 32 (*a*) shows a protected bond and (*b*) and (*c*) two types of unprotected bonds.

FIG. 33

42. Compressed Stud Terminal Bond.—It is important that the contact between the copper conductors of the bond and the iron rail be so made as to secure a permanent low-resistance connection between the two devices.

Fig. 33 shows a cross-section of the web of a rail and a bond terminal in which the stud terminal was installed by means of a screw compressor, a device with which a man operating a 40-inch lever can exert a pressure of 20 tons. The hole in the web of the rail is drilled and two grooves cut in the walls of the hole. The stud terminal of the bond is brightened by emery paper, then inserted in the hole and pressure applied. The copper flows into the grooves and further pressure forms the rivet head as shown. Soda and water or plain water should be used instead of oil to lubricate the drill when boring the holes in the web. The surface of the walls of the hole should be bright and free from oil or moisture and the bonds should not be installed in damp weather. A solution of red lead and linseed oil may be applied to the bond terminals and adjacent surface of the rail after installation, to seal the joint from moisture.



FIG. 34

Fig. 34 shows a protected bond of this type made of copper ribbon and cast copper terminals *a* and *b*. Fig. 32 (*a*) shows the position on the rails of two bonds of this general type but

made of flexible cable. When the channel plate is in position the bond is covered.

The main portion of the bond may be formed of solid copper, flexible cable, or ribbon. The stud terminals may be formed by welding together a portion of the wires of the cable or ribbon conductors, or made separately and welded or soldered to the conductors. The conductors are usually bent so as not to interfere with the bolts of the joint and to allow for slight contraction or elongation of the rails, due to temperature changes, without causing serious stresses on the contacts of the bond terminals.



(a) (b) (c)

FIG. 35

Bonds may be installed on one side of the rails or on both sides; in the latter case, the method is called *double bonding*. One or more bonds on each side may be used. Sufficient copper is used to cause the conductance of the joint as a whole to be nearly the same as the conductance of an equal length of rail.

43. Hammered Stud Terminal Bond.—Fig. 35 (*a*) shows a bond provided with terminal studs that may be hammered into place after the holes in the rail heads, one of which is shown in (*b*), have been drilled by a special milling cutter. The holes in the studs indicated in (*a*) fit over the pins formed

in the rail heads as indicated in (*c*), thus obtaining large contact surface.

44. Soldered Bonds.—A bond that is soldered to the base of the rails is shown in Fig. 32 (*c*) and one soldered to the head of the rails in Fig. 36. A special application of these bonds is for temporary work or for bonding old rails where the cost of removing channel plates and renewing bolts would be prohibitive.



FIG. 36

The installation of soldered bonds requires the utmost care to insure good electrical and mechanical union between the copper and steel. All rust and scale must be removed from the steel surfaces and the rails heated until the cleaned surfaces show a light blue color. Soldering flux, preferably zinc chloride, is then applied and a bar of solder rubbed on the cleaned surfaces until they are thoroughly tinned. The bond is then clamped on the rails and the rails again heated sufficiently to melt wire solder applied to them; the clamp is then tightened and wire solder melted on the edges of the terminals as the joint cools. After the joint has cooled it should be painted with waterproof paint.

45. Electrically Welded Bonds.—Fig. 37 shows the installation of two welded bonds at a joint of a conductor rail. These bonds may be applied either to the head or foot of the track or conductor rails.



FIG. 37

Fig. 38 shows a welded bond applied to the conductor rails of a conduit system. The two parts of the bond are separately welded to the rails and when the rails are in place, the free ends of the bond conductors are clamped or soldered together.

A special car on which is mounted a rotary converter, transformer, and welding clamps is used to weld the bonds onto the rail.



FIG. 38

46. Copper-Welded Bonds.—In some cases the copper conductor of a bond is welded to the rail by pouring melted copper into a mold clamped against the rail and into which the end of the bond conductor is placed. Fig. 39 shows the mold in position. The interior includes two chambers connected by a narrow neck. Melted copper, from a crucible carried on a special car, poured into one of these chambers surrounds the copper conductor and comes in contact with the cleaned rail surface. Excess copper flows into the second chamber and assists in raising the temperature of the rail to a point where the copper in the first chamber is welded to the rail. The joint is then allowed to cool, the mold removed, and the excess copper cut loose at the narrow neck, leaving the bond terminal as indicated in Fig. 40. Copper cables may be welded to the third rail or to track rails by this method.



FIG. 39



FIG. 40

47. Bonds Using Amalgam. — The conductance of the contacts between the rails and the channel plates is greatly improved if the contact surfaces are cleaned and coated with an amalgam of copper or other metal. In some cases the

amalgam is held in cork cases and these are compressed between the rails and the channel plate. In joints of this kind, the channel plate serves as the bond conductor and the amalgam affords a low-resistance path between the plate and the rail.

48. Cross-Bonds.—The two track rails should be connected together at intervals of 500 feet approximately by cross-bonds, thus affording a low-resistance path around a poor joint in either rail.

On double track the four rails should be cross-bonded at about the same intervals as for single track. Parts of crossings and switches that are bolted together are in many cases electically connected together by long copper cables.

In order to increase track conductance, bare copper cable is sometimes laid along the track and connected at intervals to the joint bonds. The rails at a point near the station are connected to the negative bus-bar by large cables. The cables are usually welded or brazed to the rail.

SPECIAL WORK

49. Designation.—Track construction relating to curves, branch-offs, crossings, etc., is usually known as **special work.** Some of the more common forms of special work are shown in Fig. 41. A *plain curve* is shown at (*a*); it may be right-hand or left-hand, simple, or compound. A *left-hand branch-off* is shown at (*b*) and a *right-hand branch-off* at (*c*); these are used where a branch road leaves the main line. When determining whether left or right, face the point of departure of the branch.

A *connecting curve and crossing* are shown at (*d*); a *plain* Y at (*e*); a *three-part* Y at (*f*); and a *through* Y at (*g*). The three-part Y can be used in place of a loop to turn cars at the end of a line. A *reverse curve* is shown at (*h*); it is used where a cross-street is broken at the main street. A *right-hand cross-over* is shown at (*k*) and a *left-hand cross-over* at (*l*); they are installed at intervals in the track so that a car may cross from one track to the other, thus shortening the regular run in case of the disablement of the car or to make up time. A *diamond turnout*

is shown at (*m*); an *ordinary siding* at (*n*); and a *thrown-over turnout* often used for temporary work to avoid interference with track repair at (*o*). Other than the names just given to these parts are used in some localities.



FIG. 41

Fig. 42 shows a layout of special work and indicates the names given to some of the more detailed parts as recommended by a large steel company.


Right-hand Run-off Mate
Right-hand Tongue Switch
Right-hand Mate
Curve Cross
Triple Curve Cross
Double Curve Cross
Girder Cross
½ Girder Cross
Left-hand Mate
Left-hand Tongue Switch
Left-hand Run-off Mate
Left-hand Tongue Switch
Right-hand Run-off Mate
Right-hand Tongue Switch
Left-hand Tongue Switch
Left-hand Run-off Mate
Right-hand Mate
Left-hand Tongue Switch
Right-hand Tongue Switch
Left-hand Mate

FIG. 42

50. Construction.—Important special work is made up at the steel works and shipped ready to install. The work of construction must be carried out with great precision. The site of the proposed work is surveyed and a drawing made; this drawing is checked and from it the work is laid out in actual size with chalk on a hard smooth maple laying-out floor; if the layout checks correctly, the lines on the floor are used as guides for making wooden templets for the patternmakers and rail benders. When the separate parts of the job are complete, it is assembled in the laying-out yard where any mistakes that may have escaped preceding inspections or any inaccuracies due to uneven shrinkage of the cast parts or to carelessness in the bending may be detected and rectified. The system of checking and rechecking the job in the various stages of its progression from the surveyor to the shipper is so thorough that the chances of error are a minimum. Special work on electric railways generally lasts longer than on steam railways, because subjected to lower tonnage and speed; also on electric railways the rules generally require stopping or slowing at crossings and intersections.

51. In switches, frogs, and crossings, the greatest wear takes place at the points of the switches and the breaks in the tread of the rail, places subjected directly to the pounding of the wheels. Various methods have been adopted for inserting hard steel at these places. One make of special work, called *manganese*, takes its name from special plates of hard manganese steel that are placed at the intersections; these are held by special bolts or fastenings so that worn plates can be readily renewed. Another class of special work, known as *guarantee work*, is guaranteed to last as long as the abutting rails; in it, tempered-steel wearing plates are held by keys and zinc poured in around the inserted piece. In a third class of special work, known as *adamantine work*, the crossings are made of steel castings.

Fig. 43 shows a crossing of the guarantee type. Renewable hardened-steel plates *a* are set in as indicated; the joints are stiffened by cast welding the rail ends at the crossings. The

piece as a whole is in two parts fastened together by means of standard joints. The crossing illustrated is for groove rails, but similar construction is adaptable for use with high T rails.



FIG. 43

Fig. 44 shows a cast manganese-steel crossing; it is made in two pieces and connected together by standard joints.

Fig. 45 indicates the arrangement of the renewable parts in a guarantee-curve crossing. The hardened-steel plate *a* is held by the wedges *b* and *c*, which are embedded in zinc to prevent them from working loose. To remove the plate, the wedges are driven down.

52. Gauntlet Track.—For double track through a narrow street or tunnel or over a narrow bridge, the *gauntlet*



FIG. 44

construction indicated in Fig. 46 may be used. The gauntlet construction is cheap and simple, the special work being limited to two plain ordinary frogs.

53. Curves.—Curves are of two kinds, *simple* and *compound*, or *easement*, curves. **A simple curve** is described with but one radius throughout its length, while a compound curve



FIG. 45

is so constructed that the radii become shorter as the middle point of the curve is approached from either end. A compound curve is easier riding than a simple curve. Street-railway curves are usually designated by the radius, in feet, at the center. Long curves of light rail are sprung in, as a rule; that is, the rail is pried over with a bar and spiked into position, the paving being relied on to keep the track in place. The main objection to "springing in" a curve is that in course of time the ends of the rails may straighten out and make an angle at the joint; this difficulty is most likely to occur with heavy rails or on curves of short radii. The car trucks in rounding such a curve will change direction in jumps, instead of gradually, and impart to the car a disagreeable, jerky motion not to be found on a curve that is smooth and regular. On curves of heavy rails and moderate radius, a portable rail bender should be used, while shorter curves should be bent to a templet with a power bender. With ordinary T rails, curves having



FIG. 46

a radius of 500 feet or over can be sprung in, but with girder rails or high T rails 800 to 1,000 feet is the smallest allowable radius.

54. Easement, transition, or compound curves are formed by combining curves of different radii, so that the entrance of the car into the curve shall be gradual, and a sudden shock avoided. The curve at the point where it branches from the straight part of the track, or a tangent, as it is called, is of long radius and the radii are gradually decreased until the radius of the center of the curve is reached. All steel companies who make electric-railway special work, have standard transition curves made up of a number of radii such that the length of arc of any one radius is not over 5 feet, and cars ride very smoothly around such curves.

55. Testing Clearances.—Single-track curves must be laid out so that cars will go around them freely without either end overhanging the corner of the sidewalk or striking any obstruction. On double-track curves, two cars should be able to pass each other without danger. The layout of a double-track curve therefore depends on the length and width of cars to pass on it, on the car overhang at the ends of single-truck cars and in the center of double-truck cars, on the distance between the track centers, the curvature, the elevation of the outside rail, and the length of the wheel base. Car fenders should be considered, since a fender increases the effective length of the car.

The best plan is to lay out on paper and to scale a plan of the proposed curve; then, by means of a pasteboard dummy that scales the dimensions of the outside lines of the car, the actual clearance at all points can be readily determined. The positions of the car wheels may be indicated by holes in the dummy through which the track can be seen, or transparent paper may be used, so that the dummy can be made to take the right path around the curve. For the safety of passengers, a clearance of at least 12 inches should be allowed on each side of the car if cars are to pass each other on curves. Special precautions are necessary where the center-pole method of line construction is used.

56. Rail Elevation on Curves.—Wheels tend to climb the outer rail in curves because the tendency for the car to

move straight ahead is overcome by the pressure of the head of the outer rail against the flanges of the wheels. If the flange of a wheel is much worn or chipped or if there is considerable space between rails at a joint in the curve, the tendency for the wheel to climb is increased, because the flange may catch on the rail. Elevating the outer rail or lowering the inner one or dividing the total change between the two eliminates a

TABLE III

RAIL ELEVATIONS

Radius of Curve, Feet	Speed of Car	
	6 Miles per Hour	19 Miles per Hour
	Elevation of Rail, in Inches	
1,200	.078	.780
900	.156	1.287
600	.234	1.989
450	.312	2.613
300	.429	3.939

portion of the side thrust on the rail. Where cars round curves at high speed, elevation of the outer rail is necessary; these elevations for certain stated conditions may have the values indicated in Table III. On curves as installed in city streets where the car speeds are low, rail elevation is usually not essential.

MAINTENANCE OF TRACK

57. Smooth, level, even track is absolutely essential for easy riding cars and minimum cost of maintenance of superstructure, rolling stock, and track. Rough uneven track jolts passengers, causes the trolley to fly off and possibly injure itself or the overhead work, racks the rolling stock, batters the track into still worse shape, and may be the cause of serious accidents and loss of life.

Safe, agreeable, and efficient operation, therefore, demand the maintenance of good track. Substantially constructed new track, although higher in first cost, can be maintained at less cost than poorer track with cheaper construction. Proper maintenance requires *good lining*, *surfacing*, and *gauging;* only a trained eye can detect such defects unless they are very serious.

58. Lining the track refers to the elimination of horizontal kinks that tend to give cars a swaying motion; **surfacing** refers to the elimination of vertical kinks in the track that cause jouncing. Depressions in the track are caused by poor joints, soft spots in the roadbed, poor tamping of the ballast, or washouts under the ends of the ties. Poor surfacing increases the wear on rolling stock and rails and may cause accidents; when the wheel of a heavy, high-speed car drops into a depression, it delivers a blow that is liable to break the wheel, the axle, or the rail. The effect of such blows can be seen on old track with poorly maintained joints; on a double-track road, for example, the rail ends on the north side of the joints of the north-bound track and on the south side of the joints of the south-bound track are hammered into cup-shaped depressions, and are said to be **cupped.** On single track the rail ends on both sides of the joint become cupped. Furthermore, this continual pounding on low spots forces the rails laterally out of line and if this condition is long neglected it becomes very difficult to correct. Poorly lined or surfaced track also increases the resistance to train movement and consequently increases the energy required to operate cars. Measurement of the current required to start a car on different parts of supposedly level track will often show great differences.

59. Gauging refers to the maintenance of proper distance between rail heads and is very important especially on straight track. On curves, distances between rail heads a little more than the normal gauge if not beyond the limits of actual safety, are less objectionable, because the wheel flanges press against the outer rail, and if that is a true curve the running will be satisfactory. The rails on straight or curved track should not be close enough together to bind the wheel flanges.

60. Rail Breaks.—Rail breaks are most likely to occur in freezing weather, when the rails are most brittle and the roadbed most inflexible. Broken rails are extremely dangerous, especially in the outer rail of a curve, where the forward outer wheel flanges may catch in the break and cause derailment. Continuous thorough inspection is the only safeguard, and even this may not prevent an accident for a train may break a rail and be derailed thereby.

61. Weeds.—Weed growth on a track lubricates the rails and causes the driving wheels to slip. Weeds also conceal defects in the track and make approximate lining and surfacing by eye impracticable. Among the methods used to remove weeds are digging them out, cutting them off, killing them with high-voltage alternating current, and burning them by means of crude-oil burners extending from a special car; the last method is the cheapest and most convenient when much of this work is to be done.

ELECTRIC-RAILWAY CALCULATIONS

LINE CALCULATIONS

CONDITIONS AFFECTING THE SIZE OF FEEDERS

VARIABLE CONDITIONS

1. Line calculations, as here considered, deal with the determination of the sizes of conductors required between the station or substation and the cars to transmit the electric energy needed under specified conditions of operation.

No general rule can apply to the values to be used in all of the conductor calculations involved in the design of a given electric-railway system. The practice of dividing the line into insulated sections simplifies calculations, because each section may be considered as governed by its own load conditions. If these conditions could in any case be assumed with certainty, the problem for that section could be easily solved; but the solution would not apply to other sections, for it is unusual for two sections to have the same load conditions. Besides, a change of attractions along the line or a shift of suburban improvements may develop a gradual change in load conditions more serious than a daily or weekly shift. A certain line layout may meet all existing requirements, but subsequent changes in the requirements may unbalance the system. It may then be necessary to make new calculations and either change the

COPYRIGHTED BY INTERNATIONAL TEXTBOOK COMPANY. ALL RIGHTS RESERVED

amount of conductor and its disposition or install devices for maintaining the voltage; such as boosters and storage batteries. Conductors placed with good judgment may satisfactorily improve the voltage at a desired point, but in some cases the installation of devices for boosting the voltage at that point may result in more economical operation.

LIMITING CONDITIONS

2. Increasing the total cross-sectional area of the conductor system raises the voltage and saves energy by reducing the line loss and this saving can be approximately calculated. Knowing the cost of a unit of energy at the power station, the direct saving to be effected by a proposed increase of conductor may be obtained; then, knowing the cost of the added conductor, including installation, the interest on its total cost can be computed.

Improving the feeding system not only saves directly, by reducing the line losses, but it saves indirectly, because raising the voltage increases the car efficiency and speed and decreases the number of cars and men required to meet a certain time-table. Besides, the improvement in service attracts and creates travel by adding to the pleasure riding.

It pays to install more conductor if the cost of the energy saved in a year plus the added income each year exceeds the interest on the total cost of the added conductor. These statements may be expressed in the form of a limiting equation such as:

interest on the conductor cost = value of energy saved + added income due to improved service

The limiting value is that the value of the left-hand member of the equation should not exceed the value of the right-hand member.

FEEDER FORMULAS

3. Copper Conductors.—The resistance R of a conductor of commercial copper 1 foot long and 1 circular mil in cross-section is usually taken as 10.8 ohms. A conductor l feet in length and of 1 circular mil in cross-section has a resistance of 10.8 l, but if the cross-section of the conductor is a circular mils, the conductor resistance is, $R=\frac{10.8\,l}{a}$.

The resistance of any wire to the passage of direct current is equal to the drop in volts u through the length of the wire divided by the current I, or $R=\frac{u}{I}$.

As these two values of R are equal, $\frac{10.8\,l}{a}=\frac{u}{I}$;

or, $$\text{circular mils } a=\frac{10.8\,l\,I}{u} \qquad (1)$$

Drop, in volts, in the feeder

$$u=\frac{10.8\,l\,I}{a} \qquad (2)$$

EXAMPLE 1.—A copper feeder 1,000 feet long must carry a current of 100 amperes, with a drop of not more than 20 volts. What must be the sectional area of the conductor, expressed in circular mils?

SOLUTION.—Substituting the values of $l=1{,}000$ ft., $I=100$ amp., and $u=20$ volts, in formula **1**,

$$a=\frac{10.8\times1{,}000\times100}{20}=54{,}000 \text{ cir. mils.} \quad \text{Ans.}$$

EXAMPLE 2.—A copper feeder having a sectional area of 54,000 circular mils transmits a current of 100 amperes a distance of 1,000 feet. What is the drop, in volts?

SOLUTION.—Substituting the values of $l=1{,}000$ ft., $I=100$ amp., and $a=54{,}000$ cir. mils, in formula **2**,

$$u=\frac{10.8\times1{,}000\times100}{54{,}000}=20 \text{ volts.} \quad \text{Ans.}$$

4. If the copper conductor alone is to be considered, the value 10.8 ohms per mil-foot is used and the drop u is that in

the feeder alone. Formulas 1 and 2, Art. 3, may, however, be modified so as to take into consideration the approximate added drop in the track-return circuit by using the value 14 ohms per mil-foot for the combination of copper and steel-rail conductors and the value of u as the total drop in both the outgoing and the return conductors.

The size of the copper conductor is then,

$$\text{circular mils } a = \frac{14\,l\,I}{u} \qquad (1)$$

and the drop in the outgoing and the return conductors is,

$$u = \frac{14\,l\,I}{a} \qquad (2)$$

The formulas of this article should be used only when the track bonding is known to be in good condition. If the track is poorly bonded, the calculated results will not be reliable.

5. Aluminum Conductors.—Aluminum feeders are used to some extent in low-tension railway work. Comparison of conductors of different materials receives treatment in *Long-Distance Transmission of Electrical Energy*. The resistance per mil-foot of aluminum conductor is here taken as 17.17 ohms. The formulas relating to the outgoing aluminum feeder alone are,

$$a = \frac{17.17\,l\,I}{u} \qquad (1)$$

$$u = \frac{17.17\,l\,I}{a} \qquad (2)$$

EXAMPLE 1.—An aluminum feeder 1,000 feet long must carry a current of 100 amperes, with a drop of not more than 20 volts. What must be the sectional area of the conductor?

SOLUTION.—Substituting the values of $l = 1{,}000$ ft., $I = 100$ amp., and $u = 20$ volts, in formula 1,

$$a = \frac{17.17 \times 1{,}000 \times 100}{20} = 85{,}850 \text{ cir. mils.} \quad \text{Ans.}$$

EXAMPLE 2.—An aluminum feeder having a sectional area of 85,850 circular mils transmits a current of 100 amperes a distance of 1,000 feet. What is the drop, in volts?

SOLUTION.—Substituting the values of $l = 1{,}000$ ft., $I = 100$ amp., and $a = 85{,}850$ cir. mils, in formula 2,

$$u = \frac{17.17 \times 1{,}000 \times 100}{85{,}850} = 20 \text{ volts.} \quad \text{Ans.}$$

6. If the added drop in the return circuit is also to be considered, as explained in connection with copper feeders, the value 22 ohms per mil-foot for the combination of aluminum and steel-rail conductors gives approximate results when the rail bonds are in good condition. The formulas of Art. **5** become,

$$a = \frac{22\, l\, I}{u} \qquad (1)$$

$$u = \frac{22\, l\, I}{a} \qquad (2)$$

TRACK RESISTANCE

RAIL AND BOND DATA

7. Resistance of Steel Rails.—The resistance of steel rails varies greatly, as it depends on the composition of the steel. Track rails are selected for their wearing qualities; hence, hardness is essential, but the harder the rails the higher is the resistance. The service of conductor, or third, rails, however is not as severe as that of track rails, hence these rails are sometimes made of softer steel, in which cases they are better conductors than the track rails.

The relative resistance of steel track rails as compared to similar rails if made of copper is frequently taken as 12 to 1 or 13 to 1; the relative resistance of conductor rails made of soft steel to similar rails if made of copper is sometimes taken as 8 to 1. These ratios will be referred to as the *resistance ratios;* they do not apply to all rails, and the manufacturers should be consulted when greater accuracy is desired.

8. Comparison of Newly Bonded Joint and Solid Rails.—A comparison of a newly bonded rail joint and a

corresponding length of solid rail indicates, in some cases, that the resistance of the joint is as low or sometimes lower than the resistance of the rail. After the rails have been in service, the jarring to which the joints are subjected may greatly increase the resistance from rail end to rail end.

A bond conductor of 0000 B. & S. wire has a sectional area of .1662 square inch, which, taking the resistance of rail steel as twelve times that of copper, is equivalent to $.1662 \times 12 = 1.994$ square inches of rail. Assuming that a bond 1 foot long connects two 60-pound rails, each rail having a sectional area

TABLE I

LENGTH OF RAIL EQUAL IN RESISTANCE TO 1-FOOT BONDS

Weight Rail Pounds per Yard	Rail Cross-Section Square Inches	Copper Section for Equal Conductance Square Inches	Kind of Bond							
			One 0000	Two 0000	One 000	Two 000	One 00	Two 00	One 0	Two 0
			Feet of Rail Equal in Resistance to Bond 1 Foot Long; Resistance Ratio 12 to 1							
60	6.0	.5	3.00	1.50	3.80	1.90	4.80	2.40	6.00	3.00
65	6.5	.54	3.26	1.63	4.10	2.05	5.20	2.60	6.52	3.26
70	7.0	.58	3.50	1.75	4.44	2.22	5.60	2.80	7.00	3.50
75	7.5	.63	3.76	1.88	4.74	2.37	6.00	3.00	7.52	3.76
80	8.0	.67	4.00	2.00	5.06	2.53	6.40	3.20	8.00	4.00
85	8.5	.71	4.26	2.13	5.38	2.69	6.80	3.40	8.52	4.26
90	9.0	.75	4.50	2.25	5.70	2.85	7.20	3.60	9.00	4.50
95	9.5	.79	4.76	2.38	6.00	3.00	7.60	3.80	9.52	4.76
100	10.0	.83	5.00	2.50	6.32	3.16	8.00	4.00	10.00	5.00

of 6 square inches, the resistance of the bond conductor will be equivalent to $6 \div 1.994 = 3$ feet of rail. The contact resistance between rails and bond terminals is not here considered.

The resistance of a rail joint is the resistance of the parallel paths consisting of the channel plates and the bond conductor and its contacts with the rail. The resistance of the paths through the channel plates, especially after the joint has been in service for some time, is so uncertain that they are not usually considered when the resistance of the joint is being calculated.

The cross-section of the bond conductor that is to be installed is usually proportioned to the size of rail used; thus, 90-pound rails should be bonded more heavily than 60-pound rails; the increase in bond conductance is preferably obtained by using two or more bonds in parallel for each joint.

Table I shows rail lengths equivalent in resistance to bonds of different cross-sections but all 1 foot long. The resistance of the bond contacts is not considered in this table. For example, if a joint with 70-pound rails is bonded with two No. 0000 bonds each 1 foot long, the parallel resistance of the two bonds is equivalent to that of 1.75 feet of rail, the resistance ratio being 12 to 1.

9. A rail is *bonded to full conductance* when the resistance of a given length of bonded rail is considered as being equal to the

TABLE II

SECTIONAL AREA OF BONDS WITH RESISTANCE EQUIVALENT TO THAT OF RAILS

Weight of Rail Pounds per Yard	Resistance Ratio	
	12 to 1	13 to 1
	Circular Mils of Copper Equal to Steel of Resistance Ratio	
50	530,515	489,705
60	636,618	587,646
70	742,721	685,587
75	795,773	734,558
80	848,825	783,528
90	954,928	881,469
100	1,061,030	979,410

resistance of a continuous rail of the same length plus the total contact resistance of the bonds used on the rail. Rails on roads that operate under very heavy traffic conditions are sometimes bonded to full conductance, but usually it is unnecessary to install so much bond copper.

Table II shows the sectional area of copper conductors that have the same resistance per unit length as steel rails having

resistance ratios of 12 to 1 and 13 to 1. Table III shows the resistance per mile of rails and tracks bonded to full conductance. Table IV shows the resistance per mile of conductor rails having a resistance ratio of 8 to 1.

TABLE III

RESISTANCE PER MILE OF RAIL AND TRACK BONDED TO FULL CONDUCTANCE, RESISTANCE RATIO 12 TO 1

Weight of Rail Pounds per Yard	One Rail, No Joints Ohm	One Rail, 176 Joints Ohm	Two Rails, 352 Joints Ohm	Four Rails, 704 Joints Ohm	Contact Resistance per Joint Ohm
60	.08765	.094954	.047477	.023739	.0000415
65	.08090	.087641	.043821	.021910	.0000383
70	.07513	.081378	.040689	.020345	.0000355
75	.07012	.075963	.037982	.018991	.0000332
80	.06573	.071204	.035602	.017801	.0000311
85	.06187	.067009	.033505	.016752	.0000292
90	.05843	.063270	.031635	.015818	.0000275
95	.05535	.059926	.029963	.014982	.0000260
100	.05259	.056955	.028476	.014239	.0000248

TABLE IV

RESISTANCE PER MILE OF CONDUCTOR RAIL BONDED TO FULL CONDUCTANCE, RESISTANCE RATIO 8 TO 1

Weight Rail Pounds per Yard	One Rail, No Joints Ohm	One Rail, 176 Joints Ohm	Two Rails, 352 Joints Ohm
60	.058433	.0632994	.0316497
65	.053933	.0584210	.0292105
70	.050080	.0542512	.0271256
75	.046746	.0506400	.0253200
80	.043820	.0474799	.0237399
85	.041246	.0446824	.0223412
90	.038953	.0421958	.0210979
95	.036900	.0398920	.0199460
100	.035060	.0379816	.0189908

RAIL-RESISTANCE FORMULAS

10. Track-Rail Resistance.—One square inch equals 1,273,000 circular mils, approximately. If 1 mil-foot of copper wire has a resistance of 10.8 ohms, a bar of copper 3 feet long and 1 square inch in sectional area will have a resistance of $\frac{10.8\times3}{1{,}273{,}000}$ ohm. If the resistance ratio is 12 to 1, the resistance of a bar of rail steel 1 yard long and 1 square inch in sectional area is $\frac{10.8\times3\times12}{1{,}273{,}000}$ ohm. The sectional area A in square inches of a rail may be determined approximately by dividing the weight per yard W_y, in pounds, by 10, or $A=\frac{W_y}{10}$. One yard of rail having a weight of W_y has a resistance approximately of $R_y=\frac{10.8\times3\times12}{1{,}273{,}000\,\frac{W_y}{10}}$ ohm; therefore,

$$R_y=\frac{.003}{W_y}\text{ ohm} \qquad (1)$$

One thousand feet of rail having a weight per yard of W_y has a resistance $R_t=\frac{.003\times\frac{1000}{3}}{W_y}$; therefore,

$$R_t=\frac{1}{W_y}\text{ ohm} \qquad (2)$$

One mile of rail having a weight per yard of W_y has a resistance $R_m=\frac{.003\times\frac{5280}{3}}{W_y}$; therefore,

$$R_m=\frac{5.28}{W_y}\text{ ohm} \qquad (3)$$

EXAMPLE 1.—What is the resistance of 1 yard of rail-steel bar weighing 10 pounds a yard and having a resistance ratio of 12 to 1?

SOLUTION.—Substituting for W_y in formula **1**, its value 10, $R_y=.003\div10$ $=.0003$ ohm. Ans.

EXAMPLE 2.—What is the resistance of 1,000 feet of steel rail weighing 50 pounds a yard and having a resistance ratio of 12 to 1?

SOLUTION.—Substituting for W_y in formula 2 its value 50, $R_t = \frac{1}{50} = .02$ ohm. Ans.

EXAMPLE 3.—What is the resistance of 1 mile of steel rail weighing 100 pounds a yard having a resistance ratio of 12 to 1?

SOLUTION.—Substituting for W_y in formula 3 its value 100, $R_m = 5.28 \div 100 = .0528$ ohm. Ans.

11. Conductor-Rail Resistance.—The following formulas for determining the resistance of conductor rails of special steel are based on the resistance ratio of 8 to 1.

$$R_y = \frac{.002}{W_y} \text{ ohm} \qquad (1)$$

$$R_t = \frac{.666}{W_y} \text{ ohm} \qquad (2)$$

$$R_m = \frac{3.52}{W_y} \text{ ohm} \qquad (3)$$

12. Calculation of Track Resistance.—In the formulas of Arts. **10** and **11**, the resistance of a continuous rail is assumed. The formulas apply to bonded rails if they are bonded to at least full conductance. It should be understood that these formulas give results of only approximate accuracy and that these results do not necessarily check exactly with data, such as given in Tables III and IV.

A single-track road has two lines of rails in parallel; a double-track road, four lines of rails; and a four-track road, eight lines of rails; therefore, when considering the resistance of the portion of the return circuit formed by the rails, the resistance of one rail for the calculated distance should be divided by the number of rails in parallel. It is considered that the rails are bonded to full conductance and that the tracks are cross-bonded.

If the condition of the joints is not known, 100 or more of them should be measured for resistance in order to determine what resistance if any should be added to the resistance of the rails.

FEEDER PROBLEMS

DISTRIBUTION OF VOLTAGE IN THE TRANSMISSION CIRCUIT

13. It is necessary to provide sufficient conductor in the feeder portion and in the track-return portion of the complete circuit to maintain at the cars the voltage required for satisfactory operation. The weight of rail is determined by the traffic considerations and the resistance of the track circuit can then be estimated. The amount of current may be estimated from the number, weight, and speed of the cars liable to be in service at the same time on the section of road under consideration. The probable drop in the track circuit may then be calculated. On different roads the total drop in the transmission circuits usually varies from 10 to 20 per cent., where boosters are not used, and may be as high as 40 per cent. of the total generated voltage when a booster is in service.

The drop in the feeders, neglecting that in the mains and trolley wires, is equal to the total allowable drop in the transmission circuit minus the drop in the track portion of the circuit. The size of the feeders may be calculated if their length, the current, and the allowable drop, in volts, are known.

STATION AT ONE END WITH LOAD AT OTHER END

14. Fig. 1 shows the layout of a single-track road 5 miles long. The station is at the extreme left and the load consists of ten 10-ton cars requiring a total current of 200 amperes.



FIG. 1

The generator voltage is 500 and the voltage at the other end of the line when all cars are operating at that point must be 400; that is, the allowable drop is 100 volts. The track consists of 80-pound rails bonded to full conductance. The trolley wire is

No. 00 and is in parallel with the feeder, the two conductors being connected at intervals. What must be the size of the feeder *A B* when the total load is at the end of the line remote from the station, a condition that rarely occurs, but which calls for maximum sectional area of feeder conductor for a given drop.

The resistance of the track is taken as .0356 ohm a mile, as indicated in the fifth line of the fourth column of Table III. The resistance of the 5-mile track-return circuit is $.0356 \times 5 = .178$ ohm; the drop, in volts, is .178 ohm $\times$ 200 amperes $= 35.6$ volts; and the drop, in volts, for the feeder and trolley in parallel is $100.0 - 35.6 = 64.4$ volts.

15. Size of Copper Feeders.—A copper feeder to carry 200 amperes 5 miles, or 26,400 feet, with a maximum drop of 64.4 volts may be calculated by substituting the values of l, I, and u in formula **1**, Art. **3**. The sectional area of the combined feeder and trolley is, $a = \frac{10.8 \times 26{,}400 \times 200}{64.4} = 885{,}000$ circular mils.

The sectional area of the No. 00 trolley wire is approximately 133,000 circular mils, therefore the copper feeder must have a sectional area of $885{,}000 - 133{,}000 = 752{,}000$ circular mils. A 750,000 circular mil cable is the nearest standard size and this should be used.

16. Size of Aluminum Feeders.—The size of an aluminum feeder to be used in place of the copper feeder may be determined for the problem of Art. **14**, by first finding the part of the total current that the No. 00 copper trolley carries. Substitute in formula **1**, Art **3**, the values, $a = 133{,}000$; $l = 26{,}400$, and $u = 64.4$; $133{,}000 = \frac{10.8 \times 26{,}400 \times I}{64.4}$; from which,

$$I = \frac{133{,}000 \times 64.4}{10.8 \times 26{,}400} = 30 \text{ amperes.}$$

If the trolley current is 30 amperes, the current in the aluminum feeder is $200 - 30 = 170$ amperes. Substituting the values of l, I, and u in formula **1**, Art. **5**, $a = \frac{17.17 \times 26{,}400 \times 170}{64.4}$ $= 1{,}197{,}000$ circular mils, about. The nearest standard size

of aluminum cable has a sectional area of 1,000,000 circular mils. If this were used the drop would be a little over that allowed in the problem.

The mil-foot constant for copper is taken as 10.8 and the constant for aluminum as $10.8 \times 1.59 = 17.17$; therefore, a simple method to determine the equivalent size of an aluminum feeder when the size of the copper feeder is known is to multiply the sectional area of the copper feeder by 1.59. The sectional area of the copper feeder of this problem is 752,000 circular mils and $752{,}000 \times 1.59 = 1{,}196{,}000$ circular mils, the sectional area of the aluminum feeder. The difference in the results obtained by the two methods is negligible.

STATION AT ONE END WITH LOAD EVENLY DISTRIBUTED

17. Under ordinary operating conditions, the cars are distributed with approximate regularity along the length of the road. The current in the feeder is greatest at the station end and gradually decreases to zero at the distant end. If the cars are evenly distributed, it may be assumed when making feeder calculations that one-half of the total current is transmitted the whole length of the feeder or that the total current is transmitted from the station to a point distant one-half the length of the feeder.

If an even distribution of the load of ten cars is assumed in the installation shown in Fig. 1 and the feeders calculated for 50 volts total drop when the total current is considered as transmitted one-half the total length of the road, the following results are obtained.

18. The value of l in formula **1**, Art. **3**, is now $26{,}400 \times \frac{1}{2} = 13{,}200$ feet; the value of I is the total current, 200 amperes; the resistance of $2\frac{1}{2}$ miles of single track laid with 80-pound rails is $2\frac{1}{2} \times .0356 = .089$ ohm and the drop due to the passage of 200 amperes is $.089 \times 200 = 17.8$, the value of u being $50 - 17.8 = 32.2$ volts. Substituting values in the formula, the sectional area of the combined feeder and trolley is, $a = \frac{10.8 \times 13{,}200 \times 200}{32.2} = 885{,}000$ circular mils.

Subtracting the sectional area of the trolley, the sectional area of the feeder is 885,000 − 133,000 = 752,000 circular mils for a copper feeder.

An aluminum feeder for the same service should have a sectional area of 752,000 × 1.59 = 1,196,000 circular mils.

19. The size of the feeder is the same as that required to supply a similar total load banked at the end of the system, but with a maximum allowable drop of 100 volts. With the same size of feeder and total load, a distributed load will cause but one-half of the drop as a banked end load. If the drop is to be the same in both cases, the distributed load will require a feeder only one-half the size of that for a banked end load.

If one-half of the current is considered as transmitted the whole length of the road, the value of $l = 26{,}400$ feet and the value of $I = 100$ amperes and the calculated result is identical with that of the other method.

STATION AT CENTER OF ROAD WITH LOAD BANKED AT ONE END

20. With the station at the center of the road and the total load banked at one end, the amount of conductor is much less than with the station at one end and the total load banked at the distant end. In the case of ten cars, requiring a total current of 200 amperes, at A or B, and the station at S, Fig. 2,



FIG. 2

with the generator voltage 500; the maximum allowable drop 100 volts, and the single track laid with 80-pound rails, the drop in the track circuit $2\frac{1}{2} \times .0356 \times 200 = 17.8$ volts. The value of u is $100 - 17.8 = 82.2$; the value of $I = 200$ amperes; and the value of $l = 13{,}200$ feet. Substituting these values in

formula **1**, Art. **3**, $a = \frac{10.8 \times 13{,}200 \times 200}{82.2} = 347{,}000$ circular mils for copper feeder and No. 00 trolley wire. The sectional area of the copper feeder is $347{,}000 - 133{,}000 = 214{,}000$ circular mils; so a No. 0000 copper feeder would probably be used.

An aluminum feeder for the same service should have a sectional area of $214{,}000 \times 1.59 = 340{,}000$ circular mils.

The result of locating the station at the center instead of at the end of the road as in the problem of Art. **14** is to permit the use of a feeder approximately one-fourth the size.

21. Allowance for Rail Drop.—An allowance for rail drop is incorporated in the constants of the formulas of Arts. **4** and **6**. These constants are based on the assumption that the resistance of the rail return is not usually as high as the resistance of the overhead portion of the circuit nor less than .25 per cent. of it. The formulas are approximate for calculating feeders when the bonded joints are in good condition. If after installation the total drop is found to exceed that assumed, the bonding of the joints probably needs attention.

STATION AT CENTER WITH SECTIONALIZED LINE

22. Fig. 3 shows the general arrangement of feeders, mains, and trolley wires for a double-track road that is divided into seven sections by insulators *a*, *b*, *c*, *d*, *e*, and *f*. The number of cars in each section, the total current taken by each section, the length of the sections and of the feeders *1* to *7* which extend from station *g* are as indicated. The two trolley wires are of No. 00 copper; feeders No. *1*, *2*, *3*, *4*, and *5* are of copper and feeders *6* and *7* of aluminum. The feeders are connected to the centers of the sections and the mains and the trolley wires are tied together at frequent intervals. The rail-return circuit is assumed to be in such condition that the constants 14 ohms per mil-foot for the combined copper and track and 22 ohms for the combined aluminum and track may be used, as explained in Arts. **4** and **6**. The drops in the mains and in the trolley wires will not be considered in the feeder calculations. A total


2 Cars
6000'
40 Amperes
12000'
92 Amperes
4 Cars
5500'
8000'
10200'
3 Cars
8500'
60 Amperes
5480'
5480'
1800'
1800'
a
b
c
d
e
f
g
1
2
3
4
5
6
7
7 Cars
5280'
182 Amperes
7 Cars
2640'
210 Amperes
7 Cars
2640'
210 Amperes
7 Cars
5280'
182 Amperes

FIG. 3

of thirty-seven cars are used to enable the road to operate a 2-minute time table. The bus-bar voltage is 600 and a line voltage of 550 is maintained at all sections. The permissible drop in the transmission circuit of each section is, therefore, 50 volts under the assumed conditions. The sections in which the traffic is congested take more current than the outlying sections because there are more cars on the central sections and they start oftener. The following data relates to the various sections:

Number of Feeder	Length of Feeder Feet	Material of Feeder	Number of Cars in Section	Number of Tons	Current Supplied Each Section Amperes	
					Per Ton	Per Feeder
1	1,800	Copper	7	70	3.0	210
2	1,800	Copper	7	70	3.0	210
3	5,480	Copper	7	70	2.6	182
4	5,480	Copper	7	70	2.6	182
5	8,000	Copper	4	40	2.3	92
6	10,200	Aluminum	3	30	2.0	60
7	12,000	Aluminum	2	20	2.0	40

23. Copper Feeders.—Formula **1**, Art. **4**, is used to determine the sectional area of the copper feeders. The values for the different feeders that are to be substituted in the formula may be taken from Fig. 3 or from the tabulated data of Art. **22.**

For feeders Nos. 1 and 2, $a=\frac{14\times1,800\times210}{50}=106,000$ circular mils, about. The nearest standard conductor is No. 0. In this case, however, the carrying capacity of the conductor dictates the choice of at least a No. 00 conductor, as will be explained later.

For feeders No. 3 and 4, $a=\frac{14\times5,480\times182}{50}=279,000$ circular mils. The nearest standard single conductor has a

sectional area of 250,000 circular mils. Two No. 00 conductors having a combined sectional area of 266,200 circular mils would probably be used.

For feeders No. 5, $a = \frac{14 \times 8{,}000 \times 92}{50} = 206{,}000$ circular mils.

The nearest standard conductor is No. 0000, which has a sectional area of 211,600 circular mils and would probably be used.

24. Aluminum Feeders.—Formula **1**, Art. **6**, is used to determine the cross-sectional area of the aluminum feeders.

For feeder No. 6, $a = \frac{22 \times 10{,}200 \times 60}{50} = 269{,}000$ circular mils.

The nearest standard aluminum conductor has a sectional area of 250,000 circular mils and would probably be used.

For feeder No. 7, $a = \frac{22 \times 12{,}000 \times 40}{50} = 211{,}000$ circular mils.

The nearest standard aluminum conductor is No. 0000, having a sectional area of 211,600 circular mils, and this would probably be used.

25. Current-Carrying Capacity of Feeders.—When calculating the size of a long feeder for a permissible drop in volts, the calculated result will usually indicate a size of feeder large enough to carry the necessary current safely. When the size of a short feeder is calculated, however, the result may indicate a size of feeder that is not large enough to carry the current safely. It is well, therefore, to check the calculated wire with a table showing the current-carrying capacity of conductors.

In the case of the feeders *1* and *2* of Fig. 3, the calculated feeder No. 0 is not large enough to carry safely a current of 210 amperes, therefore, a No. 00 or larger feeder should be used for each of these sections. The feeders indicated by the other calculations are of sufficient sectional area to carry safely the required current.

When checking the carrying capacity of an aluminum feeder, reference should be made to the carrying capacity of the

equivalent copper conductor as indicated in *Long-Distance Transmission of Electrical Energy*. The carrying capacity of an aluminum feeder may be safely assumed equal to that of a copper conductor of equal length and resistance; in fact, the aluminum conductor being larger has greater radiating surface and should remain cooler than the copper conductor when carrying the same current.

Table V indicates approximately the current-carrying capacity of copper feeders with an allowance of about 25° F. rise in

TABLE V
CURRENT-CARRYING CAPACITY OF COPPER FEEDERS

Gauge Number	Approximate Sectional Area of Feeder Circular Mils	Capacity of Feeder Amperes
	500,000	509
	400,000	426
	350,000	388
	300,000	355
	250,000	319
0000	211,600	275
000	167,800	237
00	133,100	195
0	105,500	168
1	83,690	143

temperature above the surrounding air. The current-carrying capacity of a conductor does not increase in direct proportion to its sectional area because the cross-section increases as the square of the diameter and the radiating-surface area as the first power of the diameter.

26. Checking Feeder Calculations for Drop in Voltage.—The data of Tables VI and VII may be used to check the results of the feeder calculations. Take for instance feeder 7. The resistance of 1,000 feet of No. 0000 aluminum cable, Table VII, is .08 ohm approximately; 12,000 feet has a resistance of .96 ohm. The feeder drop with a current of 40 amperes

TABLE VI

PROPERTIES OF STRANDED COPPER CABLES

B. & S. Gauge Number	Diameter of Bare Cable Mils	Area of Bare Cable Circular Mils	Weight of Cable, in Pounds		Number of Feet per Pound	Resistance of Cable at 68° F. Ohms	
			Per 1,000 Feet	Per Mile		Per 1,000 Feet	Per Mile
	1,632	2,000,000	6,100	32,208	.164	.00518	.02733
	1,412	1,500,000	4,575	24,156	.219	.00690	.03644
	1,152	1,000,000	3,050	16,104	.328	.01035	.05466
	1,000	750,000	2,288	12,078	.437	.01380	.07290
	819	500,000	1,525	8,052	.655	.02070	.10930
	728	400,000	1,220	6,442	.819	.02590	.13660
	679	350,000	1,068	5,636	.936	.02960	.15620
	630	300,000	915	4,831	1.093	.03450	.18220
	590	250,000	762	4,026	1.312	.04140	.21860
0000	530	211,600	645	3,405	1.550	.04890	.25830
000	470	167,800	513	2,709	1.950	.06170	.32580
00	420	133,100	406	2,144	2.460	.07780	.41080
0	375	105,500	322	1,700	3.210	.09810	.51800
1	330	83,690	255	1,347	3.940	.12370	.65300
2	291	66,370	203	1,072	4.930	.15600	.82400
3	261	52,630	160	845	6.250	.19670	1.03900
4	231	41,740	127	671	7.870	.24800	1.30900

TABLE VII

PROPERTIES OF STRANDED ALUMINUM CABLES

B. & S. Gauge Number	Diameter of Bare Cable Mils	Area of Bare Cable Circular Mils	Weight of Cable, in Pounds			Resistance of Cable at 75° F. Ohms	
			Per 1,000 Feet	Per Mile	Feet per Pound	Per 1,000 Feet	Per Mile
	1,152	1,000,000	920.0	4,858	1.087	.01695	.0895
	996	750,000	690.0	3,645	1.450	.02260	.1193
	814	500,000	460.0	2,430	2.040	.03300	.1790
	725	400,000	368.0	1,944	2.720	.04240	.2240
	679	350,000	322.0	1,701	3.110	.04840	.2560
	621	300,000	276.0	1,458	3.620	.05650	.2980
	567	250,000	230.0	1,215	4.350	.06780	.3580
0000	522	211,600	195.0	1,028	5.730	.08000	.4230
000	464	167,800	154.4	816	6.480	.10100	.5330
00	414	133,100	122.4	647	8.160	.12700	.6730
0	368	105,500	97.1	513	10.300	.16000	.8470
1	328	83,690	77.0	407	13.000	.20200	1.0690
2	291	66,370	61.0	323	16.400	.25500	1.3500
3	261	52,630	48.5	256	20.600	.32200	1.7000
4	231	41,740	38.5	203	26.000	.40600	2.1440

is 38.4 volts. Assuming that 90-pound rails are used on the double track and that the distance along the track from the distant end of feeder 7 to the station, Fig. 3, is 3.1 miles, approximately, the resistance of 1 mile of double track with 90-pound rails, Table III, is .015818 ohm; 3.1 miles will have a resistance of .049 ohm. The drop for a current of 40 amperes is 1.96 volts. The drop in feeder and track return is 38.4 $+1.96=40.36$ volts. This indicates that the bonds must be in poor condition to bring the total drop to 50 volts when a No. 0000 feeder is used.

Copper feeder 5 may be checked in a similar manner. The resistance of 8,000 feet of No. 0000 copper conductor, Table VI, is $.0489\times8=.3912$ ohm. The resistance of 2 miles of track is $.015817\times2=.031634$ ohm. The total resistance of feeder and track is $.3912+.031634=.422834$ ohm. The drop in the feeder and track when carrying a current of 92 amperes is $.422834\times92=38.9$ volts. The rails may be bonded to considerably less than full conductance and yet the total drop will not exceed 50 volts when feeder 5 is of No. 0000 copper wire.

SINGLE-PHASE ALTERNATING-CURRENT ROAD

27. When alternating current is used for propulsion, the drop in voltage in the feeder and track return of a system is much greater than when the same value of direct current is used, because of the inductance of the circuit. It has been experimentally determined that the impedance of the overhead copper feeder and trolley wire with 25-cycle alternating current is 1.5 times their resistance to the passage of direct current; and that the impedance of the track return is 6.6 times its resistance with direct current. These are figures of approximate value only. Under conditions of similar values of current and drop in voltage, the feeder for alternating-current propulsion would therefore be much larger than that required for direct-current propulsion.

It is customary, however, to use higher voltages and correspondingly lower currents in alternating-current railway work. Alternating voltages as high as 11,000 are in use, and with the

same per cent. drop as in direct-current work, the allowable drop, in volts, for the alternating-current feeders is high enough to permit the use of feeders of moderate size.

28. The calculation of feeders for a single-phase alternating-current road may be made with approximate accuracy as follows: The drop in the track return for the same value of direct current as the alternating-current load is calculated and this value multiplied by 6.6 gives the track-return drop for alternating current. The total alternating-current drop is found by multiplying the impressed line voltage at the station by the per-cent. drop that is to be allowed. Subtracting the alternating-current track return drop from the total drop gives the alternating-current drop to be allowed for the feeder. The direct-current drop for the feeder equals the alternating-current drop divided by 1.5. When the direct-current drop for the feeder is determined, the size of copper feeder may be calculated by formula **1**, Art **3**, and for an aluminum feeder by formula **1**, Art. **5**.

THIRD-RAIL ROAD

29. Conductor rails have considerable current-carrying capacity, and with roads on which the load is not heavy, the conductor rails serve to transmit the entire current, thus making



FIG. 4

unnecessary the use of copper feeders. On third-rail roads involving the operation of trains over long distances, however, copper feeders are usually installed.

Fig. 4 shows a double-track road supplied with current through two conductor rails *a* from a substation *b* at the middle

of the system. The station voltage is 650 and the allowable drop is 100 volts when one-half of the total load is banked at either end of the road. The load consists of four 50-ton cars, which require an average current of 2.5 amperes per ton, the total current is $4 \times 50 \times 2.5 = 500$ amperes; so a load of 250 amperes is considered as being banked at each end of the road. The track is laid with 90-pound rails. The two conductor rails are discarded 70-pound track rails with a resistance ratio of 12 to 1. These rails are normally connected in parallel and have a total sectional area of 17,825,000 circular mils and in case of trouble may be divided into four sections by the switches c. The total distance that the two conductor rails may be extended from the substation and still keep within the allowed drop in voltage is to be determined.

30. The approximate distance l that the conductor rail or rails of a third-rail road may be extended from the station or substation may be calculated from the formula,

$$l = \frac{a\,u}{190\,I}$$

in which, a = total sectional area of conductor rails used to supply current to section of road under consideration;

u = allowable drop in these conductor rails and track return, in volts;

I = current in these conductor rails.

Substituting the values stated in the problem,

$$l = \frac{17{,}825{,}000 \times 100}{190 \times 250} = 37{,}526 \text{ feet} = 7.1 \text{ miles.}$$

The conductor rails may be extended to a distance of 7.1 miles from the substation in either direction, without the drop exceeding 100 volts.

31. If 70-pound conductor rails having a resistance ratio of 8 to 1 were substituted for the discarded track rails the allowable distance would be, $l = \frac{a\,u}{146\,I}$; or $l = \frac{17{,}825{,}000 \times 100}{146 \times 250} = 48{,}836$ feet = 9.25 miles.

32. The results of the calculation of Art. **31** may be checked as follows: The resistance of the two 70-pound conductor rails in parallel, bonded to full conductance, and having a resistance ratio 8 to 1 is, by Table IV, $9.25 \times .0271256$ ohm, and the drop is $9.25 \times .0271256 \times 250 = 62.73$ volts. The resistance of 9.25 miles of four lines of 90-pound track rail in parallel, bonded to full conductance, is, by Table III, $9.25 \times .015818$ ohm and the drop is $9.25 \times .015818 \times 250 = 36.58$ volts. The totai drop is $62.73 + 36.58 = 99.31$ volts. This checks closely with the allowable drop of 100 volts.

IMPORTANCE OF LOW-VOLTAGE DROP

33. In order to maintain satisfactory service on an electric road, it is important that the voltage at any portion of the line be approximately the value for which the car motors were designed. Low line voltage may be due to low generator voltage, or to excessive drop in the line caused by overload, poor condition of the track bonds, or small feeders.

Low line voltage is likely to result in damage to the car apparatus because of the abuse to which it is subjected by the motorman in an endeavor to keep the car on schedule time. With low voltage the speed of the car when the controller is on its final running position is much lower than normal and motormen are apt to make up time by rapid acceleration with the result of causing burnt controller fingers, motor windings, and commutators.

Excessive drop also means a large amount of electric energy lost in the transmission circuit. The relative cost of generating electric energy and of installing increased conductor determines whether or not it is advisable to use additional feeders.

LINE TESTS

BOND TESTS

34. Test of the conductance of rail joints should be made at intervals to determine their electric condition. The usual method is to compare the resistance of a length of 3 feet of rail, including the bonded joint, with the resistance of 3 feet of solid rail. The resistance of the joint is expressed as equivalent to the resistance of a certain number of feet of solid rail of the same sizes as the jointed rail. The bond makers assume for newly made joints a rail equivalent as low as 2.5 feet and this may be realized with careful installation. The advantage of bonds with low rail equivalent is that a good rail-return path is assured for possibly several years without further attention.



FIG. 5

The resistance of the rail-return portion of the circuit, especially on double-track roads, is but a small part of the total resistance through feeders and rails; therefore, the joints may uniformly deteriorate somewhat without materially affecting the drop, in volts, of the transmission circuit. In cases where the load is not very heavy less copper can be used for the bonds, resulting in a higher rail equivalent; but care should be taken that the joints are maintained in good condition.



FIG. 6

A large number of tests of joints in actual service indicate that the rail equivalent of the bonded joint is seldom less than 6½ feet and that an average value is about 12 feet.

Among the methods employed to test bonds are those employing a differential voltmeter, a Wheatstone bridge, and a bond testing car.

35. Differential Voltmeter Method.—Fig. 5 indicates the connections of a differential voltmeter *a* when used to test bonded joints. The voltmeter has two coils and is provided with three terminal leads *b*, *c*, and *d*. Terminals *b* and *c* of one coil are in contact with the rail equal distances from a joint between them and terminal *d* at some point farther along the rail. The current in the rail causes voltage drops between the contacts, and these voltages establish currents in the two coils. The two magnetic fluxes set up by the coils are in opposition and contact *d* is moved along the rail until the needle of the instrument rests at zero. This indicates that the drop in voltage between *b* and *c* equals that between *b* and *d*. The resistance of the length of rail *b c* including the joint is then equal to the resistance of the length of solid rail *b d*. The lengths of rails between terminals are read from the scale to which the rail contact points are attached.

36. Bridge Method With an Adjustable Contact. Fig. 6 indicates the connections of a millivoltmeter when used for testing a bonded joint. The millivoltmeter *a*, with a scale having the zero point at the center, is provided with three terminals, two of which *b* and *c* are a fixed distance apart and are placed equidistant from the joint between them. The other terminal *d* is moved along the rail until a balance of the bridge resistance is indicated by the instrument needle resting at zero. When the bridge is balanced, the number of feet of rail between *b* and *d* is the solid rail equivalent of the joint.

37. Bridge Method With Fixed Contacts.—In Fig. 7 is shown a bond-testing outfit operated on the Wheatstone bridge principle with three fixed contacts *a*, *b*, and *c* that make good connections with the rails when the supporting rod is pressed down by the operator's foot. The plate *p* is placed

over the center of the joint. There is 3 feet of solid rail between *a* and *b* and 3 feet of rail including the joint between *b* and *c*. The bridge is balanced by adjusting the resistance sections *d*, Fig. 8, by means of switch *s* mounted on the test box carried by the operator. The telephone receiver *e* worn over the operator's ear and connected in series with a mechanical circuit-interrupting device *f* then makes minimum sound when the interrupter is operated. If the balanced position of switch *s*



FIG. 7

is as shown, the resistance of *g h* is to that of *a b* as the resistance of *h k* is to that of *b c*. The contact points of switch *s* are numbered to give the resistance of the bonded joint expressed in terms of 3-foot rail lengths. If the balance point is on contact No. 1 the resistance of the section of rail including the joint is equal to 3 feet of solid rail; a balance on contact No. 1.5 means that the resistance of the joint section is equal to $3 \times 1.5 = 4.5$ feet of solid rail. Joints indicating a high resistance are usually marked for repairs.

In some forms of bond testers, the telephone receiver is replaced by a galvanometer. A small switch button on the instrument controlling the resistance sections is turned until the galvanometer needle rests at zero. The rail equivalent is then read from a scale at the point at which a needle attached to the rotating button rests.

38. Autographic Bond-Testing Car.—Fig. 9 (*a*) indicates the more important connections of the Herrick bond-testing apparatus as installed on a test car for the purpose of making a record, on a moving chart, of the comparative condition of the bonded joints as the car passes over the track.



FIG. 8

In order to assure sufficient current in the rail for readable deflections on the instruments, the generator of a motor generator set *a* is connected through a reverse switch and truck wheels to the rails. The reverse switch serves to make the direction of the local current agree with that of the rail-return current from other cars on the section.

The drop in voltage between the brush terminals *b* and *c* that bear on the rail treads is measured by a sensitive millivoltmeter *d*. The needle and scale of this voltmeter are shown enlarged just above *d*. A portion of the needle *e* of the millivoltmeter *d* is of metal and when deflected moves over, but without touching, a metal sector *f* and several metal segments *g*. Each scale segment is connected to a corresponding metal point in a row of terminals *h* at the recording device.

A paper chart, the movement of which is caused by the car mechanism, passes between the row of terminals *h* and a metal



(a)



(b)

FIG. 9

roll *i* as indicated in the detail sketch, view (*b*). A small induction coil operated by a battery and interrupter has one secondary terminal connected to sector *f*, view (*a*), and the other terminal to roll *i*. The secondary circuit includes spark gaps between *f* and *e*, between *e* and the particular segment *g* over which the needle may be moving at any instant; and between the point on *h* corresponding to the active segment *g* and the roll *i*. When the interrupter operates, sparks jump through the three gaps and the chart will be perforated.

The position of the hole depends on the deflection of the needle *e* which in turn depends on the drop in volts between *b* and *c*. Bonds in good condition are indicated by holes near the margin of the chart and faulty bonds by holes near the middle of the chart, as at *j* and *k*, view (*b*).

The apparatus for tests on one rail is indicated; there is, however, duplicate apparatus that makes a record for the other rail. The faulty bond indicated at *j* is on one rail of the track and *k* indicates a faulty bond on the other rail.

39. If the bonded joint is in unusually bad condition, the needle *e*, Fig. 9 (*a*), swings far to the right, making a spark hole nearer the middle of the chart than normal. The needle *l* of a less sensitive millivoltmeter *m* which is connected normally in parallel with millivoltmeter *d* is moved sufficiently to cause a star wheel to dip into mercury cups. A local-battery circuit is then completed including relay *n*. This relay operates a switch that cuts out of the circuit millivoltmeter *d*, thus protecting it from overload damage, and at the same time closing a circuit through coil *o*, which causes a pen *p* to make a small mark, like *q* or *r*, view (*b*), on the margin of the chart at the point where a faulty bond is also indicated by the spark holes. As soon as the faulty bond is passed the needle *l* drops toward zero, and millivoltmeter *d* is again cut into circuit.

A pen *s*, view (*a*), near the middle of the chart, is moved by a magnet controlled by a push button operated by the tester so as to make a mark on the chart as the line poles are passed by the car. At the same time the number of the pole is printed on the chart by means of a numbering stamp. In some cases

a small quantity of blue powder is automatically squirted on the track at the location of faulty bonds. After a test run, the chart should be carefully inspected and the faulty bonds repaired.

Bond tests are of most service when made periodically so that successive results of tests can be compared and deteriorations noted.

FEEDER AND TRACK-RETURN TESTS

40. After a road has been in operation for a considerable period, the drop in voltage on certain sections may be much greater than on other sections operating under similar conditions. Tests may be made to determine whether the fault is in the feeder or the track-return portions of the circuit.

Fig. 10 indicates the connections for a test on the transmission circuit. The generator at the station is shown at *a*;



FIG. 10

a circuit-breaker at *b*; a feeder to the section under test at *c*; an adjacent feeder, used as a voltmeter lead, at *d*, this feeder being temporarily grounded at its station end; trolley sections at *e* and *f*; a section insulator at *g*; an ammeter at *h*; a water rheostat at *i*; a voltmeter at *j* in position for measuring the drop in voltage of the track return; and the same voltmeter at *k* connected for measuring the drop in voltage in the feeder.

The test is usually made at night when all car load can be removed from the section. The breaker *b* is closed and the water rheostat is adjusted to get readable deflections of the voltmeter. Care should be taken that none of the load current

passes through any part of the conductors used as extension leads of the voltmeter, as *d*, *e*, and *f*. The voltmeter connections to the rail should be made near the point of the load-current connection, but should be a separate contact. The ammeter indicates the total current in the circuit; the voltmeter *j* indicates the drop in voltage in the track return; and the voltmeter reading divided by the ammeter reading is equal to the resistance of the rail-return portion of the circuit.

To determine the drop in voltage in the feeder, the voltmeter *k* should be connected as indicated by the dotted lines and a connection made between the left ends of *c* and *d*, the station ground connection of *d* being removed. This voltmeter reading divided by the ammeter reading equals the resistance of the feeder *c*.

The test determines the resistance of the two portions of the transmission circuit; therefore, the portion responsible for the excessive drop is determined. A test of this kind on the track is useful in determining the total resistance of a length of track including rails and bonded joints.

GENERAL ENGINEERING FEATURES

RAIL CALCULATIONS

41. Relation of Rail Weight to Sectional Area.—The relation of rail weight to sectional area (see Art. **10**) is expressed by the formula,

$$W_y = 10\,A$$

in which W_y = weight of rail, in pounds per yard;
A = sectional area, in square inches.

EXAMPLE 1.—A rail weighs 95 pounds per yard; what is its sectional area, in square inches?

SOLUTION.—Substituting for W_y its value 95 in the formula, $95 = 10\,A$, $A = 95 \div 10 = 9.5$ sq. in. Ans.

EXAMPLE 2.—A rail has a sectional area of 8 square inches; what is its weight per yard?

SOLUTION.—Substituting for A its value 8 in the formula, $W_y = 10 \times 8 = 80$ lb. per yd. Ans.

42. Weight of Rails Per Mile.—The weight of rails per mile W_m of single track, expressed in long tons, is equal to the weight per yard W_y of the selected rail multiplied by $\frac{11}{7}$, or

$$W_m = \tfrac{11}{7} W_y \qquad (1)$$

The formula for double-track construction is,

$$W_m = \tfrac{22}{7} W_y \qquad (2)$$

EXAMPLE.—A single track is laid with rails weighing 100 pounds per yard; what is the weight per mile of track, expressed in long tons?

SOLUTION.—Substituting, in formula **1**, the value of 100 for W_y, $W_m = \frac{11}{7} \times 100 = 157$ tons. Ans.

CURVE CALCULATIONS

43. Methods of Designating Curvature.—The method of stating the curvature of simple curves on interurban tracks is to state the number of degrees subtended by a chord 100 feet in length, the ends of which touch the center line of the track. A *chord* of a circle is any straight line between two points in the circumference of the circle; it subtends the angle between radii drawn from its ends. Thus, in Fig. 11, $a\,b$ is a chord that subtends the angle $a\,c\,b$. A line perpendicular to the chord at its middle point and ending in the circumference of the circle, as $d\,e$, is the *middle ordinate* of the chord.



FIG. 11

When considering track curvature, it is usual to refer to the center curve of the track, which is equally distant from either track rail. The difference in curvature between the center curve

and either rail curve is very small for track curves having a long radius, but is much greater for track curves of small radius.

For city work, it is customary to designate the track curvature of simple curves by the length, in feet, of the track radius of the arc formed by the center line of the track at the curve. This radius is indicated by *c e* in Fig. 11.

The radius of the inner-rail curve is found by subtracting one-half the track-gauge distance plus the width of the rail head from the track-curve radius; and the radius of the outer-rail curve is found by adding one-half the track-gauge distance to the track-curve radius. The track-curve radius equals the radius of the outer-rail curve minus one-half the track gauge.



FIG. 12

44. Assume that the outer-rail curvature of a simple railway curve is as shown in Fig. 12. Stretch a tape line from a point *a*, touching the rail head on the inner side of the curve, to a point *b* touching the rail head at another point and note the length, in feet, of chord *a b*. With the tape held taut, measure the length, in feet and decimal of a foot, of the middle ordinate *d e*. From these two measurements the radius of curvature *c e* of the outer rail can be calculated, using the formula

$$r = \frac{a^2 + b^2}{2a}$$

in which r = radius of outer rail, in feet;
a = middle ordinate, in feet;
b = half the length of chord, in feet.

EXAMPLE.—On a simple curve for city work a 20-foot chord is laid out on the outer rail, and the middle ordinate is 18 inches. The width of the rail head is 2.25 inches = .19 foot, and the track gauge is 4 feet $8\frac{1}{2}$ inches = 4.708 feet. What is the radius of: (*a*) the curvature of the outer rail? (*b*) the track curvature? (*c*) the curvature of the inner rail?

SOLUTION.—(*a*) Substituting the value of $a = 18$ in. $= 1.5$ ft., and $b = 10$ ft. in the formula, $r = \frac{1.5^2 + 10^2}{2 \times 1.5} = 34.08$ ft. Ans.

(*b*) The radius of the track curvature is $34.08 - \frac{4.708}{2} = 31.73$ ft. Ans.

(*c*) The radius of the curvature of the inner rail is

$$31.73 - \left(\frac{4.708}{2} + .19\right) = 29.19 \text{ ft.} \quad \text{Ans.}$$

45. Bending Rail to a Given Radius.—Rail bending for short curves for city streets is usually done at the rolling mill. Rail benders are often used on the installation work for bending rail for longer curves. When bending a rail for a simple curve of any given radius r, the middle ordinate of any arbitrarily chosen chord on the selected curve should be known; then the curvature of the rail can be tested during the process of bending, for the middle ordinate for a given chord is the same for any position of the chord on a simple curve.

If the radius and the length of the chord are known the middle ordinate can be calculated by the formula

$$a = r - \sqrt{r^2 - b^2}$$

in which the letters have the same meaning as in the formula of Art. **44.**

EXAMPLE.—It is desired to predetermine the length of a middle ordinate of a 20-foot chord used to check a simple outer-rail curve, the radius of which is 34.08 feet.

SOLUTION.—Substituting the values of r and b in the formula,

$$a = 34.08 - \sqrt{34.08^2 - 10^2} = 34.08 - 32.58 = 1.5 \text{ ft.} \quad \text{Ans.}$$

46. Construction of Simple Curves.—Simple curves can be laid out with a tape line, as shown in Figs. 13 and 14.

A line *a b* is laid out perpendicular to rails at the end of one section of the tangent, or straight portion of the track, and a corresponding perpendicular line *c d* at the end of the other section of the tangent track. A steel square held against the rails aids in laying out the perpendicular lines. The point *e* at which the lines *a b* and *c d* cross is the center of the rail and track curves. The line *a e* is the radius of the outer-rail curve and the line *e f* the radius of the inner-rail curve. The radius *a e* is used to locate points on the curvature for the outer rail, and



FIG. 13



FIG. 14

these are marked with stakes. Points on the curvature of the inner rail are also located in a similar manner by using the radius *e f*.

Templates of wood may be prepared to which the rails are bent by the rail bender, or a rail may be bent a little at a time and laid on the ties to see whether its curve conforms to the location stakes. As rail ends are hard to bend to a true curve, sections at the ends of the bent rails are sometimes cut out and new holes drilled for the rail joints. The improvement in curvature often warrants the extra labor.

GRADE CALCULATIONS

47. Per Cent. Grade.—The per cent. of a grade is usually considered in railway work as being numerically equal to the number of feet that a car is raised when traveling over 100 feet of track; thus, if a car is raised 6 feet in passing over a distance of 100 feet of track, the grade is 6 per cent. In general, the per cent. grade g is

$$g=\frac{r\times 100}{d},$$

in which r is the number of feet the car is raised in passing over a track d feet in length.

EXAMPLE.—On a certain grade a car is raised 4.3 feet in traveling over 344 feet of track; what is the per cent. of grade?

SOLUTION.—Substituting the values of $r=4.3$ and $d=344$ in the formula, the grade is $g=\frac{4.3\times 100}{344}=1.25$ per cent. Ans.

48. Grade Rise.—If the per cent. of grade g is known, the number of feet r that a car is raised when passing over a distance d can be calculated by the formula

$$r=\frac{g\,d}{100}$$

in which g is taken as a whole number.

EXAMPLE.—A car runs over 344 feet of track that has a grade of 1.25 per cent.; through what distance is the car raised?

SOLUTION.—Substituting the values of $g=1.25$ and $d=344$ in the formula, $r=\frac{1.25\times 344}{100}=4.3$ ft. Ans.

TRACK TESTS

49. Curvature Tests.—Fig. 15 indicates the **straightedge method** of testing a simple curve for accuracy of curvature. This consists in holding a straightedge $a\,b$, provided with an adjustable perpendicular projection $d\,e$ at its middle point, against the head of either the inside or the outer rail.

This test is made on the inside of the rail curve. If points *a*, *e*, and *b* touch the rail head simultaneously when the straightedge is applied to one part of the curve, they should touch at all parts of the curve; if they do not, the curve is not true. This method is useful on curves sufficiently short for a 6-foot to 10-foot straightedge to show a middle ordinate long enough for differences to be easily noticed. A steel tape and rule may be used in place of the straightedge for curves of longer radius.



FIG. 15

50. A test by the **sighting method** is indicated in Fig. 16. It may be used where the radius of curvature is too great for even a tape line to be used. From a point *a* at a joint on the outer rail sight across to a point *b* on the same rail that is so located that the sighting line is tangent to the gauge line of the inner rail at some point *d*. The middle ordinate is now the track gauge, usually 4 feet 8½ inches. The number of rails between *a* and *b* should be counted and this number should be approximately the same when the test is made on any portion of the simple curve.



FIG. 16

51. Grade Test.—The per cent. grade of a track may be tested as indicated in Fig. 17. A level *a* is placed on a long straightedge *b* and the straightedge adjusted so as to be level; a rule or tape is used to measure the distances *c d* at right angles to *b* and the track distance *d e*. The per cent. of grade can then be calculated as explained in Art. **47**, where *r* is the distance *c d*, Fig. 17, and *d* is the distance *d e*.



FIG. 17

ELECTROLYSIS

52. Elementary Principles.—The form of electrolysis here considered relates to the gradual eating away of metal objects buried in the ground, such as gas and water pipes, which action is likely to occur when the pipes act as conductors for portions of the return current of a railway system.



FIG. 18

If two iron plates A and B, Fig. 18, are buried in the ground and so connected that electricity flows from A through the earth to B, plate A will be eaten away or pitted while plate B will not be damaged. This is practically the same electro-chemical effect that takes place in electroplating, where metal is taken from a plate, or anode, and deposited on the article to be plated. The point to notice is that wherever electricity flows *from* a metal conductor into damp earth, the conductor is eaten away, provided that the drop in voltage between the conductor and the adjacent earth is sufficient to effect the chemical decompositions; but where electricity flows



FIG. 19

from the earth *into* the conductor, the latter is not damaged. The rate at which the metal will be eaten depends on the strength of the current.

53. Electrolysis Due to Railway Currents.—Fig. 19 indicates in a simple manner how electrolysis may be caused by the flow of stray electricity of an electric-railway system. The normal path of the current, if the rail-return section is in good condition, is indicated by the full-line arrows. In case of poor bonding, some of the return electricity may flow from the rail to an adjacent pipe and from the pipe to the ground near the station, as indicated by the dotted arrows. The pipe is likely to be damaged at the point near the station where the electricity flows from the pipe to the earth.

Fig. 20 indicates a modification of the simple case shown in Fig. 19. The stray electricity leaves the rail *a*, Fig. 20, enters the pipe *b*, and flows through this pipe until a better path is found in the lead covering of the cable *c*. Electricity flows



FIG. 20

along *c* until the track again forms a better path, when it flows back to the rail. The path of the stray electricity is indicated by the arrows. Electrolytic action may occur at the points where the electricity flows from the rail, the pipe, and the cable.

54. Prevention of Electrolysis.—A large system of piping forms a conducting network of very low resistance in parallel with the track, hence it is very difficult to prevent part of the current from leaving the track and entering the pipe. However, if proper steps are taken, the bad effects of electrolysis can be largely avoided; the following are the main points that experience has shown should be observed:

1. The trolley wire should be made the positive side of the system.

2. The track should be thoroughly bonded and the bonds maintained in good condition.

3. Any metallic connections that may exist between piping or cable systems and the track should be located and removed.

4. Return feeders should be run out from the station and connected to those pipes that carry the greater part of the current; thus, the current in the pipes will be drained off without passing from the pipes to ground.

5. Where service pipes, cables, or underground conductors pass under tracks or through other regions where they are exposed to electrolytic action, they can often be protected by covering them with glazed tile or by placing them in a trough filled with asphalt.

6. If in any part of a system the rail return carries an excessive current, return feeders should be run so as to relieve the rail of part of the current and prevent an excessive drop in voltage along the rail. The greater the drop in voltage in the rails, the greater is the tendency for the current to pass off to neighboring pipes.

The remedy given under 3 is important. Very often accidental connections exist between the rails and pipe so that current can pass directly to the piping system. This is specially the case where pipes run across iron bridges that also carry railway tracks. Before attempting to drain off the current from a piping system, all metallic connections between track and pipe must be removed. Where pipes pass across iron bridges, the best plan is to insulate the pipe from the bridge, or if this is impossible, insulate the pipe by the insertion of insulating joints at either end of the bridge.

Remedy 4 is very commonly practiced and gives good results if properly applied. The return feeders should be attached to the pipes that carry the most current and, as a rule, the current so returned to the power house will not be more than 5 or 6 per cent. of the total current; if it exceeds this amount it is probable that there is a metallic connection somewhere between the track and pipes. Pipes crossing under street-car tracks are subject to electrolysis, and when laid or repaired are easily covered with tile or run in a box.

RAILWAY MOTORS

PRELIMINARY CONSIDERATIONS

OPERATING REQUIREMENTS

1. The motors commonly used in America for electric-railway work are of the series-wound type because of their strong starting torque. The larger number of railway motors are intended for operation with direct current, but by a modification in design, series-wound commutator motors are adapted for operation with either direct current or single-phase alternating current. A car equipped with these motors and with the necessary switching apparatus may pass directly from a road operating with one kind of current to a road operating with the other kind.

Railway motors must withstand harder service, both mechanically and electrically, than most motors in stationary applications. Motors for electric locomotives are sometimes mounted within the cab, but for electric cars are generally placed on the trucks, where they are exposed to dirt and dampness. Because of limited space allowance, the motor must be built very compactly and its capacity relative to its size is high. The frame is usually of cast steel; but the frame halves of some motors are formed of steel plates pressed into the desired shapes. The frame must protect the active parts from water and dirt and yet allow ventilation of armature and field coils. The heat set up by the current in the windings may be removed from the motor frame by proper ventilation, so as to prevent rapid deterioration of the insulating material.

COPYRIGHTED BY INTERNATIONAL TEXTBOOK COMPANY ALL RIGHTS RESERVED

GEAR REDUCTION

2. The armatures of large motors for electric locomotives are in some cases installed directly on the axles of the trucks; in other cases the motors are mounted in the cabs and connected by driving rods and connecting-rods to the locomotive drivers. In such cases the armatures rotate at the same rate as the drivers.

The railway motor of moderate size is usually provided with a pinion on the armature shaft that engages with a gear mounted on the axle of the car. In order to protect the pinion and gear from dirt, to lessen wear, and to diminish the noise of operation, they are enclosed in a gear-case that contains a quantity of heavy oil.

The armature revolves at a comparatively high speed and the car axle at the lower speed desired for the service in which the car is engaged. The reduction in speed depends on the relative number of teeth in the pinion and gear; the less the number in the pinion, as compared with those in the gear, the greater will be the reduction in speed of the car axle from that of the motor armature.

3. The **gear ratio** of an equipment will here be understood as the ratio of the number of teeth in the gear to the number in the pinion. While this is the usual way of expressing gear ratio, it is sometimes given as the ratio of the number of teeth in the pinion to the number in the gear. The pinion has, in nearly every case, fewer teeth than the gear, so that there is little cause for confusion no matter which way the ratio is stated. If, then, a motor has 14 teeth in the pinion and 68 in the gear, the gear ratio is $68 : 14 = 4.86 : 1$ and the motor armature rotates 4.86 times as fast as the axle.

Table I gives the speed of car axles, in revolutions per minute, for different car speeds and diameters of wheels. By multiplying the revolutions given in the table by the gear ratio in any given case, the speed of the motor armature is obtained.

EXAMPLE.—A car is mounted on 33-inch wheels and runs at a speed of 20 miles an hour; how many revolutions a minute do the motor armatures make if there are 65 teeth in each axle gear and 15 in each pinion?

SOLUTION.—The speed of the car axle, Table I, for 33-in. wheels and a speed of 20 mi. an hr., is 203.7 rev. a min. The gear has 65 teeth and the pinion 15, hence the gear ratio is 65 : 15. The speed of the armature is, therefore, $203.7 \times \frac{65}{15} = 883$ rev. a min., approximately. Ans.

TABLE I

REVOLUTIONS OF CAR AXLE CORRESPONDING TO VARIOUS CAR SPEEDS

Speed of Car Miles per Hour	Speed of Car Feet per Minute	Speed of Car Axles in Revolutions per Minute						
		30-Inch Wheels	31-Inch Wheels	32-Inch Wheels	33-Inch Wheels	34-Inch Wheels	35-Inch Wheels	36-Inch Wheels
6	528	67.2	65.0	63.0	61.1	59.3	57.6	56.1
8	704	89.6	86.7	84.0	81.5	79.1	76.8	74.7
10	880	112.0	108.4	105.0	101.8	98.9	96.1	93.4
12	1,056	134.4	130.0	126.0	122.2	118.6	115.2	112.1
14	1,232	156.9	151.7	147.0	142.6	138.4	134.5	130.7
16	1,408	179.2	173.4	168.0	163.0	158.2	153.6	149.4
18	1,584	201.7	195.1	189.0	183.4	178.0	172.9	168.1
20	1,760	224.0	216.8	210.0	203.7	197.8	192.1	186.8
22	1,936	246.5	238.4	231.0	224.1	217.5	211.3	205.5
24	2,112	268.8	260.0	252.0	244.4	237.3	230.4	224.2
26	2,288	291.3	281.8	273.0	264.8	257.1	249.7	242.9
28	2,464	313.8	303.4	294.0	285.2	276.8	268.9	261.4
30	2,640	336.1	325.1	315.0	305.6	296.6	288.2	280.2
32	2,816	358.4	346.8	336.0	326.0	316.4	307.4	298.8
34	2,992	380.9	368.4	357.0	346.3	336.2	326.6	317.6
36	3,168	403.4	390.2	378.0	366.7	356.0	345.8	336.2
38	3,344	425.8	411.8	399.0	387.1	375.7	365.0	354.9
40	3,520	448.0	433.6	420.0	407.4	395.6	384.2	373.6
42	3,696	470.6	455.2	441.0	427.8	415.3	403.5	392.3
44	3,872	493.0	476.8	462.0	448.1	435.1	422.6	411.0
46	4,048	515.4	498.5	483.0	468.5	454.8	441.9	429.7
48	4,224	537.6	520.0	504.0	488.8	474.6	461.1	448.4
50	4,400	560.2	541.8	525.0	509.2	494.4	480.3	467.0

MOTOR RATING

4. The rating of a railway motor is commonly based on the mechanical output that the motor can maintain at the car axle for a stated time without causing the rise in temperature in any part of the motor to exceed certain limits. Another rating is the continuous current input at a stated voltage that a motor can take from the circuit without exceeding certain temperature limitations.

Because of the variable conditions under which railway motors operate, no brief and definite rating that applies to all cases can be assigned to these motors. The American Institute of Electrical Engineers has adopted rules for tests to determine the rating of railway motors, which to a considerable extent have also been adopted by the manufacturing companies. These rules are modified from time to time and persons interested should consult the latest revision.

DIRECT-CURRENT MOTORS

DESCRIPTION OF MOTOR

5. Fig. 1 shows a direct-current railway motor of modern type. The motor is provided with commutating poles and arranged for forced-air ventilation. The enclosed frame *a* is of cast steel in one part and known as the *box type* to distinguish it from the frame that is in two parts and known as the *split type*. The screened intake for the air-cooling system is shown at *b*; the suspension lugs, which serve to hold the motor to the truck, at *c*; the iron gear-case, which is bolted to the motor frame and encloses the pinion on the armature shaft and the gear on the axle of the truck, at *d*; the cover over the opening provided for the inspection of the brush rigging and the commutator, at *e*; the pinion-end bracket, which is unbolted when the armature with the pinion on the shaft is to be withdrawn from the frame, at *f*, view (*a*); the commutator-end bracket,

at *g*, view (*b*); the axle bearings, at *h*, and the armature and field-coil leads, at *i*.

6. The armature, one main pole piece with its coil, and one commutating pole piece with its coil, are shown in Fig. 2. The armature core shown has 29 slots in which are placed



FIG. 1

29 groups of coils, each group containing 4 coils, making the total number of coils 116. The main pole pieces are laminated and the commutating pole pieces are of drop-steel forgings. All of the pole pieces are bolted to the frame of the motor. The field coils are wound with asbestos-insulated copper strap,

impregnated with insulating compound, and their surfaces are protected by layers of japanned webbing. The core laminations of this armature are assembled and keyed directly on the



FIG. 2

shaft on which the commutator spider is also pressed. Ventilating holes are provided lengthwise through the core. The commutator has 115 bars, to which are connected the 230 leads of the 115 active coils of the armature, 1 coil of the total of 116 coils being left unconnected. The commutator micas are



FIG. 3

grooved, or undercut, to a depth of $\frac{3}{64}$ inch. This custom, which aids in the prevention of sparking, is quite generally followed. All of the motor bearings are oil-lubricated.

7. A centrifugal fan *a*, Fig. 2, at the pinion end of the armature core revolves with the armature and sets up a circulation of air in the direction indicated in Fig. 3. The fan is located at the end of the armature core marked *a*, Fig. 3. The air enters through the screened opening *b*, Fig. 1 (*a*), passes over the field coils and the outside surface of the armature, Fig. 3, then through the commutator and lengthwise holes in the armature core out through the centrifugal fan and openings in the pinion-end bracket of the frame. A constant stream of cool air thus enters the frame, circulates around the heated parts, and absorbs and carries away heat. The motor, therefore, runs cooler for a given load than it would if the fan were omitted.

FEATURES OF CONSTRUCTION

8. The construction of the modern railway motor is the result of many years of experience of designers and operators of this type of apparatus. Some of the details of construction



FIG. 4

have been developed especially to meet the difficult requirements of railway service, while others apply to motors intended for either railway or stationary service. Some of the more

important of these features are here treated, but they do not necessarily belong to the same type of motor or to the motors made by one company.

9. Commutating Poles.—The relative positions of the main pole pieces and the commutating pole pieces are indicated in Fig. 4. There is usually the same number of main pole pieces as commutating pole pieces and each of the latter is located midway between a pair of the former. The object of the commutating poles is to improve commutation for either direction of rotation of the armature; the theory of this action has been explained in a previous Section.

Many of the electric troubles of car motors are due to sparking between the brushes and the commutator. The motor



FIG. 5

load is variable and this causes variations in the armature reaction. Unless the effects of these variations are neutralized by the flux of the commutating poles, the positions of the neutral spaces will be changed, thus tending to produce sparking. The motor in most car applications must revolve in either direction; therefore, the brushes are usually set at the no-load neutral point. The application of commutating poles to railway motors thus causes good commutation under all ordinary load conditions and with fixed positions of the brushes.

10. Armature Spider.—In some railway motors, the armature-core punchings are assembled on a spider that also serves to support the commutator. The armature shaft is forced into the spider under heavy pressure. With this construction, a shaft damaged in operation can be pressed out and

repaired or a new one substituted without disturbing the armature winding and connections. Ventilating space can also



FIG. 6

be easily provided between the spider ribs on which the core is assembled.

Fig. 5 indicates one form of armature spider. The core laminations are held between the fixed shoulder on the spider and the removable end ring.

11. Armature Coils.—Fig. 6 shows a group of three individual coils assembled into a single armored cell. Some coils are formed with round wire and others with copper strap. Cotton, mica, linen tape, and insulating compound are used to insulate the coils from one another in the cells and the cells from the surfaces of the armature slots. The coils are so placed and joined together as to form a *series-* or *wave-connected* winding. This arrangement requires only one positive and one negative set of brushes, which may be placed at points on the commutator convenient for inspection.



FIG. 7

12. Commutator.—Fig. 7 shows one form of commutator used on railway motors. The bars are made of hard-drawn copper and insulated from one another and the commutator

shell by mica strips and cones. The shell is in two parts, which are forced by heavy pressure into the V-shaped notches in the ends of the commutator bars, after which the ring nut *a* is set up tight against the shell and locked by small screws, one of which is shown. The bars are thus firmly clamped together. In this case the shell is mounted on a spider designed for forcing on the armature shaft; in other cases, the commutator shell is pressed on an extension of the armature spider.



FIG. 8

13. Brush Holders.—Fig. 8 shows a brush holder arranged for two carbon brushes. Each holder is supported by two steel studs cemented into porcelain bushings. The studs pass through holes in the motor frame and are bolted firmly in position. The brushes are pressed against the commutator by adjustable springs. Flexible copper shunts between the carbon brushes and the holders relieve the springs from carrying large currents.

14. Pinions.—Pinions are usually mounted on a tapered seat formed at the end of the armature shaft, as indicated in Fig. 9. With this construction, the pinion can be more readily removed than when mounted on a straight seat, as in early practice.



FIG. 9

In some cases the pinion nut, Fig. 9, is placed in a counterbore at the end of the pinion, in order to save space in the gear-case. A method of locking the nut is also indicated. The pinion *a*, mounted on its tapered seat, has a small groove *b* cut at the

bottom of the counterbore. A portion of the steel washer *c* is hammered into this groove. The nut *d* is run on and screwed home and one edge of the washer is turned up against the nut



FIG. 10



FIG. 11

with the aid of a thin tool that will lift the edge of the washer as indicated at *e*. The washer prevents the nut from turning, the pinion prevents the washer from turning, and the pinion key prevents the pinion from turning on the shaft.

15. Gears.—The type of solid axle gears shown in Fig. 10 is put on the axle under heavy pressure; further protection against slip and turning on the axle is furnished by a key. The style of gears shown in Fig. 11 are made in two parts that may be clamped together around a shaft. A keyway is shown at *k*. The life of gears is increased by special hardening treatments of the steel and by the use of special lubrication.



FIG. 12

16. Lubrication of Bearings. Both the axle and the armature bearings of the earlier motors were lubricated with grease. In such cases the bearing must heat and melt the grease before lubrication starts. Oil lubrication of railway motors is now, however, quite generally employed.

Fig. 12 indicates one method of applying oil to the armature bearings. Axle-bearing lubrication is effected in practically

the same manner. The armature shaft *a* is exposed directly to the oil-soaked waste stored in chamber *b*. The oil is poured into the bearing through the separate chamber *c*. The waste in chamber *b* absorbs the oil and delivers it to the surface of the shaft. After the oil passes through the bearing it is collected in a drip chamber *d* and, after filtration, may be used again.

Oil guards mounted on the armature shaft close to the bearings prevent oil from reaching the commutator or the armature windings. The oil from the guards is sometimes deflected to the drip chamber or thrown to the street.

In some motors, the bearing sleeve is of bronze overlaid with a thin surface of Babbitt. If the Babbitt melts, the shaft will be supported by the bronze sleeve and the armature will thus be prevented from striking the pole pieces.

ALTERNATING-CURRENT MOTORS

DESCRIPTION OF MOTOR

17. Most of the alternating-current motors used in America are of the series-wound commutator type that may be used



FIG. 13

with either direct current or alternating current. Fig. 13 shows the exterior of a 100-horsepower motor of this type provided

with a box frame and detachable end brackets for the removal of the armature. The laminated field core is so constructed as to form four projecting pole pieces, on which are mounted



FIG. 14

the four main field coils, each consisting of a few turns of heavy copper strap.

A **compensation winding,** consisting of copper bars connected at the ends by copper straps so as to form a continuous



FIG. 15

winding, is distributed in the slots in the pole pieces, as shown in Fig. 14, in order to obtain a distribution of magnetomotive force similar to that of the armature conductors.

The compensating winding of a motor intended for either direct- or alternating-current circuits is connected in series with the armature and the main-field winding. In a motor used exclusively on alternating-current circuits, the compensating winding is short-circuited, either as a whole or by sections, and is separate from the armature circuit. The compensating winding thus becomes the secondary of a transformer of which the armature forms the primary.

Fig. 15 shows an armature used with this type of motor. The armature is parallel-wound and requires four sets of brushes. The motors are usually wound for 250 volts and 25 cycles.

FEATURES OF OPERATION

18. Reversal of Current.—When an alternating current is established in the field and armature windings of a series motor, the current reverses through each winding at the same time. The polarities of the pole pieces and of the poles formed on the armature core, therefore, reverse at practically the same



FIG. 16.

instant and continuous rotation in a given direction is thus maintained. In Fig. 16, curve *a b c* represents one cycle of an alternating current. In the portion *a b*, the direction of current is assumed to be from motor lead *d* to lead *e*, resulting in the polarity and rotation shown. At *b* the direction of current is reversed. Lead *e'* is now positive and lead *d'* negative;

the polarities of field poles and armature poles are thus reversed, but the direction of rotation remains unchanged, as indicated.

19. Self-Induction of Windings.—When operating with alternating current an electromotive force of self-induction is set up in the windings. In the case of the main-field windings, this electromotive force is reduced to its lowest value by decreasing the turns of the exciting field coils to the least number capable of providing the necessary magnetic flux. The less the number of turns that are acted on by the passage of the alternating magnetic flux through them, the smaller becomes the electromotive force of self-induction.

The mutual induction between the conductors of the compensating winding and the adjacent conductors of the armature windings greatly reduces the effect of self-induction in both windings. The compensating action is similar, whether the compensating coils are in series with the armature and main field coils or whether they form a separate circuit or circuits excited by the transformer action of the armature coils.

Besides improving the power factor of the motor, the current in the compensating winding so neutralizes the armature reaction that proper commutating conditions may be secured with fewer turns on the field winding, and thus a weaker field than would otherwise be possible.

20. Effect of Transformer Action on the Armature. When the armature is rotating in the magnetic field established by alternating current in the main field coils, a counter electromotive force is generated in the armature coils in the same manner as in a direct-current armature. There is also set up in the armature coils an electromotive force due to the alternating magnetic flux passing through the pole pieces and armature. The latter action is practically similar to that of a transformer. The first, or mechanically generated, electromotive force is proportional to the speed; the second, or electrically generated, electromotive force is proportional to the frequency of the alternating current. The first electromotive force is the useful one, as it is the counter electromotive force of the motor.

In half of the coils between any two adjacent brushes, the electromotive force generated by transformer action is opposite in direction to the electromotive force generated by transformer action in the remaining coils of the group, for one-half of the coils are affected by the flux emanating from a north pole, while the other coils are simultaneously affected by the flux entering a south pole. The effects of transformer action are thus practically neutralized and the counter electromotive force is affected but little, if any, by the transformer action, provided the brushes are properly placed.

21. When an armature coil is short-circuited by a brush during commutation, it forms a closed secondary circuit, the primary of which is the adjacent main field coil. The ohmic resistance of the coil itself is low, and to prevent the establishment of a large current, the armature coils have but one turn each, which limits the electromotive force generated in the closed coils, the frequency of the system is low, and the leads connecting the junction of adjacent coils to the commutator bars in some motors have sufficient resistance to limit the current to a safe value. The leads are active only when the coils to which they are connected are being commutated.

In railway motors of ordinary size, the resistance leads are usually tapped to the armature winding at the rear end of the core and brought to the commutator bars through the same slots as the main winding. In some very large motors, the leads are tapped to the armature winding at the front end of the core, carried to the rear end, doubled back to the front, and then connected to the commutator.

MOTOR CHARACTERISTICS

22. When the suitability of a motor for a given class of service is to be determined, information regarding its performance is a necessary factor. These data are obtained from tests made by the manufacturers, and are usually presented in the form of curves, known as **motor characteristics,** or **performance curves.** These curves commonly show the relation between values of the current, speed, tractive effort, horsepower, and efficiency. As the heat of the windings limits the output of a motor, and this heat is due to the current, the other properties considered are usually referred to the values of current taken by the motor under various operating conditions. In the curves, the current values are usually laid out on the axis of abscissas and the other values on the axis of ordinates.

The performance curves shown in Fig. 17 relate to data for a 100-horsepower single-phase motor when operating with direct current and a terminal voltage of 150. For low speeds the motors operate four in series across a 600-volt circuit. The curves are drawn for a gear ratio of 63 to 20 and for 36-inch driving wheels.

23. Speed.—If the voltage is constant, only one armature speed corresponds to each value of motor current. For example, the car speed, Fig. 17, for a current of 400 amperes is 13 miles an hour. As the motor is series-wound, the armature speed decreases as the load increases, the car speed corresponding to a current of 600 amperes being 10 miles an hour.

An increase in line voltage increases the car speed in almost direct proportion, especially for lower and moderate speeds. If the speed of a car is 11 miles an hour at 500 volts, the car speed at 600 volts is $11 \times \frac{6}{5} = 13.2$ miles an hour, approximately. At higher speeds accurate results are not obtained with this proportion because of the greatly increased effect of air resistance.

24. Tractive Effort.—The armature conductors are moved by the interaction of the current in them with the flux of the pole pieces. The force applied to the conductors is



FIG. 17

transmitted through the pinion and gear to the car axle and thence to the car wheels fixed to the axle.

The force exerted at the tread of both of the wheels on the car axle is known as the tractive effort of the motor and is

usually expressed in pounds. Any change in the gear ratio, wheel diameter, or current affects the value of the tractive effort. When the motor is taking a current of 400 amperes, the tractive effort is 1,850 pounds, as indicated in Fig. 17.

25. Horsepower.—The nominal rating of a railway motor is considered as the mechanical output at the car axle. The power at the car axle is less than that at the armature shaft due to losses in gears, bearings, etc.

The car speed in feet a second for a given current multiplied by the corresponding tractive effort in pounds and divided by 550, the number of foot-pounds a second equivalent to 1 horsepower, gives a point on the horsepower curve, Fig. 17. For example, the speed at 400 amperes is 13 miles an hour, or $\frac{13\times5,280}{60\times60}$ feet a second, and the tractive effort is 1,850 pounds. The power is $\frac{13\times5,280}{3,600}\times\frac{1,850}{550}=64.1$ horsepower, approximately, as indicated in Fig. 17. For a current of 600 amperes, the horsepower is 91, approximately.

26. Efficiency.—The commercial efficiency is the ratio of the useful output to the total input. The efficiency of the motor when provided with gears is indicated in Fig. 17. For example, at 400 amperes input the efficiency is 81 per cent., approximately. The maximum efficiency is 82.5 per cent. at a current input of 300 amperes.

27. Comparison and Modification of Values.—By selecting a point on one curve, corresponding values on the other curves may be found by determining the place where a vertical line through the selected point cuts the other curves and then reading the values of these points by means of the data lines on the margins.

The characteristics, as given, usually apply to one motor, so that if the property sought involves all the motors on a car, the data obtained from the characteristic curve must be modified accordingly. For example, the tractive effort available for propelling a car equipped with four motors would be the tractive

effort of one motor multiplied by four. Should the total current required to propel a car at a certain speed be desired, the total tractive effort being known, the tractive effort of one motor is found by dividing the total value by the number of motors and the corresponding current of one motor as ascertained from a characteristic curve such as Fig. 17, is then multiplied by the number of motors.

MOTOR INSTALLATION AND MAINTENANCE

INSTALLATION

28. Nose Suspension.—The term **motor suspension** applies to the manner of supporting the motor on the car axle and truck. Fig. 18 shows an arrangement called a *nose suspension*. One end of the motor is supported by bearings on the car axle and the other end on a suspension bar connected across the frame of the truck. The pinion *P* engages the gear *G* on the car axle on which the driving wheels *W* are also mounted.



FIG. 18

Fig. 19 shows in more detail a type of nose suspension quite generally adopted as standard on account of its simplicity. A link *a* connects the motor to the suspension bar *b* and springs *c* and *c'* cushion the motor impact in either direction on an angle iron *d* riveted to the truck, thereby relieving the truck of direct shock.

29. The motor should be so installed on the axle that when the car is on a straight track, the motor rests neutrally in the axle space between the gear on one side and the axle collar on the other. The use of a crowbar to make parts fit, on either the motor or any portion of the suspension, should never be permitted, as such a course causes excessive wear of axle-bearing flanges. All suspension parts must be kept tight;



FIG. 19

otherwise, failure of the rigging may let the motor down when the car is in operation. When running over rough track, the motor jumps up and down, bringing both springs into action. In starting, where the motors are hung front to front or back to back, the top suspension spring of one motor and the bottom spring of the other are compressed. This continual jarring and movement tends to loosen suspension parts, which soon produce a ringing, rattling noise. The suspension springs should be neither too weak nor too strong; if too strong they will lack flexibility, and if too weak they will close every time the car gets a jolt; in either case the motor is subjected to vibration liable to jounce the brushes from the commutator and cause flash-overs.

30. Location of Motor.—On either a two-motor, two-axle, or a four-motor, four-axle car, a motor is geared to each

axle and the motors should usually be hung between the axles of each truck. The motors are then near the truck centers and have little motion relative to the car body. Short leads may therefore be used, with little chance of grounding them. The stresses on truck parts are also less than when the motors are hung outside the axles, because there is less leverage.

When starting a car or when the motors are used to stop it, the pinions tend to crawl around their respective gears in opposite directions and the resulting stresses are greater with the motors outside of the axles than when they are hung between them.

When two motors are to be hung on an eight-wheel car, most master mechanics prefer to put both motors on the same truck, because then but one heavy truck is required and the first cost of trucks and the dead-weight to be hauled, are minimized. Furthermore, the brake rigging is simplified, car-floor trap doors are needed at but one end, and car wiring is made cheaper and simpler. Finally, where pit room is limited or pits are short, both motors may be reached while only one end of the car is over the pit.

MAINTENANCE

31. On most well-ordered roads, two kinds of car inspection are practiced: *quick inspection*, which is made every day or night or on alternate days or nights; and *overhauling inspection*, which is the thorough inspection attending overhaulings made at intervals, based usually on car mileage.

QUICK INSPECTION

32. Quick inspection is limited to weaknesses that may be observed without disassembly of parts. It includes inspection of air-gap clearances on motors having bearings of the grease-fed type, and inspection of cotter pins and nuts on important parts such as suspension rigging, brake rigging, motor frames, and gear-cases. As failure of a suspension or brake rigging is apt to be a very serious matter, these parts

should be inspected as often as practicable. On high-speed cars, wheels should be inspected for cracks and chipped flanges at least once a day. The general adoption of steel instead of cast iron for car wheels has greatly decreased the trouble from broken wheels, and only the hammer test for cracks is required. The motor leads should be gone over, to eliminate contacts with the motor frame, suspension rigging, or other metal parts, and to detect loose connections or actual open circuits. The blowing of a circuit-breaker will of course give notice of an actual ground; but the object of the quick inspection is to find the abraded motor lead before it actually gives trouble.

An open circuit in a motor lead of a two-motor car, becomes evident from the slow action of the car during operation; but numerous cases are on record where four-motor cars have operated for weeks on three motors, because a lead of one motor had pulled out of the connecting sleeve. Cars in this condition have been turned in repeatedly for slow speed attributed to the brakes binding. Good contact of the motor ground wires should be insured at each inspection. Commutator covers should be lifted and inspection made for short brushes, tight brushes, broken brushes, tension fingers resting on the holder, instead of on the brush; burnt, broken, or weak tension springs, broken brush shunts, loose holders, holders resting on or too far from commutator, holders rubbing head of commutator, brushes riding over end of commutator, burnt armature head, burnt or loose string band, accumulation of carbon dust on brush holders, or on string band, or its equivalent, evidence of oil on commutator, rough commutator, black commutator, and red commutator indicating poor commutation or excessive heating. These simple causes of prospective trouble make a long list; but the eye of an experienced inspector can detect any of them at a glance. Any unhealthy motor condition, as a rule, is evidenced by the condition of the brushes and of the commutator; if the cause of their bad appearance is not evident and easily removed, the car should be marked to be held in. On motors in which only one brush per holder is used, most of the small troubles just enumerated are sufficient to cause a flash-over and the operation of a car circuit-breaker.

But on motors in which two or more brushes to a holder are used, the only evidence of irregularity may be a difference in the appearance of two zones of the commutator because one brush carries too much current and another carries little or no current.

33. On motors with grease-lubricated bearings, quick inspection should of course include the grease boxes; on all motors, the inspector should see that no grease- or oil-box covers are missing. Any accumulation of mud around the grease covers should be prevented by frequent use of a stiff wire brush, especially on armature grease-box covers. As the passing of the hand along the grids of a grid rheostat will readily reveal any broken units, this quick test should be made; broken grids often run for weeks without being reported and they may be the cause of blistered controller fingers, sparking brushes, or both.

OVERHAULING INSPECTION

34. Frame.—At the time of overhauling, the motors are entirely disassembled and all parts laid out where they can be inspected thoroughly. The frame is scraped, wiped inside and out, and carefully inspected for cracks, especially around the armature and axle journals. The entire inside of the frame, except the pole-piece seats, is painted with a compound whose glaze prevents the adherence of moisture. Formerly, cracked frames were thrown into the scrap; but by the use of any one of several different processes, they can now often be repaired.

Missing grease-box lugs, springs, and covers are replaced; hinges, gaskets, and linings of inspection covers and lids are renewed; all bearing chambers are thoroughly flushed with light oil, defective motor-lead bushings are replaced, nuts and bolts are put into working order, and missing cotter pins are replaced. In fact, the frame is put as nearly as possible into its original condition. The pole pieces are thoroughly scraped to give perfect seating, and the tapped holes are cleaned with oil.

35. Gear-Case and Gears.—Gear-cases may have cracked, bent, or have broken lugs, and if made of sheet metal

the cases may be bent, from contact with raised paving stones or other obstructions. Bent cases should be straightened and broken lugs replaced. Defective felt dust guards around the axle hole should be repaired or replaced, and loose rivets replaced, or tightened, if necessary, care being taken not to bend the case. A new gear-case should be cleared of all internal burrs and any gear-case should be cleaned before installation. No dependence is to be placed on the old lubricant, as it may contain nuts or rivets that may be drawn up between gear and pinion and thus cause bending of the armature shaft. If the gear and pinion are in good condition, no further disturbance is necessary than to see that the nuts are tight and well secured. If, on account of broken or worn teeth, the gear must be replaced by a new gear, a new pinion should be installed and the replaced pinion reserved for use with a worn gear; the use of a worn pinion with a new gear shortens the life of the gear. A pinion that is to be used again should never be removed with a cold chisel, because the resultant flattening of the ends of the teeth is liable to bend the next armature shaft with which it is used. By the use of pinion pullers, which are usually available, a pinion may be forced from the shaft without injury.

The small clearance between a gear and its case should be equally distributed on both sides of the gear. As the gear is carried on the axle and the gear-case on the motor frame, the end play, due to axle-collar or bearing-flange wear, unless discovered and repaired, will cause the gear to rub and wear through the case.

When tightening a split gear, the bolts nearest the axle should be tightened first, so that the outside bolts may act as a lock. All bolts should be firmly tightened. In order that the motors may properly divide the load, all motors on the same car should have the same gear ratios and the gears and pinions should be properly mated, otherwise the wear on both will be excessive.

36. Pole Pieces and Field Coils.—Field coils should be examined for mechanical injuries and their resistance compared with that of a similar new coil known to be standard. Results

will be misleading, however, unless the suspected coils are subjected to mechanical pressure similar to that due to the pole pieces or shields by which they are secured against vibration in the motor. The fastening devices, as well as the heat of the motor draw the turns of the coil together, and to obtain reliable results from resistance tests, these conditions must be reproduced. If any of the coils are abraded or are oil- or water-soaked, they should be sent to the coil room to be dried and recovered and new coils substituted. Before the old coils are replaced in the motor, they should be given, preferably by dipping, a coat of insulating paint that will take a gloss, the leads should be trimmed, tinned, and taped, if necessary, and the coils then set aside to dry. The coil insulation shrinks in service and some form of washer must be used to take up the clearance, for if the field coils are allowed to shake around in their fastenings, grounds or loose-connection troubles will result. If the coils are a loose fit on the pole pieces, they should be made tight by winding on dipped webbing; they should then be forced on the pole pieces with a rawhide mallet and a block of wood. The pole piece and coil are then placed in the motor and the bolts inserted and tightened, the rawhide mallet being used to tap the pole piece. One of the bolts is then removed and the clearance between the pole piece and its seat is tested with a piece of steel wire bent at right angles on the end and ground thin. If the knife edge cannot be forced in between the pole piece and its seat, a good seating may be assumed, in which case the bolt is replaced and screwed home; the other bolt is then taken out and the test is repeated.

37. A commutating pole piece should be so installed that the distances from the straight edges of the pole to the adjacent main pole pieces throughout their lengths should not vary more than $\frac{1}{16}$ inch. To test this adjustment make a hard-wood block of the proper thickness to bear against a main pole on one side and a commutating pole on the other.

38. The correct polarity of main and commutating poles should always be insured by test before reinstalling the armature or closing the motor frame. The main field coils alternate

in polarity and so also do the commutating field coils. For a given polarity of main field coils and brush holders, the direction of rotation of the armature is best found by experiment.

In the case of a motor, the relative polarity of main and commutating poles is such that in the direction of rotation, an armature conductor must pass from a main pole of given polarity to a commutating pole of the same polarity and on to another main pole of opposite polarity. The absolute polarities



FIG. 20

of main and commutating poles may be tested with a compass, or their relative polarities with an iron nail. If a nail is loosely held between two poles of like polarity, it will turn to a position at right angles to a line between the poles. If the adjacent poles are of opposite polarity, the nail will then turn to a position parallel to the same line. Whenever the main and commutating poles are of the wrong polarity with regard to each other, the motor will spark badly and the commutating-coil terminals must be reversed.

39. Armature.—Some motors are provided with split frames, whose lower portions, with or without the armature, may be swung down, as indicated in Fig. 20. The arrangement permits an inspection of the interior of the frame without the removal of the motor from the truck. In other cases, the lower frame is entirely unbolted from the upper and is lowered into the car-barn pit by means of a portable hydraulic jack.

If the motor has a box frame, the armature is removed by unbolting one of the end brackets and sliding the armature through the opening. The motor is taken from the truck and placed on a stand provided with a sliding carriage *a*, Fig. 21; the armature is held between center *b* and *c*. The loosened



FIG. 21

bracket is shown at *d*. When the carriage is moved to the right by means of wheel *e* the armature is exposed.

40. Accumulations of dust should be blown from all ventilating ducts, preferably with compressed air. All moisture of condensation must be exhausted from the air hose before applying air to the armature. If practicable, the cleaning should be done under a hood piped to the atmosphere and exhausted with an air siphon, so that the dust ejected will not settle on everything in the vicinity. The armature should be swung in a lathe and tested for bent shaft; while there, the commutator may be turned, a new string band run on, and a new hood installed, if these repairs are required. The distance between the bearing surfaces must be gauged as a check against excessive end play, which should not exceed $\frac{3}{32}$ inch, even if it is necessary to put on new thrust collars.

Some shops straighten bent shafts, but as a rule, it is much better practice to press in new shafts, as a straightened shaft tends to resume its bent condition, and this condition may cause brush troubles and flash-overs. A record should be kept of any motor whose armature shaft has been straightened. When a shaft is renewed, the new shaft should be given the old one's number with a letter affixed and the old shaft should be scrapped, otherwise confusion in records will arise.

If the pinion nut thread is so badly damaged that it cannot be reclaimed, the shaft may be spliced with a piece upon which to cut a new thread, but the better way for all except small motors in very light service is to renew the shaft. The same course should be followed where it is necessary to cut more than two pinion keyways on account of the keyways having become hammered out.

If the armature connections show evidence of looseness, either the armature core or the commutator may be loose; if the core is loose, the chances are that it has worn its fastenings so that it should be reassembled. If the commutator is loose, the commutator bolts should be tightened while the commutator is hot, after which the commutator should be turned. All commutators should be rounded off at the end to minimize breaking out of the mica. After turning or grooving, all burrs reaching across the mica between bars must be picked out. Grooving is generally carried to a depth of about $\frac{3}{64}$ inch; after grooving, the edges of the bars must be smoothed with a scrapper to decrease the milling action on the brushes.

A better scheme than the common practice of laying extra armatures down on a rack, is to stand them up in holes bored for the purpose. Less floor space is required and the armatures are entirely covered with less trouble. Canvas bags slipped over them form a simple and effective protection. If oil gets on the commutator at any time, it should be thoroughly washed off and out of the grooves with gasoline. The flash-overs and breaker blowing caused by oil on a commutator will probably be attributed to almost everything else before the real cause of the trouble is located. Armatures should not be rolled on the floor, where they may come in contact with projecting nail

heads, but should be rested on felt or similar substance, and should be carried from place to place, not rolled.

41. Brush Holders.—The type of brush holder that is mounted on studs fastened to the motor frame is free from many defects that characterized the old wood-insulated holders. Considerable attention, however, is required by the independent holders, to avoid wrong adjustments of holders and of tension springs, loose holders, loose brushes, loose leads, broken shunts, excessive armature end play, excessive accumulations of copper dust, etc. The last-named cause of trouble is minimized by the increased length of the leakage path, due to the corrugated insulators. Irrespective of the type of holder used, the brushes must be held the proper distance apart. On motors of the two-pole type, the set of the holders should be such that the distance from the center of contact of a brush to the center of contact of a brush in the opposite holder is one-half the circumference of the commutator; on a four-pole motor, the distance from center to center of brushes should be one-fourth the circumference of the commutator; and on a six-pole motor, one-sixth the commutator circumference. Instead of taking the stated fractions of the commutator circumference, one-half, one-fourth, or one-sixth of the total number of commutator bars are generally considered as the counts between brushes, and the bars between corresponding brush edges, forward or rear, are connected instead of between brush centers. A four-pole motor with a 215-bar commutator, for example, should have $215 \div 4 = 53\frac{3}{4}$ bars between the forward edges of brushes in adjacent holders. With the correct count between adjacent holders assumed, the location of the holders as a whole should be such that the armature speed is the same in both directions for a given load. The importance of having the count correct, as well as everything else pertaining to brushes and holders, cannot be emphasized too strongly. Most motor troubles can be traced, directly or indirectly, to brush or brush-holder irregularities.

42. Bearings.—Excessive wear or eccentric boring of bearings allows the armature core to strike the pole pieces;

if not repaired, this condition will soon destroy the armature. One of the first symptoms of core rubbing is the repeated blowing of the car circuit-breaker, due to the increased load imposed by the mechanical friction between the core and poles; the motor will heat, will use oil much faster than other similar motors, and will show a decided tendency to throw oil.

The air gap of a newly installed armature should be tested with a gauge to see that it is uniform all round. After two months of operation, wear is usually noticeable in the armature bearings, and they are usually changed at the time of overhauling, whether they really need it or not. In course of time, also, the armature shaft wears smaller so that standard bearings do not fit perfectly. In some shops several sizes of standard bearings, and armature shafts turned to these standard sizes are kept in stock, a shaft worn below the smallest standard size is either further turned and the bearing surface renewed with a sleeve or it is replaced with a new one. Other shops prefer to have a lathe at each place where overhauling is done, so that bearings kept in the rough may be bored to exact size.

43. Lubrication.—Good lubrication is absolutely essential to successful and economical operation, and oil has given better results at lower costs than did grease in older types of motors. In well-managed systems a careful record is kept of the oil consumed by each car, and if one car consumes much more oil than another, an investigation is made and the cause located and removed. The oil should be used economically; the usual way is to apply with a measure a specified quantity of oil to each bearing for a specified mileage. With careful lubrication, $\frac{1}{16}$ inch of good Babbitt will last 3 months or more; but the bearings are usually replaced oftener.

44. Armature and axle bearings should be as tight as possible without binding. An armature can usually be turned by hand, when a tendency to bind can be easily detected. A positive test for the fit of the axle-shaft bearings is to jack up the car wheels so that they can run freely, also the motor so as to remove friction from the car-journal bearings, and then operate the motor with an ammeter in series; the bearings

should be as tight as may be without increasing the current above a value previously established by experiment.

On many roads maintenance of axle bearings is not given sufficient attention. Under ideal conditions, a rolling contact exists between pinion and gear in operation, and to get action of this sort the proper distance between gear and pinion centers must be accurately maintained. Wear in the axle bearings changes this distance and gear friction increases in a measure as bearing wear increases. One of the symptoms of such neglect is that pinion and gear-teeth do not wear evenly; the teeth wear thinner on one end than on the other.

45. Connections.—The leads should be brought out of all motors in standard order, and a standard order of connection to the car cable should be observed. Much time can thereby be saved in overhauling and in testing incident to trouble work. A wireman can then identify a positive brush or field lead at a glance, and no time will be lost in so connecting the motors that all tend to move their cars in the same direction for a given position of the reverse switches. Another advantage of standard connections is that a left-hand armature, as armatures of reversed polarity are generally called, can be detected as soon as it is installed in a motor because it will turn in the wrong direction.

46. Starting Resistance.—Sparking of brushes is sometimes due to the starting resistor being so sectionalized that current is applied to the motors in too great impulses. The resistor may have been wrongly divided in the first place, a part of it may have become short-circuited, or a parallel section of it may have become open-circuited. When overhauling the motors the starting resistor should be carefully inspected for loose, burnt-out, broken, or buckled units and for defective jumpers.

47. Circuit-Breakers.—Tests should also be made of the car circuit-breakers and of their adjustment to blow at a value consistent with the motor rating. Reliable circuit-breakers will save time and expense by revealing slight troubles that would soon become serious, if neglected.

ELECTRIC-CAR EQUIPMENT

MOTOR-CIRCUIT AND AUXILIARY APPARATUS

TRUNK CONNECTIONS

TRUNK WIRE

1. **Trunk connections** relate to the wires and devices traversed by the motor current from the current collector of the car to the controller, and are also sometimes considered as including the ground wires of the motors.

2. The **trunk wire** is the feed-wire from the collector; a portion of it carries the total current required for propulsion, heating, lighting, and signaling purposes.

Fig. 1 shows the general arrangement of the trunk wire for a small single-truck car. The current path from the trolley wheel to the controller trolley wire *T T* is indicated by the order of the numbers. The roof wires are protected by canvas tacked to the roof. Where the wire passes through the car bonnets, the passage is made water-tight by the use of lead or of special compounds made for the purpose. The vertical wires, or *risers*, pass through the bulkheads of closed cars or through grooves in the corner posts of open cars. The risers are often installed in iron conduits. In any case, the wires must not come in contact with nails, screws, or the sliding door. When the conduits are used bell mouths are employed at each end of the pipes to

COPYRIGHTED BY INTERNATIONAL TEXTBOOK COMPANY. ALL RIGHTS RESERVED

prevent abrasion of the wires and the upper end of the conduits are bent over and filled with insulation to prevent the entrance of water.

3. Fig. 2 shows an arrangement of the trunk wire for a car that operates on both third-rail and single-overhead trolley systems. The two trolley stands, located near the ends of the car, may or may not be connected; in either case a roof wire runs from each stand to one side of a single-pole, double-throw



FIG. 1

switch, to the other side of which a riser from the third-rail trunk wiring connects. The change-over switches are located in the vestibules or cabs.

All of the contact shoes are connected by taps to a spine wire installed on the under side of the car floor. With this arrangement, the third rail may be placed on either side of the car and some of the shoes will be active.

The handle posts of the change-over switches are connected through circuit-breakers, located either in the vestibule or under the car, to the controller posts T. A circuit-breaker or enclosed fuse is sometimes connected to the spine wire at the point where it joins to the riser. In other cases, a shoe fuse is installed on

the shoe beam above each contact shoe. By means of the change-over switch, the controller is connected to either the trolley stands or the contact shoes as desired and the collecting device not in service is entirely cut off from the live circuit.



FIG. 2

4. Fig. 3 shows the arrangement of the trunk wire on a car operated on a conduit system. Besides the hood switches in the car bonnets two circuit-breakers, called *ground switches*, and two fuses (not shown) are installed under the car.

On conduit cars, extra facilities must be provided for the interruption of the motor circuit, because, while nominally operating on a metallic-return system, one side of the circuit is generally grounded. Circuit-breaking devices as close to the conductor rails as possible are installed to prevent damage to the car apparatus by accidental grounds.



FIG. 3

5. Where motor cars are operated in trains that include intervening trail cars, the spine wires of the trail cars are joined with those of the motor cars by means of couplers; otherwise, when there is sleet on the third rail or on the trolley and different cars alternate in getting good contact, the resultant jerking will be liable to pull the train in two.

TROLLEY FITTINGS

6. The **trolley** is the device on the roof of the car for collecting current from the overhead conductor, called the *trolley wire*. The grooved *trolley wheel* rolls against the under side of the wire and makes electric contact with it; the wheel rotates on an axle in the *fork*, or *trolley harp*, riveted to the upper end of the trolley pole. The lower end of the pole is clamped to the upper portion of the *trolley stand*.

Short cars are usually equipped with only one trolley; some long cars have two trolleys either of which can be used. The



FIG. 4

wheel follows the trolley wire better when trailing over the rear end of the long car than when the trolley is placed at the center of the car.

7. The **trolley stand**, one type of which is shown in Fig. 4, consists of two parts, or members, the *spring base* carrying the socket clamp *a* for the trolley pole and the *trolley foot*, which is bolted to the car roof. The base is pivoted to the foot and can be swung around on a roller bearing to suit either direction of car movement. The socket *a* is also pivoted at *b* and has an arm *c*, to which four springs are connected. The other ends of these springs are joined to an arm *d*, which is part of a slide *e*. The slide is mounted on a projection *f* of the trolley base, and the tension of the springs, which force the trolley wheel against

the wire, may be adjusted by the adjusting screw *g* at the end of the slide. The car-roof wire is connected to the trolley foot at *h*. On some stands a spring cushion stop is provided near the



FIG. 5

lower part of the base to reduce the shock to the base and car, in case the trolley wheel leaves the wire.

8. The **trolley pole,** Fig. 5, is usually from 12 to 15 feet long, is about 1½ inches in diameter for about 2 feet from the large end *a*, and then tapers through part *b* to a diameter of about 1 inch. Most poles are of hard-drawn steel tubing and offer great resistance to bending. Slight bends are generally straightened by using a post with a hole in it as a vise and then straightening the pole by hand pressure. Bad bends may be straightened by hammering, but in any case the pole should not be heated.



FIG. 6

9. Trolley harps, Fig. 6, are made of iron or brass and are shaped so they will not easily catch on the overhead work if the wheel leaves the wire. One end of the copper spring *a* is attached to the harp and the other end bears against the side of the wheel. The springs relieve the bearings by conducting a portion of the current from the wheel to the harp.

10. Trolley wheels, one of which is shown in Fig. 7, are made with great care to get the proper degree of hardness; if too soft they wear away too rapidly, and if too hard they injure

the trolley wire. Much study has been devoted to the proper metal composition for the wheel and to the most suitable shape



FIG. 7

for the flanges *a* and for the groove *b*. A bushing is provided at *c* and the axle, which passes through hole *d*, is oiled through hole *e*. Wear in the bushing causes the wheel to rattle. To



FIG. 8



FIG. 9

keep an ordinary bushing in good order, it should be oiled every 15 or 20 miles.

Fig. 8 shows an assembled harp and wheel with the wheel engaging the trolley wire. Fig. 9 shows a platform that may

be used for the systematic inspection and oiling of wheels and other trolley parts.

11. The pressure of the wheel against the wire usually ranges from 20 to 40 pounds, depending on the tautness and alinement of the trolley wire, the speed of the car, and the condition of the roadbed. The compression required on the trolley-stand springs depends on the desired pressure of the wheel against the wire, the weight, fittings, and length of the pole. A spring balance attached to the wheel may be used to test the wheel pressure against the wire; the reading of the balance is taken when the pull exerted on the wheel through the balance is just sufficient to cause the wheel to leave the trolley wire. When the car is in operation, if the pressure is too weak, the wheel may leave the wire; and if too strong, the wear of the wire, the wheel, and the wheel bearings will be excessive. The wheel pressure is regulated by adjusting the tension of the trolley-stand springs.



FIG. 10

TROLLEY ACCESSORIES

12. Trolley catchers are devices intended to prevent damage to overhead wiring, in case the trolley wheel leaves the wire. The catcher is usually installed on the dash iron of the car and can be carried from one end of the car to the other as desired. A rope connects the upper end of the trolley pole to the catcher. Should the wheel leave the wire, the mechanism of the catcher

will act and hold the pole after the wheel has risen a very short distance. The pole in this position is less liable to cause damage than if it were allowed to assume a vertical position.

13. A trolley retriever, Fig. 10, is a device somewhat similar to the trolley catcher, but in case the wheel leaves the trolley wire, the retriever pulls the pole down until the wheel is 3 or 4 feet below the wire and, therefore, clear of all interference with other overhead wires. A portion of the retriever



FIG. 11

mechanism allows the rope to wind on or unwind from a reel as the trolley wheel rises or falls while following the wire. When the wheel leaves the wire, the rope is wound on the reel and the pole is lowered by the action of a strong spring that is suddenly set in action within the retriever.

14. Trolley guards, Fig. 11, are sometimes installed on the trolley wires at the crossings of electric and steam roads, under bridges, and at the approach of tunnels. In case the

trolley wheel leaves the wire, the guard will lead it back into its proper position on the wire and the car will not lose current in what may be a dangerous situation. The guard is held in place by special suspension wires.

CIRCUIT-BREAKERS

15. Broadly considered, a **circuit-breaker** is a device for readily opening and closing a circuit, either manually or automatically. As generally understood, a circuit-breaker, usually referred to simply as a *breaker*, is a switch that opens automatically when dangerous current conditions occur in the circuit of which it is a part. The broader definition includes both switches and automatic breakers and both will be discussed under this head.



FIG. 12

The types of breakers used on cars to open the motor circuit depend on the nature of the operating system, to a certain extent on the size of the car, and on whether the control is manual or automatic. When operated by hand, the device is usually installed in the car hood, within easy reach of the motorman; hence the name, *hood switch*. The manually operated switches in the two car hoods are usually connected in series, as in Fig. 1.

Automatic breakers are usually placed in independent circuits, as shown in Fig. 2, to enable the motorman to close the circuit quickly after a breaker has opened. If the two breakers were in series and the rear one opened, the circuit could only be closed after considerable delay.

16. Breakers Tripped by Hand.—Fig. 12 indicates one part of a manually operated, quick-break main switch for an

equipment not exceeding 200 horsepower in capacity. The part shown is for attachment to the roof over the motorman's head. A magnetic blow-out coil, indicated by dotted lines, and located in the lower portion of the box, is connected between the right-hand switch terminal and the block to which the switch arm is electrically joined.

Fig. 13 shows a type of quick-break switch used in motor circuits of multiple-unit cars to open the circuit leading to the car apparatus when inspections or tests are being made. The switch is intended to carry safely the full-load current, but not to be used for opening the circuit except, when in an emergency,



FIG. 13



FIG. 14

the automatic breaker in the same circuit fails to operate. When the switch is opened, the upper blade first leaves the switch jaws and puts in tension the two springs connecting the upper and lower blades. When the tension becomes sufficiently strong, the lower blade leaves the switch jaws very suddenly and opens the circuit.

Fig. 14 shows a disconnecting switch used for disconnecting high-tension car wiring during inspections and tests. This switch is not intended for opening loaded circuits. It is operated by means of wooden poles provided with hooks that may be inserted in the holes in the switch blades.

17. Breakers Automatically Operated.—When a loaded high-tension car circuit is to be opened, an oil switch is often used. Fig. 15 shows a type of oil switch used on a multiple-unit car operating on a single-phase, alternating-current system. A magnet *a*, when energized, operates through a system of levers to close switch contacts *b* installed in a case



FIG. 15

containing insulating oil. The lower contacts *b* are mounted on a crosshead supported on a wooden rod. If current through the operating coil ceases, the switch opens by gravity.

In the open position of the switch, as shown, a pin on an extension of the armature depresses two spring contacts away from the contact piece *c* and in the closed position the same pin raises two other springs from the same contact piece. The

springs and contact piece constitute what is known as *interlock switches*, the purpose of which is to make the closing or opening of certain control circuits dependent on the position of some main switch. They are used in some methods of speed control of multiple-unit trains. This switch may be arranged to be operated by either closing or opening the circuit of the operating coil *a* by means of a hand-operated switch, or automatically by means of a relay that may be installed in some control circuit.



FIG. 16

The insulating oil must be non-explosive and non-freezable in the coldest weather encountered.

18. Figs. 16 and 17 show a circuit-breaker much used in cars taking not over 200 amperes. This breaker opens automatically on overload and can be opened manually by pressing the button shown outside the case in Fig. 16. It is closed by moving the handle, shown projecting below the case, to the right. The terminals *h* and *i*, Fig. 17, serve to connect the circuit, to the magnet coil *v*. If the current in the



FIG. 17

circuit exceeds the value for which the breaker is adjusted, or if the button outside the case is depressed, the armature *g* is brought against the releasing lever *f*; the switch contacts located in the blow-out flue shown at the left, then snap open. The compression spring *s* which is located between the top part of the handle and the switch arm, serves to hold the contacts firmly together when the switch is closed. When a loaded circuit is opened by this breaker, hot gases are expelled through the blow-out flue.

FUSES

19. In some installations, a **fuse** is used in conjunction with a breaker as a further element of safety, should the breaker fail to operate.

Fig. 18 shows an **enclosed fuse** and its enclosing asbestos-lined iron box. The fuse is connected in circuit by means of the



FIG. 18

switch clips shown near the ends of the fuse cylinder. When the fuse has blown, the *telltale* wire *a* also burns out and indicates that the main fuse has operated. A new fuse can be easily placed in the clips.

20. Fig. 19 shows the interior of a type of **magnetic blow-out fuse box,** the hinged cover being dropped. The

circuit wires enter the box through holes in the cover and are fastened to the fuse terminal blocks by the nuts shown. The fuse consists of a copper ribbon stretched between the blocks. The cross-section of the fuse is decreased at the center by a hole punched in the fuse. The central part of the fuse thus has the least current-carrying capacity, and the fuse will melt at that point. The arc takes place some distance from either terminal, and the terminals are less liable to damage than if the fuse melted at a point near one of them. In the fuse box shown, the current in the fuse sets up in the iron plates on the box and cover the magnetic flux that helps to extinguish the arc. In high-tension fuse boxes, blow-out coils are provided. A new fuse is placed in the clamps, which may be tightened by the two knobs shown at the sides of the box.



FIG. 19

21. Fig. 20 shows a type of **expulsion fuse** sometimes used in high-tension car circuits. The fuse is inserted in a tube made of insulating material. Terminal pieces on the tubes fit in switch clips mounted on porcelain insulators. When a fuse blows, the sudden accumulation of gas in the chamber at the



FIG. 20

base of the fuse expels the metal vapor and blows out the arc. The tube may be removed from the clips and a new fuse wire inserted.

MOTOR RHEOSTATS

22. Motor rheostats consists of resistors with taps leading to the controller. The resistance in the motor circuit can



FIG. 21

thereby be cut out in steps as the car speed increases and the motors thus allowed to build up a counter electromotive force.

Fig. 21 shows a type of rheostat made of cast-iron grids in two rows, each row supported by two insulated rods. The rods pass through U-shaped openings in the grid lugs, so that any grid can be removed and replaced as indicated. The adjacent terminals of two grids are in contact with each other



FIG. 22

on one rod and insulated from each other on the other, thus causing the current to take a zigzag path through the rheostat.

Fig. 22 indicates the method of mounting the grids on one side of the rheostat. The rheostats are usually mounted under the car in a position where water will not readily reach them.

LIGHTNING ARRESTERS

23. Carborundum-Block Arrester.—Fig. 23 shows a type of carborundum-block arrester. The spark gap is formed between a terminal plate shown at the right and the carborundum block. The other terminal of the arrester is a plate connected directly to the left side of the block. The discharge current due to lightning jumps the gap and spreads itself over the carborundum block along a number of minute discharge paths. The nominal voltage of the line is not sufficiently high to maintain arcs across these small air gaps after the lightning discharge has ceased. The arrester then assumes its normal condition.



FIG. 23



FIG. 24

Fig. 24 illustrates the arrangement of the parts of the carborundum-block arrester and the case in which it is enclosed.

24. Magnetic Blowout Arrester.—Fig. 25 shows an arrester in which the arc due to the trolley current following the lightning discharge across the air gap is extinguished by means of a magnetic blowout coil. The terminal pieces for the spark gaps *a* are mounted on the cover and when in position lie between the pole pieces *b* of the magnet *c*. The magnet coil is in parallel with a portion of the resistor *d*.

Fig. 26 shows the connections of the magnetic blowout arrester. The action of the choke coil in the motor circuit



FIG. 25



FIG. 26

tends to divert the current of the lightning discharge across the air gap and directly through the whole length of the resistor to a ground connection on the motor frame. When the trolley current follows through this discharge path, some of it energizes the blowout coil and extinguishes the arc at the air gap. The arrester is then in readiness for another lightning discharge.

25. Arresters Opening the Ground Circuit.—Fig. 27 shows a type of arrester in which the arc is disrupted by opening the ground circuit. The line wire is shown at *a* and the ground wire at *b*. The coil *c* is connected in parallel with the lower

portion of the resistor *d*. At the upper end of *d* is a fixed air gap. A plunger armature in coil *c* rests on a fixed grounded contact in an insulating tube shown below the coil *c*. The current of the lightning discharge passes across the fixed air gap and through the resistor and plunger to ground. When the trolley current follows, some of it energizes the coil *c*, thus lifting the plunger and opening the circuit at the lower fixed contact in the tube. The arc is extinguished, the plunger falls back in position, and the arrester is ready for further service.





FIG. 27



FIG. 28

26. Aluminum Electrolytic Arresters.—When aluminum is treated in certain electrolytes, a film forms on its surface. This film offers very high resistance to the passage of low-voltage electricity between the aluminum and the electrolyte and very low resistance to high-voltage electricity, especially

if it is alternating at high frequency, as is the case with lightning discharges. By nesting together a series of cup-shaped aluminum trays with intervening spaces, and filling each tray with electrolyte, a very effective lightning arrester is formed. Each assembly of this kind forms a cell, or unit.

Fig. 28 gives end (*a*) and side views (*b*) of two cells connected in series with a fuse between a trolley line and ground. Each cell bridges a gap and each gap is also bridged by a resistor. A lightning discharge breaks down the resistance of the film and the electricity flows readily to ground; but as soon as it has passed, the film reforms and prevents the escape of electricity at the normal voltage, except a small leakage current, which serves the useful purpose of keeping the film in proper condition. If the cells are to be left idle for a considerable time, the electrolyte should be withdrawn. When the cells are again placed in service, the electrolyte should be put in and the film reformed by connecting the cells in series with five 32-candlepower, 120-volt incandescent lamps across a 600-volt circuit. The lamps will usually brighten for an instant and then darken, as the film is formed. Inspection should be made at regular intervals.

LIGHTING, HEATING, AND AUXILIARY APPARATUS

ELECTRIC-CAR LIGHTING

27. Lighting-Circuit Diagrams.—The lighting circuits on a car include the lamps for interior use, the platform lamps, the headlights, the signal lamps, and switching arrangements for cutting one or more of these devices into or out of service, as desired. The signal lamps should be provided with a source of energy independent of the trolley system to insure their operation when needed.

28. Fig. 29 shows a very simple lighting-circuit diagram, including interior lamps *a*, platform lamps *b*, headlights *c*, and a single-pole, double-throw, knife-blade switch *d*. With the

switch in the upper position, the headlight at the left end and the platform light at the right end are connected in series with the interior lamps across the line. With the switch in the lower position, the other platform lamp and headlight are active.

29. Fig. 30 shows a car-lighting diagram for a large side-entrance car. The circuits are numbered from *1* to *5*, inclusive. Each circuit is provided with a fuse and all circuits are controlled by a main switch *a*. The headlights which are in circuit *5* are controlled by a single-pole, double-throw switch *b*. Circuits *3* and *4* include only interior lamps. Each of circuits *1* and *2* includes four interior lamps and one sign lamp *1 c* or *2 c*. Circuit *5* includes two interior lamps, two sign lamps *5 c*, switch *b*, and one of the two headlights *5 d*, depending on which way switch *b* is closed.

Each of the sign lamps is in series with lamps of an interior circuit; therefore, any derangement of a sign circuit is indicated by the lamps within the car going out.



FIG. 29

30. Fig. 31 shows a wiring diagram for signal lanterns that may be operated from either the trolley circuit or from a storage battery. There are two trolley signal lamps and two battery signal lamps at each end of the car. The main switch is shown at *a*; one double-pole, double-throw switch at *b*, and one at *c*; a storage battery at *d*, and a relay at *e*. When the trolley lamps are in series, this relay forms a connection between terminals *1* and *2*, and when the battery lamps are in service, between *1* and *3*, the ground connection formed through *1* and *2* then being cut out.

Switches *b* and *c* serve to cut in or out of circuit the signal lamps on their respective ends of the car. While the trolley circuit is active and the relay connection remains between *1* and *2*, these switches control the trolley signal lamps only; if the trolley current fails, the relay connection is automatically transferred to points *1* and *3*, and switches *b* and *c* then serve to control the battery signal lamps. With the switches *b* and *c*


5d
1c
2c
3
4
1
2
5
Trolley
a
b
5c
5d

FIG. 30


Battery Lamps
Trolley Lamps
c
Trolley
Fuse
Pilot lamp
a
d
+
Lamp
e
Ground
b
Trolley
Lamps
Battery Lamps

FIG. 31

in the positions shown and with the trolley current off, the battery signal lamps at both ends are active. The pilot lamp is also active, showing that the battery is discharging. When the trolley circuit again becomes active, the relay connects the trolley lamps in circuit and cuts out the battery lamps.

The battery is charging when the trolley lamps are active, as there are five lamps and the storage battery in series across the circuit.

31. Fig. 32 shows a signal lantern and the relative positions of the trolley and battery signal lamps. The lens may be of



FIG. 32

the desired color to act as a danger signal or to indicate the classification of the car. Usually one lantern of a pair is used as a *tail-light* and the other as a *marker* to show the kind of service or the destination.

HEADLIGHTS

32. The illumination of headlights for electric cars or trains is usually provided by an incandescent lamp, an arc lamp, or both. A high-speed interurban train requires a considerable distance in which to stop after detecting an obstruction on the track; therefore, a headlight containing an arc lamp that will project a strong light for 1,000 feet or more, is required. Such a light is undesirable for city work because

of its blinding effects on drivers of other vehicles and pedestrians. An incandescent lamp provided with a reflector is commonly employed in headlights for city service. Cars operating in both city and interurban service sometimes have a combination headlight in which are installed an incandescent and an arc lamp. Occasionally separate devices are used, the incandescent headlights are mounted permanently on both ends of the car and the arc headlight is of the portable type. The headlight is usually carried on the front of the dash of cars operating singly and on the top of the bonnet of cars used in train service.

33. Incandescent Headlights. Incandescent headlights may be of the portable or permanent type, and set within a hole in the dash, mounted on a bracket in front of the dash, or installed on the car bonnet.

Fig. 33 shows a type of portable incandescent dash light consisting of an incandescent lamp, a reflector, and an enclosing case. The case has an extension contact piece that may be inserted in a receptacle S attached to each end of the car. A cover C protects the interior of the socket when the dash light is not in service.



FIG. 33

Fig. 34 shows a wiring diagram to be used for a portable dash light on a car equipped with two five-lamp circuits. The circuits from the trolley T are controlled by a switch S and protected by a fuse in a fuse box $F.\ B.$ Both circuits are grounded at G. The lamp for the dash light is indicated at 7. When the contact piece of the dash light is in the receptacle at the right, the lamp 7 is cut into circuit with the four lamps L, and the lamp L_1 is cut out of circuit by the opening of the two lower springs in the receptacle. When the dash light is installed at the left end of the car, the

lamp L_2, which, as shown is in circuit, is cut out and the dash light substituted.

34. Arc Headlights.—Fig. 35 is a general, and Fig. 36



FIG. 34

a sectional, view of a combination incandescent and arc headlight. An incandescent lamp is attached inside the door and



FIG. 35

may be used to provide light for city work. When the arc lamp is used, the incandescent lamp is cut out of circuit, but the

lamp itself remains in the front of the headlight. The arc-light carbons are inclined at an angle of 45° with the perpen-



FIG. 36

dicular, to present a large area of crater to the center of the reflector. The initial drawing of the arc or its reestablishment and the feeding of the carbon are automatically controlled by a coil in series with the arc.

Fig. 37 shows a wiring diagram for a headlight of this type.



FIG. 37

The resistance used in series with the arc light is such as to admit a current of 3½ amperes at a line pressure of 550 volts,

the drop across the arc then being about 75 volts. Both the incandescent attachment, supported on the door, and the arc-lamp circuits have plugs and receptacles of their own, and in order to obviate the necessity of pulling the plug of the lamp circuit that is not wanted, both receptacles are connected to a two-point switch, the position of which determines which circuit shall be supplied with current. When the headlight is changed from one end of the car to the other, both plugs must be removed from the receptacles.



FIG. 38

35. Fig. 38 shows the exterior of a portable luminous arc headlight used in suburban and city service; Fig. 39 illustrates the interior and Fig. 40 the electrodes. The operating mechanism and the electrodes are placed in separate chambers in order to protect the coils from the arc gases. The upper or positive electrode is of copper and will last from 1,000 to 2,000 hours; the lower or negative electrode is an iron tube filled with a mixture of magnetite, chromium, and titanium and it will last from 150 to 175 hours.



FIG. 39

The arc takes a current of 2 amperes at about 90 volts. The negative side of this headlight is grounded to the casing; therefore, only one plug and socket is required to connect the headlight in series with a resistor across the circuit.

36. For high-speed interurban service a luminous arc headlight taking a current of 4 amperes may be used. In order to dim the light when desired, an incandescent lamp placed in the case may be cut into circuit and the arc lamp cut out; or the current through the arc lamp may be reversed in direction and caused to pass through an additional resistor. With the copper electrode acting as a negative, the light will be lessened.



FIG. 40

Fig. 41 shows a wiring diagram for a 4-ampere, two-terminal headlight, arranged for reversing the current through the arc lamp by means of the double-pole, double-throw switches. The extra resistance in circuit when the copper is used as a negative electrode decreases the operating current to about 2½ amperes.

ELECTRIC CAR HEATING

37. Electric heaters are extensively used for electric car heating because of their convenience and cleanliness. An



FIG. 41

electric car heater consists of resistance wire in an enclosing case. The wire is heated by the current, and the case keeps the

clothing of passengers away from the hot wires while allowing a circulation of air. From 4 to 20 heaters may be required to a car, depending on the size of the car, the climate, the kind of traffic, and the make of heater. A number of small heaters symmetrically placed produce an even distribution of heat. To keep a 20-foot closed car comfortable during average winter weather in the vicinity of New York City requires about 10 amperes at 500 volts, or about 8.3 amperes at 600 volts; this is between 6 and 7 horsepower per car. A rough estimate for winter weather in a cold climate is that one-third of the total energy required for the operation of the car is utilized by the heaters. The reason for this high proportion is that the heating current is used continuously and the propulsion current intermittently.

Heaters are usually arranged to provide three degrees of heat by means of a switch and division of the heaters into groups. On some roads the heating of the car is left to the discretion of either the conductor or the despatcher, and in other cases, the heating is controlled automatically by means of a circuit-closing thermometer.

CONSTRUCTION OF ELECTRIC HEATERS

38. Fig. 42 shows a type of heater in which the active wire formed into a spiral is wound in the grooves of a porcelain



FIG. 42

tube. The tube is supported on a steel rod extending between metal heads. The terminals are brought out through porcelain

bushings at one or both ends, as desired. One, or more, of these wire spirals is enclosed in a case, a portion of which, as shown in Fig. 43, is perforated to allow circulation of air.

39. In some heaters, the spiral of wire is supported on



FIG. 43

knobs *a*, as indicated in Fig. 44. Knobs *b* serve as anchors for the terminals of the heating element.

Another method of mounting the spiral is shown in Fig. 45.



FIG. 44

The support consists of a $\frac{1}{4}$-inch curved, enamel-covered steel rod *R*, which touches the spiral *S* in only a few places.

The object of the spiral construction of bare wire is to allow the air free access to nearly the entire surface of hot wire. The



FIG. 45

tension on the turns, due to the method of mounting the spiral, tends to keep them from touching and thus cutting out of circuit some of the resistance.

HEATER CIRCUITS

40. All manually operated car electric-heater systems employ practically the same method of connecting the heaters and regulating the heat. Fig. 46 shows circuits for four heaters,



FIG. 46

each heater having two coils of unequal resistance. The top coils are connected in one series and the bottom coils in another. The switch can be closed so that either series will be in circuit alone or so that the two series will be joined in parallel across the circuit, thus providing for three degrees of heat.

41. Fig. 47 illustrates a switch used in heater circuits. The trolley terminal is shown at *T* and terminals *1* and *2* are



FIG. 47

connected to the two heater circuits, as indicated in Fig. 46. Arms *a*, *b*, and *c*, Fig. 47, rotate with the central part of the switch; the positions of the switch are indicated by the numbers

and the word "off" marked on the black disk, as seen through the hole in the cover. In the position shown the top and



FIG. 48

bottom heater circuits are in parallel and the heaters are giving maximum service.

42. Fig. 48 shows, for a large center-entrance car, two independent circuits that contain ten heaters each, with two elements in each heater. The temperature of the car is controlled by means of a thermostat and an automatic switch. This thermostat is adjusted to cause the heater circuit to open if a certain temperature is exceeded and to close if the car temperature falls below this fixed point. One or more of the heater circuits, as the weather conditions require, are placed in service by means of small switches and the thermostat then regulates the temperature of the car.



FIG. 49

HEAT REGULATION

43. Fig. 49 shows a type of automatic switch for the control of heating circuits, and Fig. 50 indicates the connections of the switch to a circuit-closing thermometer. In both figures resistors are shown at *a* and *b*, the operating coil of the heater switch at *c*, a blow-out coil at *d*, a relay coil at *e*, a fuse at *f*, and in Fig. 50, a circuit-making thermometer at *g*. The mercury of the thermometer as it rises makes a connection between a fixed and an adjustable contact. The operating coil *c* is energized by current through *a*, *c*, and *b*, to ground, Fig. 50. Coil *c* closes the switch, and the heaters receive current through the blow-out *d* and switch. When the temperature of the car rises to the point for which the upper thermometer terminal is adjusted, the relay is energized by current through *a*–*c*–*f*–*e*–*g*–ground. The relay contacts shown above coil *e* close, thus short-circuiting the operating coil *c*, which causes the switch and the heater circuit to open. When the temperature falls below the desired point, the short circuit is removed from coil *c*, which acts to close the heater circuit.



FIG. 50

The upper contact on the thermometer can be set to regulate the temperature at any desired value from which, through the action of the automatic switch, but a small variation is allowed.

COMBINED HOT-AIR AND VENTILATING SYSTEMS

44. In some systems for heating and ventilating cars, fresh air is drawn from the roof, side, or bottom of the car, heated by passage through a small coal furnace, and then discharged

through a distributing duct usually placed on one side of the car. The movement of the air stream is set up by a blower mounted on the furnace. Fig. 51 indicates the general features of a heating and ventilating system of this type. The air enters at *a*, passes through the preliminary heating chamber *b* into the blower, and is then forced through the final heating chamber *c* into the distributing duct. The duct has slots of varying widths that provide proper distribution of the heated air throughout the car.



FIG. 51

45. In place of a coal furnace, an electric heater is sometimes used to warm the air and a blower provided to force the air through the heater and distributing duct. Fig. 52 shows



FIG. 52

the exterior of an electric heater and blower and Fig. 53 indicates the air passages. The heater elements, composed of wire

wound in spiral form, are arranged in groups so that all or part may be connected in circuit. Automatic control by means of a thermostat serves to close or open the heater circuit in accord with the temperature conditions.



FIG. 53

46. In the hot-water system of car heating, the water flows through a closed circuit of piping including a pipe spiral placed within the fire-box of a small coal furnace. To prevent damage by freezing care must be taken to drain the pipe of water in case the car is to be out of service for a considerable time.

AUXILIARY CAR DEVICES

CONTROLLER REGULATORS

47. The **controller regulator** is a device attached to the top of a controller to retard the movement of the handle toward the running position, as too rapid movement would damage the electric apparatus. Fig. 54 shows the exterior of one type of a controller regulator called an *automotoneer*. The lower casting *a* is fixed to the top plate of the controller and the upper casting *b* turns with the controller shaft.

Fig. 55 shows the inside of the lower *stationary casting a*, containing an inner row of notches and an outer row of stops. The dog *b* is attached to the upper casting by a ball-and-socket joint or bearing, and is so mounted that its lower part is free to swing outwards as it slides along the inner row of notches on *a*. In the position of the dog shown in Fig. 55 its lower end has been forced outwards by one of the inner notches, so that the side of the straight stem of the dog engages with one of the stops in the outer row. This action blocks further forward movement of the dog, of the upper casting, and of the controller

shaft until the pressure of the motorman's hand is released from the handle, when the dog swings inwardly by gravity through the path *c*, thus clearing the stop and allowing the handle to be turned again until the dog engages with the next outer stop.



FIG. 54

These operations are repeated for each notch on the controller. The number of stops on the automotoneer is such that its notching movement corresponds to that of the controller on which it is mounted. The handle must therefore be advanced in a series of alternating steps and pauses, which is precisely



FIG. 55

the method necessary for proper acceleration of the motor speed. The controller can be thrown to *off* position as quickly as desired, for the dog will then assume an inclined position and slide over the stops and the notches on the stationary casting.

The upper and lower castings are locked together by means of a ring of balls placed between them. Half of the ball race is cut in a boss on the upper casting and half on the lower casting. Steel balls which are poured into this raceway when the parts are in position while allowing rotation of the upper casting, prevent its removal.

BUZZER AND BELL CIRCUITS

48. Fig. 56 shows the connections of buzzers *a* and bells *b* on a center-entrance car. The current for the two circuits is obtained from the trolley through a switch, a fuse, and a resistor. Twenty push buttons are connected to the buzzer circuit. The



FIG. 56

passenger may signal for a stop by pressing any one of these buttons, and both buzzers, which are in series, will operate.

The bell circuit is for the use of the motorman and the conductor. If button *c* or *d* is pressed, bell *b* on the right operates; if button *e* or *f* is pressed, bell *b* on the left operates. Single-stroke bells are used and the ordinary one-, two-, or three-bell signals may be given.



FIG. 57

DOOR-OPERATING CIRCUITS

49. Fig. 57 shows the electric circuits for the operating magnets that control the valves of the air cylinders used to open and close the two double doors on some center-entrance cars.

The magnets are energized by the trolley current. The circuit of the magnets *a* for opening the doors can be completed only when a push button is pressed and relay contacts *c* are closed, which occurs only when there is no car movement. The circuit of the magnets *b* for closing the doors can be completed at any time by pressing another push button.

While the car is running and the motor circuit is complete from the trolley to ground, main switch *No. 5* is closed and its interlock is open. Relay coil *d* then receives current through a resistor, and contacts *c* are kept open. When the motor circuit is opened, main switch *No. 5* opens and its interlock closes. As long as the car continues to coast, relay coil *d* receives current due to the electromotive force generated by the armature of *No. 2* motor rotating in a residual flux. Thus contacts *c* remain open until the car stops, and only then can the doors be opened. The *No. 5* interlock and the switch for the *c* contacts are



FIG. 58

shown in the positions assumed when the car has stopped. The reference letters and numbers shown near the motor circuit relate to the various parts of a car-wiring diagram, which subject is treated in another Section.

DOOR-SIGNAL LAMPS

50. Fig. 58 shows the wiring diagram for signal lamps that indicate whether or not the car doors are closed, and for the devices that make it impossible to start the car until the doors are closed. By means of a double-throw switch *a*, both these features can be made inoperative.

With switch *a* in its upper position, current for operating the master controllers must pass through the relay contacts *b*, and with the switch in its lower position, these contacts are out of circuit. The relay

contacts are closed only when coil *c* is energized, and this occurs only when all of the door switches *d* are closed.

Two-way switches *e* and *f* serve to make the signal lamps at either end operative. If the doors are closed, with the switch *a* in the position shown, a circuit is completed through switch *a*–fuse–*e*–coil *c*–four door switches *d*–*f*–signal lamps at the right–*G*. By turning the signal-lamp switches *e* and *f*, the signal lamps at the other end of the car can be used.

A resistor in series with one signal lamp of each pair makes the brightness of the two lamps differ and helps to insure against failure by burning out of both lamps simultaneously.

REGISTER-RINGING DEVICE

51. Fig. 59 shows the wiring plan for an electrically operated cash register. When the push button *a*, placed on a pedestal near the conductor's station, is pressed, the operating coil *b* within the register rings the signal bell and rotates the counting mechanism. If the button is held down a device *c* in the register automatically opens and closes the circuit, repeating the signal and registering any desired number of fares.



FIG. 59

CAR SIGNS

52. The main requirements of a good car sign are that it is always readable, indicates many destinations, is easily changed, and is durable. Fig. 60 (*a*) and (*b*) shows the general features of a car sign of the curtain type that with slight modifications may be mounted on the hood, the dash, or the side of the car. Light in the rear of the curtain makes the letters readable from the outside of the car. For side installation, the car lamps will usually provide sufficient illumination. For car-end installation where direct light from the car is not available, lamps

within the sign case are usually employed. An indicator near the handle of the sign-rotating mechanism, or lettering on the



FIG. 60

back of the curtain, used in connection with a pointer, shows what sign is exposed and if it is centered.

INSTALLATION OF CAR WIRES

53. The wires installed on a car may be divided into two groups: those connecting the devices of the motor circuit, such as trolleys, car motors, controllers, rheostats, circuit-breakers, lightning arresters, etc., and those connecting the devices of the lighting, heating, and auxiliary circuits and referred to independently as light wiring, heater wiring, signal wiring, etc.

Car wires have been installed in canvas hose, wooden molding, or pressed boards made of insulating material. On modern equipments of the best type, however, iron conduits are extensively used. With platform controllers that handle main-motor current, the motor and rheostat wires are carried from one controller to the other either in one pipe, which runs down the center of the under side of the car between the two center sills, or in two pipes, one on each side of the car. In either case the taps from the wires are taken out through *condulets*. All trolley and ground wires and their taps are best run in separate pipes to lessen damage that may occur from lightning discharges.

In cars equipped for the multiple-unit system of control, the small control wires from the master controller to the box containing the motor switches are drawn into a single conduit. The group of main wires from each motor to the switch box are included in single conduits. Other conduits are provided for the heater, lighting, and signal wires.

54. In order to limit the effect of self-induction when alternating current is employed, some form of non-metallic conduit should be used when only a single wire is installed; but if a metal conduit is used both sides of a circuit must be installed within it. If a metal conduit should be used for a single wire carrying an alternating current, and the conduit touches any metal portions of the car in such manner as to form a closed circuit, the conduit may act as the secondary of a transformer, the primary of which is the single wire. The conduit may thus be heated and injure the insulation of the enclosed wire. Care should be taken, if alternating current is used, to prevent a closed circuit of piping, even if the wires of both sides of the circuit are installed in the conduit. The metal conduit is grounded so that if a wire within the pipe comes in contact with it, the fuse protecting that circuit will blow.

55. The "National Electrical Code," issued by the National Board of Fire Underwriters, contains rules relating to the installation of car wiring. These rules are subject to revision and the latest edition of the "Code" should be consulted by any one having charge of car wiring.

56. The current used in determining the size of motor, trolley, and resistance leads is taken as a percentage of the full-load current required by the motors, based on 1 hour's run. Table I shows percentages. The full-load current is equal to

$$I = \frac{746 \times n \times H.P.}{E \times a}$$

in which n = number of motors;

$H.P.$ = horsepower of each motor;

E = line voltage;

a = efficiency, expressed decimally, of geared motors.

For estimating current in order to select conductors, the approximate efficiency of the motors with gears may be assumed to be 85 per cent.

Table II indicates the safe carrying capacity of rubber-covered wires.

TABLE I

PERCENTAGE OF FULL-LOAD CURRENT IN LEADS

Size of Each Motor Horsepower	Motor Leads Per Cent.	Trolley Leads Per Cent.	Resistance Leads Per Cent.
75 or less	50	40	15
Over 75	45	35	15

TABLE II

ALLOWABLE CARRYING CAPACITIES OF WIRES

B. & S. Gauge	Current Amperes	Size of Wires Circular Mils
8	35	16,510
6	50	26,250
5	55	33,100
4	70	41,740
3	80	52,630
2	90	66,370
1	100	83,690
0	125	105,500
00	150	133,100
000	175	167,800
0000	225	211,600

EXAMPLE.—Determine the size of: (*a*) trolley leads, and (*b*) motor leads to be used with an equipment of four 50-horsepower motors, the line voltage being 500 and the efficiency of the motors with gears 85 per cent.

SOLUTION.—(*a*) In the formula, $n=4$, H. P. $=50$, $E=500$, and $a=.85$; then

$$I=\frac{746\times4\times50}{500\times.85}=351 \text{ amp.}$$

From Table I, the size of the trolley leads is based on 40 per cent. of the full-load current 351 amp., or $351 \times .4 = 140$ amp. From Table II, the safe size of wire for 140 amp. is No. 00 B. & S., having a cross-section of 133,100 cir. mils. Ans.

(*b*) The approximate full-load current for each motor is one-fourth of 351 amp., or 88 amp. From Table I, Motor Leads, 50 per cent. of 88 amp. is 44 amp.; from Table II, the wire to be used is No. 6 B. & S. Ans.

COMBINED FARE BOX AND REGISTER

57. Many devices have been developed for the purpose of receiving and counting the money, tickets, and transfers delivered by the passengers. Fig. 61 shows one type of combined fare box and register. The hopper is mounted above the coin-examination box and has separate openings for coins and for tickets. The coins are deposited through a series of perforations and fall through a channel into the glass enclosed examination box. They then pass through the counting mechanism into the cash drawer, from which they may be removed by the conductor for making change. The insertion of a ticket through a separate slot moves a trigger that makes an electric contact and causes inked rollers to cancel the ticket, which is then deposited in the ticket box. The cranks shown at the right serve to operate the releasing and registering mechanism.



FIG. 61

58. In some systems of fare collection, an ordinary register is used in connection with a fare box. The fare box records the cash fares and cancels the tickets and the register records the total number of fares of all kinds. The difference between the total number of fares on the

ordinary register and the sum of the canceled tickets in the fare box and the transfers taken by the conductor must be the number of cash fares.

SAND BOXES

59. Lever-Operated.—Application of sand to the rail



FIG. 62

will, under some conditions, greatly increase the friction between the drivers and rails and thus aid the car to climb a grade, control the speed when descending a hill, and lessen the time taken to bring the car to a full stop.



FIG. 63

Fig. 62 shows one type of sand box that may be operated through levers moved by hand or foot.

Fig. 63 illustrates the method of releasing the sand. A rocker casting *a* when in normal position is below the mouth of the sand hopper *b*. On pouring sand into the box, the rocker casting is first filled and this sand blocks the mouth of the hopper which may then be filled. To operate the box, the rocker casting is swung to

one side and the sand pours through the pipe leading to the rail in front of the drivers.

60. Air-Operated.—Sand boxes on cars equipped with air brakes may be operated by an air blast directed on the sand in a trap attached to the lower part of the hopper.



FIG. 64

Fig. 64 shows the trap portion of an air-operated sand box. Pipe *a* is connected to the air-brake system of the car. The lower part of trap *b* is nearly filled with sand which normally blocks the flow of sand from the hopper. When the box is to be operated, a valve in pipe *a* is opened and a jet of air blows the sand from the lower portion of the trap through the sand pipe and on to the rail. While the air blast continues, the sand will flow from the hopper to the trap and then to the rail.

AIR GONGS

61. Fig. 65 indicates a method of operating a platform signal gong by air as well as by the usual foot-lever. The mechanism for foot operation is shown at *a*. When the button, which projects slightly above the floor of the platform, is depressed, the hammer strikes the gong.



FIG. 65

The pneumatic part *b* is a D-shaped casting which forms a raceway for a steel ball. When air is admitted, the ball is driven around the raceway, the upper end of which is cut away, so that the ball hits the gong.

Fig. 66 indicates the piping connections for a foot-operated air valve to a gong. A double air valve may be used in a



FIG. 66

similar manner for the operation of the sand box in combination with either a whistle or a signal gong.

TRACK SCRAPERS

62. The purpose of track scrapers is to keep the rails clear of snow until the sweeper cars get into action. Fig. 67 shows one type of scraper the plates of which are spring-supported and may be forced into contact with the rails by a hand-operated shaft or by compressed air. Scrapers may be installed at one or both ends of the cars, to conform to service requirements.



FIG. 67

CAR BODIES

63. Car bodies are made in a very large variety of styles to conform to operating conditions. Body lengths range from 18 to 80 feet, and the construction may be open for summer service, closed for winter service, or semiconvertible for use throughout the year.

The modern tendency in body design is to reduce the weight of the cars per seated passenger, install ball or roller bearings, shape the ends of the bodies to lessen air resistance, and otherwise to reduce to a minimum the energy required for operation.



FIG. 68

Car bodies over 20 or 22 feet in length are usually equipped with double trucks because a long rigid single truck will not readily pass around curves at street corners.

If a semiconvertible car body is used, the trucks and motor equipment remain with the body during winter and summer, thus obviating the necessity of keeping both closed and open car bodies and the labor of changing the motor equipment from one to the other twice a year. In some semiconvertible bodies, the window sashes during the summer can be pushed into pockets in the car roof. In other cases, the window panes are removed and stored; heavy curtains then protect the passengers from rain. In either case plenty of ventilation is secured.

64. Car bodies of the type shown in Fig. 68, have platforms arranged for the entrance and exit of passengers by different routes and are used where the prepayment system of fare collection is employed.



FIG. 69

This system of construction and collection tends to diminish the number of accidents, since the passengers leave and enter within view of either the conductor or the motorman.

Center-entrance car bodies are sometimes used and where the traffic is very heavy, double decks are sometimes provided, thus greatly increasing the seating capacity of the cars. One type of double-deck, stepless, center-entrance car is shown in Fig. 69.

In some railroad systems, light-weight cars without motor equipment, called *trailer cars*, are coupled to the rear ends of the regular cars during rush hours. As soon as the traffic lessens, the trailers are disconnected and the motor cars continue in service.

The seating arrangements are varied. Some car bodies are intended for cross-seats, some for lengthwise seats, and others for a combination of the two seating systems.



FIG. 70

TRUCKS

65. Classification of Trucks. A **truck** may be defined as a set of wheels in a framework designed to support the whole or part of the weight of a car body and equipment. The main requirements of a good truck are that it is easy riding, durable, of simple construction, the wearing parts are easily renewable, and the main members cannot be distorted under service conditions. The trucks should be self-contained, that is, one framework must include the wheels and axles, the brakes, the motors, and the driving gear.

Trucks may be divided into two general types of construction: The *single*, or *rigid truck*, in which the car body is bolted to sides of the truck framework; and the *swiveling truck*, two of which are required per car; the ends of the car are then supported through bearings placed at or near the center of each truck. The latter type may be subdivided into the ordinary truck and the maximum-traction truck.

The rigid truck and the ordinary truck have four wheels of equal size and may carry one or two motors each. The maximum-traction truck has two large and two small wheels and carries only one motor, which is geared to the axle with the large wheels. The bearing of this truck is not in the center, but is so placed that about 70 per cent. of the weight supported by the truck rests on the large driving wheels. The weight

on the small wheels is sufficient to keep them on the rails as the car is rounding a curve.

66. Experiments have shown that for a given car weight, maximum-traction trucks require less energy expenditure than rigid trucks with a 7-foot wheel base. The wheel base is the distance between the point of contact of the forward wheel of a rigid truck with the rail and the corresponding contact point for the rear wheel of the truck on the same rail. The rigid truck is more apt to bind on curves than the maximum-traction truck with its shorter wheel base.

The ordinary truck with one motor has the disadvantage that the driving power is all exerted from one axle, while the



FIG. 71

weight that limits tractive effort rests on two axles. The result is that the drivers tend to spin when heavy duty is impressed on the motors because the friction between the drivers and the rails is not sufficient to prevent wheel slipping. When a smaller motor is put on each axle of the truck, spinning is less likely to occur.

Large cars for interurban service are usually of the double-truck type. In some cases one truck is designed to support two motors and the other truck, which is of much lighter construction, is not equipped with the motors. For heavy service a motor is usually installed on each axle of both trucks.

67. Types of Trucks.—Fig. 70 shows one type of single, or rigid, truck, Fig. 71 an ordinary truck, and Fig. 72 a

maximum-traction truck. On a single-truck car, the car body is bolted to the upper framework of the truck. Trucks for



FIG. 72

double-truck cars are attached to the car body by means of bearings placed at or near the center of the trucks, and king pins around which the trucks may turn as the car passes around a curve.

68. Fig. 73 shows a type of center bearing employing balls to lessen the friction. The upper member is mounted on the car body, the lower member on the truck. Part of the car weight is sustained and the car body kept balanced by rub plates, or side bearings, which are circular bronze plates, one set mounted on the truck and a similar set on the car body. These plates are kept well lubricated. The upper member of the center ball bearing and the upper rub plates are shown in position underneath a car body in Fig. 74.



FIG. 73

A car body mounted on two trucks sits higher above the rail than a closed car body using only one truck because the wheels on a double-truck car must clear the body when the trucks turn around their king pins as occurs when the car is on a curve.

69. Axle Bearings.—Fig. 75 shows one form of bearing construction used on rigid trucks. The bearing surface at the end of the axle on which the wheels are mounted is shown at *a*, the bearing brass at *b*, and the box casting at *c*. The weight



FIG. 74

resting on the truck transmits pressure through the spring *s*, held in a socket of frame *f*, to the box casting and the bearing brass. Since the pressure is always downwards, the bearing brass extends only part way around the shaft.

If the piece *d* is removed the frame may be lifted clear of the



FIG. 75

axle and bearing casting. The axle is lubricated by oil-soaked waste *g* placed in the lower part of the bearing casting.

70. Wheel Bearings.—Fig. 76 shows a roller bearing for a car wheel that rotates on a fixed axle. The vertical stress is



FIG. 76

carried by rollers *a* turning on a sleeve *b* on the axle; the end thrust is taken up by ball bearing *c*. The rollers and balls are carried in retainers.

LENGTH OF WHEEL BASE

71. The wheel base should be long enough to support the car body so as to prevent excessive oscillation of the car, but its length should not cause the wheels to bind on the shorter track curves. A car body that demands a wheel base exceeding 8 feet should be provided with double trucks. A car having an excessive wheel base requires considerable energy to pass around curves of short radius, and causes excessive wear of rails and wheels. On curves of longer radius the energy requirements and the wear are greatly lessened.

To enable cars to round curves with the least effort and to save the wheels and rails, guard-rail flanges at curves should be kept clean and well greased. In laying out a road, all the curves should be made of as long a radius as possible and when purchasing trucks for an existing road, the radii of the curves should be considered.

72. Wheels.—The wheels used on electric cars vary from 30 to 36 inches in diameter; on ordinary street cars, the diameters are usually from 30 to 33 inches. Somewhat larger wheels must be used for heavy work, so as to give more clearance for the motors; therefore, diameters of 33 to 36 inches are quite common. For light cars operating at low speed, cast-iron wheels with chilled treads are sometimes employed. For high-speed interurban work and for heavy city traffic at low speed, a wheel provided with a tire made of rolled open-hearth steel is often used.

The tire can be fastened to the cast-iron center by bolts, or retaining rings, but the usual method in wheels for electric cars is to fuse or cast-weld the tire to the center. The tire is heated, placed in the mold, and the iron center poured; the melted iron fuses the tire and a perfect joint between the two results. The main advantages of steel-tired wheels that compensate for their

high cost as compared with chilled cast-iron wheels are: (1) Greater strength and security; these wheels are not likely to fly in pieces, however high the speed may be or however severe the stresses due to rough track or very cold weather. (2) They are much less liable to develop flat spots. (3) They are less liable to slip, since the wrought steel tire has, with the steel rail, a much higher coefficient of friction than a chilled cast-iron wheel and the action of the brakes is more effective.



FIG. 77

(4) They avoid trouble due to chipped or to broken flanges. (5) The rim can be made thick so that the wheel will wear a long time before becoming unsafe; with chilled wheels the depth of chilled metal is limited.

Fig. 77 shows sections of two fused steel-tired wheels; view (*a*) is a 30-inch wheel weighing 650 pounds, used on trail cars for an elevated road; view (*b*) is a 34-inch wheel, weighing 688 pounds, for an interurban road.

On the treads and flanges of the wheels depends greatly the ease with which a car will take a curve. The treads should not be so wide that they run on the paving outside of the track, and the shape, depth, and width of the wheel flange should be governed by the corresponding dimensions of the rail groove.

CAR HOUSE

73. The **car house,** or **car barn,** is a building used for storing cars that are not in use, for inspection, and for minor repairs. Storage under cover is usually provided only for cars that are not in regular commission. A car fitted to operate all day in all kinds of weather requires no shelter over night, especially, when storage room is expensive. Where practicable, car-barn tracks should be far enough apart to admit of easy passage between rows of cars, and if the light in the aisles is good the labor and time required to change equipment at the end of the seasons may be much reduced.

In some car houses, the storage room may be all on one floor; in others, as, for example, in New York City, it may be on several floors, as the cost of land makes any other arrangement impracticable. In such cases the cars are conveyed to the upper floors by elevators and are shifted from the elevators to the several storage, inspection, or repair tracks by transfer tables. Where cars must be handled by elevators, stripped, out-of-season car bodies are usually stored on the upper floors, where they may be supported on horses or barrels, as there is no chance for the cars to be run out in case of fire. Where the storage room is on a level with the street, the car bodies should be supported on temporary trucks. Where possible, every storage track should lead to the street. In some car houses, the tracks are graded toward the street, so that the cars may be easily run out in case of fire. Sprinkler systems, the efficiency of which has often been demonstrated, are installed in all modern car houses.

PIT ROOM

74. For inspection of trucks and motors, pits about 4 feet 8 inches deep should be located directly under the tracks, no pit to be shorter than any car to be placed over it. The amount of pit room to be allowed per car depends on how much trouble the equipments give, on the class of work done at the car house, and on the ability of the car-house organization to so lay out the work that minimum pitting time per car is realized. A value based on long experience under varying working conditions with different equipments and different track layouts is 1 linear foot of pit room for each car that runs into a depot; that is, to accommodate two hundred cars, a car house should have pit room under at least 200 feet of track. This allowance would be scant for a car house full of crippled cars; but it is liberal where trucks are run from under and all overhauling is done above the floor line. This practice is popular because a more thorough job can be done when all parts are in full view in good light.

The pits should have cement bottoms with natural drainage; they should be well equipped with both stationary and extension lights. The floor level between tracks should be covered with removable boards. Underneath the floor line, the pit room should be open from wall to wall. A couple of shelves and a row of small bins in each pit, to hold bolts, nuts, and washers of the commoner sizes, will save much time. If the pits are arranged for heating in the winter and for cooling in the summer, the efficiency of the work done is increased.

The well-equipped pit room is supplied with motor- or air-driven dismantlers, that raise the car body from the trucks, which may then be run to their destination by hand or by connecting the motors to the circuit through a rheostat. A pole with wire attached may be used to make connection with the trolley wire. The same air supply may be employed for blowing out motors and controllers, and for operating small air lifts.

REPAIR SHOP

75. All heavy repairs, alterations, and manufacturing operations pertaining to cars should be made in the **repair shop.** A well-appointed repair shop includes a machine shop, carpenter shop, mill, blacksmith shop, paint shop, winding room, commutator room, controller room, store room, external oil room, and a wheel-grinding annex. In the machine shop, all general machine work is done, such as fitting bearings, turning commutators and shafts, cutting keyways, recutting bolts, etc. In the winding room, field coils, armature coils, armatures, heater coils, governor coils, rheostats, etc. are repaired or constructed. In the commutator room, the parts of commutators are assembled and the finished commutators are tested. In the controller room, controllers, switches, circuit-breakers, brush holders, etc. are repaired and assembled. There is usually work enough on small roads to keep one blacksmith and helper busy on brake rods, levers, hangers, fenders, trucks, and on line, track, station, and building construction work.

The shop should be a fireproof structure designed to afford maximum cleanliness and light. The best shops are so laid out that a car can progress from the pit room to and through the paint shop without retracing its route. The ideal arrangement is to separate the body and truck in the pit room, send the body on temporary trucks to the carpenter shop, and to lay out all repair work on body and truck so that they can be brought together and the car as a whole completed and tested before running it into the paint shop, from which it emerges ready to operate.

MACHINE SHOP

76. The machine-shop tools should be placed in such positions that there will be good light on the work and also to occupy minimum floor space. The number and kind of machines depend on the class of work. Enough machines should be provided to keep up with the work. The following machines would probably be required: One lathe for axles with wheels mounted,

one smaller lathe for armatures and bearings, one speed lathe, two sizes of drill press, one boring mill, one metal saw, one power saw, one planer, one shaper, one bolt cutter with right- and left-hand dies, one milling machine, one wheel press, one axle straightener, one grindstone, emery wheels, one punch press, one ratchet drill. On a small road the preceding list can be considerably modified by a good mechanic who knows how to do almost any kind of work on almost any kind of machine available.

WINDING ROOM

77. Where floor space is limited, the winding may be done in a gallery built around the wall above the machine shop; with this disadvantage, however, that heavy parts and material must be elevated. Winders should have direct window light where it is practicable. For a road operating one hundred cars or over, from 6 to 8 square feet of floor space per car should be sufficient winding space. For a small road, more space would be required per car. The outfit of every winding room in which coils are made and installed should include the following: One armature banding machine, one field-coil winding machine, armature-coil winding machines, taping machines, coil forms for each type of armature used on the road; brick-enclosed gas stove for heating soldering irons; a gasoline stove can be used if the tank is removed to a safe place; device for taking off and pressing on commutators, pinion puller, stands for armatures in course of winding, racks for completed armatures, racks for insulation stock, insulation-cutting machine, coil-pressing machine, glue pots to melt glue for holding coil papers in place, ample facilities for dipping coils in varnish or compound, and a good oven, unless air-drying varnishes are used.

The winding room should have duplicate substantial patterns of every standard piece of insulation used; one set should be hung in a convenient place and duplicate sets should be stored in a fireproof vault; every piece should be clearly and indelibly marked. Time and labor are saved if all armatures are handled with buggies and cranes. The journals should be protected with sleeves of fiber or of paper.

COMMUTATOR ROOM

78. The commutator room should be in the care of a good mechanic who understands commutators. It should contain a lathe, drill press, milling machine, and oven for baking the commutators. If it is the practice to groove commutator mica, either a mica-grooving machine or a milling machine adapted to that work should be provided. The commutator room should carry a full line of mica gauges and ring and plug gauges used to fit commutators to their seats on the armature shafts. A suitable press, for subjecting a commutator to external pressure while tightening it, should be supplied so that the job can be done without twisting the commutator bars out of alinement. An adequate supply of assembly rings and a full line of wrenches for adjusting them, are also essential. No emery wheel should be allowed in the room, because particles of emery trapped between bars cause trouble. The commutator room is best located next to the armature room; it should be enclosed and should have good light and ventilation. A reliable test for locating connections between bars or between a bar and the shell should be installed.

CONTROLLER ROOM

79. The controller room should be located where the dust incident to blowing out controllers, will not reach the commutator room, insulating bench, or coil winders; adjacent to the machine shop is a good place. On the brush controller holder repair bench there should be suitable gauges to insure the correctness of brush holders made or repaired.

MILL AND CARPENTER SHOP

80. The mill is the room in which the wood-working machines are placed and the carpenter shop is where the cars are run in for general body repairs. Both rooms may be within the same enclosure—the mill at one end and the carpenter shop at the other. The best place for them is near the machine

shop, pit room, and paint shop, a line of single or double track running through, so that a car can enter at one end of the building and go out at the other. In the mill there should be a planer, boring machine, lathe, band saw, circular saw, and grindstone.

PAINT SHOP

81. The paint shop should be at the extreme rear of the main shop and should have free access to the street; it should be provided with as many doors on the street side as there are tracks, so that in case of fire the cars can be run out without any shifting or transferring. The paint shop should receive only cars that have been repaired and are ready to run on the road except for the painting. Each track in the shop should have a trolley wire over it, the whole system of trolley wires being kept cut out by means of a switch except when they are to be used. Under no circumstances should the car bodies be set on horses or barrels in the paint shop; the risk of fire is too great. They should always be on temporary trucks, and where possible, at the head of each line of cars should be a car fully equipped, so that in case of fire they can be coupled together and towed out of danger. Another good plan is to have the tracks down grade out of the house, so that when the brakes are released or the chocks removed from the wheels, the cars will run out by gravity. The great fire-risk incidental to the storage of so many inflammable materials, oils, varnishes, etc., demands an absolutely fireproof wall between the paint room and the rest of the shop, communication between the two shops being only through self-closing fireproof doors. As a prime precaution against fire, the building should be of brick, with a fireproof roof and a cement floor. The floor should be graded to gratings that lead to the sewer or to a cesspool and the roof should be designed to give the best possible light and ventilation. All inflammable materials should be kept in a small, absolutely fireproof room that will admit barrels, etc., without trucking them the entire length of the paint shop. The question of fire-risk in a paint shop is a serious one, as the shop is generally full of cars that will burn quickly if once started.

BLACKSMITH SHOP

82. The blacksmith shop must be located where the coal dust and gases from the forges cannot reach the paint shop. It should contain at least two forges, anvils, and a blower. One forge should be provided with an ordinary bellows all ready to be connected on, in case of accident to the blower or its motor. Besides the usual complement of forge tools, there should be a machine hammer, shears, and a drill press.

GRINDING ROOM

83. If the brakes on a trolley are applied too hard on it for any reason the car skids along the track, flat spots, or **flats,** as they are called, are found on the tread of the wheel. These flats cause the wheels to pound on the rails, and unless they are removed by grinding or a new wheel put on, the trouble is likely to increase. In many car wheels of cast iron, the tread is chilled in the molding so that the iron is very hard to a depth of $\frac{3}{8}$ or $\frac{1}{2}$ inch. If the wheel is worn down so that the chilled portion is ground through, it is useless, as the soft iron under the chilled part will last only a short time. Small flats can often be removed by substituting for the regular brake shoe a special wheel-truing shoe provided with emery, carborundum, or similar abrasive.



FIG. 78

Fig. 78 shows one of these shoes; it simply replaces the regular brake shoe and in the course of a few hours' run the abrasive blocks *a* grind the wheel true. A bad flat is removed by a regular grinder, which is a device for holding a revolving emery wheel against the tread of the wheel to be ground. The wheels may be ground either in place on the car or separate from the car. The better practice is to use the car-wheel grinder at one of the depots, if the wheels are to be ground on the car. Where the wheels are taken out to be

ground, extra means must be provided for driving the axle; whereas, if ground on the car, one of the car motors can do the work. In either case, the car wheels should make from 20 to 40 revolutions per minute, and the speed of the rim of the emery wheels should be about 5,000 feet per minute. Steel-tired wheels are trued up by turning in a lathe.

SPEED CONTROL

METHODS OF SPEED CONTROL

GENERAL REMARKS

1. The subject of speed control for electric-railway cars deals with the methods of starting cars from rest and controlling their speed while in motion. Series motors are usually employed to drive the cars, and change of motor speed is obtained by varying the voltage impressed across the motor terminals. A low voltage is at first impressed on the terminals of each motor, and its armature need revolve only at low speed in order to generate sufficient counter electromotive force to limit the motor current to the value required for the load condition. A higher voltage is then impressed and the motor speed increases until the counter electromotive force is sufficient to limit the motor current to that required by the new load condition. Finally, full line voltage is impressed and the motor runs at maximum speed for the voltage and load conditions, provided the field-coil connections remain unchanged.

The three methods commonly used for varying the voltage impressed on the motors are: (1) the introduction of an adjustable rheostat, or resistor, in series with the motors; (2) changing the motors from series to parallel connection across the circuit combined with the use of an adjustable resistor; and (3) the connection successively of the motor terminals to the taps of an autotransformer. The first two methods are for direct-current and the last for alternating-current operation.

COPYRIGHTED BY INTERNATIONAL TEXTBOOK COMPANY. ALL RIGHTS RESERVED

RHEOSTATIC CONTROL

2. Simple Form of Controller.—The switch that is generally used to regulate the speed of an electric car is called a **controller**, and in most cases one of these devices is installed at each end of the car. A very simple form of rheostatic controller is shown in Fig. 1.



FIG. 1

An iron shaft *a* has projecting from it lugs *b*, on which are mounted copper segments *c*. The two lower segments are of the same length, but the others are of different lengths. The shaft is insulated from the handle *d* and the base *e* by insulating couplings *f*. The *brushes*, or *fingers*, which, when the shaft is turned, make contacts with the segments, are indicated at R_1, R_2, R_3, R_4, and *m*. The fingers marked *R* are connected to the three resistor sections. The trolley connection *T* is made at finger R_4, and the motor connection is made at finger *m*. The motor is grounded at *G*. The dotted lines *1*, *2*, *3*, and *4* indicate the relative positions of the fingers on the segments when the segments are turned into contact with the fingers on the first, second, third, and fourth *notches* of the controller.

The off-position is indicated in Fig. 1. The circuit is open between fingers R_1 and *c* and *m* and *c*. At notch *1*, fingers R_1

and *m* are in contact with their segments *c* and as all of the segments are connected together through their supporting lugs and the shaft, the motor circuit is closed and all of the resistor is active. At each notch a separate section of the resistor is short-circuited by the segments and shaft so that on notch *4* all of the resistor is short-circuited and this is a ***running*** notch. The resistor is not usually intended to be left in circuit; therefore, notches *1*, *2*, and *3* are not running notches.

3. Theory of Rheostatic Control.—When the whole resistor is active, a considerable part of the line voltage is expended in forcing current through the resistor and, therefore, the voltage impressed on the motor is low, resulting in a low speed. As the sections of the resistor are short-circuited, a larger part of the line voltage is impressed on the terminals of the motor and its speed increases accordingly. At the running notch, practically the full line voltage acts on the motor and its speed is maximum under given voltage and load conditions.

Speed control by rheostat alone is used for mine locomotives, hoists, cranes, etc., but not usually for railway cars.

SERIES-PARALLEL CYLINDER CONTROL

DISTRIBUTION OF VOLTAGE

4. Series-parallel control is common for direct-current railway work; it requires less resistance and is more economical than rheostatic control. Two or four motors are generally used with series connections for low speed and parallel connections for high speed, thus giving the name series-parallel control.

For example, with two motors, Fig. 2, in series across a 500-volt circuit, the pressure across each motor is only 250 volts and each will run at about half of its full speed without resistance in circuit. For higher speed, the connections are changed from series to parallel by means of the controller, thus impressing

on each motor 500 volts, as indicated in Fig. 3, and resulting in full speed. Some resistance is used in starting and in passing



FIG. 2



FIG. 3

from series to parallel connections, but no resistance is in circuit on the running notch of the series or parallel position.

SERIES-PARALLEL CONTROLLER

5. In Fig. 4 is shown a type of controller intended to control the speed of two motors by the series-parallel method. The main controller shaft *a* supports six castings. All of the castings are insulated from the shaft and from one another and all of the segments on each casting are electrically connected. The cylinder of the reverse switch *b* carries the segments used for reversing the direction of rotation of the motors. The row of fingers for the main controller segments are shown below *c* and the row for the reverse segments below *d*. The small coils shown below *e* are blow-out magnet coils. Their action is to assist in breaking the arcs that tend to form when the segments leave the fingers. The arc forms a movable current-carrying

conductor. The current in the blow-out coil establishes through iron extension plates and in the air near the fingers a magnetic flux. The arc conductor moves across the flux and the arc is blown out between partitions *f*, called *arc deflectors*, which in their running position partly enclose the fingers. The parti-



FIG. 4

tions of insulating material prevent the hot gases of the arc from forming short circuits across adjacent connections. Cut-out switches *g* and *h* serve to cut out of circuit either motor in case of a fault in one motor.

The main controller shaft should take up a definite position corresponding to each notch; therefore, a device is provided,

usually in the form of a notched wheel, called the *star wheel*, mounted near the top of the shaft. The star wheel turns with the shaft, and a small roller is drawn by a spring into the notches, making the movements positive and definite.

An interlocking device prevents the reverse-switch shaft from being turned unless the main shaft is at off-position. This prevents reversing the motion of the car when current is in the motors. The reverse-switch handle *i* cannot be removed except at the off-position of the reverse switch, at which position the motor circuit is open.

When the reverse-switch handle points ahead, the car runs forwards, and when it points back, the car runs backwards.

CAR-WIRING DIAGRAM

6. Explanation of Marks on Diagram.—Fig. 5 shows the connections of two controllers and two motors for series-parallel operation. The fingers are indicated by the small black circles and their blow-out coils by the zigzag lines to the left of these circles; the segments, by the black rectangles; the controller castings, each of which supports a group of connected segments, by the outline rectangles *1*, *2*, *3*, *4*, *5*, and *6*; and the positions of the fingers for the controller notches, by the vertical dotted lines. These motors are provided with commutating poles, the windings of which are not indicated in Fig. 5, and have taps *M1* and *M2* that when active cut out portions of the main field windings, thus increasing the speed of the motors. The cut-out switches are shown at the right of the upper portion of the controller and the reverse switch just below.

There are many hundreds of wiring diagrams showing methods for the speed control of railway cars. It is the purpose here, however, to treat only of the general principles of the different methods of speed control and to familiarize the student with the usual manner of representing motor and controller connections so that any ordinary wiring diagram may be read.

7. Controller Steps.—Fig. 6 shows in detail the method of tracing the circuits of a car-wiring diagram. The blow-out


Trolley
Fuse Box
Circuit Breaker
Combined Switch a
Kicking Coil
Lightning Arrester
G
To
Controller No.1
Running Points
1 2 3 4 5 5' 6 7 8 9
R2
T
R1
R3
R2
e
R4
+2
0
-11
G
C2
M2
FF2
C1
M1
FF1
1
2
3
4
5
6
Cut-Out Switches
A2
+2
G
A1
R4
-1
-11
Forward Reverse
F1
AA1
C1
-1
F2
AA2
C2
G
Ground Connection
To F1
To C1
No.1 Motor
A1
Arm
AA1
M1
F1
R1
R2
Resis


Cut-Out
and Heaters G
Controller No. 2
Running Points
1 2 3 4 5 5' 6 7 8 9
R2
T
R1
R3
R2
a'
R4
+2
-11
G
C2
M2
FF2
C1
M1
FF1
1
2
3
5
6
Cut-Out Switches
A2
A1
-1
+2
G
R4
-11
Forward
Reverse
F1
AA1
C1
-1
F2
AA2
C2
G
Ground Connection
To C2
To F2
No.2 Motor
A2
Arm
AA2
F2
M2
FF2
Field Coils
R3
R4
Schematic Diagram
First Step Series
T
G
First Step Parallel
T
G
Transition
T
G
G
Full Parallel, Fields Tapped
T
G


Step 1 (Forward)
Step 2
Step 3
Step 4 (Running)
Step 5 (Running)
Transition Point 5'
Step 6
No.2 Cont.
No.2 Cut-Out
No.1 Cut-Out
Forward
Cut-Out
Ground Connection
T
R1
R2
R3
R4
A1
A2
AA1
AA2
F1
F2
FF1
FF2
C1
C2
M1
M2
G


Step 7
Step 8 (Running)
Step 9 (Running)
No. 1 Controller Step 1 (Reverse)
No. 2 Controller Step 1 (Forward)
Ground Connection
Forward
Reverse
No. 2 Cont.
No. 1 Cut-Out
No. 2 Cut-Out
Cut-Out

FIG. 6

coils, fingers, segments, resistor, field coils and armatures are represented the same as in Fig. 5, but Fig. 6 shows the connections of these parts on the successive steps of the controller. *The student should trace each path on Fig. 5 as it is shown on Fig. 6.* This is important in order to gain facility in tracing wiring diagrams.

Any diagram can be traced in this manner and a simple schematic diagram made to show connections on each step.

For example, with the circuit-breaker of No. *1* controller, Fig. 5, closed, the reverse switch in forward position, the cut-out switches closed to the left and the drum of controller No. *1* turned until the fingers rest on the *first series step 1*, the current path is as shown in step *1*, Fig. 6. Fingers *T* and *R1* rest on segments of casting *1*; fingers *+2* and *c* on segments of casting *3*; fingers *C2* and *FF2* on segments of casting *5*; and fingers *C1* and *FF1* on segments of casting *6*. The armatures and field coils of both motors and all the sections of the resistor are in series, as shown in the schematic diagram, Fig. 5, and the *first step*, Fig. 6.

On the *second series step*, an inspection of the development of the controller segments shows that the only change in the segments caused by the movement from step *1* to step *2* is such that finger *R1* is now inactive and upper finger *R2* is active. One resistor section is cut out, since the current can pass from finger *T* through finger *R2* to *R2* on the resistor.

On the *third series step*, the change in segments is such as to make finger *R2* inactive and finger *R3* active. Finger *T* is now connected through finger *R3* to *R3* on the resistor and there is only one section of the resistor in circuit.

On the *fourth series step*, which is the first series running point, upper and lower fingers *R2*, and finger *e* of the first part of the circuit are active. Finger *T* is now connected through fingers *R2*, *R2*, and *e* to *a* on the No. *2* controller and all of the resistor is cut out.

On the *fifth series step*, which is the second series running point, the change in segments is such as to cut out portions *M1–FF1* and *FF2–M2* of the motor field windings. Fingers *M1* and *M2* and taps *M1* and *M2* are now active. The speed on the fifth step is higher than on the fourth step because the

weakened magnetic flux of the motors necessitates a higher speed, in order to generate the proper counter electromotive force for the load conditions.

On the *transition point 5'*, Figs. 5 and 6, a section of the resistor is cut into circuit and for an instant both ends of the No. *2* motor circuit are grounded, thus temporarily short-circuiting this motor.

On approaching the *sixth step*, which is the *first parallel resistance step*, fingers *+2* and *c* drop their contacts with casting *3* and the No. *2* motor circuit is opened. When the sixth step is completed, fingers *R4* and *+2* make contacts with casting *3*, and the armature end of No. *2* motor circuit is connected to point *R4* at the end of the last section of the resistor. The two motors are in parallel and one section of the resistor is connected ahead of the junction of the motors.

On the *seventh step*, which is the *second parallel resistance step*, the three sections of the resistor are in parallel ahead of the motors which are also in parallel.

On the *eighth step*, which is the *first parallel running point*, fingers *T*, *R2*, *R2*, and *e* are active and all of the resistor is cut out.

On the *ninth step*, which is the second parallel running point, fingers *M1* and *M2* and taps *M1* and *M2* are active and the motors are in parallel without the resistor and with portions of the field windings cut out. This is the high-speed point.

8. Motor Connections.—When two motors are placed on a single truck, it is customary to install them back to back, with the commutator ends of the two motors toward opposite sides of the truck. When the motors are so placed, the rotation of the two armatures must be in opposite directions, when viewed from the commutator end of each motor, in order for the motors to act in unison in driving the car. The controller connections must be so made that the current in the field coil of one motor must be in the opposite direction to that of the current in the field coil of the other motor, provided the armature currents have the same relative directions. In Fig. 6, first step, the current enters the *A1* end of the No. *1* armature and the

corresponding *A2* end of the No. *2* armature, but the current enters the *F1* end of the No. *1* field coil and the *FF2* end of the No. *2* field coil. The rotation of the No. *2* motor is, therefore, opposite to that of the No. *1* motor.

9. Action of Reverse Switch.—If the reverse switch, Fig. 5, is thrown so that the reverse segments are in contact with the fingers, the direction of the current through the field coils of both motors is opposite to that when the forward segments are active and, therefore, the motion of the car is reversed. In the next to the last tracing of Fig. 6, the path of the current is indicated for the first reverse series steps. The relation between the directions of the armature and field currents is maintained throughout the reverse steps on the No. *1* controller. The directions of the field currents should be noted in Fig. 6 for the tracing for the first forward series step and for the first reverse series step of the No. *1* controller.

10. Braking by Reversing.—The car may be stopped suddenly by throwing the main controller handle to off-position, throwing the reverse handle to its reverse position, and then advancing the main controller handle. The motors will then tend to drive the car in the direction opposite to the direction that the momentum of the car is driving it; the car will come to a sudden halt and move backwards if the current is left on. This action causes very severe stresses on the apparatus, and should be resorted to only in case of an emergency.

11. No. 2 Controller Connections.—The No. *2* controller, Fig. 5, is similar to the No. *1* controller except that the short connecting wire, or jumper, near *x* is used on the No. *2*, but not on the No. *1*, and the field-coil connections of each motor are reversed because forward movement when referring to one end of the car is the opposite to the forward movement when referring to the other end of the car. It is necessary, therefore, that for reverse on No. *1*, the motors should rotate in the same direction as for forward on the No. *2* controller. The last tracing in Fig. 6 indicates the path and direction of the current for the first forward series step of the No. *2* controller. It should be noted that the direction of the current

in the field coils of both motors is the same for the first reverse series step of the No. *1* controller (next to the last tracing) as for the first forward series step of the No. *2* controller (last tracing), thus the car motion that is backwards for the No. *1* is forwards for the No. *2* controller.

12. Action of Cut-Out Switches.—Cut-out switches serve to disconnect a faulty motor in a two-motor equipment or a pair of motors in a four-motor equipment in case one motor of a pair is faulty. The two motors of a pair are connected together in parallel and may be considered as one motor in regard to general connections. Suppose that No. *2* motor, Fig. 5, develops a fault and the blade of the upper cut-out switch on the No. *1* controller is thrown to the right, point $+2$ on the cut-out switch, Fig. 5, and the first tracing, Fig. 6, is grounded at *G*, and there is an open circuit between points $+2$ and *A2*. The No. *1* motor and three sections of the resistor are connected between the trolley and the ground connection of the upper cut-out switch and the circuit of the No. *2* motor is opened at that point, as indicated by the dotted connecting lines under point $+2$, first tracing Fig. 6.

If the No. *1* motor is faulty, the two blades of the lower cut-out switch are thrown to the right and the blades connected together by the double clip at terminal *R4*, Fig. 5. Point *x* is now connected to point -11 and the No. *1* motor circuit is opened between points *x* and *A1* and -1 and -11. The No. *2* motor circuit is completed through *x–11–b–c*, etc., Fig. 5. The path is indicated by the dotted connection near *x* on the first tracing of Fig. 6.

MOTORS USED AS BRAKES

13. Forward Movement of Car.—Under certain conditions, the motors of a car may be used to brake the car independently of the mechanical brakes and of the connection of the car to the trolley line. The ability of the motors to act as generators enables them to perform this duty.

The case first considered is when a car equipped with two motors is running forwards down a hill, with the brakes out of

order and the trolley off the line. If the reverse switch is thrown to reverse position and the controller to any one of the parallel steps, preferably the first resistance parallel step, one of the motors will almost immediately pick up as a generator and the current from this generator will pass through the other motor, tending to drive that motor in opposition to the motion of the car. The machine acting as a generator requires energy to drive it and this is furnished by the moving car. The combined action of both machines is, therefore, to retard the speed of the car. As the speed slackens, the retarding effect decreases so that the car cannot be brought to a stop on a down grade by this method. The speed is greatly reduced, however, and it may be possible to stop the car by placing an obstruction on the rail.

14. In order for either one of the series motors to pick up as a generator, its circuit must be complete and the relative direction of rotation and of flux must be suitable. Throwing the reverse switch to reverse position gives the proper relation between rotation and flux, and moving the controller handle to a parallel position completes the circuit by grounding one terminal of each motor and interconnecting the other two terminals, as indicated by step *6*, Fig. 6. The relation between armature and field-coil connection would be, however, that indicated in step *1* (reverse), Fig. 6.

Both motors tend to start generating and to set up electromotive forces that directly oppose each other; but one machine starts to pick up a little before the other, owing to the fact that the residual magnetism of one machine is usually a little stronger than that of the other, as explained in connection with series generators in parallel in a previous Section. The stronger electromotive force overcomes the weaker electromotive force, and the first machine picks up as a generator and forces current through the other machine, which acts as a motor.

15. Backward Movement of Car.—In case the car starts to run backwards down a hill and the motors are to be used as brakes, the overhead switch should be knocked off,

the reverse switch left on its forward position, and the controller drum turned to a parallel position. As the car is running backwards, the rotation of the armatures is reversed, so that the armatures and field coils are properly connected to make the motors generate and set up braking action.

16. Braking Action With Four-Motor Equipment. When there are four motors on the cars arranged in two pairs, the braking action will occur if, when the car is moving forwards, the reverse switch is thrown to reverse position and the controller left at the off-position. For backward movement, the braking action occurs when the reverse switch is thrown to forward position and the controller left at the off-position.

17. Precautions.—It is well to know how to use the motors as brakes in case a brake chain should snap and the line lose its power, thereby rendering both the brakes and reversing gear ineffective. It is not well, however, to make a practice of stopping a car in this way, for as the fuse or breaker is outside of the local circuit, consisting of the two motors and the reversing mechanism, the motors are not protected from overload. Again, the sudden reversing of the armature of the machine, acting as a motor, strains the pinion just as does regularly reversing, or "plugging," the car under headway.

SERIES-PARALLEL MULTIPLE-UNIT HAND CONTROL

MASTER CONTROLLER AND MOTOR CONTROLLER

18. When a car is intended to be used as a part of a train, some form of multiple-unit system is employed to control the speed of the train. In the multiple-unit system, a *master controller* distributes current through control circuits that include the operating coils of switches. The switches are in the main circuits of the car motors and resistor and act in response to movements of the master controller. The currents required for the control circuits of the operating coils are small and the master controller, therefore, is very compact. Its operation

and general appearance is, however, similar to that of the larger type previously described.

By extending the control circuits from car to car by means



FIG. 7

of cables and jumpers, each car is operated as a unit in parallel with the other cars from any master controller, usually the

controller on the front end of the first car of the train. The system is sometimes used on a car intended for heavy service and for single operation. The heavy wiring required for the motor circuits need not be brought to the master controller and much space on the platforms is gained by the use of the small master controller. The motor controller contains a group of main-circuit switches and is placed under the car. The operating coils of the motor controller are connected by the control cables to the master controller.



FIG. 8

Fig. 7 shows a *motor controller*, or a *contactor box*. The switches, or contactors, are at positions *a*; the motor cut-out switches, at *b*; the motor reverse switches, at *c*; the cut-out switches for the control circuits, at *d*; and an overload relay, at *e*.

CONTACTORS

19. The *contactors* vary in details of construction to suit different operating conditions, but their action is usually based on the same general principles. Fig. 8 shows the working parts of a contactor intended for 2,400-volt service. In contactors for lower voltage, the parts are arranged more compactly. When current passes through the operating coil *a*, the switch

contacts *b* and *c* are closed by means of a connecting-rod extending to the armature *d* of the coil. When the current in the coil ceases, the switch contacts open and any arc that tends to form between them or their projecting horns is blown out by the blow-out coil *e*.

The movement of the armature *d* also causes the shaft of the interlock switch *f* to move. Small disks mounted on the shaft move into or out of contact with stationary terminal posts. The contacts *b* and *c* form a part of the main motor circuit and the contacts of the interlocks form part of the control circuits. The interlocks serve to arrange circuits for the operating coils of the contactors.

In car-wiring diagrams, the operating coil *a*, the contact points *b* and *c*, the blow-out coil *e*, and the interlock *f* are usually represented as indicated in the detail sketch.

CUT-OUT SWITCHES AND REVERSER

20. Fig. 9 shows the motor cut-out switches *a* and *b* and the reverser *c*. In a four-motor equipment, switch *a* cuts out



FIG. 9

one pair of motors and switch *b*, the other pair. The reverse switch is provided with two operating coils, both of which are

included in the control circuits. One coil turns the reverse-switch cylinder to forward position and the other coil, to reverse position. The reverse switch reverses the connections of the field coils of the motors.

OVERLOAD RELAY

21. Fig. 10 shows one form of overload relay. The coil *a* is in the motor circuit. In case of excessive current, armature *b* is drawn up, moving latch lever *c* and releasing the armature *d* of the coil *e*. The action of armature *d* opens through levers *f* the contacts of three small switches of the control circuits. The blow-out coils of these switches are shown at *g*. The circuits of the switches include operating coils of active contactors and when the switches open, the motor circuits are opened by the contactors. The current in coil *a* then ceases and the armature *b* drops. The control switches may be closed again by passing current from the control circuit through the reset coil *e*. The armature *d* is then moved toward coil *e* and its action closes the switches.



FIG. 10

CONTROL AND RESET SWITCH

22. Near the master controller is a small double-throw switch, one type of which is shown in Fig. 11. The switch in one position closes the supply circuit for the master controller, and in the other position closes the circuit to the reset coil of

the overload relay in the motor controller. In the reset position, only temporary contact is desired and the handle is held against a spring pressure that will return it to off-position



FIG. 11

when the hand is removed. The notches on the segment near the center of the switch allow the switch to remain at off-position or at closed position on the left contact.

CAR-WIRING DIAGRAM

23. In Fig. 12 is shown a car-wiring diagram for a multiple-unit system with hand-operated control (the Sprague-General Electric type M K). The diagram shows connections for a large car that is usually operated singly, but which, if desired, may form part of a train. At starting, the acceleration of the car depends on the time taken by the operator to move the controller handle through the different steps.

The wires for the control circuit are indicated by light lines and for the motor circuit by heavy lines. The small open circles located in the control circuits indicate resistors and the numbers near the circles indicate the resistances in ohms. One end of the control circuit is connected to the upper contact

of the main switch and the other end to the ground. The full voltage of the line is impressed on the control circuit, but the resistors and the operating coils limit the current to a small amount (about 2 amperes per car). One hood switch controls the current for both master controllers and a controller and reset switch at each end of the car control the current for the master controller at that end and for the reset coil of the overload relay.

To start the car, the main control switch is closed and the control and reset switch for the master controller that is to be active is first thrown so as to make contact at the reset side, which energizes wire *10* and the reset coil of the relay, and is then finally closed to the controller side. The master controller reverse switch is thrown to forward position and the master controller is then moved through the steps.

24. Control Circuits.—In Fig. 13 are indicated the paths of the control currents through the circuits formed when the controller is moved through the steps. The devices, such as controller fingers, operating coils, interlocks, resistors, etc., in Figs. 12 and 13, are indicated in a similar manner. Each path, indicated in Fig. 13, should be traced on Fig. 12.

On the first step, Fig. 13, the control current passes through No. *1* casting of the controller, the forward segment of the controller reverse switch, the forward operating coil *0* of the reverser, the two lower interlocks attached to coil *0* and to ground. The operating coil immediately causes the two lower interlocks to open, the upper interlock to close, and the path is then indicated by the lower connections from the forward operating coil of the reverser. Contactors *7* and *9* of this path are closed. Another path is through wire *1*, contactor *1*, and wire *6*. Contactors *1*, *7*, and *9* are active.

When tracing the steps, the positions of the interlocks of the active contactors should be noted. In Fig. 12, the positions of the interlocks when the contactors are inactive are indicated. In Fig. 13, the interlocks are numbered the same as the contactors to which they are attached, as interlock *10* of the first step.


Reverse
Forward
Control Switch
Controller and Reset Switch
Fuse
Lightning Arrester
Kicking Coil
Main Switch
Coupler Socket
Cut-Out Switch
Overload
Resetting
Relay
R1
R2
R3
R4


Motor Circuit Connections
R1
R2
R3
R4
R5


Wire Colors
No. 1 = Red
" 2 = Green & White
" 3 = Red & White
" 4 = Green
" 5 = Black & White
" 6 = Red & Green
" 7 = Blue
" 8 = White
" 0 = Black
" 10 = Red & Blue
ble No. 8 connects to No. 0 and No. 0 to No. 8 at cut-out switch in contactor box
Controller and Reset Switch
G
Coupler Socket
Reversers
50 Ohm
No. 1 Cuts out No. 1 and No. 3 Motors
" 2 " " " 2 " " 4 "
Reversers
Field Coils
Contactors closed on each step
Steps
Contactors
1 st.
2 Nd.
3 Rd.
4 Th.
5 Th.
6 Th.
7 Th.
8 Th.
9 Th.

Fig. 12


Step 1.
Contactors
1-7-9
Step 2.
Contactors
4-7-9
Step 3.
Contactors
2-4-7-9
Step 4
Contactors
2-4-5-7-9
Step 5.
Contactors
4-5-6-7-9
Forward
Relay
Rel.
For.
G


Transition Point and Step 6. Contactors 3-4-7-8-10
Step 7. Contactors 2-3-4-7-8-10
Step 8. Contactors 2-3-4-5-7-8-10
Step 9. Contactors 1-2-3-4-5-6-7-8-10
Forward
Relay
Rel.

FIG. 13

On the transition point and step *6*, the changes in the active controller segments and active interlocks cause the changes in the current paths noted in the figure. The portion of the paths connected by dotted lines indicates the preliminary paths. The full-line paths are for step *6*.

In all of the control circuits, except the preliminary circuit for the reverser, either of the two control switches used in the overload relay of this system is included in the circuit; therefore, in case of excessive current, these switches open, which causes the contactors to open the motor circuits.

25. Motor Circuits.—The sketch, Fig. 12, showing the motor circuit connections and the table showing the contactors closed on each step serve to indicate the motor connections at each step. On the first step, with contactors *1*, *7*, and *9* active, the main current passes through four sections of the resistor and two pair of motors in series. Each pair of motors consists of two motors in parallel. On the sixth step, with contactors *3*, *4*, *7*, *8*, and *10* active, the current passes through one section of the resistor *R2–R3*, and then through the four motors in parallel. The resistor sections are used either in series or in parallel or in combination on the different steps.

26. Reverser.—When all of the fingers of the reverser, Fig. 12, bear on the large segments, as shown, current in the field coils has one direction; when the reverser drum is turned so that only the upper row of fingers is on the large segments and the lower row on the small segments, current in the field coils is in the other direction. The direction of car movement is thus changed by turning the reverser drum.

When the forward segment of the controller reverse switch at either master controller is active, the operating coil of the reverser that is then energized moves the reverser to the position for forward motion of the car. When the reverse segment is active, the reverser is moved to the position for backward motion.

27. Couplers.—Cars to be used in multiple-unit trains are provided with sockets mounted near each platform and which are connected to the wires of the control cable on the car.

Two coupler sockets are shown in Fig. 12. A jumper cable with plugs at either end serves to connect the sockets of adjacent cars. The control system is thus extended throughout the train and any master controller will control all of the motors on the train. If the motors on one car are not to be used the control cut-out switch, shown below the left-hand master controller, Fig. 12, is thrown so as to open all of the control circuits.

SERIES-PARALLEL MULTIPLE-UNIT AUTOMATIC CONTROL

AUTOMATIC CLOSING OF SWITCHES

28. In automatic control, the controller handle may be moved slowly from step to step or the handle may be thrown at once to either full series or parallel running position and the switches in the motor circuit will close automatically and in the same order as for the gradual movement. A limit switch, the operating coil of which is included in the motor circuit, opens by means of its interlock certain of the control circuits in case the motor current exceeds the value for which the switch is set and delays the closing of further switches until the current decreases to a safe value.

UNIT SWITCHES

29. The motor switches in the Westinghouse system of multiple-unit control here considered are closed by compressed air taken from the air-brake system of the train. The magnet valves operating the switches are controlled by the currents in the control circuits and the proper distribution of these currents is made by the master controller.

Fig. 14 shows a unit switch. The magnet valve is shown at *a*; the air cylinder at *b* with part of the casing broken away to show the coiled spring inside; and the main switch contacts and their projecting horns at *c* and *d*. A blow-out coil is so placed in front of the arc shield *e* that its magnetic flux passes through

the space occupied by the contacts *c* and *d*. If the unit switch is provided with an interlock, the segments of the interlock are mounted on the projecting arm *f* of the piston rod. The interlock fingers are fixed in position and the segments move up and down against the fingers, thus making or breaking the control circuits necessary to cause the progressive action of the unit switches. The general arrangement of the interlock fingers and segments is shown in Fig. 15.

When the magnet valve *a*, Fig. 14, is energized, the small air valve *g* is depressed, allowing air from the inlet *h* to pass to the bottom of the piston in the cylinder *b*. The piston and its rod are forced upwards, closing the switch and moving the segments of the interlock. The switch remains closed as long as the air pressure exists on the piston. If the circuit of the magnet valve is opened, the inlet valve *g* closes and an exhaust valve under the magnet opens, allowing the air under the piston to escape. The spring in the air cylinder then opens the switch, which also happens when the air pressure in the system fails from any cause.



FIG. 14

The unit switches are arranged in a switch group, placed under the car, and connected to the control circuit, the motor circuit, and the air-brake system. Fig. 15 shows the interlock side of a switch group with the cover removed from the case. Control cables are shown passing through one end of the case, and bushed openings for the entrance of the motor leads are shown near the top.



FIG. 15

OVERLOAD TRIP

30. Fig. 16 (*a*) shows the construction of the overload trip at one end of the switch group. The trip coil *a* is the blow-out coil of the adjacent unit switch. In case of overload, the plunger *b* is drawn into the trip coil, thus opening two control circuits by withdrawing contact disks *c* and *d* from stationary contacts *e f* and *g h*. At the same time a spring *i* is compressed and the end of the plunger of a reset magnet falls into a notch *k*, thus holding the control circuits open, as in (*b*). By closing a reset switch near the operator, the reset magnet *j* is energized, the plunger withdrawn from notch *k*, and the spring *i* closes the control circuits again, if the overload has been removed. The tripping point is adjustable by screwing in or out the small rod attached to plunger *b*. This rod turns within the shell that holds the disks.



FIG. 16

CAR-WIRING DIAGRAM

31. Fig. 17 is a simplified, schematic, car-wiring diagram of the Westinghouse unit-switch automatic control. In this diagram, the parts are arranged where most convenient to show connections, regardless of their true arrangement. The master controller, the main contacts of the unit switches, and the motor circuits are shown above the train-line cable and the control circuits and the magnet valves of the unit switches below this cable. The operating coil of the limit switch is shown to the right of motors Nos. *2* and *4*, and its interlock is indicated near the disk marked *Limit*, in the control circuit.

The combined blow-out and trip coil of line switch *LS1* is shown below the main fuse. The control disks of the trip interlocks of the two line switches *LS1* and *LS2* are marked *Overload Trip* and are in circuit with the magnet valves of these switches as shown in Fig. 17. The reset coil of the overload trip is in circuit with control wire *8*, as shown at the right side of the diagram.

The segments and the fingers of the interlocks are indicated by the blocks and by the small circles. When the switches are *out*, the segments make contact with the fingers on a line even with the word *out*; and when *in*, on a line even with the word *in*. The main contacts of the unit switches are indicated in the motor circuit by short vertical parallel lines.

The voltage impressed on the magnet valves of the control circuits is that between points *6* and *7* or *7* and *G* on the control resistor connected between the trolley and the ground. In some equipments, the current for the control circuits is obtained from a storage battery.

32. With connections complete and the car ready to start, the controller handle can be thrown at once to notch *4*, Fig. 17, for forward movement of the car or to notch *2*, for backward movement. In the following, it is assumed that the handle is moved to the forward parallel-running notch *4*.

When tracing the circuits, the table of sequence of switches, shown near the right-hand upper corner of Fig. 17, should be


Trolley
Master Controller
Forward
Reverse
Control Switch
Main Switch
Blow-Out Coil
Main fuse
B.O.
B.O. & Trip
Reverser
Limit Coil
J.R.
Cut-out Switches a, b and c are connected to No. 1 Handle and d, e and f to No. 2 Handle
Sequence of Switches
Ser.
Tran.
Par.
Receptacle
Train-line Cable
Reverser Interlocks
Overload Trip
Limit
Control Resistance
Reset Coil
J in
JR in
G in
M1 in
J out
LS1 in
out in
M1 out
LS1
LS2
G
M2
M1
J

FIG. 17

frequently consulted and the position of the interlocks of the switches noted for each new path. The movements of the interlocks prepare the control circuit for the closing or opening of the switches next to be affected, and for the transfer of some of the magnet valves from a pick-up circuit including the interlock of the limit switch to a retaining circuit that does not include it. The limit switch thus drops its control of the switches that have been closed and only applies its guarding features to switches about to close.

33. Fig. 18 indicates the control circuits that carry currents for energizing the different magnet valves, the positions of the interlocks (in or out) that are active in each circuit, the sequence of opening and closing of the switches, the methods of transferring some of the magnet valves from the pick-up to the retaining circuit, and which of the magnet valves are affected by the overload trip and by the interlock of the limit switch. Figs. 17 and 18 should be studied together when tracing circuits.

The first current tracing shows the circuit of the reset coil when the control switch is closed temporarily to the right. The next tracing shows the circuit when the control switch is closed to the left and the master controller is active. Current passes through the resistor and the wires *6* and *7* are energized.

The magnet valve of switch *LS1* is energized through the wire *7*, fingers *7* and *F* on the controller, and wire *F*. This switch and switch *M1* close at once, followed immediately by the closing of switch *JR*.

The interlock of the forward magnet valve of the reverser is in forward position; therefore, the magnet *F* is not in circuit since the reverser is in proper position for forward movement of the car.

If the reverser is in the wrong position when the master controller handle is moved either way, one of its magnets *R* or *F* is automatically energized and the reverser is moved to the position corresponding to the movement of the master controller.

The operating coil of switch *LS2* is in series with an overload trip contact and the interlock of the limit switch and


Control Sw.
Trolley
Reset Coil
G
R-O. Coil
Exciting Circuit
1. 2. LS1 Closes
3. M1 Closes
Simultaneous
4. JE Closes Subsequent to LS1
5. LS2 Closes
6. R1 Closes
7. RR1 Closes
8. R2 Closes
9. Series
R2 Closes
10. R3 Closes
11. RR3 Closes
Limit
Upper
O.T.
For
Out
In

FIG.


3. Transition
12. J Closes and Opens its Interlock, Causing JR and Six Resistor Switches to Open
13. G and M2 Close. The Opening of G Interlock at 38 Causes J to Open
4. Parallel
14. R1 Closes
15. RR1 Closes
16. R2 Closes
17. RR2 Closes
18. R3 Clo s
19. RR3 Closes
Limit
Limit J
RR3 In
G Out
J
J In
M1 In
LS2 In
M2 Out
JR Out
LS1 In
M2 In
R1 Out
R1 In
M2 In
LS2 In
M1 In
G In
RR1 Out
RR1 In
R2 Out
R2 In
RR2 Out
RR2 In
R3 Out
R3 In
LS1 I

cannot close until the motor current falls enough to allow the limit switch to close. As soon as switch *LS2* closes, its own interlock transfers its magnet valve to another circuit containing the same overload trip contact, the other overload trip contact being in series with the coil of switch *LS1*. These two switches, therefore, open in case of overload, followed immediately by the opening of all the other switches because of the opening of the *LS1* interlock in the circuit of wires *6* and *7*. The reset switch enables the motorman to start operations again. In Fig. 18, temporary connections are represented by dotted lines, as in the first circuit of magnet *LS2*.

It is well to consider the motor circuit, Fig. 17, for the various steps. Note from the table of sequence of switches the switches that are active and consider that the small gaps by which the switches are indicated are closed. Then trace the motor circuit. For instance, on the second step of the progression with switches *LS1*, *LS2*, *M1*, and *JR* closed, the two pair of motors and six sections of resistors are connected in series. Each pair of motors consists of two motors in parallel.

On steps *3* to *8*, Fig. 17, sections of the main resistor are cut out of circuit. Fig. 18 shows the control circuits that first pick up these resistor magnets in circuit with the limit switch interlock and then transfer each in turn to a retaining circuit that is not controlled by the limit switch. In case the limit interlock opens, due to an unsafe current, it does not affect the switches that have been closed, but delays further closing of new switches until the current has been reduced to a safe value by the increased speed of the motors.

Switch *J*, Figs. 17 and 18, closes on the transition positions and its interlock opens, causing the switches controlled by the circuit containing wire *6* to open. As soon as switch *G* closes, its interlock opens the circuit of wire *38*, and switch *J* opens.

On step *9*, Fig. 17, the two pair of motors are in parallel and each pair has three sections of the resistor in series with it. On the succeeding steps, the resistor sections are cut out. Switch *JR* remains inactive on the parallel steps since the interlock of switch *M2* is in its *in* position.

On step *12*, the motors are in parallel with the resistor cut out.

If the controller handle is advanced to the second notch, the switches will close automatically until the motors are in series-running position. The active switches are then indicated by step *8* of the sequence of switches.

On reverse operation, the pair of motors are in series on notch *2* of the controller. The finger *R* is then active and the reverse will be thrown to its proper position for backward motion of the car.

SINGLE-PHASE SPEED CONTROL

GENERAL ARRANGEMENT OF PARTS

34. In the United States, the development of alternating-current traction has been based mostly on the single-phase system employing a series-wound commutating motor. A single-phase system of the Westinghouse type is here considered.

The car speed is controlled by connecting successively the several taps of an autotransformer or of the secondary coil of a two-coil transformer to the terminals of the motors. The autotransformer or the primary coil of the two-coil transformer is connected between the trolley and the rails. By this means the voltage impressed on the motors is varied and the car speed adjusted. In some equipments, a resistor is also used to aid in controlling the car speed.

The voltage between the trolley and rail may be, for different installations, from a few thousand to 11,000 volts; the maximum voltage impressed on the terminals of each motor is, however, only about 275 volts. When two motors are employed, they are usually connected in parallel. With four-motor equipments, the two motors of a group are usually connected in series and the two groups in parallel.

With a two-coil transformer, the motor circuit is insulated from the ground and the motors and auxiliary apparatus are not connected to the high-tension line.

The control-circuit and motor-circuit combinations are made by means of a master controller and unit switches in the same

general manner as previously described. A storage battery is used to furnish current for the control circuit and the magnet valves are, therefore, designed for direct-current operation. A small motor-generator set is provided so that the storage battery can be charged as required.

PREVENTIVE-REACTANCE COILS

35. In an equipment where no resistor sections are used to control the speed, the motor circuit is connected to the transformer taps through reactors, called **preventive-reactance coils.** This method as applied to a two-coil transformer is indicated in Fig. 19. One end of the motor circuit is connected to the center of one coil, each end of which is joined to the center of other coils, and the four ends of these two coils to the transformer taps. As the unit switches close, the terminals of the two coils nearest the transformer are connected successively to the higher voltage taps, as indicated by the dotted connection of the lower coil. The coils prevent sections of the transformer from being short-circuited and the motor circuit from being opened during the progression of the switches. The voltage impressed on the motors is thus increased in steps.



FIG. 19

CAR-WIRING DIAGRAM

36. Preliminary Control Circuits.—Fig. 20 is a schematic diagram of an automatic, alternating-current, car equipment of the Westinghouse type. Fig. 21 shows the control circuits from the positive to the negative battery terminals. Reference should be made to both figures.

Two pantagraph trolleys are used, which are raised or lowered through the action of small switches at the master controller. The battery switch, Fig. 20, is closed, a plug placed in the lower receptacle $B+$ shown below the master controller, and the push button marked "Trolley Up" on the left side of the controller is pressed. The control circuit is indicated in Fig. 21. The up-trolley magnet valves are energized, the trolley latches released, and springs raise the trolleys.

The trolleys are lowered by pressing the push button marked "Trolley Down" on the right side of the controller, Fig. 20. The control path is as indicated in Fig. 21. The trolley down magnet valves are energized and these allow compressed air to operate pistons that lower the trolleys. Automatic latches secure them in this position.

The line switch LS, indicated in the diagram of motor circuits, Fig. 20, is closed when the plug is inserted in the lower receptacle. The path, Fig. 21, includes the upper interlock of the overload trip. If the upper trip interlock opens, due to overload, the line switch LS opens. The upper trip interlock remains open and prevents reclosing the line switch until the interlock is reset by inserting the plug in the upper, or reset, receptacle. The reset coil is then energized and the interlocks forced to their normal operating position, as shown in Fig.20. The line switch is then closed by placing the plug in the lower receptacle. With this arrangement of trip interlocks, only the reset coil on the car on which the overload trip has operated will be energized. The circuits of the reset coils of the other cars are open, due to the normal position of the lower interlocks.

In the equipment under consideration, the brake is automatically applied if the controller is moved to off-position and the plug left in the lower receptacle. The brake-valve magnet


Forward
Reverse
Forward
Reverse
AB BK
BB+
Trolley Up
Trolley Down
BK
Signal Switch
Conductors Signal Valve
LS
Trolley
C.O.
C.O.
Limit Switches
Gr.
Main Schematic of Motor Circuits
Brake Valve
Overload Trip
Cir.Bkr. LS
Trolley Down
Trolley Down
Reset
No.7 out
No.5 out
No.2 out
No.7 in
Trolley up
Over-Speed Relay
Battery
Line Relay
M.G.
Mot-Gen.
20 ohms ea
No.6
No.5
No.4
No.3
No.2
No.1
Out in
Limit Switches
Control Cut-out
Sequence Table

FIG. 20

is energized and this admits compressed air to a relay valve which opens an exhaust port in the brake pipe, thus applying the brakes. If it is not desired to set the brakes when the controller is moved to off-position, the plug is removed from the lower receptacle. The path of the current through the brake-valve magnet is indicated in Fig. 21.

The circuits thus far mentioned in connection with Fig. 21 are completed with the master controller in off-position. They may be called *auxiliary circuits*.

37. Progression of Switches and Operation of Safety Devices.—When considering the control circuits made by the drum of the master controller, it is assumed that the controller is thrown at once to the third forward notch. The progression of switches is then as indicated in Fig. 21. The plug is in the lower receptacle and the reverser is in its forward position. The current paths, Fig. 21, the sequence table, and the motor circuit diagram, Fig. 20, should be carefully studied when tracing the control circuits.

Switches *1* and *7* close at once, since fingers *A B*, *1* and *3* are active as soon as the controller segments touch them. The interlock of the limit switch is at first included in the pick-up circuit of each of switches *2* to *6*, inclusive, and then cut out of circuit as the switches are successively transferred to the holding circuits. The limit switch delays the successive closing of the switches until the current is reduced to the value for which the limit switch is adjusted. One limit switch is adjusted for normal operation with both motors in service and the other is set at a higher value for use when one motor is cut out. This allows the remaining motor to operate at a higher than the normal rate during the time necessary to return the car to the barn. The control cut-out switch serves to make either of the limit switches active.

The line relay interlock is included in the holding circuits of switches *1* to *6*, inclusive. The operating coil of the line relay is connected between a transformer tap and the ground. If the current goes off the line, the interlock of the line relay opens which, in turn, opens the switches *1* to *6*, inclusive. If


Auxiliary Circuits
Trolley Up
Lower
B+ B+ BB+ BB+ 6 6 6 90 90 BR- BR- B- B-
Up (Left)
Up
7 Out
Trolley Down
B+ 12 12 12 BR- BR- BR- B- B-
Down (Right)
Down
Line Switch
B+ B+ Lower 8 8 Trip 18 BR- BR- BR- B- B-
BB+
LS
Trip Reset
B+ Upper 7 7 7 50 51 B- B- B-
#7 Out
Trip
Reset
Brake Valve
B+ B+ Lower AB+ AB BK BK B- B- B- B- B-
BK
Brake Valve
Over-Speed Relay
When #5 closes over-speed relay interlock thrown in
1. Nº 7 closes
B+ B+ Lower AB+ 1 1 R 14 BR- BR- B-
#5 Out
#7
#2 Out
When #2 closes
15
#7 In
Reverser (Forward)
Line Relay
2. Nº 1 closes
3 3 3 3 35 36A 36 27 27 96 96E B-
#3 Out #4 Out #5 Out #7 In
#1
Limit Switch
Line Relay


3. Nº 2 closes
4 Nº 3 closes and Nº 1 opens
When #3 closes, its interlock opens the circuit of #1 and #1 opens
5 Nº 4 closes
6 Nº 5 closes and Nº 3 opens
Over-speed interlock now active in circuit of #7 magnet valve. When #5 closes, its interlock opens the circuit of #3 and #3 opens
7 Nº 6 closes
#2 Out #1 In
C.C.
#7 In
#2
#2 In
26
26
26R
Line Relay
B-
Limit Switch
4 4 4 4
37 33 31 29 28 27 27 26
#3 Out #2 In #1 In
#3
36 27 27 26
#3 In #5 Out #7 In
38 32 30 29 28 27 27 26
#4 Out #2 In #1 Out
#4
27 26
#4 In #7 In
5 5
40 39 32 30 29 28 27 26
#5 Out #4 In #2 In #1 Out
#5
27 27 26
#5 In #7 In
41 41 42 42 39 32 30 29 28 27 27 26
#3 Out #5 In #4 In #2 In #1 Out
#6
#6 In

FIG. 21

the current returns before the controller is moved, the switches will again close in regular order.

The overspeed relay is active only after switch *5* is closed. The overspeed relay is provided to keep the cars from attaining a dangerous speed on down grades with the controller on. One current-operating coil of the relay is in series with one of the motors and the voltage-operating coil is connected across the terminals of the armature circuit of the same motor. The voltage coil tends to open the interlock of the relay and the current coil tends to close it. The lifting of the relay interlock depends on the difference between the effects of the two coils.

If the motor is running down grade with the current on, the effect of the comparatively small current in the current coil of the relay may be overbalanced by the effect of the voltage coil. The current in this coil depends on the difference of potential across the armature, and at high speed the voltage may be enough to cause the relay to open and thus open switch *7*. The opening of the interlock of switch *7*, shown near the end of the *27* wire, opens the holding circuits of switches *3*, *4*, *5*, and *6* and these switches open. The motors are thus cut out of circuit.

Switch *2* remains closed and its interlock in *out* position until the controller is thrown off. If the controller is on and the overspeed relay again closes, the other switches cannot close because No. *2* interlock is in its *in* position and the circuit of No. *7* magnet thereby opened. The controller handle must first be moved to *off*-position, allowing No. *2* switch to open, and then moved to the desired running point.

The conductor's valve is used to produce signals by means of the air whistle. The signal switch, Fig. 20, is closed by pulling on a rope that extends through the train. The magnet valve, the circuit of which is closed by the switch, connects the air system to the whistle. The switches in the local circuits of all magnet signal valves, except the one on the first car, are open; therefore, only that valve is active.

38. Motor Circuits.—When switches *1* and *7* close, the low-voltage tap and section *R1–R2* of the resistor are active

in the motor circuit. The resistor is cut out by switch *2*. When switch *3* closes, the intermediate-voltage tap and section *R1–R4* are active. This resistor is cut out by switch *4*. When switch *5* closes, the high-voltage tap and resistor section *R4–R5* are active. This resistor is cut out when switch *6* closes. There are three efficient running positions of the controller where there are no sections of the resistor in circuit.

CONTROL FOR STORAGE-BATTERY CAR

39. In Fig. 22 is shown a car-wiring diagram for a storage-battery car. The two motors and four sections of the resistor are first connected in series across the terminals of the battery.



FIG. 22

As the controller handle is advanced, the resistor sections are short-circuited, the motors then connected in parallel with two sections of the resistor in each motor circuit, and finally these sections cut out. The series-running position is No. *4* and the parallel-running position is No. *7*.

In Fig. 23 is indicated the connections of the battery, the controller and the motors for step *1* and step *5* of the controller. The five lower fingers of the controller are connected to leads


Step 1.
a 1 1 b No.1 19 For. A1 AA1 For. F1 F1 FF1 R5 R3 R1 R2 R4
FF2 F2 F2 For. A2 AA2 For. No.2 No.2 c
Step 5.
d 2 2 e
R3 R5 FF1 F1 For. AA1 A1 For. 19 No.1 b 1 1 c
R1
R2 R4 FF2 F2 For. A2 AA2 For. No.2 No.2 c

FIG. 23

from the resistor. The sections of the resistor are short-circuited as the corresponding fingers touch casting *2* on steps *2*, *3*, *4*, *6*, and *7*.

CONTROL FOR GASOLINE-ELECTRIC CAR

40. In Fig. 24 is shown a car-wiring diagram for a gasoline-electric car with a 750-volt, commutating-pole generator direct-connected to a gasoline engine, a series-parallel controller, and two commutating-pole motors mounted on the car axles. The controller serves for changing the connections of the two motors, and for adjusting the generator voltage by means of a rheostat in its shunt-field circuit. The engine is started by compressed air from the brake system.

Fig. 25 shows the current paths for the first and last positions of the controller. In the first position, the two motors are in series and the generator-field excitation is least, giving low voltage for starting. In the last position, the two motors are in parallel and the generator voltage is highest, giving highest car speed.


R4 R2
R3 R1
G
G.F.
R5
A2
A2
A1 A1
B.O.
a
b
Rev.
For.
-1
1
T
A1
d
e
f
A2
-11
c
G
2
3
4
5
6
G
Shunt Field
Comm. Field
Arm.
Generator
G.F.
Ground
AA1
AA2
Comm. Fields
No.1
No.2
A1
AA1
Arm.
A2
AA2
Arm.
FF1
F1
Main Field
FF2
F2
Main Field

FIG. 24


First Step
T 2 2 A1 A1 A1 A1 AA1 AA1 For. F1 FF1 For. -1
-11 5 5 A2 A2 A2 A2 AA2 AA2 For. FF2 F2 For. G
G
G.F. B.O. a G.F. R1 R2 R3 R4 R5 G b G
Last Step
T 2 2 A1 A1 A1 A1 AA1 AA1 For. F1 FF1 For. -1 -11
d 3 3 c f 4 4 A2 A2 AA2 AA2 For. FF2 c
FF2 6
6
G For. F2
F2 G
G
G
G.F. B.O. a 1 1 b G

FIG. 25

EFFICIENCY TESTS

INTRODUCTION

COMPARISON OF METHODS

1. The commercial efficiency of a generator, or a motor, is the ratio of the output to the input, both being expressed in the same unit of power. An earlier method for determining this ratio was to run the machine under full-rated load conditions and to actually measure both the input and the output; by dividing the output by the input, the efficiency was at once determined. Some of the later methods of testing do not necessitate full-load operation. The machine in such a test is run as a motor without load, and the losses are determined by tests and by calculation.

The output of a machine must be equal to the input minus all the losses that occur; or, the output plus the losses equals the input. Knowing either the input or the output and the losses, the efficiency may be calculated. If the way that the losses vary with the output or the input is known, the efficiency throughout the range of load may be calculated.

2. The advantages of the running-light method over the earlier method, of which the Prony-brake test is an example, are: (1) The machine need not be run under full-load condition, as the losses can be determined from data taken at light load, and the full-load values calculated approximately. This saves power and does not require bulky apparatus for absorbing the load. (2) The results are more accurate. Since the

COPYRIGHTED BY INTERNATIONAL TEXTBOOK COMPANY. ALL RIGHTS RESERVED

losses are small compared with the total input, a moderate percentage of error in the small measurements produces only little effect on the final efficiency; whereas, with the same percentage of error in the older method, in which total measurements are used, the efficiency is liable to an error at least as great as the errors of the readings.

A disadvantage is that in some machines the manner in which the losses in the machine under test vary with the load may not be definitely known. Generally, however, it is sufficiently accurate to assume that the machine meets the average conditions determined by numerous tests on the same general type of apparatus. This is especially true for direct-current apparatus.

LOSSES

3. The losses occurring in a generator or a motor come under the following headings:

1. Bearing friction and windage, together with brush friction on the commutator or on the slip rings. This may all be classed roughly as a friction loss, and, with constant speed, can be considered as independent of the load; that is, these losses may be assumed to remain constant at all loads. Where a machine is mounted on the shaft of a prime mover in such a manner that it cannot be separated therefrom, the frictional losses in bearings and in windage should be excluded from the efficiency calculations, owing to the practical impossibility of determining them satisfactorily.

2. I^2R loss in the armature, where I is the current in the armature and R the resistance of the armature. This loss changes greatly under different load conditions, but by means of tests and calculation may usually be definitely determined.

3. I^2R loss in the shunt-field and series-field windings, each being calculated separately. In a self-exciting machine, the losses in the field rheostat, the shunt winding, and the shunt to the series field are included in the field losses. For the shunt winding on a constant-potential machine, the loss does not vary greatly for different loads; in an overcompounded generator, the shunt-field loss increases somewhat as

the terminal voltage increases. The loss in the series winding varies for different load conditions, since the current through the series winding is changed.

4. I^2R loss in the brushes, and brush contact due to the current flowing against the resistance offered by the brushes and by their contact with the commutator. The resistance of carbon brushes decreases as the current heats the brush. It is difficult to state exactly the value of the brush resistance or the drop in volts caused by the current and brush resistance, since the composition of the brush, the current density, the brush temperature, the speed of rotation of the commutator, and the brush pressure are all factors in determining the values. In the case of carbon brushes worked at a density of from 30 to 40 amperes per square inch of contact surface, it is usually sufficiently accurate to allow a drop of about 2 volts for the complete set of brushes. The drop in volts multiplied by the armature current gives the approximate I^2R brush loss.

The relation between current density and drop in volts in the set of brushes may be expressed with approximate accuracy, when ordinary carbon brushes are used, by the following statements:

Up to 10 amperes per square inch, current density, the drop for every ampere per square inch is .125 volt.

Above 10 amperes per square inch, current density, the drop is 1.25 volts + .025 volt for every ampere per square inch above 10.

For 5 amperes per square inch, the drop is $.125 \times 5 = .625$ volt. For 40 amperes per square inch, the drop is $1.25 + (40 - 10) \times .025 = 1.25 + .75 = 2$ volts.

5. Molecular magnetic friction, or hysteresis, due to the constant reversals of magnetism in the armature core. This varies under different speed and voltage conditions, and should be determined with these conditions at normal value, since they do not usually vary in any simple proportion according to the speed or to the voltage.

6. Eddy-current losses in the armature core, in the pole faces, in wide conductors, and, in the case of cross-connected

armatures, the losses brought about, under certain conditions, by cross-currents from one portion of the windings to another portion. The eddy-current losses are usually small in direct-current machines, but are of more importance in alternating-current machines.

The sum of these losses corrected for full-load conditions gives the total loss at full load. The output divided by the output plus the losses, and the result multiplied by 100, or the input minus the losses divided by the input, and the result multiplied by 100, equals the efficiency expressed in per cent. By calculation and test the losses for a few different loads may be determined, and an efficiency curve constructed that will show very closely the efficiency at any load within the range of the machine.

DIRECT-CURRENT MACHINES

RESISTANCE MEASUREMENTS

4. Methods of Making Tests.—The resistance of field coils, the armature, and brushes vary under different load conditions; but, in the calculations, it is customary to use the constant values of resistance that the apparatus assumes during continuous operation at normal load. If convenient to load the machine, the resistance measurements may be made after a run that is sufficiently long for the machine to assume a constant temperature. This may be from 6 to 18 hours, according to the size and construction of the apparatus. In case the machine cannot be loaded conveniently, the cold resistances may be measured and then corrected for a normal value of temperature rise. This may have been stated in the machine specifications, but if not, approximately correct results may be obtained by assuming a rise of from 25° to 40° C. above room temperature. The standard room temperature is usually taken as 25° C.

The measurement of low resistances, such as those of armatures and series-field coils, requires special precautions.

since the values are very small. For this reason, the ordinary Wheatstone bridge is not suitable. A potentiometer, however, may be used satisfactorily if available.

The resistance measurement most frequently used is known as the "fall-of-potential method." The resistance to be measured and a known resistance of about the same value and of sufficient carrying capacity to transmit the current necessary for readable deflections without undue heating are connected in series in a circuit through which a steady current flows, preferably from a storage battery. By means of a low-reading voltmeter, the drops of potential are measured across the terminals of the unknown and the known resistance. The currents must have the same value when each measurement is made; therefore, it is well to insert an ammeter in the circuit in order to check current readings. If the currents are of the same value, the drops of potential are directly proportional to the resistances.

Let X = unknown resistance;
R = known resistance;
V' = voltmeter reading when connected across X;
V = voltmeter reading when connected across R.

Then, $$X : R = V' : V$$

or, $$X = \frac{V'R}{V}$$

If a known resistance is not available, the resistance of the field coils or of the armature may be determined by allowing current to flow through the part to be measured and then dividing the drop of potential across the terminals by the current flow through the device.

5. Precautions.—In measuring the resistance of armatures, the shunt-field circuit should be opened, and the voltmeter leads, consisting of flat copper strips, should be placed under adjacent brushes of opposite polarity in such a manner that firm contact with the commutator is secured. All of the brushes should be well fitted to the commutator. Further precautions are necessary, depending on the type of armature. If the armature is parallel wound, it will

probably have balancing rings or cross-connecting rings. The armature should be turned so that the brushes bear on commutator segments connecting as directly as possible to the balancing rings. Fig. 1 shows the proper position for the brushes; B_1+ and B_2+ are in contact with commutator segments connected to the same balancing ring, while B_1-



FIG. 1

and B_2- rest on other segments connected to another balancing ring. A reading of the voltmeter should be taken with the brushes in the position shown; then, the armature should be moved so that the brushes bear on segments connected to another pair of balancing rings, and a second reading taken. The mean of the two readings should be used. When the brushes are on segments that are cross-connected

by balancing rings, all the parallel circuits of the armature are connected in parallel, independently of the brushes; and, as the voltage drop is taken across the commutator, and not across the brushes, the effects resulting from unequal contact between brushes and commutator are eliminated.

In a series-wound armature or a parallel-wound armature without balancing rings, the precautions to be taken are to have the brushes well fitted and to connect the voltmeter leads directly to commutator segments situated the correct distance apart. This distance is equal to the total number of segments divided by the number of poles. In these armature measurements, the brush resistance is excluded, since the voltmeter terminals are placed on the commutator bars.

6. The brush resistance plus the armature resistance may be measured by connecting the voltmeter terminals to the bus-rings, shown in Fig. 1, care being taken that the brushes are placed so as to connect as directly as possible with the balancing rings. This measurement is subject to errors, since the resistance of the brushes and their contact resistance with the commutator differ for different current densities; also, if the brushes are not well fitted, the contact resistance may be far from normal.

It is usually better to measure the armature resistance alone, by placing the voltmeter terminals on the commutator bars, and then make allowance for the drop in voltage due to the current flowing through the brush resistance and the contact resistance.

7. When making the resistance measurements of the series-field coil (the series-field coil being in parallel with its adjusted series shunt), the voltmeter terminals should make contact directly with the terminals of the series coils. The coil terminals should be sandpapered, if necessary, in order to secure good contact with the voltmeter wires. The loss in the shunt-field windings may be determined by another method, as explained later.

8. Temperature Corrections.—The cold-resistance values of the armature and the series coil may be corrected

for full-load conditions. A temperature coefficient of .38 per cent. per degree centigrade for an initial room temperature of 25° C. may be assumed for the copper conductors. First, assume a rise of 25° C.; the increase in resistance is approximately $(.0038 \times 25)\ 100 = 9.5$ per cent. By increasing the cold resistance 9.5 per cent., or multiplying the cold resistance by 1.095, the hot resistance is determined. If an increase in temperature of 40° C. is assumed, the increase in resistance is $(.0038 \times 40)\ 100 = 15$ per cent. By increasing the cold resistance 15 per cent., or multiplying the cold resistance by 1.15, the hot resistance is determined.

The corrected resistance of a part of the machine multiplied by the square of the current passing through it gives the I^2R loss in that part.

RUNNING-LIGHT TEST

GENERATOR TEST

9. Preparations for Test.—In order to determine the combined friction, core, and eddy-current losses of a generator, the machine should be driven as a motor without load and the input measured. The machine, if new, should be run about an hour before taking readings, in order that the bearings may become thoroughly lubricated. The test may be made with the machine cold, and little error will be introduced. The speed must be the same as the rated generator speed in order to have the same windage and friction losses. The speed may be adjusted by the shunt-field rheostat. The field excitation should be as near as possible that required when the machine is a generator and is delivering its full load.

The electromotive force applied to the terminals when the generator is running as a motor should be higher than the normal terminal voltage when running as a generator. This is done in order that the counter electromotive force generated in the motor armature (which, when the motor is running light, is nearly the same as the electromotive force

impressed on the motor terminals) will be about the value of the total electromotive force generated in the generator armature. This total generated electromotive force at full load is equal to the generator-terminal electromotive force plus the drops in voltage, under full-load conditions, in the brushes, series-field coil, and armature.

The exact value of these drops may not be known, and the values may differ on different types of machines, but on some testing floors, a value of 3 volts for every 125 volts of the rating of the generator is allowed when testing for full-load efficiency. This means that if the rated voltage of the generator is 250 volts, the electromotive force applied to the motor terminals should be 256 volts.

10. Running as a motor in this way, the line supplies energy to overcome the bearing and brush friction, the windage, the core losses, and the eddy-current loss in the conductors. There is some I^2R loss in the armature during the test, due to the flow of the small armature current against the armature resistance. For extremely accurate work, this I^2R loss may be subtracted from the running-light loss. This I^2R loss, however, is usually so small that no appreciable error is made in the final result if it is neglected in the calculations; it should, however, be noted and allowance made for it if the loss in any case is found to be of sufficient importance.

11. Test Connections.—The connections for this test are shown in Fig. 2, where A is an ammeter connected in series with the armature of the machine to be run as a motor. Care should be taken that the ammeter is so connected as to measure only the armature current and not the armature and shunt-field current. B is a voltmeter for measuring the electromotive force applied to the armature terminals, and C is an ammeter connected to the shunt-field coil. The ammeters are protected by short-circuiting switches, which are opened only when a reading is to be made. D is the armature; F, the shunt field; SF, the series field, not used in this test; R, the shunt-field rheostat; S, the

main switch; *CB*, the circuit-breaker, and *WB* a water rheostat, or better, a metal rheostat, or a booster for adjusting the voltage applied to the armature terminals. A tachometer is used to measure the speed of the machine at any instant.



FIG. 2

It is necessary that the speed conditions should be known at the instant the other instruments are read; therefore, a tachometer is used instead of a revolution counter, which shows only the average speed for a given length of time.

12. Position of Brushes.—The motor is started by throwing in the circuit-breaker *CB* and closing switch *S*, *WB* being used as a starting rheostat. The brushes should be set at the no-load neutral position. This position may be determined as follows: While the motor is running, voltmeter points, connected to a voltmeter *V*, Fig. 3, reading about 15 volts, are held on the commutator surface a distance apart equal to the space between the centers of two

adjacent commutator bars. These points are moved back and forth over the circumference of the commutator until a position is reached where the voltmeter either reads zero or gives the minimum reading. This is the *no-load neutral position*, and the brushes are set accordingly.



FIG. 3

13. Conduct of Test. The resistance in the rheostat *WB*, Fig. 2, should now be adjusted, either by changing the distance between the plates or by adding a little more salt to the water, until the counter electromotive force is of correct value. In this case, the counter electromotive force is practically the same as the applied electromotive force.

The speed is brought up to its rated value by adjusting the field rheostat. The man that takes the tachometer reading adjusts the speed. When the speed and the voltage are correct, the two ammeters, the voltmeter, and the tachometer are read as near as possible at the same time. It will be found that the readings of ammeter *A* will vary somewhat, but if care is taken to read it only after the speed has been correct for at least 10 seconds, the ammeter needle will be steady and the values will not vary greatly. Five sets of readings should be taken at each load point, and the average of these readings should be used.

14. Test-Sheet Data.—The readings should be recorded on a prepared test sheet similar to that shown in Fig. 4. The resistance measurements of the armature and the series field in parallel with its shunt should be recorded first. It is assumed that the cold-resistance values are obtained and then the hot resistances calculated. The values recorded on

TEST SHEET *Date*_____

D.-C. MOTOR OR GENERATOR *Tested by*_____

Rating, 500 K. W. Volts, 575. Amperes, 870. Speed, 400 R. P. M.
Machine No. 1. Dimension of Brushes, 1 in. × 1½ in. Number of Studs, 8.
Number of Brushes per Stud, 8. Current Density, 22 Amps.

RESISTANCE MEASUREMENTS

Armature				Series Field and Series-Field Shunt			
Volts	Amps.	Res., Cold	Res., Hot Calculated	Volts	Amps.	Res., Cold	Res., Hot Calculated
.0435	6	.00725	.00794	.0388	20	.00194	.002045

RUNNING LIGHT

Volts	Amps. of Arm.	Watts	Amps. Shunt	Speed
525	28.7	15,068	5.76	400
540	29.2	15,768		400
556	29.7	16,513		400
571	30.4	17,358		400
586	30.9	18,107		400
601	31.7	19,052		400

EFFICIENCY AND LOSSES

Per-Cent. Load	0	25	50	75	100	125
Terminal volts as generator	525	537.5	550	562.5	575	587.5
Amps., line	0	232.5	455	666	870	1,064
Amps., shunt field	5.76	5.9	6.03	6.17	6.31	6.5
Amps., arm.	5.76	238.4	461	672.2	876.3	1,071
Amps., series field and series-field shunt	5.76	238.4	461	672.2	876.3	1,071
IR drop	0	2.9	5.6	8.2	10.7	13.2
Volts as motor, running light	525	540	556	571	586	601
Friction and core losses	15,068	15,768	16,513	17,358	18,107	19,052
I^2R arm. loss	0	451	1,687	3,588	6,097	9,107
I^2R shunt-field and rheo. loss	3,024	3,171	3,316	3,471	3,628	3,819
I^2R series field and series-field shunt loss	0	116	435	924	1.570	2,345
I^2R brush loss	0	119	461	1,008	1,753	2,678
Total	18,092	19,625	22,412	26,349	31,155	37,001
K. W. output	0	125	250	375	500	625
K. W. input	18.1	144.63	272.41	401.35	531.16	662
Per-cent. efficiency	0	86.43	91.77	93.43	94.13	94.41

the sheet shown in Fig. 4 were based on actual measurements. The temperature rise of the armature was about 25° C. The temperature rise corresponding to the increase in resistance of the combined series field and series-field shunt is about 14° C. The temperature rise of the series field alone is somewhat more than this, since the series-field shunt changes in resistance but little with increased temperature.

The resistance measurements may be made either by the aid of a low-reading ammeter and a millivoltmeter or by comparing the drops across the known and the unknown resistances, as previously described. Enough current should be allowed to flow through the resistance, so that a readable deflection on the millivoltmeter connected across the terminals of the resistance can be obtained. A rheostat may be used to control the current.

15. The running-light readings are now taken. The machine is run as a motor, and the voltage applied to the armature terminals is adjusted so that the counter electromotive force is 525 volts, which, in this case, is the rated no-load voltage. The speed is adjusted to the correct rated value, and readings are taken on the instruments *A*, *B*, and *C*, Fig. 2. The product of the volts and the armature amperes equals the sum of the bearing friction, brush friction, windage, hysteresis, and eddy-current losses at no load. The I^2R armature loss is usually negligible at no load.

As just stated, the rated no-load voltage of the machine under consideration is 525, and the full-load voltage, 575. The rise in voltage is 50. At 25-per-cent. load, the generator terminal voltage is $525 + \frac{50}{4} = 537.5$; at 50-per-cent. load, $525 + \frac{50}{2} = 550$; at 75-per-cent. load, $525 + \frac{50 \times 3}{4} = 562.5$; at 100-per-cent. load, $525 + 50 = 575$; and 125-per-cent load, $525 + \frac{50 \times 5}{4} = 587.5$. The corresponding outputs are 125, 250, 375, 500, and 625 kilowatts.

At these loads, the current that flows through the line when the machine is operating as a generator is found by dividing the watts output by the terminal voltage.

A long shunt connection is used in this machine, so that the current for the shunt field flows through both the armature and the series-field circuit. The shunt-field current may be assumed to increase in proportion to the increase in terminal electromotive force. The overcompounding is accomplished by the series coils. At no load, the shunt-field current is 5.76 amperes, as found by ammeter *C*, Fig. 2; at 25-per-cent. load, the current is $5.76 \times \frac{537.5}{525} = 5.9$ amperes; at 50-per-cent. load, the current is $5.76 \times \frac{550}{525} = 6.03$ amperes, etc. The values of the shunt current should be recorded in Fig. 4; and to obtain the armature and series-field current, the shunt current should be added to the line current.

16. The values of terminal voltages as a generator, and the amperes in the line, in the series field and its shunt, and in the armature are recorded as shown. The IR drops in the armature, series-field circuit, and brushes, at the different load points, are found by multiplying the armature current by the hot resistance of the armature plus the hot resistance of the combined series field and its shunt, and adding to this the drop in volts caused by the brushes and brush-contact resistance. The hot resistance of the armature and series-field circuit is .00794 + .002045 = .009985 ohm.

The current density in the brushes at full load is $\frac{876.3}{1 \times 1.25 \times 8 \times 4} = 22$ amperes per square inch. For this rather low density, the brush drop might be somewhat under 2 volts, but the approximate value of 2 volts will be used in the calculations for full-load conditions and for the set of brushes (four positive and four negative groups). Brush-resistance data is rather difficult to determine with great accuracy. An approximate value based on experimental carbon-brush data is close enough for ordinary purposes, since a slight inaccuracy makes little difference in the calculated machine efficiency. For a load of 25 per cent., allow $2 \times \frac{1}{4} = .5$ volt; for 50 per cent., $2 \times \frac{1}{2} = 1$ volt; for 75 per

cent., $2 \times \frac{3}{4} = 1.5$ volts; for 100 per cent., 2 volts; for 125 per cent., $2 \times \frac{5}{4} = 2.5$ volts.

The whole IR drop at a load of 25 per cent. equals $238.4 \times .009985 + .5 = 2.9$ volts; at 50 per cent., $461 \times .009985 + 1 = 5.6$ volts; at 75 per cent., $672.2 \times .009985 + 1.5 = 8.2$ volts; at 100 per cent., $876.3 \times .009985 + 2 = 10.7$ volts; at 125 per cent., $1{,}071 \times .009985 + 2.5 = 13.2$ volts. Record these values of drops in voltage and add them to the corresponding values of generator-terminal voltage in order to obtain the running-light motor volts.

17. Make a running-light test for each of these values of motor volts, in order to obtain the friction and core losses corresponding to the different load points. The friction losses change only slightly for the different loads so long as the speed is constant, but the core losses increase with increasing load, due to the greater density of the lines of force brought about by the higher excitation.

Record the motor volts, the armature amperes, and the watts (product of motor volts and armature amperes) obtained from the running-light readings. Also record the watts under the side heading friction and core losses.

18. The I^2R armature loss is found by multiplying the square of the armature current by the hot resistance of the armature. At full load, $876.3^2 \times .00794 = 6{,}097$ watts.

The I^2R loss in the shunt field and rheostat is found by multiplying the calculated shunt-field current by the generator-terminal volts. With the exception of the first value, 5.76 amperes, the values of the shunt current obtained from the running-light test are not used in determining the I^2R loss in the shunt field. This is due to the fact that the generator values of shunt-field current would not be the same as the motor-test values because of the absence of the series field during the test. At full load, $6.31 \times 575 = 3{,}628$ watts.

I^2R series field and series-field shunt loss equals the product of the square of the current flowing through the series-field circuit and the hot resistance of the combined

series coil and its shunt. At full load, $876.3^2 \times .002045 = 1{,}570$ watts.

The I^2R brush loss is determined by multiplying the armature current at any load point by the drop in volts allowed for the brushes at that point. At 25-per-cent. load, $238.4 \times .5 = 119$ watts; at 50-per-cent. load, $461 \times 1 = 461$ watts; at 75-per-cent. load, $672.2 \times 1.5 = 1{,}008$ watts; at 100-per-cent. load, $876.3 \times 2 = 1{,}753$ watts; at 125-per-cent. load, $1{,}071 \times 2.5 = 2{,}678$ watts.

19. The losses are recorded on the test sheet, and the sum of the losses is computed for each load point. The total loss added to the output, both expressed in kilowatts, equals the kilowatt input. The commercial efficiency of the machine, expressed in per cent., equals the output divided by the input and the quotient multiplied by 100.

20. Efficiency Curve.—An efficiency curve may be plotted similar to the one shown in Fig. 5. The values of



FIG. 5

the efficiencies are laid off as ordinates, and the load points, or kilowatts output, are laid off as abscissas. The data for this curve is taken from the test sheet. The test sheet and curve should be filed for future reference.

MOTOR TEST

21. A shunt or a compound motor may be tested in a manner similar to that just described for a generator, provided the test is slightly modified to suit the altered conditions. The connections shown in Fig. 2 and a test sheet similar to that shown in Fig. 4 may be used. In the case of a compound motor, the series field should be disconnected during the running-light test.

The losses are similar to those in a generator; namely, friction and core losses L_{fc}; armature loss $I_a^2 R_a$, armature current squared times the hot armature resistance; series-field loss $I_a^2 R_{sc}$, armature current squared times the hot series-coil resistance; brush loss $I_a^2 R_b$, or $I_a V_b$, armature current squared times the brush resistance, or armature current times volts drop in brushes; shunt-field loss $I_s^2 R_s$, or $I_s E$, hot shunt-field current squared times the hot shunt-coil resistance, or shunt-field current times the line voltage.

The input at full load $I_m E$ equals the motor current, usually marked on the name plate of the machine, multiplied by the line voltage. The motor current equals the sum of the armature current and the hot shunt-field current. The output W_o, expressed in watts, at full load equals the rated horsepower of the motor, usually stated on the name plate, multiplied by 746.

The input equals the output plus the losses; the relation of the values may be expressed as follows:

$$I_m E = W_o + L_{fc} + I_a^2 R_a + I_a^2 R_{sc} + I_a V_b + I_s E$$

22. The cold resistances of the armature, series coil, and shunt coil should be measured and corrected for a normal temperature rise. Multiplying the cold resistances by 1.18 will give approximately correct results. The current I_s of the hot shunt field equals the line voltage divided by the hot resistance of the shunt field. If the motor current I_m for full load is known, subtract from it the shunt current in order to obtain the armature current I_a.

The drop in volts in the armature and series field equals $I_a R_a + I_a R_{sc}$. To this add an allowance of from 2 to 2.5 volts

for brush drop $I_a R_b$. The total drop is $I_a R_a + I_a R_{ic} + I_a R_b$. When making the running-light test to determine the friction and core losses at full load, the electromotive force applied to the armature terminals should be adjusted by rheostat WB, Fig. 2, so as to be equal to the counter electromotive force of the armature at full load. This counter electromotive force equals the line voltage minus the total drop. The motor speed should be adjusted by field rheostat R, Fig. 2, so as to be as near the normal full-load speed as possible. The brushes should be placed at the neutral position.

23. The L_k loss equals the electromotive force applied to the armature terminals multiplied by the current flowing through the armature during the running-light test. The $I_a^2 R_a + I_a^2 R_{ic} + I_a V_b$ loss equals the total drop multiplied by the full-load armature current, or $I_a (V_a + V_{ic} + V_b)$. The output W_o is known, and the $I_f E$ loss can be calculated. If the current marked on the name plate is correct, the output plus the calculated losses will equal the input. If the full-load current is not known, a trial value of current may be assumed, a running-light test made, and the other losses calculated. If the assumed current satisfies the relation between output, losses, and input, as expressed by the formula of Art. **21**, it is correct; if not, another trial value is taken. The efficiency equals the watts output divided by the watts output plus the watts lost.

24. If the counter electromotive force of the motor changes only slightly during the range of load, the L_k loss can be considered constant; the $I_f E$ loss may also be considered constant. These two losses may be called *constant losses*. Since the armature current changes at different loads, the $I_a^2 R_a$, the $I_a^2 R_{ic}$, and the $I_a V_b$ losses will change; these may be called *variable losses*. As these losses change nearly in proportion to the square of the armature current, little error is introduced in the final result if the variable loss for 25-per-cent., or $\frac{1}{4}$, load is taken as $\frac{1}{16}$ of the full-load variable loss, the current being approximately $\frac{1}{4}$ and the losses $\frac{1}{4} \times \frac{1}{4} = \frac{1}{16}$; for 50-per-cent. load, $\frac{4}{16}$, or $\frac{1}{2} \times \frac{1}{2} = \frac{1}{4}$; for

75-per-cent. load, $\frac{9}{16}$, or $\frac{3}{4} \times \frac{3}{4} = \frac{9}{16}$; for 125-per-cent. load, $\frac{25}{16}$, or $\frac{5}{4} \times \frac{5}{4} = \frac{25}{16}$. Adding the constant and variable losses for the different load points produces the total losses at these points, and the corresponding efficiencies may be calculated.

If greater accuracy is desired for the partial-load points, an efficiency may be assumed for a load point, and the motor current calculated by multiplying the horsepower at that point by 746, and dividing by the product of the assumed efficiency (expressed as a decimal) and the line voltage. The losses are then calculated. If the calculated input equals the output plus the calculated losses, the assumed efficiency is correct; if not, another assumption may be made and tested. At the low-load points, the current will be somewhat more than one-fourth or one-half the full-load value, due to the lower efficiencies.

LOADING-BACK TEST

25. Preparations for Test.—Where two direct-current generators, or motors, of the same type and capacity are available, the Hopkinson, or **loading-back**, method of testing may be employed. Both machines, one acting as a motor and the other as a generator, are made to carry full load, and all the losses are measured under these conditions.

The two machines are belted together, or have their shafts coupled, so that the one that acts as the motor may mechanically drive the one that acts as the generator. Most of the current necessary to drive the motor is delivered by the generator armature, but enough current is taken from a power circuit to make up for the losses in the motor and generator.

26. Test Connections.—The connections for a loading-back test are shown in Fig. 6, where WB is the water-rheostat, or other regulating device, for adjusting the voltage of the supply circuit; SWB, a starting water-rheostat box provided with a short-circuiting switch; A_l, the line ammeter; G, the generator, and A_g its armature ammeter; M, the motor, and A_m its armature ammeter; F_g, the generator shunt-field ammeter;



FIG. 6

F_m, the motor shunt-field ammeter; V_g, the voltmeter for the generator terminals; V_m, the voltmeter for the motor terminals; R_g, the generator field rheostat; R_m, the motor field rheostat; CB and $C'B'$, circuit-breakers; and S, S', and S'' switches for the power circuit, generator, and motor. Short-circuiting switches are provided for the ammeters. The series-field coil connections of the motor are the reverse of those of the generator, so as to make an accumulatively wound motor.



FIG. 7

Fig. 7 shows a simplified diagram of the connections for the test. The two machines are connected in parallel, and the generator and the supply circuit furnish current to the motor.

27. Conduct of Test.—The brushes of the motor and generator should be moved to their running positions. The motor is started by closing circuit-breaker CB and switches S and S'', Fig. 6, and using rheostat SWB as a starting resistance. When the motor is up to speed, the resistance of rheostat SWB is entirely cut out by the short-circuiting switch.

The electromotive force of generator G, indicated by V_g, is built up until it is equal and opposite to the supply voltage, as indicated by V_m. When in this condition, a voltmeter connected across the open switch S' will read zero volts; the voltage of G should then be increased a trifle, so that the voltmeter needle inclines slightly backwards, provided it had a positive reading before the voltage of G was brought up to that of the supply circuit. Circuit-breaker $C'B'$ and switch S' are then closed. The generator G will furnish only little, if any, current until its voltage is further raised. This is done by cutting out some of the resistance in the generator field rheostat, thus raising the generator voltage

slightly above that of the supply mains. Current will now flow from G through M. Both generator G and motor M begin to take on load. Generator G alone cannot supply enough current to motor M to enable the motor to drive G mechanically, because more electric power is required to drive M than M can mechanically supply to G, and G cannot transform all of the mechanical power it receives into electric power for M. Hence, the amount of loss in each machine must be compensated by electric power from the supply mains.

28. The load on the machines is increased to full-load conditions by cutting out resistance in the generator field rheostat R_g and by speeding up the motor by cutting in resistance in the motor field rheostat. Adjusting rheostat WB also varies the current output of the armature G, since the current depends, among other conditions, on the difference between the voltage of G and that of the supply circuit. The voltage of G must be held at its normal value.

Great care must be exercised when loading the machines, as a small change in the strength of the field of either machine will materially alter the current flowing. This is due to the low resistance of the circuit through the two armatures. The ammeters A_g and A_m will show the increase in current as the load is built up. The current through the ammeter A_l will increase but slowly. The load should be built up until ammeter A_g shows that the generator is furnishing its full-load current.

The speed should be maintained at normal value. An operator tests the speed with a tachometer and adjusts the motor field rheostat R_m as found necessary. Adjustments should be made with care, while the readings of the instruments should be frequently noted. No sudden changes in any of the conditions should be allowed, because of the danger of throwing the various magnetic and electric values involved out of balance, and thus causing excessive current flow.

29. The set should be run under full-load conditions long enough for the temperature of the generator to become

constant and to properly bed the brushes on the commutator. The time required varies for different machines and for different conditions of testing; it may be from 6 to 18 hours.

When current and voltage conditions for full load are constant and the generator has attained approximately full-load temperature, as checked by a thermometer, the readings for efficiency may be made. Readings are taken on instruments F_g, F_m, A_m, A_l, V_g, A_g, Fig. 6, when the voltmeter V_g, the ammeter A_g, and the tachometer show simultaneously that the generator voltage, the current, and the speed are correct. The average of five readings should be used and recorded.

30. Test-Sheet Data.—A form of test sheet similar to the one shown in Fig. 8 may be used. The output of the generator is equal to the product of the readings of instruments A_g and V_g, Fig. 6, or $I_{ga} \times V$. The power supplied to the motor armature is the product of the reading of the voltmeter V_g and the sum of the readings of ammeters A_g and A_l, which is totaled by the reading of ammeter A_m. The product may be expressed either as $(I_{ga} + I_l)\ V$ or as $I_m \times V$. By adding to this the shunt-field losses in both machines, or $(I_{gf} + I_{mf})\ V$, the result is the total input required to compensate for the bearing friction, windage, core losses, and I^2R losses of both machines and to provide the actually measured generator output $I_{ga} \times V$. The connecting wires should be of such size that there is little drop of potential due to current flowing through them, therefore, the readings of V_g and V_m are practically alike.

The joint efficiency is equal to

$$\frac{\text{output}}{\text{input}} = \frac{I_{ga} \times V}{(I_m + I_{gf} + I_{mf})\ V} = \frac{I_{ga}}{I_m + I_{gf} + I_{mf}}$$

The efficiency of each machine is equal to $\sqrt{\frac{I_{ga}}{I_m + I_{gf} + I_{mf}}}$.

With the values indicated on the test sheet, the efficiency of each generator is 94.7 per cent.

31. If efficiencies at partial-load points are desired, the generator-armature current I_{ga} and the generator voltage V are adjusted to the proper values for the selected load point,

TEST SHEET *Date*_____

Two Dynamos, Nos. 1 and 2 *Tested by*_____

Normal Output, 600 K. W. Volts, 660. Amperes, 910. Speed, 614.

Per-Cent. Load	Revolutions per Minute	Generator Field Current $= I_{f'}$	Motor Field Current $= I_{mf}$	Generator-Armature Current $= I_{ga}$	Generator Volts $= V$	Generator Output $= I_{ga} \times V$	Line Current $= I_l$	Motor-Armature Current $= I_m = I_{ga} + I_l$	Total Input to Machines $= (I_m + I_{f'} + I_{mf}) V$	Joint Efficiency $= \frac{I_{ga}}{I_m + I_{f'} + I_{mf}}$	Single-Machine Efficiency $= \sqrt{\frac{I_{ga}}{I_m + I_{f'} + I_{mf}}}$
25											
50											
75											
100	514	4.68	4	910	550	500,000	95	1,005	557,524	89.68	94.7
125											

Fig. 8

and a set of readings taken. The speed should be kept approximately constant during the tests on the different load points. To shut down the test, open circuit-breakers CB, $C'B'$, and switches S, S', S'', Fig. 6; then cut in the resistance of rheostat SWB, in case the set is to be started again.

SERIES-MOTOR TEST

32. Preparations for Test.—The test connections for determining the efficiency of a direct-current, series-wound motor, where two similar motors are available, are shown in Fig. 9. The shafts are coupled together so that the motor and generator armatures may rotate in unison. A simple method of securing this result is to slip an iron sleeve over both pinions. Setscrews on the sleeve are forced down between the teeth of the pinions. The starting water rheostat SWB, the circuit-breaker CB, the motor armature M_a, the motor field M_f, and the field of the motor that is to act as a generator G_f are connected in series between the trolley and the ground. The generator armature G_a is connected to a water rheostat GWB for the purpose of absorbing the load.



FIG. 9

33. Conduct of Test.—Start the motor by closing circuit-breaker CB and switch S, and operating rheostat SWB. The generator is separately excited, and current will flow through the generator rheostat GWB as soon as

TEST SHEET

*Date*_____

TWO SERIES MOTORS, NOS. 1 AND 2

*Tested by*_____

Rated Output, 125 H. P. Rated Voltage, 500. Rated Full-Load Current, 208 Amperes.

Motor Input Current	Voltage Motor Plus Generator Field	Total Input	Generator-Armature Output Current	Generator-Armature Voltage	Total Output	Joint Efficiency Motor-Generator Set	Efficiency Single Motor
208	525	109,200	192	460	88,320	81	90

FIG. 10

armature G_a starts to rotate. Adjust rheostat GWB until the motor ammeter A_m shows the proper rated full-load current for the motor. If the rated full-load current is not known, it can be approximately determined by multiplying the value of the rated horsepower by 746, and then dividing by the product of the rated voltage and an assumed efficiency, expressed as a decimal, of from 80 per cent. for small motors to 90 per cent. for large motors, or approximate input current equals rated horsepower × 746 ÷ assumed efficiency × rated voltage.

The voltage across the motor armature and its field coil should be approximately the rated voltage (usually 500 volts) when the rated full-load current is flowing through the motor armature, its field, and the generator field. The voltage across the motor armature and its field coil may be measured by temporarily connecting the voltmeter to the motor terminals (excluding the generator field).

34. The motor should be run under full-load conditions until the windings have assumed approximately normal temperature and the brushes have worn into good contact with the

commutator. Readings should then be taken of instruments A_m and V, with the switch S' in its upper position, and of A_g and V, with S' in its lower position. The reading should be taken as near the same time as possible, to avoid inaccuracies due to changes in the line voltage and load conditions. If two voltmeters are available, one may be used for the motor circuit and the other for the generator circuit, and all the readings taken at a given signal.

The product of the readings of instruments A_m and V (S' in upper position) is the total watts input to the motor-generator set. The product of the readings of instruments A_g and V (S' in lower position) is the total output of the set. The joint efficiency of the set is equal to $\frac{\text{total output}}{\text{total input}}$.

The efficiency of each machine is approximately the square root of the efficiency of the set, or $\sqrt{\frac{\text{total output}}{\text{total input}}}$. Since the motor and generator in this test are not working under exactly the same load conditions, the efficiency for each machine thus found may be slightly inaccurate; since, however, the efficiency of the motor changes but little for slight changes in load conditions, the results should be practically correct. The input current may be adjusted for partial loads, and the efficiency determined at these points. In Fig. 10 is shown a form of test sheet that may be used for this test.

ALTERNATING-CURRENT MACHINES

ALTERNATOR RUNNING-LIGHT TEST

35. Preparation for Test.—The losses in the armature and field of an alternator are of the same character as those in a direct-current machine; namely, friction losses, iron losses, and copper, or I^2R, losses for armature and field. The hysteresis and eddy-current losses are practically constant at all loads, while the copper losses increase as the square of the current and become large at overloads.

The simplest method of making an efficiency test on an alternator is to run it as a synchronous motor under no-load conditions, in order to determine the core and friction losses; then calculate the full-load copper losses for armature and field, thus obtaining the total losses, and, finally, calculate the efficiency from the relation between output and input.

36. Test Connections.—The connections for the running-light test are shown in Fig. 11. The three-phase alternator armature is shown at A, and its separately excited field at F. This is the conventional method of representing an alternator; revolving-field machines are now quite generally used. CB are circuit-breakers; S is the main switch connecting to the three-phase mains, and S' is the field switch connecting to the DC mains. To this latter switch, when opened, is connected a small resistance to take up the discharge of the field when the switch is thrown out. R is the field regulating rheostat; A_{fa}, the field ammeter; A_{fv}, the field voltmeter; A_a, an ammeter for measuring the current in one phase; W, an indicating wattmeter; PT, a potential transformer, used in case of high voltage; and ST, a series transformer, used in case of a large main current and also to prevent having high-tension wires on the testing table.

37. Conduct of Test.—The machine is started, synchronized, and thrown into connection with the *A C* mains, having the proper frequency and voltage. The field current is then adjusted until the armature current taken from the *A C* mains is of minimum value. The power factor under these conditions is nearly unity. The power expended on the



FIG. 11

armature is found by multiplying the indicating wattmeter reading by 2, since the load is a balanced one and the power factor is practically unity. It is presumed that the voltage of each phase is the same. This power represents the losses due to friction, hysteresis, and eddy currents, and these losses may, with little error, be considered as constant at all loads.

38. Copper Losses.—The copper loss for the separately excited field is equal to the product of the field current at full load and the voltage, under normal temperature conditions, across the terminals of the field coil, or to the current squared and multiplied by the hot resistance of the field. The reading of ammeter A_{fa} multiplied by the reading of voltmeter A_{fv} equals the copper loss in the separately excited field. The loss in the separately excited field rheostat is not charged to the machine. Owing to the demagnetizing effect of the armature current at full load, the full-load field current will be somewhat more than the field current obtained during the running-light test, but the effect of this increase on the efficiency calculations is practically negligible. If the machine can be run as a generator on full load, the field current may be measured, and this value can be used for determining the field copper loss. After the machine has attained its normal running temperature, the resistance of the field coils and the resistance between two armature slip rings, or terminals, of the same phase should be measured. If the resistances are measured when the machine is cold, they should be corrected for a temperature rise of about 40° C.

39. The full-load copper loss in the armature of a polyphase machine equals the product of one-half the hot resistance (or corrected cold resistance) from terminal to terminal and the square of the equivalent full-load current that would flow in a single-phase system. For a balanced two-phase circuit, the equivalent current is twice the current in any one of the four line wires. For a balanced three-phase circuit, the equivalent current is $\sqrt{3}$ times the current in any one line wire. The resistance of the three-phase armature should be measured between any two of the three terminals when the machine is hot, or the cold resistance should be measured and corrected for temperature rise. To obtain the armature copper loss of a three-phase machine, multiply the square of $\sqrt{3}$ times the rated full-load line current by one-half the hot resistance between any two terminals.

40. The total loss is the sum of the friction, hysteresis, eddy-current, I^2R field, and I^2R armature losses. The data may be tabulated on a test sheet of the general form shown in Fig. 4, but the sheet should be changed slightly to suit the altered conditions.

$$\text{Efficiency} = \frac{\text{rated output}}{\text{rated output} + \text{total loss}}$$

SYNCHRONOUS-MOTOR RUNNING-LIGHT TEST

41. The efficiency of a synchronous motor may be determined in a manner similar to that of the preceding test. The rated full-load armature current, which is usually stamped on the name plate of the machine, may be used when calculating the I^2R armature loss. The approximate value of field current is determined from the running-light test.

ALTERNATOR TEST WITH AUXILIARY MOTOR

42. Preparations for Test.—The following test requires that the alternator should be driven by a motor that is between 15 and 20 per cent. of the size of the alternator. To avoid a large amount of armature reaction in the driving motor, the motor-armature current should never be much greater than one-half of its normal full-load current. An exciter generator may be employed as a motor for this test. The direct current for the alternator field coils is obtained from another exciter or from a direct-current lighting or power line.

The motor pulley is belted to the generator pulley, and the size of the pulleys is so proportioned that the generator will run at its rated speed. It is advisable to use either a glued belt or one with a light lacing on the splice in order to prevent the ammeter needle from jumping when the splice passes over the pulleys. Belt tension should not be excessive.

In order to reduce armature reaction, the motor brushes should be set as near the no-load neutral position as possible

and still have sparkless commutation. The commutator should be run dry.

43. Test Connections and Test Sheet.—The driving motor and alternator connections are shown in Fig. 12. In addition to the alternator instruments shown in Fig. 11, voltmeter A_v, Fig. 12, is used. The wattmeter W, Fig. 11, may be omitted. In Fig. 12, the motor-armature ammeter



FIG. 12

is shown at M_a; the motor field ammeter, at M_{fa}; and the motor-armature voltmeter at M_v. R' is a rheostat for starting the motor and for adjusting the voltage applied to the motor armature; R'' is a motor field rheostat; M, the motor armature; and M_f, the shunt field of the motor. A form of test sheet suitable for this purpose is shown in Fig. 13 (*a*) and (*b*).

44. Open-Circuited Core-Loss Test.—The driving motor is started, and the alternator is brought to its rated

TEST SHEET

ALTERNATOR

Date_____

Tested by_____

Rating, 1,500 K. W. *Volts, 6,600.* *Amperes, Line, 131.* *Amperes, Field, 148.5.* *Speed, 180.* *Machine No. 1.*

266—25

OPEN-CIRCUITED CORE LOSS

Driving Motor								Generator							
Arm. Volts.	Arm. Amps.	Field Amps.	Arm. Res.	Arm. IE Watts	Arm. I^2R	$IE - I^2R$	Speed	Field Volts	Core Loss	Arm. Volts	Arm. Hot Res. Bet. Lines	Field Amps.	Speed	Friction Watts	
539	21.5	2.24	.069	11,589	32	11,557	755						180		
550	85.	2.24	.069	46,750	499	46,251	755	80	34,694	6,643	.378	139	180		
535.5	9.2	2.24	.069	4,927	6	4,921	755							6,636	

SHORT-CIRCUITED CORE LOSS

Driving Motor								Generator							
Arm. Volts	Arm. Amps.	Field Amps.	Arm. Res.	Arm. IE Watts	Arm. I^2R	$IE - I^2R$	Speed	Core Loss $+ I^2R$	I^2R	Core Loss	Arm. Amps.	Arm. Hot Res. Bet. Lines	Field Amps.	Field Hot Res.	Speed
539	21.5	2.24	.069	11,589	32	11,557	755								180
543	43.5	2.24	.069	23,620	131	23,489	755	11,932	9,739	2,193	131	.378	53.5	.58	180

FIG. 13 (*a*)

EFFICIENCY

Load, per cent. .	100	Core loss	34,694
Line volts	6,600	½ short-circuited core loss . .	731
Line amps. . . .	131	Armature I^2R	9,739
Field amps. . . .	148.5	Field I^2R	12,790
IR	43	Friction	6,636
$V+IR$	6,643	Total losses	64,590
		Output, K. W.	1,497
		Input, K. W.	1,562
		Efficiency, per cent. . . .	95.8

FIG. 13 (*b*)

speed, which should be maintained during the test. The field excitation of the motor should remain constant. The speed of the motor may be adjusted so as to have constant speed under different load conditions by varying the resistance in rheostat R', Fig. 12. Readings of the instruments should be taken only after the speed has been steady for at least 1 minute.

The motor is first made to drive the alternator without any current in the separately excited field circuit of the alternator. Then, readings of instruments M_v, M_a, and M_{fa}, Fig. 12, are taken. The resistance of the motor armature is determined immediately after this test, while the armature is still warm. The readings are then entered in the test sheet.

The number of watts expended on the motor armature is $539 \times 21.5 = 11{,}589$. The watts I^2R loss in the motor armature is $21.5^2 \times .069 = 32$ watts. $IE - I^2R = 11{,}589 - 32 = 11{,}557$ watts, and this power is expended in driving the motor armature and the alternator armature, with unexcited field, and in making up for core losses in the motor armature.

45. The alternator-armature resistance between terminals should be measured while the machine is hot, in case it can be loaded; or measured cold and an allowance made for rise in temperature; in this case, the resistance is .378 ohm.

The drop in voltage at full load, due to the ohmic resistance of the alternator armature, is equal to the line current multiplied by $\sqrt{3}$, and this product multiplied by one-half the resistance between any two terminals of the armature. For a single-phase or a two-phase armature, the drop equals the line current multiplied by the resistance between terminals of the same phase winding. One-half the resistance between terminals of this three-phase armature is $\frac{.378}{2} = .189$ ohm. The rated full-load line current multiplied by $\sqrt{3} = 131 \times 1.732 = 227$ amperes; 227 amperes $\times$ .189 ohm = 43 volts drop in the armature.

46. The separately excited field circuit of the alternator should now be closed. The motor is again started and drives the alternator on open circuit at rated speed. The field current of the alternator is so adjusted as to produce an electromotive force equal to the normal terminal electromotive force plus the full-load armature drop in volts, or $6,600 + 43 = 6,643$ volts. Another set of motor readings should then be taken, as well as readings on instruments A_w, A_v, and A_a.

The input to the motor armature minus the I^2R motor-armature loss is now 46,251 watts. Before the alternator field circuit was closed, the corresponding input was 11,557 watts. The difference between these values, 34,694 watts, is the core loss of the alternator on open circuit with full normal electromotive force plus the ohmic drop in volts in the armature. If desired, this test may be made for a number of different values of alternator-terminal electromotive force. A curve of core loss may then be plotted, using watts core loss as ordinates and terminal volts as abscissas.

47. The belt should now be taken from the pulleys, the motor run without load, readings of the motor instruments taken, and the input to the motor armature, minus I^2R armature loss, calculated. This is found to be 4,921 watts. The corresponding input when the motor was driving the unexcited alternator was 11,557 watts. The difference,

6,636 watts, equals the friction loss of the alternator. The friction loss is here considered as the combined bearing-friction and windage loss.

48. Short-Circuited Core-Loss Test.—In order to obtain data regarding the losses in the alternator, due to loading the machine, in excess of the open-circuited core loss, friction loss, and the calculated I^2R copper losses, a short-circuited core-loss test should be run. The motor is first operated to drive the alternator at rated speed with an unexcited field, and the motor readings noted. The terminals of the alternator armature are then short-circuited, as indicated at B, Fig. 12. The current in the separately excited field circuit is adjusted until the normal full-load current flows through the armature terminals. The motor readings and the readings of instruments A_a and A_{fa} are noted.

The power represented by the difference between 23,489 and 11,557 watts, or 11,932 watts, is expended in core loss and I^2R armature loss in the alternator; subtracting the I^2R armature loss leaves the short-circuited core loss. The whole value of the short-circuited core loss is much too great, since the armature current in this test is nearly 90° out of phase with the generated electromotive force and the armature demagnetizing action is excessive; therefore, one-third of this loss is often used in efficiency calculations.

49. If the alternator field current for full load is known, use this value in calculating the I^2R loss of the separately excited field. If the current is not known, use the square root of the sum of the squares of the field current, obtained in the open-circuited core-loss test at full terminal voltage plus the armature drop, and the field current, obtained in the short-circuited core-loss test at full-load armature current. In this case, $\sqrt{139^2 + 53.5^2} = 148.5$ amperes, approximately, in the field at full load.

The efficiency calculations may now be made from data obtained from the tests and from the calculated I^2R armature and field losses. These values should be set down in the test sheet, as shown in Fig. 13 (*a*) and (*b*).

INDUCTION-MOTOR TEST

50. Preparations for Test.—A simple test to determine the efficiency of an induction motor may be made, in which only one indicating wattmeter, an ammeter, and a voltmeter are required. The test connections for a three-phase induction motor are shown in Fig. 14. By means of the double-throw switch S', one end of the potential coil of the wattmeter W and one terminal of the voltmeter M_v may



FIG. 14

be connected to either line *1* or line *2*. The other end of the potential coil and the other terminal of the voltmeter are connected to line *3*, when switch S' is closed in either position. The current coil of W is in circuit with line wire *3*.

51. Conduct of Test.—At first the motor is run without load, and the number of watts required to drive it is noted. In the case of an induction motor, the current is out of phase with the generated electromotive force, the power

TEST SHEET

INDUCTION MOTOR

Running-Light Test

*Date*_____

*Tested by*_____

Rating, 5 H. P. *Volts, 110.* *Amperes, 29.* *Cycles, 60.* *Poles, 8.* *Speed, 900.* *Machine No. 1.*

Total Primary Input $W_1 \pm W_2$	Prim. Res. Bet. Lines	Prim. Amps. Per Lead	Prim. Copper Loss	Core and Friction Loss	Sec. Copper Loss	Rated Output	Losses	Input	Eff. Per Cent.
300	.156	10.4	25	275					
647	.156	29	197		450	3,730	922	4,652	80

FIG. 15

factor is less than unity, and two separate readings of the wattmeter, made in quick succession, are required. One reading is made with the potential coil across lines *1–3*, and the other reading with the potential coil across lines *2–3*. The sum of these readings will give the watts input if the power factor is over .5; if less than .5, the difference in the readings is taken. As explained in *Power Transformation and Measurement*, if the power factor is less than .5, one wattmeter will give a negative reading. The readings are recorded on a test sheet similar to the one shown in Fig. 15. When running without load, the power factor is low, one wattmeter reading is negative, and the difference between W_1 and W_2 is the total watts input.

The primary current may be measured by ammeter M_2, Fig. 14. The resistance of the primary winding between the lines is measured and recorded. The primary I^2R loss is calculated in the manner explained in the alternator running-light test for the alternator armature I^2R loss. Subtracting the primary I^2R loss from the primary input

leaves the core and friction loss, which may be considered constant at all loads.

52. Because of the construction of the rotor, its resistance cannot well be measured. In order to obtain an approximate value of the secondary copper loss, the following test may be made: Clamp the rotor so that it cannot turn. Reduce the electromotive force of the line by lowering the terminal electromotive force of the generator or by inserting equal resistances in the leads to the motor, so that full-load current flows through the primary windings. Take two readings as before, and note the total watts input. The power thus represented is mostly expended in I^2R losses in stator and rotor. Calculate the I^2R loss in the stator with the full-load current, and subtract it from the total watts input. The



FIG. 16

remainder is approximately the secondary I^2R loss. There are other small load losses involved in this value of total input, but they may be neglected without serious error.

The full-load current in this case is 29 amperes, and the primary copper loss 197 watts; the total measured input is 647 watts. Therefore, the secondary copper loss is 647 − 197 = 450 watts. The total loss is 197 + 275 + 450 = 922 watts.

53. The output at 5 horsepower is 3,730 watts, the input 3,730 + 922 = 4,652 watts, and the efficiency at full-load 80 per cent. Efficiencies at other loads may be determined by using different values of currents in the primary, when the rotor is clamped, and calculating the copper losses.

TEST SHEET

*Date*_____

TRANSFORMER TEST

*Tested by*_____

Rating, 7.5 K. W. Type, H. Cycles, 60. Primary volts, 1,040 – 2,080. Secondary volts, 104 – 208.

Prim. Amps. at 2,080 Volts	Prim. Res. Room Temp.	Prim. I^2R Watts	Sec. Amps. at 208 volts	Sec. Res. Room Temp.	Sec. I^2R Watts	Core Loss Watts	Total Losses Watts	Output Watts	Input Watts	Eff. Per Cent.
3.6	5.65	73.2	36	.0344	44.6	86.5	204	7,500	7,704	97.4

FIG. 17

TRANSFORMER TEST

54. The core loss of a transformer is obtained by connecting the secondary coil to a line having the *rated frequency* and the *rated voltage*, and measuring the input by means of a wattmeter when the primary is open-circuited. The core loss is practically constant at all loads. Fig. 16 shows the core-loss test connections.

The resistance of either the primary or the secondary coil, at room temperature, is determined by allowing direct current of known value to flow through the coil, and dividing the drop in volts across the coil by the current flowing in it. The windings should not be heated enough during the test to change their resistance. The core losses decrease somewhat with increased temperature, while the copper losses increase, so the resistances at room temperature may be used in the efficiency calculations. The I^2R loss in both coils may be computed for rated full-load current or for partial-load currents. The total loss, aside from some slight losses due to eddy currents in the iron core and in the copper conductors, is equal to the sum of the core loss, with primary open-circuited, and the I^2R losses in the primary and secondary coils. Fig. 17 shows the data of a test for a 7.5-kilowatt transformer.

SWITCHGEAR

INTRODUCTION

DEFINITIONS

1. Apparatus used for indicating, recording, controlling, or regulating the output, input, or distribution of electricity is referred to as **switchgear.** A switchboard may have mounted on it various kinds of measuring instruments, switches, fuses, circuit-breakers (commonly called breakers), signal devices, and rheostats; such switchgear is usually *direct controlled.* The use of large apparatus or high voltages may, however, require the location of some switchgear, especially circuit-interrupting devices, in places more or less remote from the switchboard at the control center from which, for reasons of convenience, they may be controlled electrically or mechanically; such apparatus is referred to as *remote controlled.* Controlling devices may require operation by an attendant or may be designed for automatic operation.

REQUIREMENTS OF SWITCHGEAR CONSTRUCTION

2. Safety.—By safety of switchgear is meant freedom from danger to operators or apparatus. Conductors under extremely high electric tension should be kept away from switchboards; the circuit-breakers, fuses, switches, etc. should be of such construction and so mounted as to avoid, as far as possible, the danger of arcs that may burn the operator or throw particles of hot carbon or metal upon him, and to avoid also the danger of arcs that may damage adjacent apparatus.

COPYRIGHTED BY INTERNATIONAL TEXTBOOK COMPANY. ALL RIGHTS RESERVED

3. Fireproof Construction.—The supporting structure, insulation, and all other parts of switchgear must be fireproof, in order to avoid the possibility of fires due to electric causes. For this reason, switchboard panels are usually made of marble or of some slate that is free from metallic veins. Insulation that is to be near parts likely to become overheated or that may be exposed to arcs must be capable of resisting high temperatures. Barrier construction made of asbestos board is sometimes installed between high-tension air-break switches and between high-tension busses for this purpose.

4. Capacity.—Knife-blade switches and circuit-breakers too small for their loads are subject to overheating, which draws the temper from the spring copper and makes the contacts poor, a condition that may cause further heating and permanent damage. If the air break of a switch or circuit-breaker is not long enough, an arc may hold across the opening and burn the contacts when the circuit is opened. Oil switches of insufficient capacity, either for current or voltage, may explode if opened under too heavy a load; therefore, they must have capacities far in excess of their normal loads.

5. Accessibility and Simplicity.—All switchgear requires some attention; instruments require calibration, fuses need replacement, and rheostats, switches, circuit-breakers, etc., require inspection, cleaning, and adjustment. In order to make such work safe and convenient, the devices should be readily accessible, but not so much so that at other times they may be a source of danger of physical injury.

Simplicity of construction and arrangement is an aid in operation and tends to reduce the liability of operating errors. The arrangement of the devices should be logical and uniform. Where there are several units of the same kind, as generators, motors, feeders, or circuits, uniformity of switchgear arrangement helps to avoid confusion.

GENERAL CLASSIFICATION

6. Switchgear is divided into two general classes: that suitable for use with direct current and that adapted to alternating current. The line of classification is not very sharp, as some apparatus may be suitable both for direct currents and low-tension alternating currents. Each class is capable of further subdivision into *circuit-opening devices*, *instruments*, *regulating devices*, and *lightning arresters*.

DIRECT-CURRENT SWITCHGEAR

CIRCUIT-OPENING DEVICES

KNIFE-BLADE SWITCHES

7. Circuit-opening devices are used wherever the conductors are to be made discontinuous quickly, conveniently, and, in some instances, automatically. Some of the devices in this class are also used for making the circuit, and all are used as a part of it.

8. Construction.—Knife-blade switches are used in direct-current circuits in capacities of from 10 to several thousand amperes and for all constant-voltage systems. In construction the jaws, or blades, of these switches bear some resemblance to the blade of a knife; each switch blade is hinged at one end and moves in a limited arc in one plane, so as to close into and open from a tight-fitting metal receptacle called a *clip*. Connection on one terminal of the switch is made to the stationary part of the hinge; on the other terminal, to the clip. The connections to these parts are made either on the front or the rear of the base, or panel, on which the switch is mounted. Practically all switches used in switchboard construction have a stud projecting back from each clip through the switchboard panel and another extending from each hinge block.

Electric connection is made to these studs on the back of the switchboard by means of wires, lugs, or copper bars held firmly in place between washers secured by one or two nuts on the studs, the whole being sometimes secured by a jam nut.

9. Varieties.—Knife-blade switches so made and installed as to open a circuit on only one side are known as *single-pole* switches. They may also be made for opening both sides of a circuit, in which case two knife blades are mounted side by side with the axes of their hinges lying in the same straight line and the blades fastened rigidly together by a suitable insulating material, such as dry wood or insulating fiber; switches of this form are designated as *two-pole*. Switches for use on three-wire systems are sometimes made for opening all three conductors at once and are known as *three-pole;* similarly, a *four-pole switch* can be used on a four-wire system.



FIG. 1

In addition to performing the duty of opening and closing one circuit, knife-blade switches may be so made as to be selective between two sources of supply or between two circuits. This is done by so constructing the switch that the blade moves through an arc of a half circle and installing a clip at each end of the arc. Such switches are designated as *double-throw* to distinguish them from *single-throw* switches. A single-pole, double-throw, three-blade switch is shown in Fig. 1.

10. Current Densities.—Knife-blade switches are usually made of hard copper or some of the copper alloys. When pure copper is used, the current density through the sliding-surface contacts of small switches may be as high as 80 or 90 amperes per square inch; if alloys are used, the current density allowable is even as much as 50 per cent. lower. In some switches of large capacity, several blades are arranged in parallel, as in Fig. 1, and heat radiation and air circulation are both increased. In

switches of this construction, the allowable current density through sliding-surface contacts is somewhat less, the amount of reduction depending on the number of contact surfaces that are partly enclosed.

Current densities allowable in the contact surfaces of connections to the switch are much higher; because the contacts, being secured firmly by nuts or clamps, instead of by the spring effect of the parts, have better conductivity. Connections between bar copper (draw filed) and cast-alloy nuts properly machined to provide a good surface may have a current density of 120 amperes per square inch. Between cast and machine-surfaced lugs and similar nuts about 110 amperes per square inch is good practice. Connections made with wire usually afford small contact surface unless the wire is flattened where it makes contact with the washers or nuts.

TABLE I

LENGTHS OF AIR BREAK FOR KNIFE SWITCHES

Voltage	Length of Break, Inches	
	100 to 500 Amperes	500 Amperes and Over
50–100	$1\frac{3}{4}$–$2\frac{1}{2}$	2–3
100–175	$2\frac{1}{2}$–3	3–4
175–300	3 –4	4–6
300–700	4 –6	6–8

11. Length of Air Break.—The length of air break necessary for knife switches depends on the current to be interrupted and the pressure tending to maintain the arc. In interconnected networks and other parallel systems the *back feed*, or tendency of parallel circuits to send a reverse current through a broken circuit, reduces to a comparatively small amount the pressure tending to hold the arc. But the back feed cannot always be depended on, and switches with sufficient opening to break a current at the full voltage of the circuit are customarily used. Table I shows lengths of air break that have been found to be good practice.

12. Quick-Break Switches.—Switches that may be required to break large currents at the higher direct-current voltages, 550 to 600, are sometimes made with a device for quickly separating the blade and clip as soon as the circuit has been opened. This construction permits the use of a switch with an air break shorter than would otherwise be desirable. The effect of slow separation of the parts is to cause the arc to hold; when the clip and blade are rapidly separated the effect of the arc is greatly reduced. Fig. 2 shows such a switch of a type in quite general use for street-railway feeders. The blade is in two parts; the main portion *a* carries the handle, and a quick-break portion *b* is held to the main blade by a strong helical spring *c*. Friction of the sides of the clip *d* holds the quick-break blade in place until the main blade has moved into the opening position far enough to put the spring under a tension sufficient to pull the quick-break blade out of the clip. As soon as the latter blade is released, the action of the spring pulls it away from the clip very rapidly.



FIG. 2

Another form of quick-break switch, Fig. 3, used for opening the field circuits of electric machines, is provided with a contact *a* in which the blade rests when the switch is open. The switch blade is in two parts hinged on a common axis and connected together by helical springs. When the switch is closed, the main blade *b* rests in the clip *c*; a downward pull on the handle stretches the springs and permits the other part of the blade to make contact with the clip *a* before the switch is completely open. Contact with clip *a* connects a discharge resistance across the field terminals, thereby preventing damage due to



FIG. 3

the high voltage induced in the exceedingly inductive field winding by a sudden interruption of the current. Because of the long, flaming arcs that occur when the current in a highly inductive field winding is broken, the knife blade has an *after break*, consisting of a carbon block *d* and carbon segments *e*, all renewable, between which the arc is formed and broken, thus preventing destructive burning of the more important and more expensive copper parts.

13. Mounting Knife-Blade Switches.—Knife-blade switches should always be mounted within such easy reach that the attendant will be able to exercise sufficient force for positive operation. The operation of knife-blade switches of very large capacity sometimes requires considerable physical effort, and for this reason they should not be mounted with their handles higher than a man's head.

Switches mounted on slate or marble must be set up tight by means of nuts on the studs; but the copper studs should fit loosely in the holes through the panel, because unusual heating may cause a stud to expand enough to crack the marble.

FUSES

14. Open Fuses.—To best perform its duty, a fuse should be of a metal that when fused will not deposit a large amount of molten metal on surrounding parts; it must have a resistance high enough that the passage of the predetermined current will heat it quickly to the fusing point, thus making the *time element* small; and it should present a minimum of surface to be cooled by stray drafts of air. For these reasons a fuse of metal with high conductivity made in small cross-section offers some advantages over those made of alloys with lower conductivities and of larger cross-sections, and copper fuses are quite generally used for breaking currents greater than 150 amperes. For smaller amperages, alloy fuses are generally



FIG. 4

used on account of the possibility of determining their rating, or fusing, current more exactly than can be done with copper fuses. In connection with low-tension generating and distributing systems, copper fuses are quite generally used; Fig. 4 shows three sizes of such fuses intended for use in a low-tension network where the back feed reduces the potential tending to maintain the arc.



FIG. 5

The length of a fuse must be such that when the metal is melted, and the metallic connection thus broken, the arc will not hold between the fuse-holder terminals. The distance between fuse-holder terminals *a* and *b*, Fig. 5, can be effectively lengthened by putting between them a barrier *c* of fireproof insulating material around which the arc will be forced to pass. The fuse *d* must not touch the barrier, otherwise the latter may conduct away a part of the heat generated in the fusible conductor and thus require a larger current to melt the fuse.

15. Enclosed Fuses.—A method of safely shortening the actual distance between terminals is to enclose the fusible conductor in a shell containing a fireproof non-conducting powder. When the fuse *blows*, or melts, the powder forms a flux with the metal, fills the gap in the conductor, and smothers the arc. Fuses of this form are called **enclosed, or cartridge type, fuses.**



FIG. 6

In order to avoid the necessity of testing to determine whether or not an enclosed fuse is blown, a *telltale*, or indicator, is generally put on the outside. This, in most cases, is merely a fuse of $\frac{1}{8}$ ampere, or less, capacity in parallel with the main fuse. When the enclosed fuse melts, the telltale fuse also blows and burns a small strip of paper pasted over it.

Enclosed fuses are made for currents up to approximately 1,000 amperes. In the smaller sizes, the brass terminals of the fuse are cylindrical, as in Fig. 6 (*a*), and fit into brass or copper clips that partly embrace them. In fuses for more than 75 amperes, the fuse terminal usually consists of a stout copper blade, Fig. 6 (*b*), that fits into a copper clip similar in form to the clip of a knife-blade switch.

CIRCUIT-BREAKERS

16. A **circuit-breaker** is an electromechanical device for automatically opening a circuit in the event of predetermined conditions, such as overload, low voltage, reversal of current, or excessive generator or motor speed. The simpler forms are constructed for automatic opening and manual closing; other forms are provided with controlling devices, such that, in addition to automatic opening, they can be closed and opened non-automatically by remote control at the will of the operator. Some hand-operated circuit-breakers are not built for the final closing of a circuit, and switches should be installed in series with them. Remote-controlled circuit-breakers can also serve as switches, and are sometimes installed without knife-blade switches in series with them.

17. Hand-Operated Circuit-Breaker.—A type of single-pole, direct-current, overload circuit-breaker for hand operation is shown in Fig. 7. Electric connections are made to copper studs *a* and *b* that terminate in large stationary copper blocks on the opposite side of the slate base *c*. The movable system of the breaker is pushed into the circuit-closing position by a lever system, and is held there against the opposition of stiff springs by the latch *d* that engages the handle *e*. The copper blocks are then electrically connected through one or more U-shaped, laminated, copper contacts *f* on the movable part of the breaker. Any iron close to the lower stationary contact-block becomes strongly magnetized by the flux established when current passes through the breaker. When the current reaches the value for which the breaker is set, the magnetism becomes strong enough to lift an armature *g* that, in rising, trips the

latch, releasing the handle and permitting the springs to bring the movable system to the open-circuit position shown in Fig. 7. A small handle on the armature provides means for tripping the circuit-breaker by hand.

The unhinged end of the armature is normally supported by the head of a threaded spindle *h* that can be raised or lowered by means of an adjusting nut, thus altering the position of the armature. The higher the normal position of the armature, the shorter is the lift necessary to trip the latch, and the less the tripping current. The spindle is set according to a scale graduated in amperes within the range of adjustment for which the circuit-breaker is designed.



FIG. 7

Some overload circuit-breakers, usually of smaller capacity than the type shown in Fig. 7, are provided with series coils of a few turns of heavy copper capable of carrying the entire current in the circuit. Inside the coil is an iron core that is lifted and trips the latch when the current reaches the value at which the circuit-breaker is set to open. The adjustment of this type of breaker is made by raising or lowering the normal position of the core inside the coil.

18. Arrangement of Contacts.—When the circuit-breaker shown in Fig. 7 is tripped, the main contacts open first, after which the current passes through auxiliary copper contacts to carbon contacts between which the final break takes place. One of the auxiliary stationary copper contacts *i* consists of a

small copper bar with its contact surface inclined to the vertical. The movable contact *j* leaves this bar immediately after the main contact opens. The lower parts of the contacts *k* and *l* are made of copper and attached to the main contacts by heavy copper shunts not visible in Fig. 7. The contact *k* is so hinged that the lower parts of contacts *k* and *l* separate before the upper parts, and the final break, or *after break*, is between the carbon blocks that make up the upper parts of the last-named contacts. The carbon blocks, which are cheap and easily renewed, thus sustain any damage due to arcing.

On some circuit-breakers of large size, the movable carbon after-break contact is so made as to hold against the stationary carbon until the copper parts have moved a considerable distance from the stationary copper blocks, and then to separate very rapidly from the stationary carbon, thus reducing the duration of the arc and the burning of the carbons.

The heat of the arc due to breaking a live circuit causes an air-current that blows the arc flame upwards. For this reason, circuit-breakers of the carbon-break type are always made with the carbon contacts at the top. For the same reason, such circuit-breakers should be mounted at the top of the switchboard; if installed separately, they should be so placed that other apparatus will not be close enough above to be injured by the heat of the arc.

19. Remote-Controlled Circuit-Breaker.—A type of single-pole, remote-controlled, electrically operated, carbon circuit-breaker, of the same general type as the hand-operated device previously described, is shown in Fig. 8. This circuit-breaker is closed by the magnetic action of a solenoid concealed in the housing *a*. When the closing switch at the control board is thrown so as to complete the control circuit through the solenoid, the plunger *b* is drawn down; this acts through a system of levers to close the circuit-breaker contacts, which are then held closed by a latch. When the closing switch is opened, the plunger is returned by the springs *c* to its normal position, where it will not interfere with the opening of the breaker when tripped. The breaker is opened either automatically by an

overload or by a trip coil that receives current at the will of the operator at the control board; in either case, the opening is brought about by springs after the latch has been tripped by the raising of an armature.

Some types of electrically operated circuit-breakers are closed by motors, but these differ from solenoid-operated breakers in mechanical details only.



FIG. 8

20. Low-Voltage Release. The low-voltage release is designed to open a constant-potential circuit when the voltage falls below a predetermined value, and consists of a coil of rather fine wire connected across the circuit. When the circuit is at or above the normal voltage, the coil receives sufficient current to maintain a magnetic flux strong enough to hold an iron core against the force of gravity. When the voltage is reduced to the tripping value, the flux is too weak to support the core, which then drops and trips the latch of the circuit-breaker. The device is adjustable by changing the height to which the core can rise in the solenoid.

Circuit-breakers used on 500- or 600-volt circuits generally have external resistances in series with the low-voltage release coils, in order that the coils themselves need not be designed to work on full voltage. The resistance may be mounted in any convenient place, but is generally placed on the rear of the switchboard panel and near the circuit-breaker, in order to shorten the wiring. The low-voltage release can be used on circuit-breakers with or without the overload release.

21. Reverse-Current Release.—One form of circuit-breaker intended for opening a circuit when the direction of current is reversed has in its base a solenoid with a movable core, or plunger, which, when the coil is energized, trips the latch of the breaker. Under normal conditions, this solenoid is not in circuit, but a reversed current of objectionable amount actuates a device that closes the circuit through the coil of a relay that connects the breaker-operating solenoid across the main circuit. In order to protect the breaker-operating coil, which is designed for momentary duty only, a small automatic switch, mechanically connected to the circuit-breaker, opens the circuit through the coil when the breaker operates. The operation and connections of this system are described in more detail in *Electric Substations*.

In some cases, circuit-breakers provided with shunt-operating coils are used for overload service. The breaker is then wired in practically the same manner as when operating on reversal of current, the difference being that the control device is arranged to close the circuit through the relay on overload current in normal direction.

Another form of reverse-current device is operated by a relay that shunts the low-voltage release, which is thereby deprived of nearly all of its current and operates as previously explained.

22. Speed-Limiting Circuit-Breakers.—A speed-limiting circuit-breaker is intended to open the circuit of a motor or synchronous converter when its speed becomes too great. A circuit-breaker having a low-voltage release attachment can be so wired that the operation of a speed-limit device will shunt the low-voltage release coil and thus reduce the current in it sufficiently to permit the core to drop and trip the breaker. The speed-limit device is mechanical in operation, employing a rotatable mechanism driven by the rotor of the machine to be protected. When the speed of the rotating mechanism exceeds that for which the apparatus is adjusted, the device, under the influence of centrifugal force, operates to open the main circuit by shunting the low-voltage release.

The form of circuit-breaker having a shunt-operating coil, as used with the reverse-current relay, can also be employed as a speed-limiting breaker by connecting the contacts of the speed-limit device so that they can close the circuit through the shunt coil.

DIRECT-CURRENT REGULATING DEVICES

STARTING RHEOSTATS

23. Starting resistances for large machines, such as booster motors and synchronous converters, in electric stations and substations are usually made of cast-iron grid units, Fig. 9, mounted in iron frames. Taps from such a resistance are connected to some form of starting switch by means of which the resistance can be short-circuited in steps. A multipoint knife switch is shown in Fig. 10 (*b*). The dotted lines in view (*a*) represent the various positions; as the blade is raised,



FIG. 9



FIG. 10

the clips are engaged, one by one, and the resistance is short-circuited, section by section, until in the vertical position of the

blade the entire resistance is cut out. The pawl *a*, Fig. 10 (*b*), prevents a too rapid notching up; after each movement of the blade, the operator must pause at least long enough to raise the pawl from a notch on the ratchet attached to a blade. The clip *b* has no electric connection; it serves merely as a buffer and as a rest for the blade when in the off-position.

FIELD RHEOSTATS

24. Field rheostats, used for the voltage regulation of generators and the speed regulation of direct-current motors, can be divided into three classes: the *series-resistance type*, *shunt-resistance type*, and *potentiometer type*.

25. The **series-resistance type of field rheostat** is represented diagrammatically in Fig. 11. The arrangement shown in (*a*) is objectionable, because if contact between the rotatable arm *a* and the contact points *b* or between the arm and the contact segment *c* should be broken, the field circuit would be opened. To avoid this difficulty, some series rheostats are connected as shown in (*b*); then if the arm fails to make contact, the field circuit remains closed, but contains all of the rheostat resistance. With the first scheme of connections, the rheostat arm must be wide enough to pass from one contact point to the next without breaking the circuit; with the second scheme the arm should be just as wide, in order to prevent the momentary



FIG. 11

introduction of the whole rheostat resistance into the field circuit each time the arm passes from point to point.

26. Field rheostats of the **shunt-resistance type,** Fig. 12, are used when it is desirable to be able to reduce the exciting current to practically zero. When the rheostat arm is in position *a*, the field winding is short-circuited; when in position *b*, the entire rheostat resistance is in shunt with the field winding; in any other position of the arm, part of the rheostat resistance is in shunt with the field winding and part in series with it. Here, also, the arm must be wide enough to bridge the gap between adjacent contact points, to prevent opening the field circuit.



FIG. 12

27. The **potentiometer type of field rheostat,** Fig. 13, a special form of the shunt type, has two arms *a* and *b* that move in opposite directions with respect to the resistance, although mounted on the same spindle and moving mechanically in the same direction. To permit such an arrangement, the contact points are cross-connected, as shown. By means of this type of rheostat, the field current can be lowered from maximum in one direction to zero, reversed, and raised to maximum in the other direction. Such rheostats are used for regulating the excitation of the fields of the series-synchronous-regulating generators of rotary converters and for varying the excitation of the regulating coils of split-pole rotary converters.



FIG. 13

28. Methods of Field-Rheostat Control.—Small field rheostats are usually mounted directly on the back of the switchboard, as shown in Fig. 14, and are operated by a hand wheel connected to the spindle bearing the contact arm of the rheostat. The rheostat shown in Fig. 14 is of *plate type*, and has three plates in parallel. The weight and bulk of grid type rheostats make it inadvisable to mount them directly on the switchboard; hand control must then be through a system of shafts and bevel gears, as in Fig. 15, or through a chain and sprocket wheels. A hand-operated rheostat should be so



FIG. 14



FIG. 15

mounted that the attendant either can see the position of its arm or can determine its approximate place by the position of the hand wheel.

29. When it is desirable to install a rheostat in a position to which mechanical operating devices cannot be conveniently run, the rheostat should be equipped for remote control. A **motor-operated rheostat** is provided with a small motor, usually series-wound, mounted on the rheostat frame and connected to the rheostat spindle through reduction gearing, as in Fig. 16, in which *a* is the motor and *b* the rheostat arm. The motor is controlled by a reversing switch at the switchboard.

30. Another form of remote-control device for field rheostats, Fig. 17 (*a*), has a ratchet wheel *a* mounted on the rheostat spindle. Motion is imparted to the wheel through two pawls *b* and *c*, one for each direction of rotation and only one of which operates at a time. A reciprocating motion is given to the pawls by the movement of a bar connected to the cores of two sole-



FIG. 16

noids *d* and *e* and to a spring. A pull by the solenoid *d* moves the pawls toward the left, and pawl *b* pushes the ratchet wheel through a small angle in a clockwise direction. Near the end of the stroke, an extension on the solenoid core engages an interrupter lever *f*, view (*b*), the movement of which opens the circuit through the solenoid and permits the spring (not shown) to bring the bar and pawls to the neutral position. This

action continues as long as the single-pole, double-throw, control switch *g* remains closed to the left. Similarly, by throwing the control switch to the right, the solenoid *e* can be made active and the rheostat arm rotated in the opposite direction, step by step. In Fig. 17 (*a*), the interrupter levers are concealed; in (*b*), the pawls are omitted. At the limit of its movement in either direction, the rheostat arm engages one of two switches *h*, which opens the circuit through the active solenoid, preventing any attempt to rotate the arm farther in that direction. The other solenoid can, however, be brought into action. The apparatus is thus automatically protected from injury due to leaving either control circuit closed too long. This device can also be used to adjust any remote resistance other than field rheostats, where automatic low-voltage and overload release features are not required.



(*a*)



(*b*)

FIG. 17

LIGHTNING ARRESTERS FOR DIRECT-CURRENT CIRCUITS

31. Theory of Lightning Arrester.—Protective devices are necessary to guard electric apparatus against abnormal rises of voltage due to oscillating static charges set up by lightning discharges in the neighborhood of a line, by switching operations, by sudden short-circuits on the line, etc. Apparatus on direct-current circuits is protected by connecting a choke coil *a*, Fig. 18, in series with the lead to each line wire and connecting each lead to the ground through a suitable discharge device, called a **lightning arrester,** at a point beyond the coil. The simple lightning arrester consists of a spark gap *b* in series with a non-inductive resistor *c* of high resistance. The choke coils are of sufficient inductance to keep violent fluctuations or surges of current from entering the station apparatus; the high-potential discharge is forced to take the non-inductive paths through the arresters to the ground. The spark gaps of the arresters are too far apart for the normal line electromotive force to send current across them under ordinary conditions; but the arcs caused by the high-tension discharges so reduce the resistance between the spark points that, were it not for devices that automatically reduce or extinguish the arc, as resistors *c*, the generator would be practically short-circuited and a disastrous after current would result.



FIG. 18

32. Arresters for Direct-Current Circuits.—Lightning arresters are made for direct-current general lighting and power circuits of 60 to 375 volts, for railway and power circuits of 250 to 2,400 volts, and for series arc-lamp circuits of 2,000 to 6,000 volts.

A type of arrester for use on constant-potential direct-current circuits is shown in Fig. 19 (*a*). The spark points *a* are mounted between two barriers on the cover. When the cover is in place, the contact clips on the spark-gap terminals engage with other clips in the back of the arrester case, thereby connecting the spark gap in circuit between the line and the ground, as shown in (*b*). The coil of an electromagnet *c*, called a *blow-out coil*, is shunted across part of the resistance rod *d*. The pole pieces *b*, view (*a*), of the magnet are extended so that the spark gap is between them. Part of the after current following a lightning discharge is shunted through the blow-out coil and sets up a magnetic flux that acts on the arc between the spark points. The arc, being a flexible conductor, is so distorted, or stretched, by this action that it breaks, or *blows out*. The gases from the arc escape through a hole in the casing.



FIG. 19

33. An example of the **horn-gap arrester,** so called from the shape of its spark terminals, is shown in Fig. 20. This type of arrester is used principally on series arc-lamp circuits,



FIG. 20

carrying either direct or alternating current. One terminal of one spark gap is connected to the outgoing line and one terminal of the other gap to the incoming line; the remaining terminal of each gap is connected through a resistance to the ground. The resistors and the shape of the spark terminals are relied on to extinguish the arc at the spark gap. The arc forms at the narrowest part of the gap, but is carried upwards by the rising air-currents due to the heat of the arc itself, until broken in a wider part of the gap, where, due to its increased length, the voltage is no longer able to sustain it. The resistors reduce the after current, as already explained.

In Fig. 21 is shown a form of choke coil used on street-railway overhead feeders. The coil is made of copper rod large enough to carry the full load of the feeder in which it is connected.



FIG. 21

34. Lightning-Arrester Ground Connections.—A well-recommended method of making a ground connection for a lightning-arrester installation is to drive a number of 1-inch iron pipes 6 or 8 feet into the earth surrounding the station and connect them by a copper wire or thin copper strip. To decrease the resistance, a quantity of salt should be

placed around each pipe at the surface of the ground, and the ground should be thoroughly moistened with water. It is advisable to connect the pipes to the iron framework of the station, and also to any water mains, trolley rails, etc. that are available. For the usual-sized station, it is recommended that three pipes equally spaced be placed near each outside wall and three other pipes spaced about 6 feet apart at a point near the arrester. This method of grounding is applicable to installations on either direct-current or alternating-current circuits.

ALTERNATING-CURRENT SWITCHGEAR

CIRCUIT-OPENING DEVICES

KNIFE-BLADE SWITCHES AND AUTOMATIC CIRCUIT-BREAKERS

35. Knife-blade switches of the types described under Direct-Current Switchgear are, without modification, suitable for use on low-tension alternating-current circuits. The current-carrying capacities of small knife-blade switches are the same for alternating current as for direct current; in the medium and large sizes, however, the skin effect is such as to cause a switch to become heated more by a given alternating current than by a direct current of equal amperage.



FIG. 22

A form of knife-blade switch for use on alternating-current circuits of voltages up to nearly 50,000 is shown in Fig. 22. These switches are usually mounted high on the board, in order to avoid the danger of personal contact and are operated by means of a long wooden pole with a hook in the end. The distances from the receptacle clip *a* to

the hinge clip *b* range from a few inches up to approximately 2 feet, depending on the voltage. These switches are not suitable for breaking heavy currents.



FIG. 23

36. Automatic circuit-breakers, such as are used for direct-current circuits, are, by slight changes, made suitable for use in low-tension alternating-current work. The changes consist of so winding the operating coil that, when alternating current is passed through it, the magnetic flux will be great enough to operate the tripping device. Alternating-current circuit-breakers must, in most cases, open all the phase conductors of a circuit together, and it is therefore common practice to have two- or three-phase circuit-breakers operated by one handle, as shown in the three-phase breaker of Fig. 23.

OIL SWITCHES

37. General Principle.—Knife-blade switches or air-break circuit-breakers are not suitable for use in high-voltage circuits on account of the long and dangerous arcs that are produced when large currents at high potential are broken in air. For such work **oil switches** are used. These are so designed that the actual electric circuit is made and broken under the surface of a high-resistance oil contained in a practically closed vessel. The weight of the oil and its cooling effect combine to smother the arc formed at the instant of breaking the circuit, and the actual length of the arc is reduced to only a fraction of what it would be if the opening were in free air. When the circuit is broken under oil, the arc, though greatly reduced in size, lasts through several cycles, becoming weaker at each alternation and finally being broken at an

instant when the current value is zero. The oil wells are usually made of cast iron or sheet iron lined with wood.

38. Arrangement of Contacts.—On potentials of 4,000 volts or over, it is common practice to open each line of a circuit in a separate oil vessel, or in a separate compartment of one vessel, and to open each line simultaneously in two places by arranging two sets of contacts in series. Fig. 24 shows a



FIG. 24

15,000-volt, 300-ampere, two-phase, oil switch with the oil well removed. Leads are brought to each pair of fixed contacts *a* through porcelain bushings *b* set into the cast-iron cover on the under side of which the oil well is supported. Each movable contact consists of two parts, a main contact *c* of heavy sheet copper brushes and a pair of auxiliary contacts *d* consisting of short, movable, copper cylinders held in place by helical springs. On opening the switch, the final break is at the auxiliary contacts, which take the arc. The movable contacts

are carried on wooden rods, which are caused to move up or down by the operation of a system of levers known as a *link mechanism.* In Fig. 24 the switch is shown in the open position.

The design of the contacts of oil switches is different in switches of various makes and capacities. Some large capacity switches not only open each line in two places but make each break in a separate oil vessel, the mechanism driving each of two vertical rods into a separate oil well, where contact is made inside of a split copper tube.

39. Manually Operated Oil Switch.—Oil switches are operated manually, electrically, or pneumatically. Manually operated oil switches are suitable for use on circuits over which are transmitted moderate amounts of energy. They are operated by a handle connecting through some form of link mechanism to the body carrying the moving contacts. For switches that are mounted on the backs of the switchboard panels the linkage is very short. When it is preferred to place the switches farther away, the link's length is increased and change of direction in their run are made by means of bell-cranks, as shown in Fig. 25.



FIG. 25

40. Control Switch.—Electric control of oil switches is obtained by means of direct current supplied to motors or solenoids. Electrically controlled oil switches are generally installed at some distance from the switchboard, which then bears only the control switch and the signal lamps that indicate

if the oil switch is open or closed and whether or not the operation of the mechanism is complete.

In Fig. 26 is shown a form of control switch used for the remote control of motor-operated oil switches and of some solenoid-operated switches. The handle is connected to the blade through a togglejoint *a*. Stops (not visible in the illustration) limit the motion of the blade so that it cannot open farther than the opening clips *b* or close beyond closing clips *c*. In hand operation, the togglejoint is kept straight. When used for automatic operation, the predetermined load conditions, such as overload, underload, low voltage, etc., are caused to operate a relay that sends current through a small solenoid in the rear of the switch. The solenoid drives a plunger *d* against the togglejoint, breaking the toggle and allowing the springs *e* to pull the blade into the opening position. The signal lamps *f* indicate to the operator whether or not the oil-switch movement is completed and the current supply properly cut off from the operating device.



FIG. 26

41. Motor-Operated Mechanism.—In Fig. 27 is shown a motor-operated oil-break switch mechanism. The direct-current motor *a* is connected through a magnetic clutch *b* to a worm-gear that rotates a crank forming one point in a *pantograph*, or straight-line, motion. The crank connects through a system of levers to arms *c* that carry vertical rods (not shown in Fig. 27) bearing the contact forks that make or break the main circuit. The vertical rods pass through the top of the concrete or brick structure forming the fireproof compartments in which are erected the oil tanks of the switch. Fig. 28 shows

the general arrangement of a complete three-phase switch, with the doors of the fireproof compartments omitted so as to reveal the interior of the compartments.

The motor starts the mechanism and causes it to pass a dead center, after which powerful coil springs drive the device, almost, but not quite, completing its movement. While the



FIG. 27

springs are operating the mechanism, the motor continues to rotate, but runs free. When the operation of the springs is complete, the motor engages the shaft through a mechanical clutch, completes the switch movement, and winds the springs to tension for the next operation. At this juncture, a cam

on the rotating shaft of the pantograph motion operates a cut-out master finger, which opens the control circuit and thereby causes the magnetic clutch to release. The master finger is held against the cam surface by springs.

A projection *d*, Fig. 27, that rotates with one of the speed-reduction gears catches on a projecting part of the mechanism if the switch, in opening, should continue its motion too far and begin to close, a condition that might result if the cam controlling the master finger were out of adjustment or if the mag-



FIG. 28

netic clutch should fail to release. The establishment of the control circuit operates a magnet that draws back the engaging projection during normal operation of the mechanism.

42. Solenoid-Operated Mechanism.—A type of large, solenoid-operated, oil switch is shown in Fig. 29. Powerful solenoids *a*, when energized by current in the control circuit, move iron cores *b* a short distance. The ends of the cores connect through sprocket chains to a system of levers carrying the contact-making parts, which are similar in design to those of the hand-operated switch shown in Fig. 24. The switch,

Fig. 29, is shown with the oil wells removed and without the brick or concrete barriers. One of the three oil tanks required for this switch is shown at *c* and its supporting pedestal at *d*. In addition to the pedestal support, the tanks are clamped to the casting *e*. Leads *f* and *g* of the large and small conductors are connected to the main and control circuits, respectively.

43. Pneumatic Operation.—Oil switches operated by compressed air are not used to as great an extent as those worked by electricity. The mechanism that has air for its operation is used where remote control is desired, but where direct current is not conveniently available.



FIG. 29

One type of switch mechanism put in action by means of compressed air is practically identical with machinery of the same type that has the solenoid for its operation except that the latter is replaced by a diaphragm arrangement actuated by compressed air. The air is controlled either by hand-operated or by electrically operated valves. Each switch is supplied from an auxiliary tank that receives air from a main storage tank. A compressor driven by an alternating-current motor furnishes the air supply.

44. Automatic Operation.—Oil-break switches provided with automatic devices for opening the circuit when the current

exceeds a predetermined amount are practically high-tension circuit-breakers. The primary of a current transformer is connected in the main circuit; the secondary is in series with the coil of a relay by means of which a direct-current circuit is closed through the operating device of the oil switch. Hand-operated oil switches with automatic release are provided with a spring-and-toggle arrangement; current through the solenoid, or trip coil, of the operating device raises a plunger that breaks the toggle and allows the spring to open the switch. In motor- and solenoid-operated oil switches the relay performs the same service as the control switch.

Some hand-controlled oil switches are operated without a relay, the secondary of the current transformer being connected in series with the trip coil of the switch. Switches of this kind do not require direct current for their automatic opening.

45. Example of Overload Relay.—An overload relay for use in connection with the operation of high-tension oil switches as circuit-breakers is shown in Fig. 30. A coil within the casing *a* is connected in series with the secondary winding of the current transformer and is designed to carry about 5 amperes at normal load on the main circuit. When the current in this coil exceeds the amount for which the relay is adjusted, a cone-shaped contact *b* is raised, by a movable core, into contact with two stationary fingers *c*, completing the circuit through the opening device of the oil-switch-operating mechanism.



FIG. 30

46. Time Element in Relay Action. Circuit-closing and circuit-opening relays are made in three types.

Instantaneous relays operate almost instantly on the occurrence of the condition, such as overload, that the relays are to control.

Inverse time-limit relays can be adjusted for a delay between the occurrence of an overload and the closing of the

relay contacts, the extent of the delay being approximately inversely proportional to the magnitude of the overload. When the type of relay shown in Fig. 30 is designed for inverse time-limit operation, the upward motion of the core with its contact-making cone is opposed by a small circular diaphragm, or bellows, within the casing at the top. On being pushed inwards by the core, the bellows forces air out through a set of narrow passages. The time required for the operation of the relay with any given current is regulated by adjusting the size of the air passages.

47. In the **definite time-limit type of relay,** the time limit is practically constant for any given setting under ordinary conditions of overload or short circuit. When adapted to definite time-limit operation, the relay just described has a compression spring interposed between the movable core and the diaphragm. In rising, the core compresses the spring and further motion of the core is prevented by a stop, making the relay practically independent of the amount of the overload; only the stored energy in the spring, if the overload continues, applies power to the diaphragm. If the overload comes on so slowly that the spring is not fully compressed at once, the time limit will vary slightly. If, therefore, the scheme of operation requires protection against a creeping, or comparatively slowly increasing, load an instantaneous relay is used to close the circuit through the solenoid of a definite time-limit relay.

48. Reverse-Current Relays.—In some cases relays are use to open the oil switch automatically when the direction of energy flow is reversed. Such a relay has two coils, one in series with the secondary of a current transformer and the other supplied from the secondary of a potential transformer. Ordinarily, the only force tending to move the contact-making part is that due to the difference of the magnetomotive forces of the two windings. When the energy flow is reversed, the force tending to move the contact-carrying device is that due to the sum of the magnetomotive forces. Reverse-current relays are made for instantaneous, definite time limit, or inverse time-limit operation.

HIGH-TENSION FUSES

49. General Features.—Although automatically operated oil switches are better for opening a circuit than fuses when any large amount of energy in the form of a high-pressure current is to be interrupted, the cost of oil switches sometimes leads to the use of high-tension fuses, which are made long, and on account of their small current capacity are small in cross-section. In order that the arc formed at the moment of fusing shall be interrupted, springs hold the fuse strip under tension, and, as soon as the metal becomes hot enough to be nearly melted, the springs break the fuse and rapidly separate the ends. In order to prevent the arc from jumping to near-by apparatus and to smother it as much as possible, the fuse and springs are nearly enclosed.



FIG. 31



FIG. 32

50. Examples of High-Tension Fuses. In one form of high-tension fuse construction the aluminum fuse strip, Fig. 31, lies between blocks of wood, as in Fig. 32, except at the part of narrow section where the blowing occurs. The blocks serve to prevent the arc from following the broken ends as they are pulled by the concealed springs.

51. High-tension fuses for use with a potential transformer of 6,600 to 60,000 volts are made to carry only a small current, usually not more than about ½ to 1 ampere. One form, Fig. 33, consists of a hard fiber tube, of a length adapted to the voltage of the circuit, bearing on the outside of one end a small metal ferrule and on the other end a brass bulb. The fuse wire is fastened by screws to the ferrule at one end and to the bulb at the other. The space within the bulb is an explosion chamber in which the fuse can blow. In order that the blowing will occur in the chamber rather than in the tube, the fuse

metal is smaller in cross-section in the former than in the latter. When the fuse blows, the explosion with the consequent expansion of the gases formed in the bulb, projects the arc out through the open end of the tube and opens the circuit. New fuses can be inserted into the holder, and a hook with a wooden



FIG. 33

handle is provided to remove the holder from the contact clips. The method of mounting this type of fuse on a potential transformer is shown in Fig. 34. The *expulsion fuse*, as the type is commonly known, with slight modifications in construction, is also used for other purposes.

52. Another type of high-potential fuse is made for use on circuits of 10,000 volts and higher. The fuse metal is held under tension by a spring, and both spring and fuse metal are immersed in an insulating and fireproof solution that fills a



FIG. 34

glass tube. When the fuse blows, the gap is immediately lengthened by the springs, which pulls the lower end downwards. In addition, the arc is immediately extinguished by means of the liquid in the tube.

ALTERNATING-CURRENT REGULATING DEVICES

53. The voltage regulation of alternating-current circuits is of such importance that an entire Section has been devoted to that subject. Therein are described apparatus that are logically classed with switchgear and would, except for their importance and the consequent space necessary for a proper explanation of them, be described here.

LIGHTNING ARRESTERS FOR ALTERNATING-CURRENT CIRCUITS

PURPOSE

54. Lightning arresters for use on alternating-current circuits are intended to protect the apparatus in the station or substation from high-frequency disturbances, either in the form of lightning or of high-frequency waves caused by surges or open-air arcs. They discharge high-frequency disturbance and prevent an unduly large potential from developing either between conductors or between conductors and ground, and they must prevent the current of the circuit from following the path of the high-frequency discharge to ground.

MULTIGAP ARRESTER

55. Action Across Gaps.—In Fig. 35 is shown a 2,200-volt **multigap arrester, with graded shunt resistance.** The arrester has thirteen air gaps between knurled cylinders of a special, so-called *non-arcing metal*, an alloy containing a metal of low boiling point and one of high boiling point. The cylinders act like plates of a condenser, each cylinder on being charged inducing a charge on the next. If the potential becomes high enough, the first cylinder discharges to the second by a spark across the air gap, and thus the second cylinder becomes charged almost to line potential; the next gap breaks down

and the discharge continues across the gaps successively to the grounded terminal of the arrester.

The line current follows the static discharge and jumps across the gaps, which now have a greatly reduced resistance. This action continues until the electromotive force passes through zero in reversing. Before the electromotive force can establish a reversed current, the arc vapor cools to a non-conducting state.



FIG. 35

An arrester with a series of small gaps discharges at a much lower voltage than an arrester with a single gap of a length equal to the sum of the small gaps. At the same time, there are enough gaps to insure the extinguishing of the arc that follows a discharge.

56. Action of Graded Shunt Resistance.—A resistance in series with the air gaps of an arrester may limit a static discharge to such an extent that an arrester with a series resistance will fail to give protection against a destructive rise of voltage under severe conditions. An arrester with graded shunt resistance, however, gives paths among which a discharge of any frequency can find a low-impedance passage to the


FIG. 36

ground. In the arrester shown in Fig. 35, for instance, one path—high resistance and two series gaps—is for discharges of low frequency or for discharging a gradual accumulation of

static electricity; a second path—low resistance and four series gaps—is for discharges of medium frequency; and a third path—gaps only— is for discharges of extremely high frequency. When the gaps of an arrester are shunted by even a low resistance, discharges of very high frequency (hundreds of thousands, or, possibly, millions, of cycles per second) find it relatively difficult to overcome the impedance of the resistance rods, but comparatively easy to pass across all the gaps, owing to the condenser effect.

The shunt resistances also assist in the prevention of arcing. It is shown by tests that whenever a number of gaps are shunted by a resistance of less than a certain ohmic value per gap, the dynamic current will take the path through the shunt resistance, even when the heaviest static discharges pass across the shunted gaps.



FIG. 37

57. High-Voltage Multigap Arrester.—High-voltage multigap arresters are made up of units, Fig. 36, in which the knurled cylinders are arranged diagonally in order to save space, for a high-voltage arrester requires a large number of gaps in

series. The cylinders are mounted on porcelain, which insulates them from one another. Units are connected together by short, metal strips.



FIG. 38

In Fig. 37 are shown the connections of a graded, shunt-resistance, multigap arrester for a 33,000-volt delta-connected, or ungrounded Y-connected, three-phase system. The fourth arrester leg, between the common connection of the other three legs and the ground, is necessary because without it, if one line conductor becomes accidentally grounded, the full line voltage will be thrown across one leg of the arrester. On a Y system with a grounded neutral, this ground leg is omitted because on such a system an accidentally grounded phase wire causes a short circuit of that phase and the arrester is relieved of the stress by the tripping of the circuit-breaker.



FIG. 39

An auxiliary adjustable gap *a* between each line wire and the corresponding arrester leg is necessary to take care of particularly severe abnormal conditions. Each auxiliary gap is short-circuited by a fuse *b*, so that it comes into service only when the fuse blows on account of an arc between phase wire and ground or because of some similar extremely severe continued stress. The sensitiveness of the arrester is also greatly

increased by a similar fuse *c* shunting an auxiliary adjustable gap and part of the main gaps of the ground leg. These fuses must be inspected frequently and replaced when necessary.

ELECTROLYTIC ARRESTER

58. The **aluminum-cell, or electrolytic lightning arrester** has the advantage of a very large discharge capacity, and can be made to discharge when the pressure on the lines has increased by only 10 or 15 per cent., thus protecting the apparatus against high potential due to surges, as well as to lightning. Aluminum-cell arresters can be installed either indoors or outdoors as may be most convenient, although they are recommended for indoor installation, as the electrolyte freezes at a temperature of about 20° F.

CHOKE COILS

59. **Choke coils** used on alternating-current systems usually have only a few turns, but these have impedance enough to choke back the high-frequency waves of a lightning discharge. For circuits operating at voltages up to 6,600, cylindrical coils of insulated wire mounted on a marble base are usually employed. For voltages above 6,600, bare wire wound into the shape of an hour glass, Fig. 38, is used. The flat spiral, or *pancake*, coil of Fig. 39 is made of insulated strip copper and has considerably more reactance than the other two forms.

THE ASSEMBLED SWITCHBOARD

DEFINITION AND GENERAL REQUIREMENTS

60. To be used most conveniently and effectively, the various devices comprising switchgear must be suitably arranged with respect to one another. Usually switches, relays, and instruments are mounted on slate or marble panels, in the rear of which are the copper busses, ties, machine leads, feeder leads, instrument leads, etc., connecting the several parts and devices of the generating and transmission system.

The combination of slate or marble panels, switches, instruments, busses, and instrument leads is referred to as the **switchboard.** The switchboard is the center from which the greatest part of the electric machinery of a station is controlled. The connections should be as simple and as easily traceable as the requirements will permit.

It is the general practice to set all of the panels in a straight line when there is sufficient space. Some instruments, such as voltmeters and synchronizing indicators, which must be observed when performing operations at various places on the switchboard, are put on *wing panels* set at an angle with the main line of the switchboard.

PRESSURE WIRING

61. Small wiring connected to instruments, control switches, relays, and the like, is sometimes called **pressure wiring.** Such wiring is generally mounted on the rear surface of the switchboard panels, where it is fastened in place by small fiber or hard-rubber cleats held by screws driven into wooden or lead plugs set in the marble or slate.

In pressure wiring, conductors with a considerable difference of potential between them may be placed side by side; it is therefore important that the conductors be well insulated, and it is desirable that the insulation be flame-proof.

DIRECT-CURRENT SWITCHBOARDS

ARRANGEMENT OF SWITCHGEAR

62. In direct-current switchboard design, it is better to have a separate switchboard panel for each generator or motor unit; if two panels per unit are required, they are usually placed side by side.

Circuit-breakers are put at the tops of the panels so that the arc which is formed when they open will not affect any of the other switchboard apparatus.

If heavy currents are carried on the busses, the switchboard instruments, unless provided with heavy magnetic shields, must not be placed in such positions as to be affected by the magnetic field around the busses. An instrument not heavily shielded magnetically should not be mounted nearer than about 6 inches from a bus carrying 400 amperes, 8 inches from a bus having a load of 1,600 amperes, or 14 inches from a bus carrying 2,500 amperes.

The switches are directly under the circuit-breakers, but far enough away so that flying particles of hot copper, or carbon from the latter may not be thrown into the faces and eyes of the operating men. The instruments are placed where they can be observed easily by the operator when he closes the switch.



FIG. 40

BUS-BARS

63. Copper bars used for direct-current busses are generally uninsulated, as it is impracticable to insulate all of the current-carrying parts, and to insulate some might lead to a false sense of safety.

Bus-bars should be supported at a distance of 8 to 12 inches in the rear of the panels and mounted on firm insulators set on brackets fastened to the structural-iron frame that supports the switchboard. If of a capacity as large as 3,000 amperes, the busses should be made of two or more wide thin copper bars spaced about $\frac{1}{4}$ inch apart, in order to give better ventilation and more surface for the radiation of heat than could be obtained by the use of one large, thick bar.

64. Air Circulation.—Air circulation between the individual bars of a bus is best when they are set on edge, as shown in Fig. 40. This method of setting busses is, however, objectionable for two reasons: The rear surfaces of panels are

rendered difficult of access for installing, repairing, or changing the small wires that are fastened to the panels; also, when busses of different polarity, or several busses of like polarity, but of unlike voltages, are together in the rear of the same panels, the distance between adjacent busses is rather small if the edgewise arrangement is used, thereby increasing the danger from short circuits. For these reasons, some engineers prefer to lay the bars flat, as shown in Fig. 41, compensating for the reduced ventilation by increasing the cross-sectional area of the busses.



FIG. 41

65. Current Density in Busses.—To prevent heating of the bars, the current density in copper busses should be rather low, especially if they are long, either continuous, or made up of sections firmly bolted together. Heating causes expansion, which puts undue stresses on the studs of switches and on the jumpers between them and the bus-bars. Bus-bars set on edge should not have a current density of more than 1,000 amperes per square inch of cross-sectional area; for bars laid flat, 950 amperes per square inch has been found to be the allowable maximum.

66. Joints in Busses.—A form of construction in quite general use for making joints in busses is to overlap the copper bars but not to bolt them. The bars are held in good electric contact at each joint by a three-cornered clamp set up by bolts. This method allows for expansion and contraction, and relieves a part of the stress on the jumpers and switch studs.

67. Separation of Busses of Unlike Polarity.—Busses of unlike polarity should be separated in such a manner as to make it difficult to start a short circuit by making an electric contact between them. When both the positive and the negative busses are on the same switchboard, the separation is sometimes made by putting all of the negative busses near the lower part and the positive busses near the top, as shown in Fig. 40. Sometimes the positive busses and switches are on

one switchboard and the negatives on another with an aisle between them.

The switchboard should never be set up so close to a wall that it will be difficult to work in the rear of it. The space between the wall and the busses should not be less than 3 feet, and a space of 5 feet is better.

ALTERNATING-CURRENT SWITCHBOARDS

DIRECT-CONTROL SWITCHBOARDS

68. Direct-control switchboards for alternating current are used in plants of small or moderate capacity (50 to 750 kilowatts) operating at voltages ranging from 240 to 3,000. The oil switches are usually secured to the back of the board, with the operating mechanism extending through the board to connect with the operating handle in front. The oil switch is usually supported on a bracket, either bolted directly to the slate or marble panel, or clamped to the framework, as shown in Fig. 42.



FIG. 42

The bus-bars are usually supported on porcelain insulators clamped to brackets near the top and in the rear of the switchboard. This location places the bus-bars out of danger and leaves room for the ready inspection or repair of the oil switches and their control mechanisms.

REMOTE-CONTROL SWITCHBOARDS

69. In stations of large capacities and greater voltages, instruments and relays are operated by the secondary currents from the instrument transformers instead of directly by current

from the main circuit, and the location of the main-circuit connections on or near the switchboard is unnecessary. Requirements of safety, space, fireproofing, etc. also make desirable the removal of high-tension apparatus and connections from the switchboard.

70. Mechanical Arrangement.—The simplest system of remote control is the mechanical arrangement shown in Fig. 25. The aisle between the switchboard and the oil switches should be wide enough for work to be safely performed on the switches or on the rear of the board. The bus-bars should be high enough to be out of reach, and high-tension leads from the oil switches should be insulated. Instrument transformers are usually mounted on the wall back of the switches.



FIG. 43

Sometimes, the switchboard is erected on a gallery overlooking the machinery and the oil switches and busses are installed on the machine floor, as in Fig. 43. A similar arrangement is used when the switchboard is installed on the main floor and the oil switches and busses are placed in the basement.

71. Electric Control. When the oil switches and the bus-bars are installed at a considerable distance from the switchboard, electric control of the oil switches is employed. Control current is carried from the direct-current operating busses on the switchboard to the oil switches, sometimes installed in a special switch room, through control leads, as shown in Fig. 44. The control leads are usually carried in conduit.

Direct-control and mechanically operated, remote-control switchboards are generally arranged with the generator oil switches and switchboard panels at one end of the busses and the feeder switches and panels at the other end; the switches are in line with the panels. In electrically controlled systems, also, the switchboard is conveniently arranged with the panels grouped together in exciter, generator, and feeder sections. The oil switches, however, need not be so grouped; that is, it is not necessary for all the generator switches to be placed at one end of the busses and all the feeder switches at the other. In some installations, this flexibility is of considerable advantage.



FIG. 44

72. Arrangement of Bus-Bars. Bus-bars are not always arranged in a horizontal plane, as in Figs. 25 and 43, and the bars are not always rectangular in cross-section. In one form of bus-bar construction for 4,000-volt circuits, round bars are wrapped with about ½ inch thickness of high-grade insulation possessing great dielectric strength. The bars are supported one above the other by wooden bushings secured to the vertical members of the steel frame that supports the oil switches.

In high-tension systems, the bus-bars are supported on large porcelain insulators and separated by brick, asbestos board,

or concrete barrier construction, as shown in Fig. 45. The



FIG. 45

advantage of separating the bus-bars in this manner is that it prevents the spreading of trouble due to a breakdown to ground and so confines the accompanying arc that it cannot reach the other bars. This form of cellular and barrier construction is not generally considered necessary on systems of voltages higher than 33,000, because at such potentials the current is limited and the arcs are not so destructive.



FIG. 46

73. Disconnecting switches, Fig. 22, are usually provided for opening the circuits between each oil switch and the busses, so that any oil switch can be isolated for cleaning and repair. In some cases, provision must be made for disconnecting the oil switch from the feeders as well as from the



FIG. 47

busses, as shown in Fig. 46. In high-tension systems the disconnecting switches are mounted on the outside of the walls enclosing the busses, and arc deflectors, or barriers, are often placed between adjacent switches.

74. Control-Board Panels.—Switchboards for electric-control systems are usually equipped with the control switches for operating the main switches; with signal lamps for showing whether the switch is open or closed and whether the operation of the mechanism is complete; and with indicating and measuring instruments for the circuits.

A *wall-type control-board panel* for a 4,000-volt system is shown in Fig. 47.

A form of control board especially suitable for large stations is the *bench board*, or *desk board*, shown in Fig. 48. By this form of construction the control switches are placed where they can be easily reached but cannot be knocked against by persons passing them, and the switches are so placed that all of them can be reached conveniently.



FIG. 48

ELECTRIC STATIONS

INTRODUCTION

NUMBER AND CAPACITIES OF UNITS

1. Location and Capacity of Station.—The location of the station is primarily one of the problems of distribution, but it is not always possible, or even desirable, to secure a station site near the load center, and it is sometimes necessary to adapt the distribution system, in some degree at least, to the location of the generating station.

The total capacity of the apparatus installed in the electric central station is determined after a careful study of the load, both existing and prospective, after which provision is made for the installation of machinery of sufficient capacity to meet the present load requirements with allowances for reasonable growth.

2. Number of Station Units.—The number of units advisable depends on the total capacity required, on the nature of the load, and on the relative importance of low first cost and low operating cost.

It is generally considered poor practice to install a plant of one generating unit. In some cases, considerations of expense have made this necessary; but, ordinarily, such an installation is undesirable, for the reason that any serious disability of one unit shuts down the entire plant. If two units are installed, each with a capacity of one-half the maximum load, the disability of one machine reduces the total capacity by only

COPYRIGHTED BY INTERNATIONAL TEXTBOOK COMPANY. ALL RIGHTS RESERVED

one-half; by safe overloading during short *peaks* (high loads) from 65 to 75 per cent. of the load may be carried by one unit. If three units are installed, each having a capacity equal to one-third of the load, the disability of only one may permit nearly, or, in some cases, all of the load to be carried through a short peak.

3. Economy of operation also requires a careful consideration of the probable daily load. Generating units, especially those driven by steam, are much more efficient when running at approximately full load than when lightly loaded; therefore, an attempt is generally made to install machines of such capacity that it will not be necessary to operate any of them very lightly loaded for any considerable time. On the other hand, small units are generally less efficient than large ones, so that it is not desirable to subdivide the capacity too far.

4. The foregoing considerations indicate the advisability of installing at least three machines. The importance of the service, however, may be such as not to warrant the increased expense of installing so many units, for one large generator is nearly always less expensive than two or three smaller ones aggregating the same capacity. The importance of security of service and the possible increase or decrease in operating economy, when using several machines, must be compared with the possible decrease or increase in economy and reduction of investment when using a lesser number of generators.

5. Similarity of Units.—It is desirable to have the units similar in size, design, and construction, in order to reduce the number and cost of spare and emergency parts that should be kept on hand. Interchangeability of parts is an important item in the design of a mechanical plant of almost any kind.

If the generating units to be used in any one kind of service are not alike in manufacture, it is important that they be sufficiently similar in electric characteristics as to give the same voltage regulation, and, if they will be required to operate in parallel, they must be sufficiently alike to permit parallel operation. Alternating-current generators must not only have correct speeds to permit parallel operation, but must also have

similar speed-regulating characteristics. If the alternators are to be belt driven, the necessary speed regulation can be secured by proper selection of pulleys. If the prime movers of alternators do not have similar speed-regulation characteristics, the generators will not operate in parallel, although, in some favorable cases, they can be connected together for brief periods for a transfer of load.

CONDUCTORS AND CURRENT DENSITIES

6. The electric conductors in a station must be of sufficient current-carrying capacity to prevent overheating. In the distribution system, the size of a conductor is generally determined by the allowable potential drop; inside the station, where distances are short, this consideration enters in a much less degree, for there the more important feature is the temperature rise of the conductors and its possible effect in detempering the spring parts of switches, overheating contacts at the joints, and causing expansion that may set up mechanical stresses in rigidly connected pieces.

Aluminum has, in some isolated cases, been used for electric conductors in stations, especially for the larger parts, such as busses, machine leads, etc., but its excessive expansion when heated and the difficulty of making good electric contacts on it have been factors in preventing its coming into common use for this purpose. Copper, on account of its high conductivity, and the ease with which it may be surfaced and soldered, is the metal most generally used in general electric construction.

7. For heavy bus-work, flat bars are in most general use; for small alternating currents, small, flat bars, or round, solid bars are suitable. If heavy alternating currents are to be carried, the skin effect may be so great as to make the use of tubular conductors preferable.

For machine leads and other similar work, stranded cable with a suitable insulating and protecting covering has been a favorite form of material. The reason is that it can be bought in one piece in any length that is likely to be needed in a station, and that it is already insulated and requires no elaborate form

of support in installation, as it can be laid in a cable trench or supported on brackets along a wall. Though more expensive to purchase than flat bar copper, cable is cheaper to install, and for low-tension work—that is, 600 volts and lower—the cost of the two, when installed, is about equal. Modern practice, in large installations of low-tension conductors, is tending toward the use of bare bar copper supported between suitable insulating materials with proper provision for avoiding short circuits.

8. In station construction providing good facilities for keeping conductors cool, a current density of 1,000 amperes per square inch of cross-section is allowable for copper conductors. Such a density will not cause serious overheating unless the conductors are unfavorably situated with reference to other apparatus liberating heat. In special cases, the current density is allowed to go as high as 1,250 or 1,400 amperes per square inch of cross-section without serious result.

DIRECT-CURRENT GENERATING STATIONS

RAILWAY STATIONS

GENERATOR CONNECTIONS

9. **Circuit Diagram.**—Generators for supplying current for railway service are nearly always compound wound and are connected with one terminal—usually the negative—grounded through the track system of the railway. The electric connections for two railway generators with series-field windings and equalizing connections on the negative side of the machines are shown in Fig. 1, in which *a* is a generator armature; *b*, a shunt-field winding; *c*, a series-field winding; *d*, a series-field shunt; *e*, the equalizer bus; *f*, the equalizer switch; *g*, a positive main-generator switch; g_1, a negative main-generator, or armature switch; *h*, a shunt-field rheostat; *i* and *j*, the series and shunt coils, respectively, of a watt-hour meter; *k*, an ammeter;

l, a circuit-breaker; *m*, the station voltmeter; *n* and *o*, voltmeter plug receptacles; *p*, the pressure bus, or common connection for the station voltmeter; *q*, an ammeter shunt.

Electrically, there is little difference whether the generators are compounded and equalized on the positive side or on the negative, as operation and performance are the same in either case. However, when equalizer switches are on the machine



FIG. 1

frame, or on a pedestal near by, the equalizing and compounding are preferably done on the negative, or grounded, side, as station attendants are then in less danger from personal contact with the live parts of the switches.

10. Generator Panel.—The front of a typical direct-current, railway, generator panel is shown in Fig. 2, which is

lettered to correspond to Fig. 1 wherever the same devices appear in both illustrations. The hand wheel h_1, Fig. 2, operates the contact-arm of the rheostat h, Fig. 1. The double-throw, single-pole, switch s, Fig. 2, controls the station lamps; its connections are not shown in Fig. 1, because the lamps are not an essential part of the railway circuits. A glass case t, Fig. 2, protects the watt-hour meter. The type of panel shown in Fig. 2 has no negative main switch, as the usual practice is to mount this switch on the machine frame. A field switch is shown at u.



FIG. 2

11. Equalizing Connections.—The function of the equalizing connection is to distribute the current output of the generators among the series-field windings in such a manner that the generators may all compound alike; therefore, the equalizer connection must always be made to the generator between the series-field winding and the collecting ring, or bus-ring, that is connected to the brush-holder studs. The equalizer connection must be of large cross-section and as short as possible, so that its resistance will be low. Resistance in equalizer connections tends toward the prevention of proper distribution of current among the series-field windings, in which case unequal compounding and unsatisfactory division of load among generators will probably result. Equalizing switches are, therefore, generally situated near the machines, either on small panels mounted on the side of the machine frames or on pedestals set close beside the machines. The equalizer bus, which is usually at practically ground potential, is run by the shortest path from one generator to another.

12. Adjustment for Proper Division of Load.—In order that two compound-wound generators operating in parallel may properly divide the load between them, the

potential drops in the series-field circuits between the equalizer connection and the bus-bar must be equal. If the resistance in the series-field circuit of one machine is too large, the series-field winding of that machine will receive less than the proper current. As a result, the compounding of that machine will be less than it should be; if the resistance is too low, the compounding will be too large.

Neither an adjustment of the series-field shunt nor a reduction of the resistance in the equalizing bus is effective in properly distributing the output current between the series-field windings when the relative resistances of the parallel paths between equalizer and main bus are not correct. The adjustment of resistance of these parallel paths is made either by increasing resistance of one of the leads or by decreasing that of the other. The increase of resistance is effected by inserting in the lead (in series) a short length of conductor of relatively smaller cross-section, care being taken not to reduce the size of the conductor to such an extent that dangerous heating would occur; sometimes the insertion of a German silver or an iron washer under a clamping nut at a joint is sufficient. Decreasing the resistance is done by inserting additional copper in parallel with the lead already installed.



FIG. 3

13. Shunt-Field Connections.—As shown in Fig. 1, the wiring of the generator is such that the shunt-field circuit cannot be opened by the use of any of the switchgear. This is a common and desirable form of connection for it makes impossible a destructive short circuit through the armature that would result if, by any mistake, an operator should open the shunt-field circuit of the generator while it is operating in parallel with other sources of direct current.

Some engineers, however, consider provision for opening the shunt-field circuit desirable. Then a special form of field switch and a field-discharge resistance are connected as shown

in Fig. 3. The field switch consists essentially of a main blade *a* and an auxiliary blade *b* rigidly held at an angle to each other and turning together on the same hinge. Just before the main blade leaves its clip, the auxiliary blade makes a contact that short-circuits the shunt field through the discharge resistance *c*. The purpose of the field-discharge resistance is to afford a path through which the stored energy in the field may be discharged. The high electromotive force that would otherwise be generated by self-induction when the field circuit is opened may thus be avoided. In Fig. 2 the field switch is shown at *u*.

INSTRUMENT EQUIPMENT

14. The instrument equipment of the usual railway-generating station consists of a station voltmeter, an ammeter for each generator, and, generally, when there is more than one generator, a totalizing ammeter connected in the bus-bar between the generator panels and the feeder panels to show the total current output of the station.

15. Ammeters are of the shunt type and in some cases all or a part of the copper run between the machine terminals and the switchboard is used for the ammeter shunt, but it is more general practice to use the regular form of alloy shunt installed on the back of the switchboard between the knife-blade switch and the circuit-breaker.

16. Individual **integrating wattmeters**, or **watt-hour meters**, for each machine are sometimes installed on the generator panels and connected in the positive lead of the generator between the machine terminal and the knife-blade switch. Although somewhat more subject to accidental damage than if it were higher, the watt-hour meter is preferably placed near the bottom of the panel because it is there favorably situated with reference to electric contacts, vibration, or presence of stray magnetic fields. When the generator is shut down, both the series and shunt circuits of the wattmeter are either dead or at earth potential. The positive end of the potential circuit of the wattmeter is connected to the positive

lead of the generator at the armature switch. The negative terminal of the potential circuit may go directly to the negative pressure bus of small size (No. 12 B. & S. wire) in the rear of a switchboard, or it may be run back to the generator and connected to the negative lead of the machine, as shown in Fig. 1.

17. The station voltmeter is wired so that it may be connected to the main busses, or to the leads of any generator. The change of connection is made by means of a plug that fits into a receptacle, one of the contacts of which connects to the voltmeter and the other to the leads of the generator, as *n*, Fig. 1, or to the main bus, as at *o*. There is a separate receptacle on each generator panel, and, in order to observe the voltage of the generator, the plug is inserted in the receptacle on the panel of that particular machine. The positive voltmeter connection to the generator leads is made on the machine side of the knife-blade switch, because then the generator voltage can be observed before the switch is closed. The station voltmeter is usually supported on a bracket that can be swung out from the switchboard to such a position that the instrument can be observed from any panel; it therefore does not show on the panel, Fig. 2.

SWITCHES AND CIRCUIT-BREAKERS

18. The main positive armature switch *g*, Figs. 1 and 2, is so situated that its handle will be about as high as the waist or chest of a man of ordinary size, a position in which it can be most easily and conveniently operated.

19. The circuit-breaker *l*, Figs. 1 and 2, is situated at the extreme top of the generator switchboard panel. The space for a distance of about 4 feet above the circuit-breaker is kept clear of any grounded metal work, switchboard instruments, switchboard framework, or anything else that might be injured by the arcs. In order to protect the switchboard panel from the destructive effect of arcs, the circuit-breakers, especially in the larger sizes, have a fireproof shield of thin fibroid on each side, also, in the rear of the contacts and between

them and the switchboard panel and also projecting above the panel in such position as to prevent the arc from burning the switchboard or communicating to the supporting steel framework. The circuit-breaker is operated on the occurrence of overload or low voltage, by means of tripping devices. As the pressure of the circuit is much higher than the 60 to 100 volts ordinarily required for energizing the low-voltage release coil, it is necessary to secure the lower voltage drop through the solenoid by inserting an external resistance, not shown in Fig. 1. This is mounted in the rear of the switchboard panel near the circuit-breaker. The supply for the low-voltage release coil is taken from between the knife-blade switch and the circuit-breaker, so that when switch *g*, Fig. 1, is open, it is necessary to close the circuit-breaker, in order to obtain current for the release coil.

In some cases, an alarm bell is provided to ring when the circuit-breaker is open. The alarm-bell circuit is closed by a plunger that is thrown out when the circuit-breaker opens. In order that the bell may not ring when the breaker is intentionally left open, a small switch is placed in the alarm circuit.

FEEDER CONNECTIONS

20. Direct-Current, Railway, Feeder Panel.—The switchboard of a direct-current, railway station has two main divisions, generator panels and feeder panels. The latter bear the switchgear necessary for the feeders that carry current from the positive bus—which extends the entire length of the switchboard and which receives current from the generators, as shown in Fig. 1—to various sections of the railway line.

The connections of a typical railway feeder panel are shown in Fig. 4. The feeder connection to the bus is made through a short length of copper that connects to the upper terminal of the feeder circuit-breaker *a* situated near the top of the panel.

The knife-blade switch *b* is situated on about the same level as the knife-blade switches on the generator panels. The switch may either be arranged with a quick-break connection or without it. The most recent practice has been to omit

the quick-break feature; the feeder circuit can be quickly opened by tripping the low-voltage release on the circuit-breaker. The knife-blade switch then becomes merely a disconnective device and is not much used for interrupting the current.

The ammeter shunt *c* is connected in the lead between the circuit-breaker and the knife-blade switch, as is also the choke coil *d*. The lightning arrester *e* is connected on the feeder side of the knife-blade switch, and, in some installations, is mounted on the rear of the panel near the floor; in other installations, the arresters are isolated from the switchboard.

The voltmeter plug receptacle *f* is connected between the pressure bus and the feeder side of the knife-blade switch to allow of the trolley voltage being read before closing the switch in cases where feeders are interconnected or continued to other sources of power.



FIG. 4

21. Auxiliary Bus.—Circuit-breakers on railway feeders are required to open under heavy overloads and short circuits and are subject to severe service. This results in an occasional burning of the contact parts and the necessity of making minor repairs at more or less frequent intervals. In order to provide for taking circuit-breakers and ammeters out of service for such repair work without interrupting the output on its feeder, the knife-blade switches are sometimes made double throw, their lower clip being connected to an auxiliary bus that is joined to the main distributing bus through a circuit-breaker and a knife-blade switch. This connection also has an ammeter, and the auxiliary bus connection can be used by simply closing its circuit-breaker and knife-blade switch and throwing the knife-blade switch of the feeder down to the auxiliary switch clip.

22. Booster Feeders.—Sometimes the very long feeders have low voltages at the ends distant from the station, although the pressure on the remainder of the system may be fairly good. Too high bus-pressure is objectionable, because motors near the station may then be burned out or otherwise damaged. In such cases, boosters are sometimes connected in series with the long feeders that require a voltage somewhat higher than that of the main bus. The booster, itself, is an auxiliary motor-driven generator and the voltage it generates is added to the voltage of the main generators.

The booster generator may be either shunt or compound wound, but is more generally compounded to provide for the extra length of the feeder, the machine generators being compounded only for a moderate length of feeder, and the booster generator for the additional length.

23. Leading Out Feeder Cables.—The method of leading out the feeder cables is generally dependent on the type of line construction used. If the distribution system is placed underground, the cables are led out of the station building through conduits or ducts leading in through the basement wall. There is a possibility of a breakdown of the insulation between the conductor and the grounded lead cable sheath of underground distributing cables with resulting arcs. For this reason, it is undesirable to group closely together a large number of cables without some fire-resisting cover around them for protection against the destructive effects of such arcs. Installations of underground cable, therefore, should be covered with conduit or cement up to the point where they are separated sufficiently to remove the danger of injury from an arc or burn on an adjacent cable. When they are installed on cable racks in such fashion that the cables are separated by about 6 or 8 inches, there is little danger from this source; but in order to lessen the danger, the lead cable sheath is generally discontinued at the point where the cables enter the cable rack.

ARRANGEMENT OF SWITCHBOARD PANELS

24. If one ammeter (totalizing ammeter) is to show the total output of the station, all the generator switchboard panels are placed at one end of the board and the feeder panels at



FIG. 5

the other, as indicated in Fig. 5. The shunt for the totalizing ammeter is then installed at *a*, so that the instrument indicates all the current output of the station. In many cases, where it is desirable to lead feeder cables out of the station by two routes and, at the same time, have a systematic arrangement of switchboard panels and outgoing feeders, generator panels are installed in the central portion of the switchboard and feeder panels on each side of them as indicated in Fig. 6. By this arrangement, the operator is obliged to observe two ammeters



FIG. 6

in order to determine the total output of the station, but this is not usually an inconvenience serious enough to interfere with the most consistent and suitable layout of feeder panels.

DIRECT-CURRENT, LIGHT AND POWER STATIONS

CLASSIFICATION

25. Generating stations for distributing direct current for light and power are of two general kinds: Those using shunt-wound generators and those using compound-wound generators. Compound-wound generators will not operate satisfactorily in parallel with storage batteries, and therefore shunt-wound generators are used in stations employing batteries either for assisting in pressure regulation or for emergency or peak-load service. If no storage batteries are used, compound-wound generators, on account of their superior voltage regulation, are generally employed, especially if the load is fluctuating. Shunt-wound machines require much more frequent attendance with fluctuating loads than do those that are compound wound.

SMALL, TWO-WIRE PLANTS

26. Generator Connections.—Small, direct-current, light and power stations are not usually provided with storage batteries and therefore generally have compound-wound generators. The amount of compounding is adjusted to regulate the voltage for some representative point in the distributing system, so that the best average result in pressure throughout the system will be obtained.

Fig. 7 shows a wiring diagram of two compound-wound generators connected to a two-wire, direct-current system. In this installation, neither of the machine terminals are grounded and both of the machine leads are brought to the switchboard and led through knife-blade switches *a* and circuit-breakers *b* to the busses. With reference to the kind of protective device preferable for such installations, engineers are at variance; some favor fuses on account of their lesser expense, while others prefer circuit-breakers because of their more reliable operation; each form is in quite general use. One circuit-breaker for each machine is the usual practice for the protection of generators

on two-wire systems; when fuses are used, one is generally installed in each generator lead—two for each machine.

27. The wiring diagram shows an equalizer connection *c* that is necessary when two or more compound-wound machines are installed, but unnecessary if there is only one unit. When two generators are to operate in parallel, one equalizer switch *d* is necessary; with more than two generators in parallel one equalizer switch is installed for each machine. In this diagram, the compounding and equalizer connections are shown on the



FIG. 7

negative side of the generator; they can be on either side, if the system is ungrounded, but the connections should not be on the same side as the circuit-breaker.

Both polarities of the machine have their armature switches *a* on the switchboard, so that the generators can be entirely separated from the conductors of the distributing system.

The installation shown in the wiring diagram has a short shunt; that is, the shunt field *e* is connected on the armature side of the series-field winding, which gives fewer joints at which the shunt-field circuit could be accidentally opened. So

far as the performance of the machine is concerned, it is immaterial whether a long or short shunt is used. Each shunt-field circuit contains the usual rheostat *f*, and each series field *g* is usually provided with an adjustable shunt *h*.

28. Instrument Equipment.—The instruments for a small direct-current station usually include an ammeter *i*, Fig. 7, for each unit and one station voltmeter *j* with a multiple-point voltmeter switch (plug and receptacles *k*) by which the instrument connection can be switched to the busses, or either set of machine leads. In some cases, pressure wires are run back from the feeder ends at the distributing centers and terminate at the multiple-point voltmeter switch, so that it is possible for the operator to observe the pressure at important feeding centers. This, however, is rather uncommon in the smaller stations and is done only when pressure regulation is of extreme importance. In some installations, a totalizing wattmeter is installed between the generator panels and feeder panels, and sometimes individual watthour meters are installed on the leads of each generator unit.

SMALL, THREE-WIRE SYSTEMS

29. Three-Wire System With Two Compound Generators.—The simplest method of supplying a three-wire system consists in the use of two generators, each supplying from 110 to 125 volts, connected in series between the two outside conductors, and with a common connection to the neutral, as shown in Fig. 8 (*a*), in which the various parts will be recognized from a knowledge of preceding diagrams. The connections shown in Fig. 8 (*b*) differ from those in (*a*) only in the arrangement of the neutral leads and switches. This is the oldest form of three-wire system, and is still used to some extent where the unbalanced load is large.

For parallel operation, two equalizer busses are necessary; one for machines connected to the negative main bus, and the other for those connected to the positive main bus. With an ungrounded system, it is immaterial on which side the machines

are compounded and equalized. However, when the neutral of the three-wire system is grounded, as is frequently done, equalizing and compounding the neutral side of each generator results in putting the equalizing switch at practically ground



FIG. 8

potential, and thus confines to the switchboard those switches which are not at earth potential.

The instrument equipment for such an installation does not differ from that of the two-wire station, except that a voltmeter

is required on each side of the system. The voltmeter connections are not shown in Fig. 8.

30. Derived Neutral With Balancer Set.—On account of the expense of providing two generators for use on three-wire systems where one of twice the capacity would be cheaper and sufficient for carrying the load, various forms of derived neutrals have been resorted to.

One device for providing for unbalanced loads, and one that automatically adjusts itself to considerable changes of load, is an **equalizer, or balancer, set,** consisting of two small



FIG. 9

dynamo units *a* and *b*, Fig. 9, exactly alike, mounted on the same shaft or, in some cases, belted to each other. The balancer units may be either shunt or compound wound, according to whether they are used in parallel with shunt- or compound-wound generators. The machine *a* connected between neutral and positive conductors (referred to as the *positive machine*) has its shunt field *c* connected between the neutral and negative conductors of the system, while the current for the shunt field *d* of the negative machine *b* is taken from the neutral and positive conductors. The result is that when the voltage of either side becomes high, the armature of the machine connected

to that side is supplied with a relatively high potential, but its field winding, being supplied from the low-pressure side of the system, is made weak, a condition that causes the machine to speed up as a motor. The other machine, under the reverse condition, has no tendency to speed up, but is driven as a generator by the motorized machine, and so constitutes an addition to the generating capacity on the lower voltage side. Thus the balancer acts as a medium of transfer of generating capacity from the lightly loaded to the heavily loaded side of the three-wire system.

The balancer set is started with one of the machines operating as a direct-current motor, the other acting as a generator on open circuit. When up to speed and voltage, the generator end is paralleled to one side of the system. The machine that starts as a motor is provided with a suitable starting box *e*, Fig. 9. Field rheostats *f* are used in connection with the balancer to regulate the speed and to provide for unbalancing the bus pressure, if such unbalancing becomes necessary, in order to obtain the proper pressure at the feeding centers.

31. If the main generator supplying the load is provided with circuit-breakers, the balancer set should also be supplied with a circuit-breaker in series with each machine and made electrically or mechanically interlocking with the one on the main generator so that when the main generator circuit is opened the balancer circuit also will be opened. This results in shutting down the balancer set, but is necessary because the balancer armatures must be disconnected before the bus is again energized; otherwise, the balancer will be severely damaged. Instead of mechanically or electrically interlocking circuit-breakers, the balancer set is sometimes provided with those having low voltage release coils, so that the opening of the circuit-breaker on one generator, while other generators remain connected to the bus, will not disconnect the balancer set unless the bus is killed, or deenergized. The ammeter in the neutral must have a two-way scale, with the zero mark in the center.

32. Derived Neutral With Three-Wire Generator. The essential features of one scheme of wiring for a three-wire generator are shown in Fig. 10. The generator has two series-field windings *a*, and therefore two equalizing busses are necessary for parallel operation. In order that the full output on either side of the machine may act on the protective devices, the fuses or circuit-breakers *b* are installed, as shown, in the circuits between the brushes and the equalizer busses. If the circuit-breakers were between the series fields and the main bus-bars and two or more generators were operating in parallel, the current tending to open a breaker might be either greater or less than the actual output of the machine, and the protective action would be unreliable. Owing to the current in the equalizer connection, the currents in the series field and the armature are not always the same.



FIG. 10

33. By the arrangement shown in Fig. 10, the equalizers are at the pressure of the outside main busses (except for the drop through the series-field windings), and the pressure of the machine must be fully built up before it is connected in parallel with a generator already running. For this reason the switching equipment is such that the series fields of the two machines can be energized before the armatures are connected, the

sequence of switching operations being as follows: Start with all switches and breakers open; throw in the series fields by closing the two double-pole main switches *c*; when the machine voltage is properly adjusted, close the circuit-breakers, one at a time (one pole at a time, if a double-pole breaker is used); close the neutral switch *d*.

34. The compensator winding *e*, Fig. 10, is of rather small capacity and is intended to carry only the difference between the currents on the two outside conductors, which, in a well-balanced system, is comparatively small. In order that the opening of the circuit-breaker on one side of the system may not throw the entire load of the other side of the machine onto the compensator, the positive and negative circuit-breakers of each machine are mechanically or electrically locked together, so that the opening of one necessarily opens the other also.

With a three-wire generator, it is the usual practice to use two ammeters *f*, Fig. 10, and, like the circuit-breakers, they must be connected between the armature and equalizer, in order that, when two or more generators are operating in parallel, they may measure only the actual current output from each. The station voltmeter *g* is connected to the usual pressure busses and can be made to indicate the machine voltage by inserting the plug into the receptacle *h*.



FIG. 11

35. If a three-wire generator is provided with either fuses or circuit-breakers, the shunt field *i*, Fig. 10, must be connected on the armature side of them, in order to avoid the opening of the shunt-field circuit when the protective devices act. If the field connections were such that the protective devices were to open the shunt-field circuit, there would be induced in the field winding a very high electromotive force, which might be

sufficient to puncture the insulation. The usual shunt-field rheostat *j* is provided.

A three-wire generator panel for a small, direct-current plant is shown in Fig. 11, which is lettered to correspond with Fig. 10, except that in Fig. 11, the letter *j* represents the shunt-field rheostat handle instead of the rheostat itself.

BUSSES AND FEEDERS OF SMALL, DIRECT-CURRENT PLANTS

36. The bus-bars of the switchboard of small, direct-current, lighting and power plants are usually mounted on insulating supports carried on brackets from the switchboard supporting framework. The connections between the busses and switches or circuit-breakers are flat copper bars bent to suitable shape and fastened in place by machine bolts.



FIG. 12

The feeder switches are on the front of the board. In the two-wire system, double-pole, single-throw, feeder switches are in general use. In small plants, it is general practice to install cartridge fuses on the front of the board immediately under or over the switches, as shown in Fig. 12, which represents a six-circuit, two-wire, feeder panel.

In stations connected with three-wire systems, all three busses are generally mounted in the rear of the switchboard panels. However, in some systems with grounded neutrals, the neutral bus is mounted on the wall near the point where the feeders leave the building, and the neutral conductors of the feeders start from this point.

On ungrounded three-wire systems, it is the more common practice to install the positive, negative, and neutral switches and fuses on the feeder switchboard. Sometimes, the neutral conductor is protected by a fuse as heavy as that in either of the outside conductors, and, sometimes, with a fuse of only one-half the size of the positive or

negative fuses. There is considerable difference in opinion as to the proper size of neutral fuses and both forms of practice are common.

In small stations, circuit-breakers on the feeders are not very common, unless the kind of service is such as to cause frequent overloads. The practice of installing ammeters on feeder circuits does not generally prevail in small plants of the type that are being considered.

MEDIUM-SIZE, DIRECT-CURRENT, LIGHTING AND POWER PLANTS

37. Generator Connections.—Medium-size, direct-current, lighting and power plants, especially if feeding a territory of moderate extent, are generally connected to three-wire systems.



FIG. 13

Fig. 13 shows the connections of a station in which most of the energy is generated by 220- to 250-volt machines *a* and *b* connected to the positive and negative (outside) conductors

of the system; smaller 110- to 125-volt series-connected generators *c* and *d* take care of the unbalance in load. Such a station, generally, has two sets of the lower voltage units, one operating while the other is shut down for maintenance or repair work; all the other units are 220- to 250-volt generators, on account of the smaller cost per unit of power for the larger machines.

Circuit-breakers, ammeter shunts, and shunt-field rheostats are indicated at *e*, *f*, and *g*, respectively, in Fig. 13; the switchboard is also provided with the usual station voltmeter and plug receptacles.

38. Busses and Feeders.—On account of the larger territory covered and the greater length of feeders, as compared with a small plant, there is some difficulty in keeping a good average pressure over the entire system of a medium-size plant. Those feeders that terminate near the station should therefore either be supplied with a lower voltage than that furnished to distant feeding centers or should have smaller cross-sectional areas than the long feeders to make a uniform fall of potential throughout the system. The latter alternative is uneconomical and, besides, introduces a risk of seriously overheating some of the conductors. If short feeders carrying large currents are installed, care should be taken to check the safe current-carrying capacity of the feeder with the full-load current that is transmitted.

The more general and preferable practice is to provide two separate sets of busses supplied by generators of different voltages. The generators and feeders are provided with double-throw switches to make the switching selective between the two different busses, which are kept at pressures suited to the requirements. In some cases, the entire supply is delivered to one bus from which another bus of higher potential is supplied through a series-booster generator that increases the pressure by a desired amount.

The instrument equipment of feeder panels in the medium-size plants is usually somewhat more complete than that in the smaller stations and includes an ammeter for each feeder.

LARGE, DIRECT-CURRENT, CENTRAL STATIONS

39. Generator Connections.—Direct-current, central, generating stations in large cities usually have storage batteries in parallel with the generators. In such stations, shunt-wound generators are employed, because the voltage characteristics of compound-wound machines render them unsuitable for operation in parallel with storage batteries. Some large stations use compound-wound generators and no batteries, and these differ from the medium-size plants chiefly in size and not materially in the system of connections.

Like the medium-size plants, large direct-current stations for lighting generally supply three-wire distribution systems. Most of the modern installations have three-wire generators.



FIG. 14

Others have one or two sets of 110- to 125-volt generators, *a* and *b*, Fig. 14, for supplying the unbalanced load, and the remainder of the generating capacity in the form of 220- to 250-volt sets, *c* and *d*, usually direct connected (mechanically) to their prime movers. The connections of shunt-wound generators, Fig. 14, are simpler than those of compound-wound generators, as indicated in Fig. 13, neither series-field winding nor equalizer connections being required for the shunt-wound machines.

40. Neither circuit-breakers nor fuses are shown in Fig. 14. These are sometimes installed, though they are not common in large city plants, especially if several large stations feed into

one common network distributing system. To protect the small apparatus with circuit-breakers and fuses and to leave the large and more costly generators entirely without automatic protection appears inconsistent; but a shunt generator, on account of its armature characteristics, requires little protection—if a short circuit occurs, the voltage drops to zero, thus providing instant and automatic protection. In addition, if two or more large stations are feeding into one system, the operation of protective devices in one station would probably lower the system pressure, overload the other station, and automatically shut it down. If this should occur, considerable difficulty might be experienced in getting the system alive again, the trouble increasing with the number of stations supplying the network. For these reasons the modern tendency is, in large stations, to install no protective devices on the shunt generators; dependence is placed on the feature of automatic protection inherent in these machines.

41. Busses and Feeders.—In large, direct-current, lighting and power stations, generators and feeders are nearly always made selective in switching between at least two busses, in order to provide for multiple bus operation to improve the distribution; three or more busses may be installed in some stations.

In some large systems the outgoing feeders are not fused at the switchboard, on account of the danger that might result from the severe blowing of fuses and the possibility of starting an arc that might communicate to other parts of the switchboard and do serious damage. In such systems, it is common practice to install fuses at the feeder end out on the line and to open the feeder switch at the station when the feeder ammeter shows indications of a ground or short circuit outside. Then the current sent by the back feed from the network distributing system into the ground or short circuit, if the trouble is between the station and the distant feeder end, must necessarily pass through the feeder-end fuses. If the current is sufficient to blow the fuses, the faulty cable is thereby isolated from the network system.

42. Instruments.—In a large, direct-current, central station there is, of course, an ammeter on each generator panel. Also, on account of the more exacting requirements in distribution—and, therefore, in the detection of unusual conditions, especially on the network distributing system—it is a general practice to install an ammeter on both the positive and negative conductors of each feeder. These not only indicate the load on any particular feeder end, but serve to indicate the existence of trouble, as short circuits or grounds, on the feeder cable itself. In large systems where the load is growing rapidly and where the feeders are interconnected, the load that each feeder carries must be known, in order that it may not become overloaded by the growth of the business in that particular section, and feeder ammeters are therefore essential.

Correct regulation of the pressures at the different feeding centers is a matter of extreme importance, and voltmeters, one for each side of the three-wire system, are installed in the station and connected to pressure wires that come back from important feeding centers. Usually, there is selected one feeder, called a *standard feeder*, that is considered representative of the feeders connected to any particular bus; when the pressure at the end of the standard feeder is correct, all the feeders supplied from the same bus are considered to have a good average pressure condition at their ends. Usually, one standard feeder is selected for each bus in operation. The voltmeters are provided with a selective switch arrangement, such that they may be switched from the pressure wires to the bus. Recording voltmeters are sometimes installed for the purpose of giving graphic records of the pressures at the feeding centers at all hours of the day, so that the operating engineer may know how efficiently the pressure regulation throughout the system has been carried on.

ALTERNATING-CURRENT STATIONS

PARALLEL OPERATION OF ALTERNATORS

43. Alternating-current generators, designed for the same pressures, frequencies, and similar wave forms, can be operated in parallel, but with somewhat more difficulty than direct-current units. If the alternators are of unlike design and construction or if the driving power of one has different speed regulation from the prime movers of the others, this difficulty is greatly increased, and may be sufficient to make parallel operation undesirable, or even impossible.

If the polarity of one of two direct-current generators normally connected in parallel is reversed with respect to the other, that is, if the negative terminal of one is connected to the positive of the other and the positive terminal of the first to the negative of the second, the result will be a short circuit in which the voltage will be the sum of the pressures of both generators and the resistance will be the sum of the resistances of the two armatures and the conductors connecting them. A short-circuit of the same character exists when the electromotive forces of two alternators connected in parallel are 180 electrical time-degrees out of phase with each other.

As the polarity of an alternator is reversing with every alternation, if another alternator is to operate in parallel with it, the second, in order to have its instantaneous polarity the same as that of the first, must be reversing its pressure at the same time, and each of the terminals that are to be connected must be alive with positive or negative potential at the same instant. When this condition exists, the electromotive forces of the alternators are said to be in *synchronism* and *in phase* with each other.

44. For the proper paralleling of alternators, three conditions are necessary: The electromotive forces should be alike or nearly so; the machines must be running nearly in synchronism

before the paralleling connection is made; the electromotive forces must be in phase with each other at the instant that the parallel connection is made. Immediately the alternators are connected in parallel, the second requirement changes to that in which the units must be in perfect synchronism.

The reason for the first requirement is to avoid a heavy flow of cross-current between machines after paralleling; for the second, so that the incoming machine can get into phase with the running machine; and for the third, to avoid serious injury to the armatures and possibly, also, to the engines, if each generator were to short-circuit the other. Perfect synchronism, after paralleling, is necessary to prevent the generators from falling out of phase, or out of step, which would cause a short circuit.

Alternating-current generators, driven by synchronous motors, are not subject to speed control for paralleling, and the steps to be taken to get them into phase with each other are treated in another Section. The condition of parallel operation is fairly stable, for, if one tends to increase slightly in speed, it takes a larger part of the load, which pulls it back in phase; or, if no load is connected, it motorizes the other generator, thus equalizing the phase relations of the two.

45. Observations to determine the proper phase relations between alternators to be paralleled can be made by the use of synchronizing lamps, by a voltmeter connected in parallel with synchronizing lamps or a special resistance, by a voltmeter properly connected between pressure leads from the machines, and by means of the synchronizer, or synchroscope. Of these, the lamps are the least reliable and the synchronizer, or synchroscope, is the best.

SYNCHRONIZING CIRCUITS

SYNCHRONIZING WITH LAMPS

46. Synchronizing With Lamps Dark.—The most common device for indicating synchronism is a circuit containing one or more incandescent lamps properly connected between the sources of the electromotive forces that are to be tested for synchronism. The simplest case is the synchronizing

connections of a pair of low-voltage (110-volt), single-phase alternators connected to mutual busses, as in Fig. 15. The alternator *a* is assumed to be supplying energy through the switches *b* to the bus-bars. The alternator *c* is assumed to be generating an electromotive force, but with its armature switches *d* open. The circuit between the two alternators is complete through the synchronizing lamps *e*. If the electromotive forces of the two machines differ widely in phase, even though equal in value, cross-currents passing between the alternators will cause the lamps to glow. If the alternators are exactly in synchronism, the electromotive forces will at each instant, except the instant of reversal, be in opposition to each other, and, if equal in voltage, no current passes through the lamps, which then remain dark. In practice, the switches *d* are closed when the machine *c* has attained approximate synchronous speed, as indicated by the lamps *e* changing slowly from brightness to darkness; the switches are closed in the middle of a dark period, and the alternators then bring each other into exact synchronism automatically. When synchronizing machine *a* with machine *c* lamps *f* are used.



FIG. 15

47. Synchronizing With Lamps Bright.—Because there is a comparatively wide range of voltage over which lamp filaments will not glow, the absence of a glow does not accurately indicate the condition of no difference of potential between terminals of the switches *d*, Fig. 15, and, consequently, synchronizing with dark lamps is somewhat uncertain. If the

lamps are connected as shown in Fig. 16, which is lettered to correspond to Fig. 15, the electromotive force tending at any instant to send current through the lamps *e* is not the difference, but the sum, of the electromotive forces of the generators at that instant. Because a change in pressure of a few volts makes a considerable change in the brightness of a lamp that is already glowing at approximately normal brilliancy, and a like change near the zero value of the voltage produces a smaller change in brightness, many engineers consider the method of Fig. 16 the more reliable form of connection. In addition, the possibility of the lamps burning out during synchronizing operations and thus being dark and giving an indication of in phase relations when the electromotive forces are really out of phase is urged in favor of bright-lamp synchronizing connections. The operation of synchronizing with lamps bright is the same as the dark-lamp method, except that the alternator switches are closed in the middle of a period when the lamps are burning brightest.



FIG. 16

48. Synchronizing-Lamp Connections for High-Voltage Single-Phase Machines.—The simple forms of connections just described are not suitable for use with high-voltage generators. By wiring enough lamps in series, synchronizing could be performed with lamp circuits connected to the generator leads, but the number of lamps required would be very large and the high voltages carried by the synchronizing circuits would be dangerous to the operator. Pressure, or potential, transformers, are always used to obtain low voltages

for the synchronizing circuits of alternators generating more than 300 volts.

In Fig. 17 are shown the connections for synchronizing high-voltage, single-phase alternators to the bus-bars. The synchronizing lamps are connected between the low-voltage winding of the potential transformer *a* and the synchronizing busses *b*. The high-voltage winding of a potential transformer *c* is connected across the leads of each alternator between the armature terminals and the armature switches; the low-voltage windings of these transformers are connected through plug receptacles *d*



FIG. 17

to the synchronizing busses. Inserting the plug switch in the synchronizing receptacle on the panel of a generator to be started completes the connections for synchronizing that generator with the main busses. By connecting the potential transformers with proper attention to polarities or by selecting a plug switch with the proper connections, the lamps can be arranged to indicate synchronism when dark or when bright, as desired.

49. The potential transformer connected to the leads of the running generator can be used to supply a low pressure

to the synchronizing circuit, as in Fig. 18; but some engineers consider that there is some advantage in synchronizing to the bus-bars, as in Fig. 17, instead of to another machine. With more than two alternators, two plugs, or sets of synchronizing switches, are necessary when synchronizing with a machine already in operation, one plug to connect the synchronizing lamps to the potential transformer of the running machine and the other to connect them to the transformer of the starting machine. Even in large stations, however, it is not uncommon to install connections so that generators are synchronized by means of pressure transformers connected on machine leads only.



FIG. 18

50. Synchronizing Circuits for Polyphase Alternators.—If one phase of a polyphase alternator is in synchronism with one phase of another alternator, the other phases will be



FIG. 19

in synchronism—provided, of course, that the machines are properly connected. Synchronizing circuits are, therefore, connected to only one phase of polyphase alternators. Fig. 19 shows two methods of connecting synchronizing circuits to three-phase, Y-connected generators with grounded neutrals. In (*a*), the connections are made between one phase conductor and the neutral; in (*b*), between two phase conductors. Generators with delta-connected armature windings are synchronized by means of potential transformers connected across corresponding phases of each machine, as in Fig. 20. The synchronizing connections of two-phase generators, also, are made across corresponding phases of each machine. In Figs. 19 and 20, the synchronizing plug receptacles are not shown. As with single-phase machines, the lamps can be connected to indicate synchronism, either when dark or when bright.



FIG. 20

Polyphase machines can also be connected so as to synchronize to the bus-bars, as shown for the single-phase machines in Fig. 17, in which the single-phase conductors can be considered as one phase of a polyphase system.



FIG. 21

51. Grounded Synchronizing Circuits.—In many installations, the secondary windings of all instrument transformers are grounded on one side to a small copper bus-bar that runs around the station and to which the

return circuits of instruments are connected. By taking advantage of the ground bus, the wiring of synchronizing circuits can be simplified considerably, as shown in Fig. 21.

SYNCHRONIZING WITH VOLTMETERS

52. Simple Connections.—Synchronizing lamps can be regarded as only approximately reliable. In order to obtain an indicating device that can be relied on, the station alternating-current voltmeter is sometimes connected in place of one of the lamps. The indication of the instrument at synchronism



FIG. 22

will be either zero or double the voltage of the potential-transformer secondary pressures, according to the system of connecting the transformers. Another method is to connect the voltmeter in parallel with one of the synchronizing lamps, so that the instrument will show the fall of potential through the lamp.

The voltmeter, when used to show the in-phase relation by its zero indication, is almost as unreliable as an incandescent lamp, because the scale of an alternating-current voltmeter is very fine near the zero point, a considerable change in voltage being required to move the indicating needle a distance that

can be observed. Therefore, the instrument should always be connected for showing the in-phase condition by a reading of double potential.

53. Woodbridge System.—The indication of synchronism by a double-potential reading of a voltmeter, also, is somewhat unreliable; the pressure changes at the times immediately preceding and following the in-phase relation are small in comparison with the changes in phase. To obviate this difficulty, a scheme of connections applicable to three-phase systems has been devised by J. E. Woodbridge. The method is to apply to the voltmeter the resultant of two alternating electromotive forces differing in phase by 60°. By this scheme, the voltmeter is supplied with an electromotive force that has a relatively rapid change at the times immediately preceding and following the in-phase condition. The method is shown in elementary diagram, without the details of instrument switching connections, in Fig. 22, in which *a* is the voltmeter, *b* a ground connection, and *c* a single-pole plug receptacle.



FIG. 23

SYNCHROSCOPE CONNECTIONS

54. Like lamps, a voltmeter cannot indicate the amount of phase difference between two electromotive forces, nor can it indicate which is leading in frequency. For paralleling alternators of comparatively large capacity, synchronism indicating

devices more accurate than voltmeters are considered necessary, and modern stations are therefore equipped with synchroscopes, or synchronism indicators.

A type of synchroscope constructed on the electrodynamometer principle is described in *Alternating-Current Measuring Instruments*. Another instrument, also of the electrodynamometer type, more nearly resembles a synchronous motor



FIG. 24

with field winding excited by alternating current. The armature is of the split-phase type with two coils *a*, Figs. 23 and 24, arranged on a rotatable core at an angle of 90° (mechanically) from each other. The phase splitting is effected by the use of a divided circuit, one branch of which contains a resistance *b* and the other a reactance *c*. The armature windings receive currents

nearly 90 electrical time-degrees out of phase with each other and are supplied by the electromotive force of the starting machine; the field winding *d* is supplied with current by the electromotive force of the running machine. If the frequency of the armature currents is the same as that of the field current, there will be no tendency of the armature to rotate. Any difference in the frequencies, however, causes rotation—one way, if the incoming, or starting, machine is too slow; the other way, if it is too fast. If the two electromotive forces to be synchronized have the same frequency but differ in phase, the pointer of the synchroscope remains in a position indicating the phase difference.

Synchroscope connections with pressure-transformer secondaries grounded are shown in Fig. 23, and Fig. 24 shows connections for transformers not grounded.

With the synchroscope, the necessity of causing the running machine to supply the field of the instrument and causing the incoming machine to supply the armature requires the use of two different plugs, one of which, when connected to the terminals of a receptacle, will cause the field circuit to be excited and the other to make the armature circuit of the instrument alive. Synchronizing lamps *e*, Figs. 23 and 24, are sometimes used in conjunction with a synchroscope. The connections can also be arranged so that the incoming machine is synchronized to the main bus-bars.

SMALL ALTERNATING-CURRENT STATIONS

EXCITER AND ALTERNATOR CONNECTIONS

55. Exciter Generators.—The connections of the apparatus of an alternating-current station are more complex than those of a direct-current plant, for the former must have, in addition to the alternators, one or more exciter sets, the connections of which are almost as complete as those of a direct-current station.

An exciter generator is of small capacity, the amount of energy required for field excitation of an alternator being

generally not more than about 2 per cent. of its own rating. Thus, if a 75-kilowatt alternator were installed, the energy required for its excitation would be not more than 1½ kilowatts; but in practice, such small machines are not used for exciting purposes, and even in a small installation an exciter generator of from 3 to 5 kilowatts capacity is employed.



FIG. 25

The exciter generator can be either shunt or compound wound, and there are many installations of each kind in regular operation. The load of the exciter is not changed, except when the station attendant is at hand to regulate its potential. Usually, also, no part of the exciter circuit leaves the station;

therefore, the exciter system is not especially liable to short circuits, which would affect the pressure regulation. There is, then, no very important reason why the exciter generator should be compound wound.

56. Single-Phase Connections.—The alternators of a small station may be single-phase, two-phase, or three-phase. The most modern stations, if supplying any power load, are three-phase, and generally with the armatures star wound in preference to delta wound, as the star winding with the neutral connected is the better for supplying an unbalanced load of single-phase circuits.

There are, however, many single-phase and two-phase installations in service. Fig. 25 shows the principal features of the wiring of a station with two single-phase alternators equipped with simple, hand-operated oil switches with automatic overload release. The alternator armature windings are shown at *a*, the alternator field windings at *b*, the field-discharge resistances at *c*, the alternator field rheostats at *d*, the compound-wound exciter at *e* with its shunt-field rheostat at *f*. The exciter switches *g* are sometimes omitted.

The diagram shows synchronizing lamps *h* connected to the secondaries of ungrounded potential transformers *i* to which the voltmeter *j*, also, is connected through plug switches. In small plants, the use of lamps for synchronizing is common; but the system of wiring shown cannot be taken as standard, because of the diversity of opinion, as to the most suitable form of connection for this work.

The trip coils *k* of the oil switches represented at *l* are energized directly from the current transformers *m* to which the ammeters *n*, also, are connected. This form of connection is in quite general use in small stations; the necessity of relays and of a direct-current operating bus is thereby avoided.

In a one-unit station, the alternator field winding is sometimes connected directly to the exciter terminals, with no exciter switches or alternator field switches in circuit. Also, with a single unit, the synchronizing connections are, of course, omitted.

57. Two-Phase Connections.—The principal features of polyphase alternator connections in small stations are shown in Figs. 26, 27, and 28, each of which is lettered to correspond with Fig. 25.

The wiring diagram of a pair of two-phase generators is shown in Fig. 26. The oil switches have two trip coils, either of which, if energized, can operate the automatic opening devices.



FIG. 26

Each trip coil is in series with a separate current transformer, one on each phase, so that the switch will be automatically opened if an overload occurs on either of the two armature circuits. The current transformers supply the indicating ammeters also, of which there is one for each phase. The voltmeter plug switches on each panel are sometimes arranged so that the voltage of either phase of the machine can be read.

58. Three-Phase Star Connections.—The essentials of the wiring of a pair of Y-wound alternators are shown in Fig. 27. Overload protection is necessary on each phase separately; a trip coil is therefore installed in series with the secondary coil of a current transformer and an ammeter for each phase conductor of the machine leads. The secondaries of the current transformers are usually grounded on one side, and the



FIG. 27

return side of the trip coils is also grounded, the return circuits being completed through the ground connections.

The most modern practice is to ground the neutrals of Y-wound alternators, in order to limit the potential between any one phase conductor and the ground. One form of ground connection consists of a copper plate, about 3 feet square and $\frac{1}{8}$ inch thick, buried in a thick bed of charcoal deep enough in the ground to be always moist and below the frost line. Such grounds may develop high resistance, owing to the disappearance of moisture from the ground surrounding the plate; a

more efficient ground consists of a number of pipes, each pointed at one end and drilled at a number of places near the point. Each pipe is driven pointed end downwards into the ground to a distance of about 3 feet below the frost line, and is then filled with crushed rock salt and water. The pipes are connected together by a bar or strap of copper and to this bar or strap is joined the neutral connection of the generators. The water and salt are renewed occasionally, and the brine perco-



FIG. 28

lates through the holes in the pipes and keeps the ground saturated with a good conducting liquid.

The voltmeter and exciter connections are not shown in Fig. 27. The latter are the same as in Figs. 25 and 26; the former (not shown) are so arranged that the voltage of any phase of any generator can be determined.

59. Three-Phase Delta Connections.—The wiring diagram of two delta-connected, three-phase alternators is shown in Fig. 28. These generators can have no neutral connection to their armatures and are not so well adapted for carrying

unbalanced loads as are the Y-wound machines. When delta-connected generators are used, it is sufficient to use an oil switch with two trip coils and to install current transformers for these trip coils on only two phases of the generators, as shown in the diagram, and this is frequently done. When the load is nearly balanced, current readings on only one phase need be taken, and the ammeter can be connected, either in series with one of the trip coils or in the circuit of a separate current transformer, as shown in the diagram. Sometimes three current transformers and a three-way switch are provided, so that ammeter readings on any phase can be taken from one instrument per generator panel. By providing the panels with suitable plug receptacles, the voltmeter connections (not shown in Fig. 28) can be so arranged that the instrument will indicate the voltage of any phase of any generator in the station. The exciter connections, being the same as in Figs. 25 and 26, are not shown in Fig. 28.

BUSSES, SWITCHES, AND DISTRIBUTING CIRCUITS

60. Busses and Switches.—If the voltage of an alternating-current system is 4,000 or less, the bus-bars are generally installed on the back of the switchboard, and oil switches for generators and feeders are supported on the rear of the panels. The oil switches are manually operated by means of a handle on the front of the switchboard. When the voltage is higher than about 4,000, which is infrequent in small stations, the switches are generally more remotely situated and the mechanical connection is made to the mechanism by longer links, bell-cranks, etc., as described in *Switchgear*. When the voltages are as low as 1,000, or even 2,000, circuits are sometimes equipped with knife-blade switches and fuses. The knife-blade switches have long air breaks and are operated either by a handle on the switch or by a long wooden pole that permits the operator to open the switch with somewhat greater safety. Low-tension stations—that is, those generating from 400 to 750 volts—usually have knife-blade switches and, if automatic protection is desired, air-break circuit-breakers. In such cases, the switchboard bears a considerable resemblance to that of a

low-tension direct-current installation, except for the instruments, which are adapted for alternating-current service.

The distributing circuits in systems of 4,000 volts or less are not always provided with oil switches. In many installations, the automatic protection consists only of high-tension fuses, either of the cartridge type, or of a semi-enclosed form. In order that a circuit may be disconnected for replacing the fuses, knife-blade switches are placed in series with the fuses, preferably on the bus side of the fuse-holder studs.

61. Distributing Circuits.—Distributing circuits from single-phase stations are, of course, all single-phase. From two-phase stations, both single-phase and two-phase circuits supply the distributing systems, single-phase for lighting circuits and two-phase for power service. From the three-phase stations, especially those with Y-wound generators, single-phase circuits supply lighting loads, three-phase three-wire lines are run for power, and four-wire three-phase circuits for combination lighting and power service. On account of the expense of running separate circuits for each kind of service, it is common practice, except in very large systems, to use the combination lighting and power circuits for general distribution and to connect lighting and single-phase power loads between the neutral and each of the different phase conductors, care being taken to balance the connected load properly.

When a grounded neutral system is used, the neutral bus is usually not installed on the switchboard, but at some convenient location in the station, generally near the place where the circuits leave the building.

MEDIUM-SIZE ALTERNATING-CURRENT STATIONS

GENERAL FEATURES

62. Alternating-current stations of medium size, intended for general lighting-and-power service, usually have polyphase generators, the connections of which do not differ essentially from those of the smaller installation. The principal difference between the small and the medium-size station is in the number

and size of the units; the details of connection of such apparatus as synchronizing circuits, protective devices, and distributing circuits; the use of more elaborate equipment, such as circuit-potential and Tirrill regulators; and the more complete use of protective devices.

TIRRILL REGULATOR

63. In order to provide good regulation of the potential at the bus-bars and thus to improve the regulation on the circuits, Tirrill regulators are sometimes installed. It is the usual practice to connect the potential coil of the Tirrill regulator to the secondary of a potential transformer, the primary of which is connected directly to one phase of the leads of the generator to be regulated. If all the generators receive field current from one exciter, the pressure transformer for supplying the Tirrill regulator may be connected to one phase of the bus-bars instead of the generator leads. The direct-current supply for the regulator is generally made selective between exciters by means of a separate switch of small capacity connected to the terminals of each exciter set or, in some instances, is made selective between two exciter busses by similar switches connected to exciter bus-bars.

PROTECTIVE DEVICES AND SYNCHRONIZING CIRCUITS

64. Protection From Overload.—The oil switches in use in the generator leads in stations of medium size where the units are of 200 kilowatts capacity, and upwards, are usually not operated by a trip coil energized directly from the current transformers, but by direct current from operating busses at a potential of about 125 volts. The direct current for actuating the tripping device is sent through the trip coil by a relay that is energized by current from the current transformers in the generator leads. The wiring for these relays and the trip coils of the oil switch is shown in Fig. 29 (*a*), (*b*), (*c*), and (*d*), for single-phase, two-phase, three-phase delta, and three-phase Y systems, respectively. In each diagram, the alternator armature winding is represented at *a*, the oil switch at *b*, a current

transformer at *c*, a relay operating coil at *d*, relay contacts at *e*, the oil switch trip coil at *f*, and the leads to the direct-current operating busses at *g*.

The operating busses are generally supplied from the exciter system, though, in some cases, the supply is from a small storage battery of about 40 amperes capacity installed especially for the purpose. The operating busses connect not only to the



FIG. 29

overload relays, but to all control devices requiring direct current for their operation.

65. Remote-Control Circuit.—In medium-size stations, it is not uncommon to have the entire oil-switch installation subject to remote control, electrically or pneumatically, at the will of the operator. The switchboard then bears, instead of operating handles, only small control switches for energizing the operating coils and for each control switch a pair of signal

lights to indicate whether or not the switch operation has been completed. The wiring diagram of such an oil switch is shown in Fig. 30. When the single-pole, double-throw, control switch *a* is thrown to the upper position, the solenoid of the relay *b* receives current and the relay contacts are thereupon closed, completing the circuit from the direct-current operating busses through the closing solenoid *c* of the oil-switch operating mechanism. The three-way switch *d* is mechanically connected to the oil-switch mechanism, so that closing the oil switch moves the contactor of the three-way switch to the left, thereby closing the operating circuit through the opening coil *e* of the oil switch and through the red signal lamp *f*, the lighting of which indicates that the closing of the oil switch is complete. When the lamp is in series with the opening solenoid, the current in the solenoid is too small to operate the oil switch; when, however, the control switch is thrown to the lower position, the opening coil is connected directly across the operating busses, and the current becomes great enough to operate the switch mechanism and open the main circuit. The opening of the oil switch closes the three-way indicating switch *d* to the right, so that the green signal lamp *g* receives current. The opening coil can also be connected in series with a current transformer to provide for automatic opening of the oil switch, in case of overload. The control switch must be opened, and left open, after the completion of each operation of opening or closing the oil switch.



FIG. 30

66. Synchronizing circuits in stations of medium size are generally provided with a synchroscope, on account of the difficulty of performing accurate synchronizing operations by the indications of lamps or voltmeters.

BUSSES AND DISTRIBUTING CIRCUITS

67. Duplicate Bus System.—The service supplied from alternating-current stations of medium size is generally more important than that supplied from the smaller plants. Hence, in order that the interruptions or inconvenience due to construction, repair, or maintenance work on the apparatus may be reduced to a minimum, there are generally at least two sets of bus-bars to which the generator leads and distributing circuits can be connected. The selective switching between different sets of bus-bars can be effected by the use of two separate oil switches, sometimes mechanically or electrically interlocked, or by a set of knife-blade transfer switches so arranged that the switches can be connected to both busses at the same time. Such switches have two blades on a common hinge, but the blades are so arranged that they can swing independently of each other and fit into clips with two receptacles. The switches can thus be *split* between busses and the connection of the machine or circuit transferred from one set of bus-bars to the other without interruption of the supply.

68. Control and Voltage Regulation of Distributing Circuits.—In medium-size alternating-current plants used for general lighting and power, the distributing circuits are usually more completely equipped than in the small plants. The feeders are provided with oil switches having automatic overload release, and in many cases the circuit switches are also electrically remotely controlled at the will of the operator.

On account of the great differences in lengths and loads of feeders, the potential drops therein differ, and it is not possible by regulating the bus voltage to supply uniform pressure over a large area. Long feeders or circuits are sometimes equipped with boosting transformers and the shorter feeders with choking transformers. This method of adjusting the supply of pressure

to the distributing circuits compensates for the different potential drops, due to different lengths of feeders, but not for the change in potential drop, due to change in load. In order to provide for this condition also, potential regulators are used. Potential regulators are capable of being changed at once from boosting to choking transformers, or vice versa, and of raising or reducing the voltage in any desired amount up to the limit of their potential capacity.

Potential regulators are usually installed in one conductor of each single-phase lighting circuit and in each phase conductor of three-phase combination lighting and power circuits. They may be either remotely controlled at the will of the operator, or automatically controlled by means of a contact-making voltmeter. When they are remotely controlled by the operator, a line-drop compensator is generally used to indicate the potential at the distant feeding center.

LARGE ALTERNATING-CURRENT STATIONS

GENERAL FEATURES

69. Alternating-current generating stations for supplying lighting and power for large systems are of two kinds: those distributing energy directly to the feeding centers in the same manner as the medium-size stations and those supplying converting and distributing substations. As the details of the distributing circuits in the first-named type of stations are the same as those in plants of medium size, the following description pertains more particularly to stations supplying converting and distributing substations.

The generators in stations of this class are nearly always three-phase, and usually have armature windings Y-connected, with the neutral grounded. Sometimes the ground is made through a cast-iron grid resistance, in order to limit the current in the neutral circuit in the event of a ground on any one phase.

If the generators are not provided with overload protection to open the oil switches in the event of severe overload, such as



FIG. 31

a short circuit, reactance coils are sometimes connected in the leads between the generators and the bus. These preventive reactances serve to limit the current and thus to prevent damage to the armature windings. Reactances for this purpose are constructed without iron in their cores and are generally self-cooling.

EXCITER SYSTEM

70. In large stations, the exciter system is generally supplied by induction-motor-driven motor generators. The equipment includes, also, steam-engine or steam-turbine-driven exciter generators, which may be used when desired and which must be used to start the system in the event of a total shut down. In addition, some of the large stations are provided with 125-volt storage batteries, which are kept continually floating on the exciter busses. When a storage battery is used, the generators of the exciter sets must be either shunt wound or flat compounded.

Some large stations have a separate exciter and exciter bus for each alternator, the exciters being driven by induction motors supplied with current from the generator leads. With this form of installation, it is necessary to provide *ties* (switches) between adjacent individual exciter busses, so

that any bus can be energized from the others, and the corresponding alternator excited until it is in operation and the individual motor-generator exciter set is started and paralleled to the exciter busses.

In Fig. 31 is shown the arrangement of the exciter system of a large generating station in which a storage battery is floated on the exciter bus-bars; motor-driven exciters are represented at *a*, steam-driven exciters at *b*, the storage battery at *c*, exciter-bus sectionalizing, or tie, switches at *d*, leads to alternator field windings at *e*, and leads to the direct-current operating busses for oil switches at *f*. This station is normally operated with the exciter bus-bars continuous, in order that the storage battery may be effective on all the exciter busses, but is so arranged that the exciter bus-bars can be sectionalized at will. The supply of current for excitation of generators and for the operating bus for all the oil switches pertaining to each unit is taken from the exciter bus-bar section corresponding to that unit.

SWITCHES, BUSSES, AND DISTRIBUTING CIRCUITS

71. Oil Switches.—In large stations, where units are of considerable size (3,000 kilowatts and upwards) and large amounts of energy are handled, oil switches are necessarily remotely controlled, either electrically or pneumatically. Modern installations of large oil switches are practically all provided with electric operating devices, either motors or solenoids. The size and design of the switches are partly dependent on the potential of the circuits in which they are placed, but the barrier type of construction is generally used, in order to prevent an arc in one oil well or compartment from communicating to adjacent phases and starting a serious short circuit, which might do great damage. In addition, there are sometimes used oil switches in which the circuit is not only broken twice in each phase under oil but each break is made in a separate oil well.

72. Bus Construction and Location.—The type of bus construction employed in large alternating-current stations varies according to the voltage of the system, but for voltages

between 5,000 and 30,000, the cellular and barrier form is in general use, in order to confine as much as possible arcs that may occur as the result of a breakdown of insulation. In some of the larger stations, the high-tension bus and switching equipment is placed in a separate portion of the building with fire-walls between the switch room and adjacent parts of the building. The oil switches are usually placed on one floor and the bus construction in a room below, as shown in Fig. 32. The operating mechanism *a* of the oil switch is mounted on the top of the oil-switch compartment *b*. In addition to the oil switch, a knife-blade disconnecting switch *c* is provided.



FIG. 32

73. Bus Systems.—The systems of arrangement of busses in alternating-current stations of large size are almost as numerous as the stations, but they may be roughly divided into five general classes: one-bus system, single sectionalized bus system, ring-bus system, duplicate bus system, and duplicate sectionalized bus system.

In the **one-bus system**, all generators and feeders connect to one set of bus-bars, which are continuous from one end of the switchboard or bus compartment to the other. Such a system is not adapted to flexibility of operation, and in order to avoid this disadvantage, the bus is sometimes divided into a number of sections, one for each generator, forming the **single sectionalized system** shown diagrammatically in Fig. 33, in which *a* indicates a generator and *b*, a generator oil switch. The bus-bars can be made continuous, when desired, by means of bus-tie oil switches *c*.

With the arrangement of Fig. 33, any section can be taken out of service for repairs or construction work; but if the section taken out is not at one end of the bus system, the sections on each side of the idle one are isolated from one another. To avoid such a condition, the **ring system** shown in Fig. 34 is employed.



FIG. 33

The ring system permits any bus-section to be taken out of service, but, like the single sectional system, it requires that the generator connected to that section be taken out of service, also. This difficulty is obviated by the **duplicate sectionalized bus system**, Fig. 35, which consists of duplicate sets *a* and *b* of bus-bars, to either of which any generator *c* can be connected by selective switching provided by oil switches *d* and *e*. The use of a reactance in the generator leads is indicated at *f*. If



FIG. 34

the distributing circuits, also, are made selective between the two sets of bus-bars, a high degree of flexibility of operation is secured.

74. Distributing-Circuit Connections.—Distributing circuits are connected to the bus-bars through oil switches, and if duplicate busses are provided, can be made selective in switching by installing two oil switches. The use of a single

oil switch and a set of transfer knife-blade switches, as described in connection with medium-size aternating-current stations is not frequently resorted to in large stations, where the circuits carry large amounts of energy, especially if the voltage is high. The most modern method of connecting distributing lines and circuits is the **group system**, by which a small group of circuits, usually four or five, are connected through oil switches *g* to a common *group bus h*, Fig. 35, which has two switches *i* and *j*, each of which connects to a separate set of distributing bus-bars, thus making the group selective in switching between the two busses.



FIG. 35

75. Sectional Operation.—Some large alternating-current stations are operated sectionally—that is, with their bus-bar system separated in two or more main divisions—on account of the danger of connecting together large amounts of generating capacity, which, in

the event of a short circuit on the bus-bars, might cause enormous damage, not only to the bus construction but to the switches and generators. The sectionalized operation is effected by opening a bus-bar tie-switch k, Fig. 35, between two divisions of the distributing busses, leaving connected to each division an amount of generating capacity, which is considered safe. As the most favorable operating condition exists when all the generating units are in parallel, sectionalized operation may effect economy unfavorably; and, in order to permit parallel operation of sections, but, at the same time, to limit the current into one section from adjacent sections, a preventive reactance l is sometimes installed in each phase conductor between the sections at the point where the bus-bar tie-switch is open. The reactances permit ordinary amounts of energy to pass between the sections, thus affording all the advantages of parallel operation; but they choke back any large amounts of energy and thereby serve to limit the extent of the damage in case of a short-circuit.

ELECTRIC SUBSTATIONS

INTRODUCTION

PURPOSE OF SUBSTATIONS

1. Electric energy in large quantities can be produced more economically in one or two large generating stations containing large units than in several stations having smaller units and, possibly, having less complete facilities for handling coal or for obtaining condensing water.

While economy in generation makes large stations desirable, the highest economy of distribution requires the shortest possible length of distributing circuit; a condition which, if fulfilled, would necessitate a large number of distributing centers scattered throughout the load territory. Even in places where the load density is great, it is not always desirable to build a generating station, as facilities for obtaining coal, removing ashes, and providing condensing water may be so poor as to make the cost of operation too great, or the cost of land may be so high that the interest on the investment in real estate would make the station unprofitable.

Electric substations offer a solution of the problem just presented. They do not require as much space as generating stations, and, when necessary, can be installed in basements or other places where generating plants would be uneconomical or impossible. There is also less difference in operating economy between large and small substations than between large and small generating stations. These conditions permit the use

COPYRIGHTED BY INTERNATIONAL TEXTBOOK COMPANY. ALL RIGHTS RESERVED

of a larger number of distributing centers than would be possible with generating plants only, and the distributing circuits are thus shortened.

In hydroelectric developments, the generating station is necessarily located near the water supply, which may be situated in a place remote from the market for the electric energy. Substations are then necessary to a complete system of distribution, because the receiving apparatus cannot use the energy in the high-pressure form that is required for long-distance transmission.

2. In the accomplishment of its purpose a substation may perform one or more of the following duties: The transformation of alternating current at one voltage into alternating current at another voltage; the conversion of alternating current into direct current; the change of one alternating current into another of different frequency.

3. Direct-Current Substations.—For variable-speed power service, direct-current motors are usually selected. Direct current is therefore usually demanded in the congested business districts of large cities, in large industrial plants, and in certain classes of electric-railway service. In such cases, if the general distribution is by alternating current, direct-current substations equipped with synchronous converters, or motor-generators, are necessary.

4. Frequency-Changer Substations.—Large alternating-current generators operate most satisfactorily at low frequency. Also, electrical energy can be transmitted most economically in the form of low-frequency current, because the reactive voltage drop in a conductor is directly proportional to the frequency. Most long-distance transmission of electricity is therefore accomplished at a frequency of 25 cycles. However, some consuming devices, such as certain types of electric lamps, demand for proper operation a frequency as high as 60. Frequency-changer substations are installed to convert the low-frequency alternating-current energy carried by transmission lines into higher-frequency alternating-current energy for

distribution among consuming apparatus. Conversely, frequency-changer substations can be employed to convert 60-cycle energy generated mainly for general lighting and power service into 25-cycle energy for alternating-current railway service.

5. Transformer Substations.—Transformer substations are used to change the high-tension alternating-current energy of long-distance transmission lines into lower-tension energy for local distribution among general lighting and power consumers. They are also employed on alternating-current railways to convert the high-tension energy from the generating station into energy at a tension low enough for the alternating-current railway motors.

SIMILARITY BETWEEN SUBSTATIONS AND GENERATING STATIONS

6. A substation, being a distributing center, has, in general, the same kind of distributing apparatus as a generating station of the same capacity distributing the same service. It is not uncommon to install substation apparatus in old steam plants and to connect the substation machinery to the generating plant distributing busses. In general, the same distributing busses, feeders, circuits, and switches that are suitable for a generating plant are suitable for a substation supplying the same amount and kind of load.

Motor-generator substations supplying either direct or alternating current have electric connections of their generators, switches, and busses very similar to those of generators driven by prime movers such as steam engines or water turbines.

High-tension bus and oil-switch construction in a substation is usually similar to that used in an alternating-current generating station of equal capacity and voltage, with the exception that it is common practice to provide automatic overload protection for substation apparatus and somewhat less common to do so for the generators in a generating plant. In addition, overload relays are commonly used in connection with the oil switches on outgoing lines from generating stations, whereas

similar protection for the substation ends of the lines is generally not provided.

The substation differs from the generating station in the type of apparatus used and in the much larger kilowatt capacity that can be installed per unit of floor space or per unit of cubic contents.

DIRECT-CURRENT SUBSTATIONS

PRELIMINARY REMARKS

CLASSIFICATION

7. The machinery employed in direct-current substations for converting alternating current into direct current is of three kinds; motor-generator sets with induction motors, motor-generator sets with synchronous motors, and synchronous converters, frequently called rotary converters. Direct-current substations can therefore be classified, in general, as *motor-generator substations* and *synchronous-converter substations*. They can be classified also as *light-and-power substations* and *railway substations*, according to the kind of service in which they are employed.

GENERAL ARRANGEMENT

8. In Fig. 1 is shown, roughly, the arrangement of some of the equipment of a direct-current railway substation. The high-tension transmission line wires enter the building through a protected opening in the rear wall. Connection to the high-tension bus-bars *c* is made through disconnecting switches *a* and choke coils *b*. From the bus-bars, wires lead to disconnecting switches *d*, remotely controlled oil switches *e*, current transformers *f*, and main transformers *g*. The synchronous converter *i* is connected to the secondaries of the transformers through reactance coils *h*, which aid in the regulation of the

direct-current voltage of the converter. The direct-current equipment, such as switchgear, not shown, is practically the same as a direct-current railway generating station of equal capacity.

NUMBER AND CAPACITY OF UNITS

9. The selection of substation units as to size and number should be made only after the actual load is known and the prospective load is estimated. Though most substation



FIG. 1

machinery is fairly reliable, any electric apparatus is subject to various forms of trouble that may temporarily put it out of service, and the best practice is, therefore, to install more than one unit in each substation. Better economy is obtained from the larger units, but when such a machine is disabled a large percentage of the substation equipment is shut down, and for

this reason also it is usually considered good practice to divide the substation capacity among two or more machines.

It is not, however, good practice to install too large a number of machine units. If the conditions permit the use of fairly large units, not more than four to six machines should be installed. These will usually provide all the flexibility of operation needed and they will require less attention, care, and expense for maintenance than will a greater number of machines of the same combined capacity. Furthermore, the smaller number of machines will require a smaller initial investment of capital.

However, in some special locations, as in basements, insufficient headroom limits the size of machinery, and the installation of a considerable number of small units becomes necessary.

Similarity of units as to size and design is desirable, as it reduces the number of emergency repair parts to be kept on hand, and, in some cases, reduces the size of the stock of operating supplies, such as brushes.

MISCELLANEOUS EQUIPMENT

10. High-Tension Bus System.—If the voltage of the high-tension transmission system exceeds about 5,000, the high-voltage conductors of the substation should be kept suitably isolated from one another by fireproof barrier construction. If the line pressure is as high as about 30,000 volts, the barrier or cellular construction is unnecessary, as the violence and destructive effects of an arc between phase conductors is dependent on the current available, and the current is more limited in systems of such high-potential.

The form of arrangement of the high-tension busses depends somewhat on the number of transmission lines and the number of substation machines. If there is more than one transmission line, and more than one unit, flexibility of operation is increased by dividing the high-tension busses into two sections, with a bus tie-switch between them, and connecting one

line and one or more machines to each section. This arrangement permits one part of the substation to be shut down independently of the other if any repairs are to be made.

In general, the alternating-current bus construction in a substation can be less elaborately arranged than that in a main generating station, but it must be at least as good and as safe as would be required in an alternating-current generating plant equal in capacity and voltage to the substation.

11. Oil Switches.—In the selection of oil switches, the same rule as to quality and safety applies; but it may be necessary to choose a type of switch that is adapted to the special conditions at hand. For example, the amount of floor space available may be limited so that a very compact switch may be much better than one occupying more room.

In substations of small or moderate size, transmission line switches for use on systems of 15,000 volts or lower may be hand-operated, remotely controlled. Bus tie-switches for connecting the different sections of the high-tension busses, if not required to carry more than about 800 amperes, may also be hand-operated, remotely controlled.

12. Direct-Current Switchgear.—A direct-current substation should have a direct-current switchboard and switchgear similar to that installed in a generating plant of the same capacity and for the same kind of service. The connections of armature leads, armature switches, rheostats, busses, instruments, and feeders will be the same as would be required for steam-driven units of the same capacity.

13. Motor-Driven Generators.—The generators of motor-generator units differ in no important respects from those used in steam-driven sets of the same capacity and speed. If the generator is directly connected to the motor, both motor and generator will have the same speed; and it is, of course, necessary that the generator be one adapted for operation at the speed at which the motor runs. If the generator is belted to the motor, the proper speed relations are secured by selecting pulleys of proper sizes. If belted units are used, the best

arrangement is one that gives a sufficient distance between the pulleys to permit the use of a slack belt.

14. Grounding Belt-Driven Machines.—Belts running at high speeds sometimes cause static electricity to be generated, and if the motor or generator is insulated from the ground there is danger of the static charge puncturing the insulation of the machine; the frames of belted machines therefore should be grounded. If it is objectionable to have them grounded through conductors having any considerable carrying capacity, the ground connection can be of high resistance, such as a lightning-arrester carbon, or the filament of an incandescent lamp connected between the machine frame and ground.

If some local condition makes a complete metallic ground connection undesirable, the intensity of the static discharge can be greatly reduced by connecting to the frame of the machine a metallic conductor with a number of sharp points and placing near the ends of the points, about $\frac{1}{8}$ or $\frac{1}{4}$ inch distant, a metallic conductor that is connected to ground. The size of this ground connection is not important except as its mechanical strength may be affected, and it should be installed in such a position that it will not be liable to be broken. It is, in effect, a lightning arrester in continuous discharge during the operation of the machine. In some cases, relief from static stress is afforded by arranging a grounded conductor with a number of points projecting near the moving belt.

15. Shunt-Field Connections.—In general, it is good practice to install direct-current generators without switches in their field circuits, the shunt-field terminals being connected directly to the armature leads. However, it is sometimes desirable, as a result of some special condition or requirement, to have facilities for readily opening the shunt-field circuit. These special conditions are more common to motor-generator substations than to main generating stations. Whenever such conditions exist, a quick-break field switch and a field-discharge resistance are used.

TRANSFORMERS

NUMBER, CONNECTIONS, AND CAPACITY

16. Number.—In the selection of step-down transformers for supplying rotary converters or motors of motor-generator sets, there is considerable latitude. If the transmission is two-phase, two single-phase transformers are generally installed, because if one is disabled it may be conveniently replaced by another. If a three-phase transmission system is used, three single-phase transformers or one three-phase transformer can be used, depending on the conditions. Three single-phase transformers are more expensive and occupy more floor space than one three-phase transformer of equivalent capacity. If one of an installation of three single-phase transformers is disabled, the injured one can usually be disconnected and replaced more quickly, and repaired at less expense, than can one three-phase transformer; if they are delta connected, the injured transformer can be disconnected in a few minutes and a part of the load can be carried on the other two, operating on an open delta, or **V**, connection. However, modern transformers are so well built and so well protected by lightning arresters, choke coils, automatic overload oil switches, and other devices that the most common practice now is to use one three-phase transformer rather than three single-phase transformers.

17. Connections.—In the use of either of the two forms of three-phase transformers, the windings may be connected either star or delta. Star-connected primaries are generally used for potentials higher than about 10,000 or 15,000 volts. When transformers are purchased, the specifications are usually prepared with particular reference to the form of connection to be used; but, in many cases, transformers already on hand, sometimes those used in connection with some other installation, must be adapted for use. In such a case, the choice as to form of connection is generally limited.

18. Capacity.—Step-down transformers for use with induction motors must be of sufficient size to carry the load at

the power factor that the motor will have when fully loaded. The manufacturer is generally able to state with a reasonable degree of exactness what the power factor of a motor will be at various loads. If, then, the output in kilowatts is divided by the product of the motor efficiency and the power factor, the result will be the input in kilovolt-amperes, and the transformer should be rated for at least as much as this.

COOLING METHODS

19. Oil-Cooled Transformers.—Transformers can be selected from three general types; oil-cooled, air-blast cooled, and oil-and-water cooled. Oil-cooled transformers are quite satisfactory in capacities as great as about 1,500 kilowatts, and air-blast transformers of 4,500 kilowatts capacity are successful; in larger capacities oil-and-water cooling is more general.

Oil-cooled transformers require the installation of no auxiliary apparatus for cooling. They should be so situated that the circulation of air around them will be good, and care should be taken, as far as possible, that the air is not first heated by the substation machines. Only about 12 per cent. of the total heat liberated from apparatus in the substation comes from the transformers, and a considerable amount of heat is thrown off from the converting machines themselves. For this reason, it is desirable that the locations of windows, transformers, and machines be such as to provide a good circulation without sending heated air around the transformer cases.

20. Blower System.—Air-blast-cooled transformers are comparatively inexpensive to purchase, but require the installation and operation of a blower fan for supplying the cooling air. The fans used are generally of the blower type, that is, fans capable of delivering a moderate amount of air at comparatively low pressure, such as $\frac{1}{2}$ to 1 ounce per square inch.

If there are a number of substation units, one blower set may supply air for the transformers of all of them; but duplicate sets are generally installed, so that the breakdown of one will not affect the entire plant. The unit system goes to the other

extreme of providing a separate blower fan and air chamber for the transformers of each unit. When this is done the blower motor is usually left switched permanently to the leads of the converting unit and it starts and stops with the main machine.

21. Blower Drive.—The fans for air-blast cooling of substation transformers may be, and are in some cases, driven by induction motors supplied with current directly from the line; but motors of such small capacity are generally made for low voltage, and therefore it is better and more usual practice to install step-down transformers for supplying all of the substation auxiliaries and to use 220- or 230-volt motors.

The size of the motor used for driving the fans is such that it will operate at almost full-rated load when the fan is furnishing air for all of the transformers it will ever have to supply. In practice, it is found that a 5-horsepower or 7½-horsepower motor is large enough to drive fans for supplying the transformer equipment for two 500-kilowatt units, and a 20-horsepower motor is sufficient for use in connection with four 1,000-kilowatt units.

In some small installations, especially where there is but one unit, it may be possible to omit the special blower motor altogether and to drive the air-blast fan belted from a pulley on an extension of the shaft of the motor-generator or rotary converter. This arrangement has the advantage of always operating when the unit is in operation, reducing expense, and leaving out one piece of apparatus, the disability of which might affect the safe operation of the entire unit.

22. Air Supply.—The air for cooling substation transformers is preferably taken from outdoors through an opening remote from the place where the heated air is discharged from the operating room.

Air taken from a point near the ground may carry considerable dust, which may partially choke the air passages in the transformers and thus produce a condition that causes overheating. Various methods are used to separate the dust from the air, but in any given case only a limited number of these can be applied.

Air taken from a stack reaching above the roof of the building will probably be fairly free from dust. If a stack cannot be used, a large chamber, or passage, between the fan discharge and the transformers is very valuable. A large passage causes a great reduction in the velocity of the air, so that much of the dust, at least the heaviest part, settles to the floor, from which it can be removed readily.

When neither of these methods is available, some form of air-cleaning device is sometimes used. In Fig. 2 is shown an arrangement that offers a large amount of screening surface for a given cross-section of air passage. The screens *a*, of copper or bronze wire, are placed diagonally between horizontal sheet-iron plates *b*. The screens, though effective in removing the large dust particles, admit the very fine dust, which is really the most objectionable in a transformer. A more effective screen is one made of cloth, either cotton or woolen, but preferably of woolen. A cloth screen can be made as thick as desired, and any required amount of screening action secured. Air-blast equipment used in connection with screens must be relatively large in capacity to compensate for the reduction in air pressure caused by the screens.



FIG. 2

23. Oil-and-Water-Cooled Transformers.—Transformers that are oil-and-water cooled require a continuous supply of cold water during operation. If there is available a supply from a system of waterworks having a head at least slightly higher than the tops of the transformers, the cooling

coils can be connected thereto, and no further auxiliary equipment will be needed. If no such water supply is available or convenient, it may be necessary to take water from a well, river, or lake and to circulate it through the cooling coils by means of a small pump. One pump, supplied with power either from a separate motor or from an extension of the shaft of a converting unit, can be used for several banks of transformers. The required capacity of the pump will depend on the amount of water to be circulated and also on the distance through which the water must be lifted. Unless the lift is considerable, the pump can be quite small, even for a large installation of transformers, because a small amount of water, with its high specific heat, will cool a comparatively large amount of oil.

Water containing a great deal of scale-forming, or pipe-clogging, deposit will soon form a thick coating inside the cooling coils, not only limiting the flow of water but reducing the rate of flow of heat from the oil to the water. For this reason, the character of the water supply is very important when water-cooled transformers are to be used.

CHOICE BETWEEN SYNCHRONOUS CONVERTERS AND MOTOR-GENERATORS

24. The choice between synchronous converters and motor-generators for a direct-current substation is dependent on cost, economy, grade of service required, and the kind of alternating-current supply available.

For several years after synchronous converters came into general use, 60-cycle converters were considered undesirable because of high commutator speeds and the liability to flash over between adjacent brush-holders. Improvements in both electrical and mechanical design have practically removed these objections, and converters operating on the higher frequency are successful even under the difficult conditions met with in direct-current railway work at high voltage.

Any variation in the alternating-current voltage supplied to a synchronous converter at once produces a variation in the

direct-current voltage; but as long as the voltage of the supply is maintained the machine is not affected by moderate changes in frequency. Therefore, if the alternating-current supply has a constant frequency but a fluctuating voltage, motor-generators give better service than synchronous converters when close pressure regulation of the direct-current output is required. If the voltage is well maintained and the frequency is variable, the synchronous converter is better. In railway service, and in most factories, very close pressure regulation is not required and synchronous converters are usually employed. Synchronous converters, including the necessary transformers, are generally less expensive in first cost and more economical in operation than motor-generators. Such converters are, therefore, in quite general use, even in places where motor-generators would give better pressure regulation.

25. A synchronous converter that normally transforms alternating current into direct is said to be *inverted* when it receives energy from the direct-current bus-bars and tends to supply alternating-current energy to the line. An objection to the use of synchronous converters is their tendency to speed up dangerously when inverting into inductive loads at time of interruption to the supply from the alternator. Such machines are therefore equipped with over-speed limit devices. The tendency to high speed occurs on failure of alternating-current supply when the converter is feeding a direct-current system having other sources of supply. The converter then becomes inverted and will speed up if the field is weak or is demagnetized by lagging alternating current.

Induction-motor-driven generators are the simplest to install and the simplest to operate, but are somewhat objectionable on account of their effect on the power factor.

Synchronous-motor-driven generators are the most expensive of the three classes of apparatus considered, and their operation is a little more complicated than that of induction-motor-driven sets. Synchronous motor-generators can be operated with a good power factor and are useful for neutralizing the lagging power factor produced by induction motors.

MOTOR-GENERATOR SUBSTATIONS WITH INDUCTION MOTORS

GENERAL REMARKS

26. As the induction-motor installation is practically the same for all the different classes of substations using induction-motor-driven generators, the induction-motor end of the substation will be treated here without special reference to the generator end.

27. The capacity of the motor selected for driving a generator must be such that it will not be overloaded when the generator is supplying its full-rated load. The capacity of the motor must, therefore, be greater than that of the generator by an amount equal to the losses of the generator. Most manufacturers in designing motor-generators generally use a motor that slightly exceeds this requirement.

28. Induction motors are designed for use on circuits of voltages as high as 6,600. Therefore, if the transmission voltage is not higher than 6,600, general practice is to provide induction motors that will operate on full line pressure. If the line pressure is higher, step-down transformers are almost always used.

STARTING METHODS

29. Starting From Transformers.—For starting induction motors of a size suitable for the driving machine of a motor-generator, two means are available. When step-down transformers are used, the least expensive form of starting equipment is made by connecting double-throw switches to low-voltage taps taken from the secondary windings of the transformers. Ordinarily, an induction motor starts very well when supplied with half its normal running voltage, and one double-throw switch connecting the motor primary first to a half-voltage tap and then to the full secondary pressure terminal is all that is required. Such a connection is shown in Fig. 3,



in which the arrangement for a four-wire two-phase system is shown in (*a*), for a three-wire, star-connected, three-phase system in (*b*), and for a three-phase delta connection in (*c*). In each diagram the secondaries of the step-down transformers are represented at *a*; the stator, or primary, windings of the induction motor at *b*; the starting position of the motor switch at *c*; and the running position at *d*.





FIG. 3

30. Other Starting Devices.—If an induction motor is to operate on full line pressure without transformers in circuit, a starting device must be provided. This device usually consists of an oil-switch or a circuit-breaker and two or more autotransformers. The switching device must have the requisite number of contact positions and it may be mounted with or separate from the autotransformers. Separate mounting is the practice with large starters. When the parts are assembled as one unit it is variously called an autostarter or a starting compensator, according to its maker. The switch serves to change connections so as to obtain reduced voltage for starting and full voltage for running. Automatic protective devices are usually provided for overloads and very often for both overloads and low voltage. In some cases the switches are simply oil circuit-breakers so interlocked that they can be closed only in the right order.

One starting device can be so connected as to be used for starting any one of a considerable number of motors. The

autotransformer *a*, Fig. 4, is connected through an oil switch *b* to the running busses, which are supplied with full line pressure, and the low-voltage terminals are connected to special starting busses to which any of the motors can be connected through their individual starting switches. The two single-throw switches *c* connected to the motor leads can be replaced by one double-throw switch *d*, in order to save expense; but



FIG. 4

two single-throw switches made interlocking, either mechanically or electrically, are safer, especially in connection with voltages greater than about 2,200.

INSTRUMENT EQUIPMENT

31. Potential Transformers.—For supplying pressure to alternating-current voltmeters, wattmeters, and watt-hour meters in substations, potential transformers are generally used. One pressure transformer, if of sufficient capacity, can be used for supplying instruments for several machines operated

from the same alternating-current busses. When this is done, it is common practice to run a small pressure-wire bus, of about No. 12 or No. 14 B. & S. gauge wire, along the rear of the switchboard panels of these machines. The pressure bus is supplied from the transformer and taps for the instruments are taken off wherever required.

Pressures for wattmeters must not be taken from potential transformers connected to a high-tension bus other than that which supplies current for the current coils of the wattmeter if there is any possibility of the potentials on the two busses being out of phase with each other, as the wattmeter indications will then be unreliable.



FIG. 5

32. Current Transformers. For the operation of ammeters, wattmeters, and overload relays, current transformers are used in the leads from the busses to the induction motors of substation motor-generator sets. In order that they may protect as much as possible of the apparatus, current transformers should be in the circuit as near as possible to the machine oil switch and on the machine side of it.

The current transformers should be so chosen that they will not be overloaded when the motor-generator is overloaded by 50 per cent. of its normal rating. Modern instruments and relays are usually made with 5-ampere windings, and the current transformer ratio should be such as to give the proper secondary current values for these devices. Thus, if the normal rating of the motor is 60 amperes, the primary of the current transformer should have a capacity of 90 amperes. Its ratio

of transformation, to give a 5-ampere secondary current, would be 90:5, or 18:1.

33. Ammeter, Wattmeter, and Overload-Relay Connections.—The use of an ammeter in the motor circuit of a motor-generator is, of course, an item of some expense, but, though the approximate current input can be figured from the output, the calculation is so long that it is generally not done, and the machine may become overloaded in current before the operator becomes aware of it, especially if there is a reduction of line voltage. For this reason, an alternating-current ammeter should always be installed in each motor circuit, although, in practice, they are generally omitted from the motor leads of small units and are only occasionally installed in connection with large units.



FIG. 6

In Figs. 5 and 6 are shown the connections of current transformers *a*, overload relays *b*, ammeters *c*, and wattmeters *d* on two-phase four-wire and three-phase three-wire installations, respectively. In case of overload, the relays complete the circuit from the operating bus through the trip coil *e* of the oil switch *f*, which is thereupon opened, protecting the motor windings *g*. The potential circuits of the wattmeters are connected to the secondaries of potential transformers *h*. An artificial neutral is secured on the three-phase system, Fig. 6, by means of a Y box *i*, in order that the wattmeter may receive the star pressure of the system. The current connections are made through the ground, as indicated.

When a three-phase transmission system is supplied by delta-connected generators or transformers, the use of only two current transformers and two relays is sometimes permissible, but one current transformer and one relay on each phase is better. When a three-phase transmission system is supplied from star-connected apparatus with a grounded neutral, each phase should be equipped with a current transformer and a relay.



FIG. 7

34. Watt-Hour Meter Connections.—The kilowatt-hour input to the motor generators of substations can be satisfactorily measured by a single-phase integrating wattmeter, or watt-hour meter.

If the transmission is two-phase, a watt-hour meter installed in one phase is sufficient. The instrument will record only one-half the energy input, but the totals can always be correctly determined by multiplying the instrument readings by two.

If the transmission is three-phase, current connections from one phase and star pressure connections from the same phase supply the single-phase instrument. If three potential transformers are used for supplying pressure for the meter, they should be connected Y, as shown in Fig. 7, in which *a* is a potential transformer, *b* a current transformer, and *c* the windings of the watt-hour meter. In this case the actual energy input will be three times that shown by the watt-hour meter.



FIG. 8

In order to save expense by using two pressure transformers instead of three, a pressure in phase with star pressure but having a value one and one-half times as great is sometimes

used. This is secured by connecting two potential transformers open-delta, or **V**, and connecting the instrument circuit from the outside secondary terminal of one to the middle of the secondary winding of the other, as shown in Fig. 8, which is lettered to correspond with Fig. 7.



FIG. 9

Watt-hour meter connections can also be made as in Figs. 5 and 6 and watt-meter connections as in Figs. 7 and 8. Polyphase instruments connected as described in *Watt-Hour Meters* can also be used.

WIRING DIAGRAMS

35. In Fig. 9 is shown a wiring diagram of a three-phase induction motor connected to step-down transformers and in Fig. 10, a diagram of a three-phase motor operating on full



FIG. 10

line potential. These two illustrations show the relations to one another of the details given in Figs. 3 to 6; in Figs. 9 and 10, no wattmeter nor watt-hour meter connections are included.

MOTOR-GENERATOR SUBSTATIONS WITH SYNCHRONOUS MOTORS

MISCELLANEOUS EQUIPMENT

36. Synchronous motors, because of their ability to improve the power factor of the system, are sometimes preferred to induction motors for driving substation generators. They are manufactured for operation on circuits with pressures considerably higher than generally applied directly to induction motors.

In the selection of transformers and cooling apparatus the same considerations apply to synchronous-motor installations as to induction-motor substations; but, as the power factor of a synchronous motor can be made 100 per cent., the transformers may have a somewhat smaller rating in kilovolt-amperes than those to be used with induction motors.

The high-tension bus and oil-switch equipment for a synchronous-motor-generator substation is the same as for an induction-motor installation, as are also the current transformers, potential transformers, and overload relays. In addition to the measuring instruments mentioned in connection with induction-motor installations, a power-factor indicator may be used in connection with synchronous motors, although its use is a convenience and not a necessity; an alternating-current ammeter in one phase is more needed.

METHODS OF FIELD EXCITATION

37. Excitation From Main Generators.—Direct current for exciting the field of a synchronous motor in a substation may be supplied from a separate exciter unit or from the generator of the motor-generator set, provided that the generator is compound wound and delivers direct current at the proper pressure for excitation.

When the second method is used, the exciting circuit may be taken either from the load busses or from the machine leads.

If the generators are protected by circuit-breakers in the armature leads, the exciting circuit is not taken from the load busses, because the opening of all the circuit-breakers would cut off the supply to the direct-current busses and thereby "kill" all the fields. As a result, the synchronous motors would likely fall out of phase and automatically open the oil switches, thus shutting down the substation. For this reason, each motor should have its field leads connected to the armature leads of the generator that it drives, and the connection should be made on the armature side of the circuit-breakers and knife-blade switches as shown in Fig. 11, which is a simple diagram of the connections of a railway unit.



FIG. 11

38. Excitation From Separate Unit.—If the main direct-current generator is shunt wound, there is some danger in using current from it for excitation purposes, as a severe short circuit on the direct-current circuit may cause the generator to lose its voltage. This would result in killing the fields of the synchronous motor, thereby causing the motor to fall out of phase. In such cases a special exciter set is safer and is generally used, though excitation by a special generator is less reliable than from the main generator leads of a compound-wound generator.

Special exciters, when used, should be installed in duplicate, as an accident to one cannot then result in shutting down the entire substation. On account of the expense of separate exciters, it is the common practice to install exciters with enough capacity to supply the fields of several or all of the main units and to connect them to special exciting busses.

Generators for exciting purposes need not be compound wound, as the load on the exciter generators is not changed except by the operator, who is then at the switchboard and at hand to regulate the pressure of the exciting busses. A separate exciter generator may be driven either from an extension of the shaft of the motor-generator or by a special induction motor.

STARTING

39. Some synchronous-motor-driven generator sets supplying direct current are used in service where it is particularly undesirable to use alternating current for starting, on account



FIG. 12

of the fluctuations in line pressure resulting from the heavy flow of starting current. These can be provided with equipment for starting with direct current, if it is always available. In this case the generator becomes, for starting purposes, a direct-current motor, and the synchronous motor acts as an alternating-current generator until synchronized to the alternating-current supply. This requires the installation of a starting resistance and starting switch *a*, Fig. 12, in the armature circuit of the direct-current generator. If the direct-current generator is compound wound, a reversing switch *b* is generally

provided for reversing the series field, in order to permit the operation of the machine as an accumulatively wound motor. To permit excitation from the machine leads during normal operation, but to provide means for excitation from the busses while starting, a split switch *c* is inserted in the shunt-field circuit. After the machine is started and the starting resistance is entirely out of circuit, the split-blade switch is used to transfer the field circuit from the busses to the machine leads. The transfer is accomplished without opening the field circuit.

The alternating-current circuits are not shown in Fig. 12. Direct-current starting, however, does not require any special alternating-current connections except that a potential transformer must be connected to one phase of the synchronous-motor armature leads to provide pressure for a synchronizing circuit.

SYNCHRONOUS-CONVERTER SUBSTATIONS FOR RAILWAYS

TYPES AND CAPACITIES OF CONVERTERS

40. Nearly all synchronous converters used in railway service are compound wound, in order that the voltage regulation may be partly automatic; because the load of a railway substation is extremely variable, and continuous attention at the switchboard would be required if shunt-wound machines were used. A compound-wound synchronous converter, if provided with a series reactance in the transformer secondary circuit, automatically regulates the potential for some distant point on the railway system.

In some cases where storage batteries are floated in parallel with synchronous converters, the compound winding has either been cut out of circuit, or shunted with a heavy copper bar, in order to avoid the unsatisfactory features of regulation that result from operating in parallel two sources of electric energy with unlike characteristics. The operation of shunt-wound synchronous converters in railway service results in poor pressure regulation on the feeder system and is seldom resorted to.

If the service is such as to require that a battery be floated on the busses, a differentially compounded booster is sometimes used in series with the battery, and the battery, with its booster, is operated in parallel with the compound-wound rotary converter.

41. The capacities of the substation units, if there are more than one, are generally so chosen that the operation of a large machine for a very small load will not be necessary. It is, of course, desirable to have more than one unit, because any disability that puts the only machine in a substation out of service results in interrupting the entire supply of the substation.

HIGH-TENSION CONSTRUCTION

42. The high-tension bus and oil-switch construction of synchronous-converter substations is made as simple and accessible as possible. If the transmission line voltage is higher than about 5,500 and lower than about 30,000, the cellular and barrier type of construction is used for the proper separation of the phase conductors after they have entered the building, or been brought out of the terminal bell of the transmission line cable.

MAIN ALTERNATING-CURRENT CONNECTIONS

43. Connection Diagram of Six-Phase Synchronous Converter.—In Fig. 13 is shown a wiring diagram of a six-phase synchronous converter that receives starting current from sectional taps on the secondary windings of the step-down transformers. The primaries of the transformers are connected Y; the secondaries are diametrically connected to the armature. The wiring of the converter is such that opposite terminals of each diametrical circuit connect to points in the armature winding 180 electrical space-degrees apart. Because of the Y connection, only .577 of the full transmission-line pressure is impressed on the primary terminals of each transformer—a desirable condition when the line voltage is 20,000 or greater.


A-C. Busses
Oil Switch
Step-Down Transformers
Positive D-C. Bus
Field Rheostat
Circuit-Breaker
Low-Voltage Release
Ammeter Shunt
Starting Box
To Fan Motor
Rear View A-C Starting Panel
Reactors
D-C. Wattmeter
To open Oil Switch
To + Operating Bus
Shunt Field
Converter Armature
Series Field
Field Break-Up Switch
Speed Limit
To Current Transformer
Grounded on Machine Frame
Equalizer
Negative D-C. Bus

FIG. 13

In order that the compound winding of the synchronous converter may be effective in performing automatic regulation of the direct-current pressure, a reactance is inserted in series with the secondary leads between the transformer terminals and the collector rings. These reactances may be self-cooling, but are generally supplied with air from the air-blast system if air-cooled transformers are used in the installation.



FIG. 14

44. Connection Diagram of Three-Phase Synchronous Converter.—On account of the superior efficiency of six-phase synchronous converters, the three-phase type is not very desirable. Fig. 14 shows the general arrangement of the wiring of the alternating-current side of a three-phase synchronous converter with delta-connected transformer secondaries. With the exception of the secondary connections, the arrangement is essentially the same as that of the six-phase unit. The direct-current connections of the two types of units are identical.

STARTING SYSTEMS

45. The alternating-current starting-switch connections of the six-phase synchronous converter, Fig. 13, are so arranged that either one-third or two-thirds of normal secondary voltage can be obtained for starting and accelerating the armature and full voltage for regular operation. Switches for starting large units are provided with carbon-break contacts.

46. Some synchronous converters are provided with induction motors for starting and accelerating the armatures. The induction motors may be supplied either from the secondaries of the transformers supplying the converters, or from a special bank of transformers used for supplying starting currents for all the units.

47. In some installations, each synchronous converter is provided with a starting-box resistance, as shown in Fig. 13, connected in the direct-current leads so that the converter can be started with direct current like a direct-current motor. Fluctuations of direct-current voltage cause variations in the speed of the motorized converter; hence, direct current from railway circuits is not convenient to synchronize railway synchronous converters. The more general practice is to get them up to speed, disconnect them entirely from the direct-current busses, and then close the alternating-current switches.



FIG. 15

48. In the three-phase installation shown in Fig. 14 the starting switch is double pole, double throw. Two of the starting pressures are taken from the middle points of two of the transformer secondaries and the third phase may be permanently connected. The running position of the double-throw starting switch is such that it connects the machine to the full-pressure terminals of the transformer. In order to secure this simple arrangement of starting circuits, the transformer secondaries are connected delta. When the star connected secondaries are used, it is necessary to use a three-pole double-throw switch connected as shown in Fig. 15. The motor is entirely disconnected from the transformer when the switch is open.

SHUNT-FIELD CONNECTIONS

49. In order that the field rheostat may be situated at or near the switchboard, the positive side of the shunt-field winding of a synchronous converter is connected to the positive armature lead at the switchboard; and, in order that the field may be properly excited whenever the machine is in operation, even though the circuit-breaker or the main positive switch *i*, Fig. 13, is open, the connection is made on the armature side of the knife-blade switch, as shown. The connection between the rheostat and the field is made by a wire or small cable that connects to the reversing field-break-up switch.

The negative terminal of the shunt field is connected to the negative lead of the armature on the armature side of the compound winding (short shunt), but it may be on the ground side (long shunt). In operation, one form of shunt connection is as good as the other, but the short shunt has the advantage of having fewer joints in the circuit, reducing the liability of an accidental opening of the shunt-field circuit.

50. The reversing field-break-up switch is provided for sectionalizing the shunt-field circuit when starting the machine with alternating current and for correcting the polarity of the machine, if it is incorrect at synchronous speed.

Sectionalization of the shunt field during starting is necessary, because when alternating current is applied to the armature when at rest or when running non-synchronously, the armature winding acts as the primary of a transformer of which the shunt-field winding is the secondary. The number of turns in the armature winding is small and the total number of turns in the shunt-field winding is quite large; therefore, if the entire shunt winding is connected, the secondary electromotive force induced may be sufficient to puncture the insulation of a field winding, or leads, and cause a breakdown. If, however, the shunt winding is sectionalized by opening the field-break-up switch, each section becomes a secondary with a much smaller number of turns, and the electromotive force induced is so small as not to be dangerous.

When starting a synchronous converter from the alternating-current side, the magnetic flux in the pole pieces is alternating until the armature reaches synchronous speed. With this method of starting, therefore, the polarity at synchronous speed is liable to be incorrect for direct-current operation. Before connecting in the shunt field, a voltmeter test is made for polarity, which, if incorrect, is reversed by momentarily throwing the field-break-up switch to the reverse position, the lower position in Fig. 13, then opening it and repeating the test. When the polarity is correct, the field switch is closed in its operating position.

EQUALIZER CONNECTIONS

51. The wiring diagram, Fig. 13, shows the rotary converter compounded and equalized on the negative, or grounded, side, which is the most common form of installation. The practice of compounding and equalizing on the grounded side has the advantage of making the equalizer switch *f*, which is usually on the machine frame, or on a small panel near it, at ground potential, and of confining to the switchboard all of the armature-circuit switches having potentials above that of the ground. The equalizer switch is placed at or near the machine instead of on the switchboard, in order to make the equalizer connection as short as possible and, therefore, to make its resistance low in comparison with that of the series fields, a condition necessary to good equalization.

52. The amount of compounding of a synchronous converter is adjusted by means of a shunt, generally of German silver, connected in parallel with the series-field winding. If the machines are alike in size, design, and characteristics, they may usually be adjusted to work well in parallel and properly divide the load in proportion to their capacities by suitably proportioning the relative resistances of their series fields and series-field shunts. If, however, they are unlike in these respects, some difficulty may be experienced in making the machines divide the load properly. The fields of a large machine may respond to changes in the series current more slowly than those of the smaller ones, and the same trouble

is experienced as with compound-wound generators. It is useless to attempt to effect any considerable change of load distribution between units by adjusting the shunts of the series fields. Though this method effectually controls the compounding of a single unit, the shunts of two machines in parallel are, in effect, equal to one shunt in parallel with both series fields. The shunts control the compounding effect of the two machines with respect to the load, but not with respect to each other. The only method of properly adjusting the load division is by a suitable adjustment of the relative resistances of the parallel paths between the equalizer circuit and the direct-current bus of the same polarity, each path including a series field.

AUXILIARY-MOTOR CONNECTIONS

53. A fan supplying air for cooling transformers in a direct-current railway substation can be driven by a motor taking direct current from the railway bus, or by an induction motor supplied with current from the secondary of the transformers of one of the converter units, the latter method being the more general practice. A direct-current motor stops whenever the bus is killed by the automatic operation of all of the machine circuit-breakers and must be started after each interruption. This difficulty is sometimes obviated by having a small power bus receiving its supply from the machine leads on the machine side of the knife-blade switches *a*, Fig. 16. By a selective system of switches *b* current for the auxiliary-power supply can be taken from any machine. However, the scheme shown in



FIG. 16

Fig. 16 introduces the liability of operating errors; induction motors are cheaper and more reliable.

54. Induction motors for air-blast fans are three-phase and are wound for operation on the three-phase secondary voltage, usually about 360 volts, of the synchronous converters. For these motors, there are two forms of starting equipment. One form consists of a double-throw switch; one side has no fuses in circuit and is used for starting the motor at full potential, and the other side has fuses that are in circuit during normal operation. The switch should be connected to the three transformer leads *a*, Fig. 13, that go directly to the armature collector rings, or else to the leads *b* on the machine side of the secondary starting switches in preference to those on the transformer side. With either of these connections, it is impossible to operate the fan motor when the synchronous-converter armature is at rest, even though the transformer may be alive.

55. If the substation transformers are oil-and-water cooled, a small motor is sometimes required for operating the pump to circulate water through the cooling coils. This motor is connected in the same manner as the motor for driving the air-blast fans.

INSTRUMENT, RELAY, AND PROTECTIVE-DEVICE CONNECTIONS

56. Instrument and Relay Connections.—The instrument connections on the direct-current end of a synchronous converter are the same as for a direct-current railway generator. The alternating-current end of the unit has overload relays, alternating-current ammeter, power-factor indicator, and, sometimes, an alternating-current wattmeter.

With respect to the connection of overload relays there is no fixed practice. Some installations are made with three overload relays supplied from three current transformers, one of which supplies current to the alternating-current instruments also. In other installations, one current transformer supplies the ammeter, one supplies the power-factor indicator, and a third the wattmeter, and each supplies one overload relay.

One side of the secondary of each current transformer is connected to a common ground, usually a ground plate, to which is connected the ground return of all the instruments. The other terminals of the current transformers connect the instruments and relays; the remaining terminals of the instruments and relays are connected to a small ground bus that leads to the ground plate.

Current transformers are most satisfactory when working with very little resistance in their secondary circuits, and for this reason some installations are made with one current transformer for the instruments and two for the overload relays, as shown in Fig. 17. This form of connection is suitable for installations in which the transformer primaries are delta connected, but is not generally used with star-connected transformer primary windings, where it is desirable to have overload protection on each phase separately.

Current transformers are inserted in the primary circuit between the oil switch and the transformers and as near to the oil switch as is convenient.



FIG. 17

57. An alternating-current relay *c*, Fig. 13, can be arranged to close the operating circuit through the solenoid of a second relay *d* with two contactors, one of which short circuits the low-voltage release coil of the direct-current circuit-breaker. The other contactor short circuits the contact points of the relay *c*, thus completing a circuit through the solenoid of the relay *d*, electrically locking it in the closed position, regardless of the position of the alternating-current relay *c*, and insuring the opening of the oil switch.

An ammeter *e* is usually connected in the field circuit of a synchronous converter.

58. Operating-Bus Supply.—A supply of direct current for operating the substation oil switches is sometimes taken

from the direct-current railway bus. This practice is not common, because oil-switch operating devices are generally wound for 110 to 125 volts and it is difficult to obtain good results by deriving the supply for their operation from 550- or 600-volt circuits.

The supply can be obtained from the railway bus by either of two methods. In one method, a fixed resistance is inserted in series with the supply to the operating circuits to reduce the potential drop across the windings of the operating devices to about 125 volts. This method is objectionable for two reasons: It causes the cut-out devices in the operating circuits of the oil switches to break a heavy arc at practically the full potential of the railway circuit and results in serious burning of the contacts. In addition, the resistance, though correct for giving the proper voltage when supplying 15 or 20 amperes for operating a switch, is too little for cutting down the pressure for the pilot lamps of the oil-switch circuits. Another method is to use a resistance through which a current passes continuously and to tap the resistance at such a point as to obtain 125 volts for the operation of oil switches and pilot lamps. The operating devices and pilot lamps then become paths in parallel with a part of the resistance.



FIG. 18

Both of the methods just explained are objectionable in operation and both have the serious defect of being inoperative when the substation is shut down, because there is then no supply of current to operate oil switches to start the substation machinery. It is more general practice to install a small storage battery of about sixty-five cells and having a capacity of 20 to 40 amperes. The battery is charged from the 550- or 600-volt railway bus with a resistance in series, as shown in

Fig. 18, or, in some installations, by means of a mercury-arc rectifier.

59. Lightning Protection.—If the ratio of transformation of the step-down transformers of a substation is large, there may occur on the secondary circuits momentary voltages greatly in excess of the normal potential and sufficient, under certain conditions, to cause a puncture of insulation between conductors and the armature core or other grounded parts of the converter and thus to present a path for the large currents, which may have very destructive effects. These so-called *static disturbances* are reduced in extent by connecting a small aluminum cell lightning arrester across the direct-current terminals of the synchronous converters.

60. Speed-Limit Device.—In order to protect a synchronous converter against the possible destructive effects of overspeeding—which sometimes occurs if the alternating-current supply is interrupted and the machine back-feeds into a line short circuit, or which is certain to occur if the field circuit is opened when the machine is running as a direct-current motor—a speed-limit device is used to open automatically the circuit-breaker when the speed reaches a predetermined value. The circuit-breaker is opened by the short circuiting of its low-voltage release coil by a centrifugal device on the shaft. The speed-limit device is usually adjusted to open the armature circuit when the speed is about 15 or 20 per cent. above normal.

61. Reverse-Current Protection.—When a synchronous converter is operated in parallel with a storage battery, either with or without a booster in series with the battery, it is desirable to install reverse-current protection to prevent the machine from inverting from the battery into a line short circuit.

Reverse-current relays are made in different forms. One form in general use on railway systems is actuated by the magnetic field that surrounds the machine lead and makes a contact that operates a relay. The contacts of the relay are so connected as to short-circuit the low-voltage release coil of the circuit-breaker and thus to cause the circuit-breaker to open.

PORTABLE SUBSTATIONS

62. On large railway systems, even though the distribution system was originally designed of ample proportions to meet all normal conditions, events are likely to occur that attract unusual travel in certain directions at irregular intervals. A special attraction at any point may necessitate running, for a short period, many cars on a branch that ordinarily handles but two or three. The system must be prepared to meet these extra demands; but the installation of sufficient capacity in feeders and substations necessitates an investment that, during a large portion of the time, yields no return. In order to meet these temporarily heavy demands with the least expense, a certain flexibility of distributing system is demanded, so that the increased capacity may be easily and quickly moved from one line to another as the conditions may demand. On a number of systems this flexibility has been attained by the use of portable substations. Practically the same apparatus as is used in a permanent substation is assembled in a specially arranged car having very much the appearance of an ordinary freight car. This car can be hauled to any place to which the high-tension lines have been extended, run on a siding, connected up, and put into service in a very short time.

SYNCHRONOUS-CONVERTER STATIONS FOR LIGHT AND POWER

FUNDAMENTAL SYSTEMS OF CONNECTION

63. Synchronous-converter substations for general light and power commonly supply three-wire systems operating at about 110 to 125 or 220 to 250 volts. In many cases Edison three-wire systems are supplied, and 220- to 250-volt machines are connected to the two outside conductors of the system with a derived-neutral connection to the neutral conductor of the three-wire system. In some cases, two synchronous converters delivering voltages of from 110 to 125 are connected


Oil Switch
Current Transformers
Step-Down Transformers
Secondary Coils of Induction Regulator
a
+
Converter Armature
−
Shunt Field
Rheostat
f
e
e
d
c
+ Bus No 1
+ Bus No 2
b
− Bus No 1
− Bus No 2

FIG. 19

to the three-wire system in the same manner as a pair of 110-volt generators. In other cases, a 250-volt converter is arranged to feed into the two outside conductors of the three-wire system, with the neutral in no way connected to the converter armature, as in Fig. 19, which shows the main connections for a six-phase shunt-wound machine.

64. Main Connections.—The installation shown in Fig. 19 is of a form in quite general use. Having no neutral connections, the unit is unable to supply an unbalanced load. Any unbalancing must be carried by a balancer set or by a storage battery.

In Fig. 19 the transformer primaries are shown connected delta, although this is not essential; if the installation were to operate on very high voltage, star connection would be used. The secondary connections shown are double-delta, six-phase, the six-phase relation being obtained by dividing the secondary windings of each transformer into two equal and independent parts, connecting the first in delta and the second in a delta reversed with respect to the first. With this arrangement there are two separate secondary deltas out of phase with each other by 180°. These connect through a six-phase induction-type potential regulator to the collector rings of the synchronous converter.

The synchronous-converter armature is connected to the direct-current bus through a circuit-breaker *a* in one lead, either positive or negative, and a knife-blade switch in each lead. When a duplicate direct-current bus system is installed, as shown, the knife-blade switches *b* and *c* are double-throw, in order that the machine can be connected to either set of busses.

The positive lead of the machine has a tap to which a starting circuit, not shown in Fig. 19, is connected for starting the converter as a direct-current motor. One starting bus and one starting resistance may be used to start all of the machines in the substation.

The connections of the three-phase delta-connected system are very similar to those shown in Fig. 14. Like the six-phase

double-delta connections, they cannot be used for supplying a derived neutral.

65. Protective Devices.—The circuit-breaker *a*, Fig. 19, is installed to open the armature circuit in the event of excessive speed of the machine and to disconnect the machine if the current reverses in direction in a predetermined amount. The reverse-current feature is sometimes omitted, as it has been found that the machine is thereby occasionally disconnected from the direct-current bus at times when the continuity of service should be preserved. The circuit-breaker is sometimes, though less frequently, used to disconnect the unit from the bus in the event of a severe overload.



FIG. 20

In Fig. 20 are shown the essential connections of the operating circuit of the circuit-breaker. The coil of the reverse-current relay *a* is energized from a special connection so situated inside the ammeter case as to make contact with the counterbalance of the needle when the pointer is in a position for indicating a reversal of current in a predetermined amount. When this contact is made, current passes through the armature coil *b* of the instrument, holding the needle firmly in position against the relay connection, thus perfecting the contact, and then passes through the relay coil *a* and through an auxiliary switch *c* on the circuit-breaker *d*. The auxiliary switch opens the relay circuit as soon as the circuit-breaker opens, and thus protects the winding of the relay coil and the armature coil of

the ammeter from a continuation of the comparatively heavy current that passes during the brief time required for opening the circuit-breaker.

The circuit closed by the speed-limit device *e* is connected



FIG. 21

between the operating bus, or the load bus, and the operating coil of the circuit-breaker. This system of speed-limit protection differs slightly from that shown in Fig. 13, in which the speed-limit device short-circuits the low-voltage release.



FIG. 22

66. Shunt-Field Connections.—The shunt-field circuit, Fig. 19, can be connected to either of the duplicate load busses by means of double-throw selector switches *d*. In addition, quick-break switches *e* and a field discharge resistance *f* are provided.

In Fig. 21 is shown a connection by which a synchronous converter can be excited from the load bus for starting and by which, after starting, the field switches are mechanically locked and electrically connected to the knife-blade switches of the

armature. After the machine is synchronized and the field switches are locked and connected to the blades of the armature switches, the armature switches can be opened, if necessary, and the field circuit will remain excited from the machine leads. The unit is provided with double-throw switches for selective connection between two direct-current busses and may be transferred from one bus to another without the danger of killing its field circuit.

In Fig. 22 is shown a simpler scheme by which the field circuit is connected through quick-break switches *a* to the machine leads. This arrangement also permits self-excitation while transferring the unit between busses. When this form of connection is used, the starting resistance is connected across one of the circuit-breakers, in order that the synchronous converter may have full-field excitation when the starting resistance is in circuit.

THREE-WIRE SYSTEMS WITH DERIVED NEUTRAL

67. Methods of Deriving Neutral.—In Fig. 23 is shown a wiring diagram of a six-phase, 250-volt, synchronous converter with diametrically connected (double-star) transformer secondary windings and a derived neutral. This arrangement is superior to the one shown in Fig. 19, as the middle points of the diametrical winding afford a source of neutral potential. As the secondary of each transformer, Fig. 23, is connected across the armature to points 180 electrical space-degrees apart, the potential of the middle of the secondary winding is midway between that of each of the outside terminals of the armature. This is the potential of the neutral conductor of a properly balanced three-wire system. Since the middle points of each of the three diametricals are of the same potential, they are connected to the neutral of the three-wire system, and the synchronous converter is able to supply current to an unbalanced load. The neutral current then passes back through the neutral connections of the transformer secondary.

A switch *a*, Fig. 23, is installed in the neutral lead, in order that the neutral circuit may be opened when the machine is to be started with direct current. Assuming the starting


To High-Tension Oil Switch
Current Transformers
Neutral
Induction Regulator Coils
Converter
Armature
Circuit Breaker
Ammeter
Ammeter
To Reverse Current Relays
Bus No.1
Selector Switch
Bus No.2
Bus No.1
Bus No.2

FIG. 23

resistance to be in the positive lead, the negative switch should not be closed when the neutral switch is closed and the armature is at rest. The other machines would then send current from the neutral of the system, through the synchronous-converter armature, through one-half the transformer secondaries, to the negative bus. This path is one of very low resistance and would constitute a short circuit on the negative side of the three-wire system.

68. When taps from the middle points of the transformer secondaries are not available, a derived neutral is sometimes obtained by connecting a suitable reactance, or one winding of a transformer, across two properly selected secondary leads and connecting the middle point of this reactance or winding to the neutral of the three-wire system. The other winding of the transformer so used is left open-circuited and inactive. A reactance serves the purpose as well as a transformer,



FIG. 24

and, being considerably cheaper, is generally used in preference to the transformer. The transformer coil or the reactance coil, as the case may be, must be connected to points of the armature 180 electrical degrees apart, as, for example, to collector rings No. 1 and No. 4, to No. 2 and No. 5, or to No. 3 and No. 6.

69. Another form of derived neutral connection for a six-phase machine is made by the use of three transformer windings or reactances connected in star, with the neutral point connected to the neutral of the three-wire system and the other three terminals connected to points in the armature winding

120 electrical degrees apart; that is, in this case to alternate collector rings, as, for example, Nos. 1, 3, and 5 or Nos. 2, 4, and 6.

The method of deriving a neutral from star-connected transformer secondaries for a three-phase machine is shown in Fig. 24.

70. Miscellaneous Connections.—A synchronous converter with a derived neutral and with one side, either positive or negative, connected to the neutral can be operated as a two-wire unit with a rather limited capacity. The machine can also be motorized through a circuit consisting of the neutral connection and either the positive or negative lead. Therefore, when the neutral switch is closed, the armature circuit is not completely opened unless both positive and negative conductors are open-circuited. For this reason two circuit-breakers, as shown in Fig. 23, are necessary in connection with the unit having a derived neutral. The operating coils (not shown) of the circuit-breakers are connected in parallel.

Ammeter, relay, and shunt-field connections are the same as those described in connection with Figs. 19 to 22, inclusive.

TWO CONVERTERS SUPPLIED FROM ONE BANK OF TRANSFORMERS

71. Two synchronous converters for operation on three-wire systems are sometimes connected to one bank of transformers. When this is done, the transformer secondaries may be wound for supplying 77 volts, three phase, to the machines, which are connected in parallel to the transformer secondary terminals. Another form of connection has each secondary divided into two parts; each part supplies 77 volts, and one unit is connected to each set of secondaries, as shown in Fig. 25. Since both of the converters are supplied from one set of transformers, the primary oil switch of the set cannot be satisfactorily used for synchronizing, and it is therefore necessary to use secondary switches, not indicated in Fig. 25, in the leads to each rotary converter. The practice of synchronizing with secondary switches is not uncommon, even in connection with

large units, and there are in regular operation many rotary converter installations of large capacity that are synchronized



FIG. 25

to the transformer secondaries by means of heavy secondary switches, some of which are adapted for remote control.

STARTING

72. Starting With Alternating Current.—Synchronous converters used in lighting and power work and having six-phase diametrically connected transformers can be started with alternating current by using the same form of starting connections as those used on railway machines. The starting connections,

however, require some special arrangement when used with units with derived neutrals, as it is necessary to provide for separating the neutral connections to the transformer secondaries during starting. Fig. 26 shows the arrangement of the secondary circuits of a rotary-converter unit for starting with one-half the normal secondary voltage. The neutral point



FIG. 26

of each secondary winding is brought out to a three-pole, single-throw switch *a* that connects the neutral points together during operation but is opened while starting. A three-pole double-throw switch *b* provides a means of supplying the converter with one-half normal secondary voltage for starting and full voltage for running.

73. Starting With Direct Current.—Fig. 27 shows the essential connections for starting a rotary converter with direct current from the load bus. During starting operations, the main positive switch *a* is open and the armature is supplied through the resistance. After the machine is synchronized, the main switch is closed and the starting switch is opened.



FIG. 27

The connections shown in Fig. 27 require a separate starting resistance for each machine. In order that one starting box may serve for a number of machines, a small starting bus *a*, Fig. 28, connected to one of the main busses through the starting resistance, is used. Each synchronous converter can be connected to the starting bus by means of a starting switch *b*. Two starting resistances can be arranged in conjunction with a double-throw switch *c* so that either can be used for starting any machine in the substation. The starting resistance is usually proportioned to carry the starting current for only one



FIG. 28

machine, and the attempt to start two or more machines simultaneously would probably burn out the resistance. Starting switches such as shown in Figs. 27 and 28 should be left open except when needed for starting a machine.

SYNCHRONIZING CIRCUITS FOR ROTARY CONVERTERS

74. Circuit With Secondary Switches.—In order that synchronous converters that are started with direct current may be properly synchronized to their sources of supply, it is necessary to install suitable synchronizing circuits and devices. These synchronizing devices and connections do not differ in principle from those used in generating stations. There are, however, some special adaptations that require brief descriptions.



FIG. 29

Converters synchronized to the secondaries of their transformers with secondary switches have the simplest form of synchronizing circuit, as no step-down pressure transformers are necessary. If synchronizing lamps are used, they



FIG. 30

are connected across the secondary switches as shown in Fig. 29, in which the circuit is arranged for synchronizing by dark lamps.

75. Synchroscope Connections.—When a synchronism indicator, or *synchroscope*, is used, it is desirable to have one instrument for use with all the units in the substation. This is accomplished by an arrangement shown diagrammatically in Fig. 30, which is a form of connection suitable for use with ungrounded synchronizing circuits. The simpler arrangement using grounded circuits cannot always be used in this case, as it would result in grounding the phase leads of the transformer secondaries and of the rotary converters.

When the units are synchronized with the transformer primary circuit, the high voltage on the supply side of the synchro-



FIG. 31

nizing switch makes necessary the use of step-down potential transformers. There is usually no objection to grounding one terminal of the potential transformer secondary coil to permit simplifying the synchronizing circuit. In Fig. 31, one synchronizing bus *a* is connected to the armature and the other *b* is connected to the field winding of the synchronism indicator. The potential transformer *c* connected to the high-tension busses has a ratio of transformation such as to give a secondary voltage suitable for the instrument. A potential transformer *d*

connected to the secondary leads of the step-down transformers supplying the rotary converter has such a ratio as to deliver the same voltage as the potential transformer on the high-tension bus. Each potential transformer has one terminal of its secondary winding grounded. The connections of the synchronism indicator are then as shown.

76. Alternating-Current Voltmeter Connections. In order that a rotary converter when synchronized to the supply may not immediately take up too much load, either direct or inverted, it is necessary that the voltages on both sides of the synchronizing switch be equal. In order that the voltages can be observed, an alternating-current voltmeter is connected to a multiple-point voltmeter switch wired to each source of synchronizing current.

AUTOMATIC SYNCHRONOUS-CONVERTER SUBSTATIONS

77. Definition.—A synchronous-converter substation is considered to be automatic when the various functions of starting, stopping, and regulating the converter are performed without the presence of an attendant in the station with the machine. Such of the control apparatus as are not automatic are manipulated by an operator located in a distant controlling station, which may be another substation.

78. Purpose.—Automatic synchronous-converter substations are useful where central-station service in a given district is to be improved, yet the load density in that district is not great enough to warrant the expense of maintaining an attended substation. With the automatic substation, the expense of heating the building is saved and the labor expense is reduced to the cost of daily inspection.

79. Starting.—A synchronous converter in an automatic substation is most conveniently started as an alternating-current motor, reduced voltage during acceleration being obtained by means of a starter in the controlling station.

The field break-up switch is automatic; just before the converter reaches synchronous speed, a special governor on its shaft closes the control circuit of contactors that operate to connect the field circuit to the direct-current bus-bars so as to give a field of the correct polarity. The voltage of the converter is then raised by means of an induction regulator in the controlling station. At the moment that the voltage across the brushes exceeds that across the bus-bars, the converter is automatically connected to the direct-current system by the operation of a differential contact-making voltmeter. This voltmeter closes the circuit through the closing coils of the circuit-breakers whenever the direct-current voltage of the converter exceeds the bus voltage by a small percentage.

80. Regulation.—Voltmeters connected through pressure wires to various points in the portion of the network supplied by the automatic substation inform the operator at the controlling station of the voltage conditions on the system, and the load on the converter in the automatic station is changed accordingly. Changes in load are effected by manipulating the induction regulator in the controlling station. The amount of load on the converter at any time is indicated by alternating-current ammeters, an indicating wattmeter, and a power-factor meter in the controlling station. Complete overload, underload, and reverse-current protection is provided.

81. Stopping.—The rotary converter is stopped by disconnecting the alternating-current supply at the controlling station. This permits the machine to rotate as a direct-current motor taking a reversed current sufficient in amount to operate reverse-current relays. The operation of the reverse-current relays opens the main circuit-breakers and disconnects the converter from the direct-current bus-bars. As the machine slows down, the field contactors open, breaking up the field winding, and everything is automatically placed in readiness for a new start.

The commutating-pole type of synchronous converter cannot be used in an automatic substation unless a special automatic mechanism is provided for raising and lowering the brushes.

ALTERNATING-CURRENT SUBSTATIONS

FREQUENCY-CHANGER SUBSTATIONS

INDUCTION-MOTOR-DRIVEN FREQUENCY CHANGERS

82. Motor-generators used as frequency changers are of two kinds: those consisting of alternating-current generators driven by induction motors and those of which the generators are driven by synchronous motors.

The induction-motor-driven sets are undesirable if close regulation of frequency is required, and they cannot be used for inverse operation, that is, for frequency conversion except in one direction. One form of induction motor used for driving generators of frequency-changer sets is constructed with a wound rotor provided with slip rings on the shaft and with brushes and leads connecting to an external resistance. With an induction motor of this type, the speed of the machine can be regulated for synchronizing the generators and also for effecting control over the distribution of load between units. With motors having wound rotors, the resistances in the rotor circuits are considerable, and a suitable form of control is provided so that the speed of the motor can be regulated from the switchboard.

The design of a substation containing frequency changers driven by induction motors is of the simplest kind; the induction-motor installation being such as has already been described. The design of the generator installation should be similar to that of a steam-generating plant with alternators of the same size and capacity.

SYNCHRONOUS-MOTOR-DRIVEN FREQUENCY CHANGERS

83. Synchronous-motor-driven frequency changers are more complicated than those driven by induction motors, and attention to details of connections is necessary if more than one

unit is to be installed. The synchronous-motor installation should be along the lines already described; the high-tension busses, oil switches, step-down transformers, air-blast equipment, starting facilities, synchronizing circuits, exciting apparatus, and synchronous motors differ in no particular respect from a synchronous-motor installation for driving a direct-current generator, except that the speed of the unit must be common to the two frequencies. When the frequency of one end of the machine is double that of the other, as, for example, fifty and twenty-five cycles, there is a wider range of speeds for the machine designer to choose from. If the ratio between the frequencies is not a whole number there is usually but one speed practicable.



FIG. 32

84. The alternating-current generator of a frequency-changer set is connected to the same kind of switchgear as would be used in a steam plant using similar generators, and, although there is no speed control of incoming units, it is necessary to install synchronizing circuits and, in some cases, a synchroscope.

In Fig. 32 is shown, roughly, the rotor of a synchronous motor-generator. The assembly consists of a four-pole field N, S, N_1, and S_1 and an eight-pole field n_1, s_1, etc. mounted rigidly on the same shaft. If the four-pole end is to be considered as a motor, it is convenient to assume that the supply is obtained from a four-pole, revolving-field alternator and is transmitted through a line having no reactance. Then, when the motor runs without load and at synchronous speed, the center line through one of its north poles N or N_1 will be parallel to a line $o\,a$ imagined to be rotating about the motor-generator shaft in unison with the center line of one of the north poles of the alternator. Each north pole of the four-pole end of

the motor-generator lines up with a north pole of the eight-pole end; therefore, the generator end, in this case the eight-pole end, will be in phase with a similar unloaded unit already in operation from the same supply.

An examination of Fig. 32 shows that two north poles of the eight-pole end line up with north poles of the four-pole end, and two north poles of the eight-pole end line up with south poles of the four-pole end. Therefore, when the eight-pole end, operating as a motor, reaches synchronism, the four-pole end, now acting as a generator, may be in phase or 180 electrical degrees out of phase with the generator end of a similar unit driven from the same source of supply.



FIG. 33

85. From the preceding, the following general statements are derived:

If the number of poles of one end of a synchronous motor-generator is double that of the other, the synchronizing instrument can be dispensed with, and voltmeter indications can be relied on for paralleling the generator end with a similar unit. When the low-frequency end of such a machine is operating as a motor, no synchronizing equipment of any kind will be needed. If the high-frequency end is used as a motor, an indicating voltmeter connected between a generator terminal of one machine and the corresponding generator terminal of the other will indicate nearly zero voltage if the two generators are in phase or about double voltage if they are 180 electrical degrees out of phase. The generators must be brought into phase before connecting them in parallel.

86. If, however, the frequency change is not in the ratio of 1 to 2, or 2 to 1, the possible phase relations between generators are more complicated. In a 25-cycle–60-cycle motor-generator the frequency of one end is 2.4 times that of the other, and for every cycle, or 360 electrical degrees, of the 25-cycle end, the 60-cycle end will have 2.4 cycles, or $2.4 \times 360 = 864$ electrical degrees. The usual arrangement of the rotor of a 25-cycle–60-cycle synchronous motor-generator is shown in Fig. 33, ten poles on the 25-cycle end and twenty-four poles on the 60-cycle end. The diagram shows that only one north pole of one end is in line with a north pole of the other end. Therefore, if one motor-generator is in operation, motorized on the 25-cycle end and without load, and another similar set is started, there will be five different relative positions in electrical phase which the generators may bear to each other, only one of which would be correct for paralleling. This phase relation will remain constant because both motors are operating synchronously and, therefore, there is no difference in frequency of the generators. In order to change the phase relation it is necessary to advance or retard the motor in electric phase, which is accomplished in the manner described in *Operation of Electrical Machinery*, Part 2.

TRANSFORMER SUBSTATIONS

TRANSFORMER SUBSTATIONS FOR RAILWAYS

87. For railway systems employing only alternating-current motors on the cars, the substations, where used, contain protective devices, transformers, control equipment, and indicating instruments. No moving machinery is employed, and, aside from inspection and resetting of circuit-opening devices, the substation requires little attention. Sometimes, the substation is so located that an employe engaged on other work may, when necessary, be called by an automatic signal to attend to the circuit-breakers.

In Fig. 34 is shown a set of connections for a transformer substation of a single-phase railway system. Time-limit relays are

provided to open the circuits in case of a serious short circuit of considerable duration, but for slight overloads or temporary short circuits, the relays do not allow the substation to be cut out. Differential relays are installed to open the circuit in case the trolley line, owing to some disorder, causes the transformer secondary coil to act as a primary.

Transformer substations are generally equipped with voltmeters, or potential indicators, and ammeters for use in the



FIG. 34

location of faults. Both the high- and the low-tension feeders are equipped with lightning arresters. The main transformers must be of the self-cooling oil type.

TRANSFORMER SUBSTATIONS FOR LIGHT AND POWER

88. For central-station work, transformer substations are used where the frequency of the current in the distributing system is the same as that of the current in the transmission

lines, but the voltages are different. Such a substation, in its simplest form, may contain only one transformer with switches but without other switchgear except, perhaps, lightning arresters. Voltage regulation in such cases can be obtained by means of voltage regulators at the generating station. In other cases, the number of feeders is large enough to require equipment with potential regulators and the presence of an operator during the periods of heavy load. In the larger substations, when the service is important, two incoming high-tension lines with a tie-switch between them are provided so that the entire substation load can be carried on either line. As in railway substations, switches must be provided on each side of each transformer so that any transformer can be completely isolated from the system. When there are more than three or four feeders outgoing from a substation, the low-tension busses are preferably installed in duplicate, necessitating the use of double-throw switches. In the usual four-wire, three-phase, feeder system each phase is independent, and single-pole feeder switches are therefore employed, as it is both unnecessary and undesirable to open all phases when trouble occurs on only one.

89. Outdoor Substations.—In large hydroelectric developments in which energy is transmitted over long distances at very high voltages, large outdoor substations are frequently employed. In these outdoor transformer substations, the high-tension apparatus is installed outdoors and the low-tension apparatus in a switch house. Transformers, oil switches, and electrolytic (aluminum-cell) lightning arresters rest on concrete foundations in the open. High-tension leads and bus-bars are supported by steel structures on concrete. These structures, as well as the transformer tanks, are thoroughly connected to a ground bus.

The transformers of the larger stations are generally of the oil- and water-cooled type; in smaller stations, the self-cooling oil type can be used. The high-tension oil switches are generally of the remotely controlled type, solenoid-operated. Automatic control is secured by the use of inverse time-limit relays.

Disconnecting switches of the horn-gap type are placed so as to be operative from the ground, and, in most cases, are provided with safety catches to prevent accidental opening. Hoods over the switches prevent the formation of sleet on the safety catches.

The transformers are frequently mounted on wheel bases, so that, if necessary, a transformer can readily be placed on a truck and transferred.

The chief advantages of outdoor transformers over those of the indoor type are lower first cost, ease of making extensions, lower fire hazard, and simplicity of layout. It is estimated that the cost of a small outdoor substation is from 25 per cent. to 50 per cent. below the cost of an indoor substation of the same capacity. This saving decreases, however, as the size of the substation increases. Some of the precautions to be observed in operating outdoor substations is to use only low-temperature electrolyte in the aluminum lightning arresters, to guard against freezing of the water in water-cooled transformers, and to enclose the apparatus so that neither persons nor animals can be injured by coming in contact with high-tension circuits.

OPERATION OF ELECTRICAL MACHINERY

(PART 1)

INTRODUCTION

PRELIMINARY INVESTIGATION

1. Immediately on taking charge of any electrical machinery, the operator should acquaint himself thoroughly with the nature of the apparatus that will be under his care, including the scheme of connections of each unit, the connections of all of the auxiliaries and operating devices, all of the mechanical details, the normal and safe overload capacities of the equipment, all regular and any special limitations as to the performance of the equipment, and all sources of danger of physical injury. Unless entirely familiar with his plant, the operator may be unable to proceed properly in trying to locate defects in the equipment; he may damage the apparatus by overloading it, or may expose himself to serious personal danger or even to loss of life.

SAFE OPERATING TEMPERATURES

2. It is important that the operator bear in mind and apply in practice certain temperature limitations that experience has indicated to be proper. Temperature limits, often considerably lower than the temperatures at which immediate damage occurs, may, if long continued, cause insulating materials

COPYRIGHTED BY INTERNATIONAL TEXTBOOK COMPANY ALL RIGHTS RESERVED

to deteriorate gradually, leading to eventual breakdown, or may so change the magnetic properties of an iron core as to cause it always afterwards to heat seriously in normal operation.

3. Insulation made up of cotton tape and linseed oil, which is quite generally used for insulating the windings of air-blast-cooled transformers, should not be operated at a temperature higher than about 90° C., or 194° F. It is much better not to exceed a temperature of 80° C., or 176° F., as this lower temperature causes much less rapid deterioration. At a little above 90° C. is the critical temperature at which the insulation begins to carbonize, a process that gradually converts insulation into a conductor, thus reducing its insulating and dielectric properties, a condition favorable to breakdown.

Cotton insulation painted with black asphaltum insulating paint, such as is commonly used for insulating armature windings of low-tension machines, is able to stand about the same temperatures, but the process of deterioration is generally somewhat slower.

4. Magnetic cores of transformers and generator armatures are made of a special grade of steel with a high permeability, in order to reduce the hysteresis losses. If, however, the steel is subjected to too high a temperature, even for only an hour or two, its magnetic properties may be so impaired that it will always afterwards have larger hysteresis losses and, consequently, will heat unduly, even under light loads. This effect becomes accumulative in some degree; the greater losses produce higher temperatures, which still further damage the iron. Experience has shown that for the grades of steel now in use for magnetic cores, the temperature limits given above for cotton insulation are about correct.

5. Knife-blade switches so constructed as to depend partly on elasticity, or spring effect, of the copper parts for tightness of electric contact should never be heated to the point at which the temper of the copper is reduced. Operation at a lower temperature may be carried on without injury. As commercial copper differs so much in quality, it is impossible to

name the critical temperature at which the temper is drawn, but, for many kinds of switches in use, it is about 75° C., or 167° F.

6. **Bare copper** used for conductors into which the joints are secured by more reliable means than the spring effect, as, for instance, by bolts, may be much hotter without injury, and a temperature of 212° to 230° F. would not be dangerous. However, it is important to observe whether or not the high temperature is causing expansion of the copper, which may

TABLE I

SAFE TEMPERATURE OF TRANSFORMER OIL

Per Cent. of Full Load	Excess Temperature of Coils Over Oil Degrees C.	Safe Temperature of Oil, Coils at 90° C. Degrees C.
40	2	88
60	4	86
80	7	83
100	10	80
120	15	75
140	20	70
160	26	64
180	33	57
200	40	50

result in a mechanical strain at any of the joints, a condition that might cause poor contact and excessive heating at the joint.

7. **Bearings** of machines should not be operated at temperatures that would cause the Babbitt to soften, but if the bearings are kept properly oiled there is not much danger of this trouble. Babbitt bearings may be safely run at 160° F., or 71° C., and brass bearings still hotter. If the hand can be held on the outside of a bearing without great discomfort, the temperature is usually safe. It should be borne in mind that the internal temperature of a bearing is much hotter than the

external, and the sensation experienced by placing the hand on the outside of the bearing should be only a guide to enable the operator to judge as to the internal condition.

8. Oil used for cooling transformers is partly carbonized by long, continued overheating. The result is the formation of a thick, muddy deposit, which settles in the oil passages and, in time, so obstructs the circulation of oil as to cause overheating of the transformers. The temperature of the oil may be regarded as a fairly good means of obtaining the approximate internal temperature of the coils. The values given in Table I may be safely used for this purpose. The temperature of the oil is taken at the surface and near the transformer casing.

OPERATION OF ELECTRIC MOTORS

DIRECT-CURRENT MOTORS

PRELIMINARY INSPECTION

9. A direct-current motor, when set up and connected, should, before being started, be given a critical inspection, with a view to determining its mechanical and electrical condition. The armature must rotate freely in its bearings, all the electric contacts must be good, the machine anchored securely in its position, the connections correct, and the brushes well seated and under proper tension on the commutator.

SHUNT MOTORS

10. **Starting.**—Direct-current motors larger than about $\frac{1}{8}$ horsepower are, in almost all cases, started at a suitably reduced voltage, in order to avoid too great a current, which might injure the windings. The most common method of obtaining the reduced pressure for starting is by means of a starting box, or rheostat, inserted in the armature circuit. The procedure in starting a motor so equipped is as follows:

1. See that the starting resistance is all in circuit, that is, the arm of the rheostat is in the starting position.

2. Close the main armature switch (line switch) or circuit-breaker.

3. Slowly move the arm of the starting rheostat from its initial position, point by point, until it has reached the limit of travel and all the resistance is cut out. If, instead of a simple starting box, the starting resistance is also used to control the speed, stop cutting out resistance when the desired speed has been reached.

4. If the starting box, or speed controller, has an automatic low-voltage release, see that the arm is securely held in place by the retaining magnet.

5. Examine the motor to see if the bearings are getting sufficient oil and if the commutation is practically sparkless.

If the motor fails to start on the first step, the rheostat arm should be moved promptly to the second step and, if necessary, to the third step. If the motor fails to start on the third step, the line switch should be opened at once, the rheostat arm allowed to go to the off-position, and an inspection begun for faulty connections, overload, etc.

The foregoing instructions do not, of course, apply to motors equipped with automatic starters.

11. Time Required for Acceleration.—The time required for speeding up the armature of a direct-current motor is dependent on the size and weight of the rotating mass. An armature of a 1-horsepower motor should ordinarily not require more than about 15 seconds for bringing it from rest to full speed. If, however, there is mechanically connected to the armature, either by direct coupling or by belt, a rotating body having a large amount of weight at a considerable distance from the center of rotation, the time of acceleration should be considerably increased. Failure to observe this precaution may result either in blowing the fuse in circuit with the motor or, possibly, in damaging the motor armature. Twenty-five seconds is ordinarily sufficient for speeding up a motor of from 25 to 75 horsepower if there is no heavy connected load, and

motors up to 500 horsepower may be accelerated in from 60 to 70 seconds.

If there is an ammeter in the motor circuit, its indications will be the best possible guide as to the proper rate of cutting out starting resistance. If the starting rheostat has a considerable number of contact points, as, for instance, ten or fifteen, the rheostat arm may be moved just fast enough to prevent the current from becoming greater than about 80 per cent. of the initial rush of starting current. If the starting rheostat has only a relatively small number of contact points, as, for instance, from three to six, the arm or switch blade should be held at each point until the current, as indicated by the ammeter, has practically stopped decreasing in value, at which time another section of resistance should be cut out.

When ammeters are installed, they should be frequently observed, as their indications enable the operator to know at once whether or not the motor is taking too large a current. As a rule, such instruments are not provided in connection with small motors and only infrequently with moderate-size ones.

12. Running.—During the operation of the motor, routine inspections should be made to see that no mechanical or electrical trouble is developing.

The field circuit of a shunt motor or the shunt-field circuit of a compound-wound motor should never be opened, even for an instant, while current is being supplied to the armature, as the result may be such a dangerous increase in speed as to cause the rotating parts to be seriously damaged. In some such cases, the centrifugal force is sufficient to cause the commutator to fly to pieces and the conductors of the armature winding to fly out of their slots; this constitutes one of the dangers of physical injury incident to improper operation of shunt- and compound-wound motors. It is customary to protect motors against such a result by inserting current interrupting, or cut-out, devices in the motor-armature circuit. When the current in the field circuit is interrupted, the magnetic flux cut by the armature conductors is very much reduced and the counter electromotive force of the motor is also reduced, thus

permitting a larger current in the armature. If the current-interrupting devices, either fuses or circuit-breakers, operate quickly enough, damage is avoided, but in many cases the acceleration is so rapid that the time element of fuse or circuit-breaker allows a dangerous speed to be reached before the circuit is opened.

Speed control of both compound and shunt motors is sometimes effected by the use of a variable resistance in the armature circuit. The operator should examine this resistance often enough to satisfy himself that it is not overheating, and that there are developing, in resistance conductors, contact arm, or contact buttons, no faults that could result in opening the circuit.

Before shutting down the motor, the operator should assure himself that the bearings are not heating unduly. Overheated Babbitt may *seize*, or, as it is frequently expressed, *freeze*, when cooled, and thus render it impossible to turn the armature when cold. This remark applies with equal force to all rotating machinery, and special mention of procedure in handling bearing troubles is given later.

13. Stopping.—The usual procedure in shutting down a motor is to simply open the main switch or the circuit-breaker. When this is done, all automatic devices return to their normal starting positions, so that if the switch is again closed no harm will result. After the motor is at rest, the operator should, however, carefully inspect the automatic devices, in order to see that they have operated properly. The arm of a starting box provided with automatic release should never be forced back to stop a motor; that type of rheostat is not designed for interrupting the current. Some types of combined starting and speed-control rheostats are made to open the motor circuit; but even with these, it is advisable to open the line switch, if the motor is to remain idle for some time.

With most drum-type controllers used with machine-tool equipment, a quick stop can be made by moving the handle quickly to the first running notch, holding it there for a moment, and then moving it to the off-position. An emergency stop

can be made by moving the handle to the first running notch, letting it rest there momentarily, and then moving it to the first reversing notch. This last method should never be used except in emergency, and in using it the handle should never be moved beyond the first reversing notch.

14. Reversing.—The direction of rotation of the motor armature can be reversed by reversing the direction of the current in either the armature or the field circuit, but not in both. If the motor is provided with a reversing switch for this purpose, it is used in the armature circuit. If no reversing switch is provided, the current supply should be cut off and the armature allowed to come to rest. Either the field or the armature terminals may then be reversed according to convenience.

COMPOUND MOTORS

15. Polarity Test.—Before starting a compound-wound motor for the first time, see that the series and shunt fields agree in direction, unless intended to act differentially. The test for polarity may be made by opening the series field circuit of the motor and sending current through the shunt circuit, as in Fig. 1 (*a*), observing by means of a pocket compass or permanent bar magnet the polarities of the pole pieces, then disconnecting the shunt circuit, sending current through the series circuit in the direction that it will have in operation, and repeating the observation for polarity. Under the latter condition, the field flux will generally be rather weak, even when the current is equal to the full ampere rating of the motor, and it is important that the device used for determining the polarity be fairly sensitive. In testing the series circuit, it is generally necessary to limit the current by a suitable resistance, such as a bank of incandescent lamps, connected as shown in (*b*).

16. Operation.—The methods of procedure followed in the operation of compound-wound motors are similar in some respects to those used for shunt motors.

A compound-wound motor can be started and stopped in the same manner as a shunt motor. Owing to the influence of the

series current, the accumulative compound motor has a strong starting torque. Its speed regulation is not as good as that of a shunt motor and, in some cases where good speed regulation is of importance, a special provision is made for shunting the series field after the armature is up to speed. Care must be taken that the special shunt circuit has good contacts and low resistance, or else a considerable current will still pass through the series field. The operator should frequently examine all the contacts in this shunt to see that they are clean and to prevent the development of a resistance that is high as compared with that of the series-winding.



FIG. 1

The direction of rotation of the armature should be reversed by changing the direction of current in the armature rather than in the fields, since there are two field windings, each of which would require reversal, thus making the change more difficult and increasing the liability of making wrong connections.

SERIES MOTORS

17. Series-wound motors are generally used for heavy duty where speed regulation is of comparatively little importance. Like shunt motors, they are started with a resistance to limit the flow of current. In many cases, as in electric cars, this starting device is so designed as to perform, also, the duties of a controller for starting, stopping, and reversing the motor and for regulating speed.

A characteristic of series motors is that when running unloaded their speed becomes excessive. This is a dangerous condition and should be avoided by mechanically connecting such motors so that the load can never be entirely removed, as by coupling or gearing to the driven machine.

ALTERNATING-CURRENT MOTORS

STARTING

18. Procedure.—Alternating-current motors, both induction and synchronous, require for starting and acceleration a current several times that required for full-load operation. Alternating-current motors, unless of very small capacity, cannot be started at full potential on account of the voltage drop that would be caused by the heavy rush of current, and also on account of the possibility of fuses being blown or windings injured by the large currents. The reduced voltage necessary for starting is derived from a starting compensator, or autostarter, or from sectional-winding connections in the transformers supplying the motor, or by the use of a starting rheostat similar to those used with direct-current motors. A starting compensator constitutes a main-supply switch as well as a starting device, but an additional main-supply switch is generally installed.

The procedure in starting an alternating-current motor, either induction or synchronous, by the starting compensator is as follows:

With the lever of the starting compensator in the off, or open, position, close the main supply switch and all other switches in series between the compensator and the supply, thereby bringing the supply pressure up to the terminals of the starting compensator switch.

Throw the lever of the compensator into the starting position and leave it there while the rotor is accelerating in speed.

When the rotor is up to speed, or nearly so, throw the lever arm of the compensator quickly over into the running position. In some cases, a latch is arranged to catch and hold the lever in the off-position if the movement from starting to running position is made too slowly.

In starting a motor with reduced potential derived from sectional taps from the transformer supplying the machine, a double-throw switch similar to the switch of the compensator can be used, or, if preferred, two separate switches so interlocked, mechanically or electrically, that only one switch can be closed at a time. The procedure is the same as that for starting by the compensator, but the danger of running temporarily on reduced voltage is not so great provided the motor is running light. With reduced voltage, an induction motor will run slower than normal, but, if unloaded, will not heat seriously, and the transformer will not be damaged.

19. Time Required for Acceleration.—Except in the case of a large motor, that is, one having rotating masses at a considerable distance from the center, the time required for the rotor to reach full speed will usually be rather short, generally less than 1 minute. A 5-horsepower motor with a rotor from 12 to 16 inches in diameter should be up to full speed in from 10 to 15 seconds; a 50-horsepower motor with a rotor having a diameter from 18 to 25 inches should be at full speed in 20 to 25 seconds; and, in the larger sizes, a 500-horsepower motor with a rotor 5 or 6 feet in diameter ordinarily requires about 40 to 45 seconds to reach full speed.

The operator will very quickly learn to recognize full speed by the sound produced by the rotating body. If there is a connected load, so that the motor is pulling against a consider-

able mechanical drag, the operator should be very careful to observe the rate of change in tone, and, if possible, change the supply voltage from starting to running pressure slightly before the motor has reached a constant speed. If the starting pressure is applied too long, the motor will be running at reduced potential and with excessive slip, and the starter may be overheated. The autotransformers in such a starter are designed to be in service only a few seconds at a time, usually not to exceed a minute; the copper and iron parts are therefore much smaller and the cooling arrangements are less complete than in a device intended for continuous service.

20. Causes of Poor Acceleration.—When an alternating-current motor appears to speed up too slowly, the cause is generally either too much load or too low a starting voltage. Low starting voltage may be due to taking the starting circuit from the wrong taps in the compensator windings, or to a poor electric contact either in the compensator switch or in the external circuit.

21. Field Excitation of Synchronous Motors.—When the procedure just given has been followed in starting and accelerating an induction motor, the operation is complete. A synchronous motor, however, must have its field winding excited with direct current before it can be put under load. When the motor has reached full speed, the field switch and all other switches in the circuit between the direct-current supply and the field windings should be closed.

The correct excitation of a synchronous motor is a matter of considerable importance. If overexcited, the motor will operate with a leading current; if underexcited, the current will be lagging. Either condition results in sending through the armature a larger current than is necessary, causing avoidable heating of the armature winding. Under ordinary conditions, therefore, the field current should be adjusted to such a value that the motor operates at unity power factor.

22. For the correct determination of the proper amount of field current, either an ammeter or a power-factor indicator is required. In connection with large units, the power-factor

indicator is generally installed, but with smaller installations an ammeter is commonly used on account of its lesser cost.

In using the power-factor indicator, the rheostat in the motor-field circuit should be so adjusted that the pointer on the instrument will remain, as nearly as possible, at the 100 per cent. mark.

An alternating-current ammeter in the armature circuit can be used for the proper regulation of the power factor, although it does not indicate the power factor directly. At unity power factor, all the current is in phase with the voltage, and for a given amount of energy and a given voltage the current is then the least. Therefore, if the operator adjusts the field rheostat of the motor so that either strengthening or weakening the field will increase the amount of current, as indicated by the ammeter, the condition of unity power factor will be obtained.

The power factor of a synchronous motor running with a load that is small compared with its capacity cannot be maintained at unity except by continual attention. Such close attention is, however, unnecessary, as, although the wattless component of the current in a synchronous motor running on light load is a very large percentage of the total, the actual energy being supplied is small; consequently, the total current may not be large enough to be objectionable.

23. Sometimes, owing to conditions beyond the control of the operator, unity power factor cannot be obtained in the operation of a synchronous motor. As a synchronous motor can be overloaded in current by improper field adjustment, even though delivering less than the rated mechanical load, the current input should then be carefully watched. If the motor is provided with an ammeter, instead of a power-factor indicator, the load condition can be observed directly, and, as the normal full-load current rating of the machine is usually marked on the name plate, it is possible to determine whether or not the motor is overloaded in current and by what amount. If no ammeter is provided, the current load cannot be found without the use of a voltmeter, a wattmeter, and a power-factor indicator.

EXAMPLE.—During the operation of a 6,600-volt, 250-kilowatt, single-phase, synchronous motor, the instrument indications are as follows: Voltmeter, 6,000; power-factor indicator, .80; wattmeter, 200 kilowatts. The normal current rating of the motor is 38 amperes. How much, if any, overload is the motor taking?

SOLUTION.—As shown in *Alternating Currents*, watts = volts × amperes × power factor, or $\text{amperes} = \frac{\text{watts}}{\text{volts} \times \text{power factor}}$. Then, the current taken by the motor is $\frac{200 \times 1{,}000}{6{,}000 \times .80} = 41.7$ amp., nearly. The overload is $41.7 - 38 = 3.7$ amp., or $3.7 \div 38 = 9.7$ per cent. Ans.

It is worthy of note that in this example two factors, low voltage and low power factor, combine to produce the overload. With normal voltage, the low power factor would, in this case, have caused the motor to take only its full rated current; with unity power factor and the voltage at 6,000, the motor would have taken only 33.3 amperes.

In applying the foregoing method of calculation to a three-phase motor, it is essential to know whether the voltmeter is connected between neutral and phase wire, indicating star pressure, or between two phase wires, indicating delta pressure. If delta pressure is indicated, the expression for current is

$$\text{amperes} = \frac{\text{watts}}{1.732 \times \text{volts} \times \text{power factor}}$$

24. Synchronous motors are sometimes operated with overexcited fields, in order to compensate for the low power factor produced on a distribution line and at the generating station by induction motors. If the induction-motor load on the distribution line is large in comparison with the synchronous-motor load, complete compensation for the lagging current due to the induction motors may not be possible. The compensation must not be carried beyond the safe carrying capacities of the armature conductors of the synchronous motors. All the precautions against overloading must be taken, and the operator should, if possible, take observations to determine the power factor on the supply line at a point between the generator and the motors.

25. Effect of Interrupted Circuit.—If the alternating-current supply to a synchronous motor is interrupted, even for

a second or two, the speed of the rotor will be reduced by the retardation of the mechanical load, and the electromotive force generated by the motor will be lower in frequency. To restore the full voltage of the supply circuit at such a time will probably cause an abnormal current and a resulting mechanical shock, the severity of which will be in proportion to the difference between the instantaneous pressures of line and motor at the time the circuit is completed. This difference is greatest when the motor and line electromotive forces are out of phase by 180 electrical degrees. The interrupted supply to a synchronous motor should not be restored except through the proper starting procedure.

Induction motors, being non-synchronous, are not required to operate under such exacting conditions as synchronous motors, although if the current supply is interrupted long enough to permit any considerable reduction in speed, the motor switch should be opened. When the cause of the interruption has been remedied, the motor should be started in the usual way. In some cases, the starters are provided with no-voltage releases that automatically return the contacts to the off-position whenever the current is cut off; in other cases, the starters must be opened by hand.

26. Observation of Slip.—The speed of an induction motor decreases slightly as the load increases. As soon as possible after taking charge of an induction motor, the operator should determine the slip that occurs at various loads, and, if operating large motors, should occasionally take observations to see if the slip is greater than it should be. Excessive slip may be caused by poor contacts in the primary or secondary circuits. Loose bars in squirrel-cage rotors are a form of poor contact in secondaries.

OPERATION OF DIRECT-CURRENT GENERATORS

PRELIMINARY INSPECTION

27. Generating machinery should not be started for operation without first being subjected to a careful inspection. The condition of the brushes and of all electric contacts that are liable to any considerable change should be determined. Any foreign articles, such as tools, rags, waste, etc., found in or about the machine should be removed. If possible, the operation of the switches in the circuit should be tested.

The condition of the armature switches of a direct-current generator is a matter of considerable importance, as inattention to the contacts may result in serious overheating. If conditions permit, each switch should be tested by being closed and opened several times to see that it works freely. The armature circuit must not be closed to live busses unless the generator is up to speed and has the same voltage and polarity as that of the busses; otherwise, the busses will be virtually short-circuited by the low resistance of the armature circuit.

SHUNT GENERATORS

28. Starting.—A direct-current generator should be brought up to normal speed gradually. After the armature has begun to rotate, the surface of the commutator should be cleaned by using a cloth or piece of waste slightly moistened with engine or dynamo oil, the commutator passing first under the oily rag and then immediately under a dry cloth to remove most of the oil, leaving the surface very slightly moistened with oil and free from accumulations of dirt. During the latter part of the acceleration, the operator should observe the polarity and potential of the generator.

29. Tests for Polarity.—If a direct-current generator is to be paralleled to any other source of potential, it is, of course, necessary that the polarities of both be alike. It is also necessary for the proper indication of measuring instruments that the direction of current is correct.

If a direct-current voltmeter properly connected across the open leads of the generator armature shows a reversed indication, the polarity is incorrect. The voltmeter indication can be checked by allowing the generator to reach full speed and voltage and then switching in series between each armature lead and the live bus to which the lead is intended for connection a sufficient number of incandescent lamps in series to require for full brilliancy the normal voltage of the machine. If the polarity is correct, the lamps will not burn; if it is reversed, they will burn at approximately full brilliancy. The connections for reversed polarity are shown in Fig. 2. For a 110-volt system and 110-volt lamps, the distribution of potential will be as indicated in (*a*) if the polarity of the generator is reversed, assuming no resistance in any of the conductors except the filaments of the incandescent lamps.



FIG. 2

The test just described can be varied to suit the facilities at hand. For example, the generator may be closed on one side, or terminal, to the bus on which it is to operate, and all the lamps connected between the other armature lead and its bus connection, as shown in (*b*). If the polarity of the machine

is incorrect, as indicated, the lamps will burn at about full brilliancy; if correct, the lamps will not burn.

Instead of the lamps connected as in (*b*), a portable voltmeter capable of taking twice the normal voltage of the generator can be used. If the polarity is correct, the voltmeter indication will be very low—zero, when the pressures on the machine and bus are equal. If the polarity is incorrect, the voltmeter will show the sum of the machine and bus voltages.

30. Correction of Reversed Polarity.—If, by observation and test, it has been determined that the polarity is reversed, the armature should be brought to rest and the polarity corrected by the safest and most easily applied method available. If a bus to which the generator can be connected is alive and of correct polarity, all the brushes of one polarity (either positive or negative) are raised from the commutator and the main armature switches of the generator are then closed. This will send current through the field windings in such a direction as to produce fields of the proper polarity. After a few seconds, the armature switches are opened, care being taken to open the circuit very slowly by gradually increasing the distance between the knife blade and the contact clip.

When the circuit is broken in this manner, a long, flaming, hissing arc will occur at the switch, but the operator should feel no concern, as the arc is perfectly normal under this condition. It is quite important that the switch is opened slowly, as a quick break would cause to be established in the highly inductive field circuit an electromotive force that might be great enough to damage the insulation. The brushes can be separated from the commutator by putting paper under them.

If inconvenient to raise all of the brushes of one polarity from the commutator, a machine lead can be disconnected between the armature and the tap for the shunt field. This is really the safer method of opening the armature circuit, because, in the first method, if one brush is overlooked, there will be a short circuit. It should be remembered that the object of either method is to establish a current in the field circuit, but not in the armature windings.

Further directions for the correction of reversed polarity of a direct-current generator are given in *Operation of Electrical Machinery*, Part 2, under the heading Care and Maintenance of Electric Machinery.

31. Adjustment of Voltage.—When the polarity is correct, an observation should be taken to determine the voltage of the generator. If the machine is to be connected to busses not already alive, the voltage may be brought to normal by adjustment of the field rheostat and the armature may then be connected to the busses by means of the armature switches. The voltage is adjusted by varying the current in the field windings; increasing the field current, increases the voltage, and vice versa. If a series rheostat is used, the field current is increased by cutting rheostat resistance out of circuit and is decreased by the reverse process. With a shunt rheostat, the field current is increased by increasing the rheostat resistance, and vice versa.

32. Correct Voltage for Paralleling.—If the generator is to be paralleled to some other source of current, as a storage battery or other shunt-wound generators, the voltage must be correct for paralleling. The correct theoretical voltage of the incoming machine depends on a number of factors; but, practically, it may properly be about 2 or 2½ per cent. higher than that of the busses to which the machine is to be connected. This will cause the generator to take a little load as soon as connected, which is not objectionable, if not too great, and is generally desirable for engine-driven units, as it is not advisable to risk motorizing the generator. If the paralleling is done at equal pressures, some variable condition may cause a reversal of current through the generator, thus tending to drive it as a motor.

If the load is steady and the speed regulation of the driving power of the generators is very good, the voltage differences just given can be reduced, and, if conditions are sufficiently reliable, paralleling can be performed at equal voltages. With voltages equal, the generator is brought into service entirely without load, a practice that can be recommended when the

conditions are favorable or when a slight motorization of the generator is not objectionable, as, for instance, when the generator is being driven by a synchronous or a direct-current motor.

When putting a generator into service for the first time or when the proper voltage difference for paralleling is not known, it may be regulated to 2 or 2½ per cent. greater than that on the busses to which the machine is to be connected. After paralleling, the rheostat may be adjusted until the load is as small as can be held steadily without danger of reversal. Then if the armature switches are opened and readings of both the bus and the generator pressures taken, the operator will have obtained, once for all, the most desirable relation between generator and bus voltages for safe and proper paralleling of these particular generators. It must be remembered that not all machines designed for the same voltage require precisely the same relation, as they differ greatly in armature characteristics.

33. Adjustment of Load.—After the generator voltage is correctly adjusted and the main armature switches are closed, the operator should at once observe, by the ammeter, the amount of load taken, in order to see that no unusual or dangerous condition exists. The generator may then be put under load by increasing its field strength. If the addition and loading of the generator renders necessary the transfer of load from other similar machines, the reduction of load on the others is obtained by weakening their fields by means of the rheostats. The transfer of load from a storage battery is obtained by reducing its potential by means of the end-cell switches, booster generators, or other means provided for the purpose. The added generator may then be continued in operation, its load being regulated by the field rheostat, increasing the field strength to increase the load on the generator and weakening the field to reduce the load.

Though the operation of shunt machines in parallel is a stable condition, unsafe load conditions can be developed by transferring to one or more machines a larger load than they can carry safely, and this may be done merely by reducing the

load on some other unit. This emphasizes the importance of observing the load on each generator every time that a change of adjustment is made in the load on any one. In addition, routine observations of load conditions should be made at frequent intervals, the frequency of inspection depending somewhat on the character of the service.

34. Regulation.—As the load on the station increases, that on each generator is also increased and the station voltage is reduced, thus requiring an increase in the field strength of each machine. If the generators are so designed as to be all alike as to armature characteristics, and if under the lighter load condition all were loaded in the same proportion to capacity, then under the heavier load condition this proportion will continue. If, however, the armature characteristics of the different generators in parallel are unlike, those generators having the largest internal armature drop will take less than their share of the increase of load and those having the lesser internal drop will take more than their share of the increase. If the generators were all alike as to armature characteristics, but not loaded alike in proportion to their capacities, the machines carrying the largest percentage of full load would take less than their proportional part of the increase. This last-named feature tends toward safety of load distribution, and therefore is not liable to develop dangerous load conditions. With unlike characteristics, however, lack of proper attention may result in too much load being thrown on some of the machines.

The reverse conditions as to regulation are, of course, true, but no dangerous load conditions are liable to develop as a result of reduction of load except when the latter gets so light as to interfere with the proper operation of the driving machinery. Some types of steam engines do not work reliably when lightly loaded, and care should be taken not to allow the load to get down to the point where racing or unsatisfactory speed regulation results. Such conditions cause variations in the voltage and impair the service. It is better practice to reduce the number of units in operation until those remaining

in service are fairly well loaded, thus improving both the regulation and the economy.

35. Effect of Excessive Overload.—If a load equal to several times normal rating is thrown on a shunt generator, its voltage and current will be reduced practically to zero. Under such a condition, although the armature may continue to rotate at full speed, the machine will be without electromotive force until the excessive load is removed. Generally, severe sparking of the brushes occurs at first when a shunt machine is heavily loaded or short-circuited; but the result is usually not destructive, as the drop in pressure causes an immediate reduction of field current, this resulting in a further lessening of the electromotive force, the effect being cumulative until the pressure and current are both zero.

COMPOUND GENERATORS

36. Paralleling.—A compound generator is started, accelerated, observed for polarity, and regulated for voltage in the manner described for shunt machines. But the parallel operation of compound-wound generators provided with the same terminal connections as shunt machines is unstable. The proper closing of equalizer switches is a matter of extreme importance in connection with paralleling compound-wound, direct-current generators, and the operator should never perform the paralleling operation without first checking the conditions of the equalizer circuit and seeing that the equalizer switch is closed. Failure to do so may result in motorizing one of the generators, reversing its polarity, or, in some cases, so severely overloading the windings of one of the units as to cause serious damage.

Two forms of practice are followed in adjusting the generator pressure before paralleling: The pressure of the incoming machine is adjusted before the equalizer switch is closed. The series-field windings of the running and incoming machines are placed in parallel by means of the equalizer switches and then the pressure is adjusted. Though the first method is,

perhaps, the more common, the latter is the better practice, as the compounding effect of its share of the load is produced before the generator is connected, thus permitting a more exact control over the amount of load that will be taken when the paralleling is completed. In the operation of railway generators, on which the load fluctuations are large, one method is practically as good as the other.

37. Regulation.—A change in voltage of a compound generator can be made by means of the field rheostat as with a shunt machine; but the compounding effect of the series-winding, under the influence of load changes, performs, automatically, much of the regulation that would require manipulation of the rheostat of a shunt machine. If the compounding is properly adjusted, the series field will correctly regulate the pressure for all changes in load within limits, and the compounding effect can be changed to suit the required conditions; that is, adjustment can be made to give a constant voltage at the station busses, or, if preferred, a little overcompounding can be produced to compensate for a drop in pressure in the distribution system and thus to maintain a constant pressure at some designated feeder terminal.

The method of changing the amount of compounding is to change the amount of resistance in the German-silver shunt connected in parallel with the series-field winding. If additional compounding is desired, more current is diverted through the series-winding by increasing the resistance of the shunt. If less compounding effect is required, the resistance of the shunt is reduced.

It should not be assumed that once a generator is started and put into service its voltage will require no further observation or adjustment; because, as the windings heat up under the influence of the load current, their resistance increases, which increases the armature drop and also decreases the shunt-field current. For this reason, the operator's attention will be required to see that the proper pressure is maintained.

38. Compound Generators With Storage Batteries. On account of the increase of electromotive force as the load

increases, a compound-wound generator is not suitable for operation in parallel with storage batteries, because the pressure of a storage battery, like that of a shunt generator, decreases as the load increases. As soon as a compound generator, paralleled with a storage battery, delivers any current to the battery, the effect is to increase the voltage of the machine, which then sends more current through the battery, the effect becoming accumulative within limits. If the series-field winding is shunted by a heavy copper bar and the series-field circuit opened, the machine is converted into a shunt generator, which operates well with a storage battery.

SERIES GENERATORS

39. Series-wound generators are used principally for supplying constant direct current for series-arc-lamp circuits. No new installations are being made, and the treatment herein covers only the general principles applicable to all the various types of series generators still in use.

Care must be taken that a series generator is correctly connected to the circuit; a reversal of the polarity of the circuit will cause the arcs to burn upside down.

Usually, one circuit is connected in series with each generator, but two or more circuits can be connected in series with one another and the combination connected to one machine, provided that proper attention is given to polarities and that the total voltage required by all lamps does not exceed the voltage capacity of the generator.

If one generator is underloaded and another in the same station is overloaded, two lamp circuits can be connected in series with the two machines, in order to distribute the load more evenly. One machine is then generally made to generate a constant voltage by making its automatic regulator inoperative, and the other machine, with its regulator, takes care of the load changes. Two forms of connection for this method of distributing a load are shown in Fig. 3, in which arrows are drawn to show current direction. The system shown in (*b*) has the

advantage over (*a*) of placing a lower voltage to ground on the generators in case a ground occurs on a lamp circuit.

40. In general, the lamp circuits should, when possible, be connected to the generators before the machines are started.



FIG. 3

A lamp circuit should never be disconnected, unless the voltage of the machine to which the circuit is connected is first reduced to practically zero by short-circuiting the field, the armature, or the machine as a whole.

Sparkless commutation on an arc machine is not to be expected, but for any given type of generator there is a normal spark that the operator should learn by observation, and the cause of any abnormal sparking should be promptly located. Some of the possible causes are faulty brush setting, poor current regulation, or a break in the armature circuit.

FIELD CIRCUITS OF DIRECT-CURRENT GENERATORS

41. Self-Excited Generators With Field Switches. In all that has been said so far about the operation of both shunt- and compound-wound generators, the operating practice described is such as should be followed with machines connected without any field switches or other convenient means of opening the field circuit. Direct-current generators operating self-excited should, in general, be connected without switches in the shunt-field circuit.

When field switches are provided, it is, of course, necessary that they be closed before the unit is started, or the machine will not generate. It is even a matter of more importance that while a generator, either shunt or compound, is operating in parallel with any other source of current, its field circuit be kept closed. If the field circuit should be opened, either by mistake or otherwise, the machine having no excitation would stop generating, and the armature, still connected to the other source of current, would be a short circuit of low resistance. If not promptly disconnected from the bus-bars, either by the operator or by automatic protective devices, the other units may be overloaded and damaged. If sufficient capacity in compound generators or in storage batteries is in parallel with the unit with the open-field circuit, its armature will be burned out if not disconnected at once.

42. Separately Excited Generators.—In some installations, it is desirable to operate generators excited either from the busses or from a special exciting set. In such cases, it is necessary that the precautions, before mentioned, are observed

with reference to any interruption of the field-circuit. When generators operating in parallel are neither self-excited nor excited with current from the load busses, all should be excited from the same exciter set, or some other means should be taken to make impossible the interruption of the field-current supply to a part and not all of the units.

EDISON THREE-WIRE SYSTEM

43. All the foregoing instructions on the operation of direct-current generators applies to the Edison three-wire as well as to the two-wire system. Only the system of connections shown in Fig. 4 requires special mention; because, though the operation of the individual generators is not greatly affected, the regulation of the station voltage is more complicated than in the two-wire system.

44. Owing to the importance of maintaining nearly constant voltage at customer's premises, general central-station practice is to regulate the bus-voltages so as to give standard conditions at feeding centers in the distribution system. Observations of voltage at these points are obtained by means of voltmeters connected through pressure wires to the feeder terminals, and the voltages on the two sides of the system at a feeding center are kept equal. It is therefore necessary to regulate together all the generators on each side of the system and to observe carefully the result on the relative pressures of the two sides.



FIG. 4

If the load is perfectly balanced throughout the distributing system, the bus pressure will be balanced also, but this is a condition that seldom exists, and usually the pressures on the two sides of a three-wire system are unlike at the station. If

it is observed that the pressure of one side is becoming too low or too high, correction should be made in the same manner as on a two-wire system; but when regulating pressure on one side, attention must also be given to the other side. High or low pressure on one side may be the result of either one of two possible conditions: Load conditions existing on one side and not on the other may make one side high or low; or the total pressure between the positive and negative sides may be unchanged and the generators on one side may be delivering a higher or lower voltage than those on the other, although the connected load may be the same on each side. The second condition amounts practically to a displacement of the neutral and is to be corrected by regulating the generators on both sides, reducing pressure on the high-voltage side and raising it on the other.

TIRRILL REGULATORS WITH DIRECT-CURRENT GENERATORS

45. The Tirrill regulator for use with direct-current generators is described in *Direct-Current Generators*. The procedure in the operation of the form for generators of small or medium size is as follows:

Before connecting the regulator, mark the position of the generator field rheostat arm at which the generator pressure is reduced about 30 per cent. below normal when the regulator is not in operation.

With the generator in operation at normal voltage and either with or without load, and with the main and relay contacts of the regulator open, close the switches connecting the main control magnets to the direct-current supply (if any such switches are provided), and close, also, the switches connecting the relay contacts to the field rheostat. Turn the rheostat arm gradually to the marked position. The regulator will begin operation as soon as the voltage has been reduced sufficiently to operate the relay, and afterwards will keep the pressure at the value for which the instrument is adjusted.

If one or more generators are in operation with Tirrill regulators, another may be connected in parallel as follows: Equalize

the voltage of the incoming machine to that of the units in operation, close the switches connecting the regulator relays to the field rheostat of the incoming generator and close all other regulator switches pertaining to this unit. Close the main armature switches. Equalize the load by means of the equalizing rheostat in the generator that has the most sensitive regulation.

46. In order to take out of service one of several generators in parallel, reduce its load, open its armature switches, and then open the regulator switches corresponding to this machine.

To take the regulator out of service, assuming one generator is in operation, turn the arm of the generator field rheostat toward the strong field position. When the relays stop vibrating, open the switch that connects them to the field rheostat. Pressure regulation may then be carried on by means of the generator field rheostat.

In order to avoid unequal burning of the main and relay contacts of the regulator, the current through them should be reversed about every 6 hours of operation. This is done by means of the small reversing switches on the bottom of the regulator panel. If the contacts burn unevenly or develop tips, they should be evened with a strip of very fine emery paper or cloth. As the contacts are made of precious metal, no more material than necessary should be removed.

47. Large direct-current generators to be regulated with Tirrill regulators must be excited by a special exciting generator, a particular form of regulator being used. The relays shunt the field rheostat of the exciter generator instead of the main generator rheostat. The regulator has a potential coil supplied from the main generator, load busses, or back feed from the feeding center, as preferred. If a switch is installed in circuit with this potential coil, it must be closed before starting the regulator. The procedure is as follows: With the generator in service at normal voltage and the regulator main and relay contacts open, close the switches connecting the potential coil to the busses or generator or back feed from

distributing center, as the case may be, and close the switches that connect the relays to the exciter field rheostat. Gradually, turn the exciter field rheostat arm to the position that would, under normal conditions, cause the exciter to generate a pressure about 35 per cent. below normal. The regulator will start operating as soon as the generator voltage drops enough to start the relays. Set the main generator field rheostat in a position for a strong field, if this setting can be obtained without disturbing the operation of the regulator.

ROUTINE CARE AND INSPECTION

48. During operation, direct-current generators should be frequently inspected to see that they are working under proper conditions. Bearings should be examined at least every ½ hour to see that a sufficient supply of oil is passing through them to avoid overheating. The commutator should be kept clean, and care should be taken to see that brushes do not get hot.

A hot brush on the commutator indicates a poor contact and relatively high resistance. Frequently, the fault is on another brush, which, unable to carry its proper proportion of the load, overloads the brush in parallel with it, though the latter has good contact and relatively low resistance. Not only the brushes that are overheating should be inspected, but the condition of the others, also, should be observed. If only one brush on a stud is heating, the trouble is probably confined to that one.

49. The operator should, as far as possible, observe the temperatures of the generators, at least to the extent of feeling the field coils and placing his hand in the air discharge from the armature. He should always be on the alert for any odor of burning insulation or for any unusual noise. Any of these conditions requires his immediate and continuous attention until the cause and its seriousness are determined and the fault remedied. A generator that is apparently burning out or smoking from overload should be relieved and shut down as

quickly as possible. Whether it shall be disconnected before another is started to take its load, or continued in operation with the risk of further damage until relieved, depends on the character of the service and the extent to which the trouble has already progressed. These matters are for the operator to decide and a specific rule of general application cannot be given. A generator that breaks down while operating in parallel with other sources of current may short-circuit the latter and cause serious damage; therefore, it should be separated from other units as quickly as possible.

OPERATION OF ALTERNATING-CURRENT GENERATORS

PRELIMINARY INSPECTION

50. Alternating-current generators should receive the same general preliminary inspection as direct-current generators. The operator should make certain that each machine is free from foreign objects, such as tools. The brushes should be inspected to see that they are firm and secure in place and make good contact with the collector rings. If possible without connecting the machine to a live circuit, the switches should be tested by operation. The operator should assure himself that all connections have been properly made and that all connectors are firmly secured.

The exciter set that is to supply the field current should also be subjected to inspection. It is a mistake to assume that because the exciter set is small and somewhat in the nature of a piece of auxiliary apparatus, it can be neglected without serious risk. Without it, or some other source of exciting current, the alternating-current generator is useless, and experience has shown that in alternating-current installations the exciter generator is often the weakest part. The operation of the exciter is carried on in accordance with the methods already described for direct-current generators.

OPERATION OF SINGLE ALTERNATOR

51. Starting.—If the exciter set is driven separately from the alternator, it should be up to speed and voltage before the alternating-current generator is started. This is merely for convenience, so that when the alternator has been started, it can be excited without delay. In installations where the exciter is belted from or is directly connected to the generator shaft, this convenience is not possible. If the alternator is to go into service alone and is to pick up circuits not already alive, it is brought to normal speed and excited with a weak field; that is, with the rheostat resistance in circuit in both alternator and exciter fields, causing the generator to deliver a low voltage at normal frequency. This is done so that when the generator is connected to the dead circuits, which may have a considerable connected load, the rush of current, which will exist for an instant, will be small. All the switches between the generator and the busses to which it is to be connected are then closed, the circuit completed by means of an oil switch, if there is one in the circuit, and the alternator voltage is then brought up to standard by means of the alternator and exciter-field rheostats.

52. Regulation.—As the field current of the alternator is quite large compared with the field current of the exciter, the greatest economy in the use of field current will be obtained by operating with as little resistance as practicable in the alternator field rheostat and performing most of the regulation by means of the exciter rheostat. Hence, this method should be used unless it results in operating the exciter at a pressure too low for good regulation. To obtain good voltage regulation, the exciter must be operated with a magnetic density so great that a relatively small change in field current will not produce a large change in magnetism and consequently in voltage. This density is not at the saturation point, but is considerably above the steep part of the magnetism curve. The operator will be able to determine whether or not he is working with too low an exciter pressure by observing the direct-current

voltmeter (or if none is provided, a lamp) connected across the terminals of the exciter generator. If there is any difficulty in keeping a steady voltage with slight variations in exciter load, which can be produced by means of the field rheostat of the alternator, the pressure of the excitation system should be raised until stable operation is obtained, the field rheostat of the alternating-current generator being adjusted as required to keep the alternating current at the proper voltage.

Voltage regulation of the alternator is carried on by means of the generator and exciter-field rheostats, and for machines operating alone, that is, not in parallel with any other units, the regulation is a very simple matter.

SERIES OPERATION

53. Alternating-current generators cannot be operated in series unless they are so coupled, mechanically, that they are in phase and cannot vary their phase relations. This may be, and is sometimes, done for special purposes by having their rotating parts mounted on the same shaft and the windings so alined that the armature electromotive forces generated will be in phase with each other. If alternators are driven separately, the condition will be unstable, the electromotive forces being in the same direction at one time and opposed at another, the final condition tending toward a difference of 180° of electric phase, which would constitute a short circuit of each machine by the other.

PARALLEL OPERATION

SYNCHRONIZING

54. Checking Synchronous Connections.—The operator must know whether lamps used for synchronizing are connected to indicate the in-step condition when they are either at their greatest brilliancy or entirely dark. If the connections are covered, or otherwise difficult to trace, the circuit can be checked

by disconnecting the leads of one alternator at points between armature *a* and the synchronizing circuit, as at *b*, Fig. 5, and then closing the main alternator switches *c* as for paralleling the alternators. With the connected machine *d* in operation, both sides of the synchronizing circuit will be energized from the same source if the synchronizing switch *e* is closed; then the indications of the lamps will be those correct for synchronizing. The main switches of the disconnected alternator armature *a* should then be opened and the machine reconnected at points *b*. This method applies to voltmeters and synchroscopes also.

55. Synchronizing With Lamps.—Some skill is required to determine the proper conditions for paralleling when lamp indications are used. The difference in frequency between the running and incoming units must not be too great, else the division of load, after the machines are together, will be unsatisfactory; if the difference is too small, it becomes difficult to determine when the alternators are in phase. The difference in frequency will be clearly indicated by the "beat" of the lamps, and the operator must choose some speed with which he can best work; preferably, the beats should not be slower than once in 10 seconds nor faster than once in three. If the synchronizing is done with dark lamps, the paralleling (main switch) connection must be made at the middle of the interval between the disappearance of the last glow and the time the same amount of glow would reappear. The right instant for paralleling can be determined by watching the beat for some time while it is steady, counting at a moderate and even rate from the instant of disappearance to reappearance of the glow, and then dividing the count by two. If the counting is well done and the speed conditions are constant, the paralleling or synchronizing of the alternators will be well done.



FIG. 5

If the pressure of the incoming alternator is not the same as that of the running units, cross-currents will flow between them; therefore, it is important to equalize their pressures by field adjustment before tying them together electrically. If, when using synchronizing lamps with a slow beat, the lamps do not go entirely out, the pressures are not properly equalized.

56. If synchronizing is to be done with bright lamps, the paralleling connection is to be completed at the instant that the lamps are at their maximum brilliancy. This is more easily determined than is the middle of the dark period, but considerable care is necessary. If the operator is too far from the lamp, he may not be able to see well enough to determine accurately the instant of maximum brilliancy. If he is too near, the light will be somewhat dazzling; then the pupil of his eye will, in a short time, fail to enlarge and close with the variation in brilliancy of the lamp, with the result that he will be inaccurate in deciding the instant when the maximum brilliancy occurs. It is not possible to state just how far away the synchronizing lamp should be, as the distance will vary with the individual, but it must be experimentally determined by each operator for himself. If the position of the lamp is fixed too near to or too far from the switch, its position can be changed to suit the individual by putting it on the end of an extension cord.

57. Since the lamps, by their beat, indicate only the difference in frequency between the running and incoming machines, they do not show whether the incoming unit is running faster or slower than the one already in operation. For this reason, the indications of the lamps should be observed, if possible, during the speeding up of the unit and continuously after that until the correct speed is obtained. If, after the incoming machine is up to speed, the beat should become too fast, the cause may be either high or low speed. Whether the incoming alternator is too fast or too slow can be determined by varying its speed and observing whether the frequency of the beat is increased or decreased.

58. Synchronizing With Voltmeter or Synchroscope. When using a voltmeter for synchronizing, it is necessary to

know whether the in-phase condition is indicated by the maximum or the zero reading of the instrument. The beat should be rather slow and the swing of the needle should be observed several times before the switch is closed. If the zero or the maximum indication is not obtained, it is an evidence that the alternating voltages are not equal.

The synchronizer, or synchroscope, gives an indication not only of the time of the in-phase condition and of the difference in frequency, but also shows whether the incoming alternator is running too fast or too slow. If correctly connected, the in-phase condition is indicated when the indicating hand is in a vertical position. Reasonable care should be taken not to connect the synchroscope in circuit until the difference in frequency between the incoming machine and the running units is small; when the difference is large, the armature of the instrument will not rotate, but will vibrate excessively.

59. Speed Control.—The method by which it is possible to make the difference in the frequencies of alternators slight depends on the kind of machinery used for driving them. Steam engines or waterwheels are usually equipped with some form of speed control. Some steam engines have governors that can be manipulated and by which the speed can be controlled; others, using shaft governors, are not subject to such control and the speed is partly controlled by the throttle.

60. Time Element in Switch Closing.—The armatures of the alternators are connected in parallel, in some cases, by closing a simple, hand-operated switch (either knife-blade or oil-immersed contact), and if this can be done quickly, that is, with a short time between the first movement of the hand and the completion of the connection, the operation is very simple. When remote-controlled oil switches are used, it is always necessary to make a proper allowance for the time required for the operation of the switch. The time needed should be known from previous observations.

61. Effects of Inaccurate Synchronizing.—Inaccurate synchronizing; that is, making the parallel connection when the potentials of the machines are too far out of phase with

each other, whether it results from unreliable indicating devices, wrong connections, failure to allow for time element of switches, or from any other cause, is a source of danger that may result seriously. The worst effect is produced when the electromotive forces are out of phase by 180 electric degrees, for then the cross-current will be maximum; but, even with a phase difference as low as 8 or 10 degrees, severe mechanical shock may result, the armature may be injured either mechanically or electrically, or the oil switch wrecked. The current and the extent of the damage resulting are dependent on the phase difference and also on the reactances of the armatures of the alternators. There are in use some alternators with armature reactances so great that two such machines may be connected together without serious result when completely out of phase; but they are not in common use, and the operator should always use the greatest possible care when connecting any alternators in parallel.

DISTRIBUTION OF LOAD

62. After alternators are tied together electrically and are operating in parallel, the distribution of load among them should be given immediate attention. The distribution of kilowatt load is dependent on the relative phase positions of their rotating parts. Alternators in parallel must run in perfect synchronism, yet it is possible for the engine, turbine, waterwheel, or other driving power, of one generator to force the rotating parts of the generator ahead in relative phase position by a few electrical degrees, as if it were making an effort to exceed the other in speed. Were it not for the synchronizing effort exerted tending to keep the machines in step, the leading unit would actually run with a slightly higher frequency than the others. The action is like that of a team of horses hitched to a load in such a way that, although they progress at the same rate, the more energetic horse does more than half the work; in fact, in extreme cases, it may do all the work, and even help to move its mate. The energetic horse is like the alternator that leads in phase. A horse that is dragged along by its mate corresponds to a motorized generator.

The kilowatt load on one of several alternators in parallel can be increased by causing it to pull ahead in phase; or, in other words, to tend to run faster than the other units (of course, it will not actually exceed the speed of the others); or, what amounts to the same thing, cause the other units to tend toward slower speed.

Prime movers with governors subject to control while running are better adapted to the control of load division between alternators than such machines as high-speed engines having shaft, or automatic, governors that are not subject to control during operation.

63. The distribution of current load between two paralleled alternators is controlled by means of the field excitation, which, when improper, will cause to pass between the armatures a cross-current of an intensity depending on the difference in the field currents of the machines. The cross-current will exist, even though the prime movers are so adjusted that each alternator bears its proper share of the power (kilowatt) load. In the machine with the weaker excitation, the cross-current will be leading; in the other, it will be lagging. By simultaneously adjusting the field rheostats, the cross-current can be varied considerably without altering the voltage of the system. Under some conditions, an alternator can be made to take sufficient leading cross-current to cause it to operate at unity power factor, even though the load has a power factor less than 100 per cent.

In general, the excitation of alternators in parallel should be so regulated that they carry current loads in proportion to their ampere ratings. With proper field adjustment, the sum of the alternator ammeter readings will be a minimum, and the alternator power-factor meters, if provided, will all read the same.

In special cases, there may be reasons why the general rule should not be applied. For instance, one alternator may have been under heavy load for several hours and consequenty subjected to considerable heating, while another may have just been put into service. Again, as a result of age or service,

the insulation of one machine may be damaged so much that it cannot safely withstand the same heating that would be safe for a similar machine in good condition.

TIRRILL REGULATORS WITH ALTERNATORS

SETTING THE REGULATOR

64. The voltage regulation of alternators is obtained by changing the field currents. The principles governing this method of regulating an alternator operating alone apply to parallel operation also; in addition, it is important that the excitation of all alternators in parallel be given attention each time that the voltage is regulated, in order to avoid troublesome cross-currents.

One of the most commonly used automatic devices for the voltage regulation of alternators is the Tirrill regulator. Usually, each installation of such a device is subject to such conditions as to make some special procedure advisable; however, there are in connection with the operation of Tirrill regulators some principles that are general.

65. Assuming that the Tirrill regulator has been correctly connected and properly adjusted, but has not yet been put into service, start the exciter and alternator, and run the alternator without load. The alternator field rheostat should be turned until all its resistance is out of circuit; if less than 55 per cent. of the normal voltage of the exciter is then found necessary to produce the rated voltage of the alternator, the exciter voltage should be raised to at least 55 per cent. of its normal value, and the alternator voltage regulated by means of the alternator field rheostat. If the exciter field is so weak that the exciter voltage is less than 55 per cent. of normal, the machine will be under conditions of unstable regulation. When the exciter and alternator voltages are at the proper values, mark the position of the alternator field rheostat arm so that this position will always be known.

If two or more alternators for parallel operation are to be automatically regulated, they should be connected in parallel without load, and their field currents regulated by means of their field rheostats until they operate without cross-currents. At least one of the alternators may have all its rheostat resistance out of circuit. If, after regulating to eliminate cross-currents, it is found that less than 55 per cent. of the normal voltage rating of the exciter is required for producing the normal alternating voltage, adjust the exciter pressure to 55 per cent. normal and readjust the field rheostats of the alternators until the alternators deliver normal voltage and have no cross-current. When this adjustment is made, mark the positions of the alternator field rheostat arms for future reference.

66. The next step is to cut into the exciter field rheostat sufficient resistance to reduce the alternating-current voltage to about 65 per cent. of the normal full-load value, and to mark the position of the arm of the exciter rheostat. This should be done separately for each exciter set that is to be used with the Tirrill regulator.

Make the direct-current coil of the Tirrill regulator alive by closing the switch in circuit with it (if such a switch is installed), and make the alternating potential coil alive by closing to it the switch connected to the special potential transformer on the machine that is to be regulated. Close the switches that connect the relay contacts to the exciter rheostat. If the main contacts remain apart after the switches are closed, adjust the auxiliary contact arm in the alternating-current, control-magnet circuit until the contacts come together and the regulator begins working. The alternating-current voltage should then be adjusted to normal by moving the auxiliary contact arm, the final position of which should be marked or observed for reference when putting the regulator into service in the future.

ROUTINE OPERATION

67. The operations just described are not to be performed in routine operation, but are the steps to be taken in putting the regulator into service when it is first installed. After these

operations have once been performed, and the various rheostat-arm positions have been marked or observed so that the rheostats can be reset to those points, the procedure should be as given below; see *Voltage Regulation of Alternating-Current Circuits.*

Close the switch connecting the direct-current coil to the exciter busses that are to be used. In some installations, selector switches between different sets of busses are installed; in others, selector switches between different exciters. Close the switch connecting the alternating-current coil to the pressure leads from the alternator that is to be regulated. Adjust the auxiliary contact arm in the alternating-current, control-magnet circuit to the marked position. Set the alternator field rheostat arms to the marked positions, keeping the alternating-current voltage at normal by proper adjustment of the exciter-field rheostat. With the main contacts of the regulator apart, close the switch or switches (if more than one) connecting the relay contacts in shunt across the exciter field rheostat, and then slowly move the arm of the exciter rheostat to the marked position. The main contacts will come together and start the regulator.

If desirable, the alternating-current voltage can be changed by means of the auxiliary contact arm in the alternating-current, control-magnet circuit.

68. All the alternator fields supplied by the exciter working with the regulator will be subject to the operation of the regulator, and, if the installation is so made as to provide for using exciters in parallel in connection with the regulator, additional ones may be cut in by the following method: By means of its field rheostat, adjust the voltage of the incoming exciter to equal that on the exciter bus, close the main armature switches that connect the exciter to the bus, and immediately close the switch connecting the relay contacts in shunt with the field rheostat of this exciter and turn the exciter rheostat arm to the marked position.

A rheostat is generally necessary to equalize the load between the exciters; it should be adjusted for proper division of current and this adjustment should be made permanent.

To take one of two or more exciters operating in parallel and controlled by the same regulator out of service, first disconnect it from the exciter bus by means of its main switch and then open its rheostat-shunt switch. If it is desired to take the regulator out of service, turn the exciter field rheostat to cut-out resistance until the main and relay contacts stop vibrating and remain apart, then open the switch that connects the relay contacts in shunt across the exciter rheostat.

69. As machine characteristics vary somewhat, in connection with some installations, experience may indicate that the regulation of the exciters is unstable when the rheostat is adjusted as described. It should be remembered that the procedure given is for general cases, and that if conditions in some installations are special the procedure may be varied somewhat to advantage. The mistake should not be made, however, of trying to use the Tirrill regulator with the exciter-field flux near the saturation point; the exciter will work better if operated with a magnetic flux that will give rather unstable pressure when regulated by hand.

70. The Tirrill regulator should be kept in good adjustment, and a few minutes of each operating day should be spent in seeing that it is kept in good condition. The contacts should be kept smooth, pivots free, connections tight, and the adjusting nuts should not be allowed to work loose. The reversing switches in the feed to the main contacts and relay contacts should be reversed about every 6 hours of operation in order to prevent the contacts from burning away unequally. Excessive arcing at the relay contacts may be due either to insufficient condenser capacity in parallel with them or to an open circuit in the connections between condenser and contacts. In the first case, the remedy is to increase the number of condenser sections; in the second, to restore the connection.

In service, Tirrill regulators are subject to one form of trouble that seriously affects the pressure regulation, and this is the sticking or fusing together of its contacts, either main or relay, but more often the relay contacts. When the contacts fuse together, the generator pressure at once rises and it is necessary

to take the regulator out of service immediately. To do this, when the contacts are stuck together, open the switch that connects the relay contacts in shunt with the exciter rheostat and immediately strengthen the exciter field by cutting out resistance with its rheostat.

OPERATING TROUBLES OF ALTERNATORS

71. It is impossible to classify all the various forms of operating trouble that may occur in the use of alternators, and, also, to prescribe definite rules of procedure for each case. It is important, however, to mention, briefly, a few general rules that the operator should keep in mind.

As it is necessary that alternating-current generators be not connected in parallel without the proper synchronizing procedure, it is equally important that when, for any cause, an alternator has been disconnected from a live circuit, even for an instant, it be not reconnected except by synchronizing and standard paralleling methods. This rule does not always apply to alternators driven by synchronous motors, as will be explained in *Operation of Electrical Machinery*, Part 2.

Severe short circuits sometimes occur on distributing systems, and sometimes in the generating station on busses, or in the windings of broken-down generators. In such cases, the effect may be to reduce the pressure in the station or, automatically, to open oil switches. The short-circuited portion of the system should be isolated by means of oil switches as quickly as possible, in order to avoid the serious results that such an overload would produce on the generators.

The exciter system is a frequent source of operating trouble, and it is not uncommon to have the service of a large unit completely interrupted by some minor trouble with the exciter generator. If alternators excited from separate sources are operating in parallel, the loss of excitation on one of them might cause that one to be run as a motor, and possibly to take a very large lagging current from the others. The unexcited alternator should be disconnected as soon as possible.

OPERATION OF ELECTRICAL MACHINERY

(PART 2)

OPERATION OF MOTOR-GENERATORS AND SYNCHRONOUS CONVERTERS

MOTOR-GENERATORS FOR CURRENT CONVERSION

INDUCTION-MOTOR-DRIVEN SETS

1. The operation of motor-generator sets converting alternating current into direct current, using either induction or synchronous motors, should be carried on in accordance with the methods for alternating-current motors and for direct-current generators. The simplest case is that of a direct-current generator driven by an induction motor, both of which are operated according to the instructions given in another Section.

SYNCHRONOUS-MOTOR-DRIVEN SETS

2. Starting From Alternating-Current Side.—Synchronous motors driving direct-current generators are generally excited from the output of the generators, and if direct current is not available until a machine is started, the procedure is as follows:

Start the synchronous motor by means of the starting compensator, leaving it unexcited until up to speed. Throw the

COPYRIGHTED BY INTERNATIONAL TEXTBOOK COMPANY ALL RIGHTS RESERVED

compensator handle to the running position and, as soon as the direct-current generator begins to pick up, close the field switch of the synchronous motor and all other switches necessary to complete the excitation circuit of the motor.

It is very important that no considerable amount of load be connected to the generator until the synchronous motor has been excited; therefore, if the motor-field circuit is connected to the generator leads, do not close the armature switches to the direct-current load busses until the motor is fully excited. If the field switch connects the exciting circuit to the load busses and if these are dead, disconnect the load, close the generator armature switches, and then the motor field switches, adjust the motor field rheostat, and then reconnect the load. If the busses are alive before the motor-generator is started, excite from them as soon as the motor is up to full synchronous speed and before closing the generator switches.

3. Starting From Direct-Current Side.—In some installations of this type, provision is made for starting the motor-generator by using the generator temporarily as a direct-current motor and synchronizing the motor to the alternating-current busses.

If the direct-current generator is compound wound, it should be provided with switches for reversing the series field for starting purposes. The procedure is as follows: Reverse the series fields, excite the generator by closing its field switch, if one is provided, adjust the generator field rheostat for strong field excitation, and close the starting circuit with all the resistance in circuit. If the generator is excited from its own leads, and has no field switch, the machine cannot be excited before closing the starting switch; but, as the starting current is limited by the resistance box, no harm will result. In this case, adjust the field rheostat for strong field excitation and close the starting circuit with all the resistance in circuit. When starting a set for the first time test the field poles with a piece of soft iron, and if the polarity is correct, gradually cut out resistance from the starting circuit until it is all cut out. If the machine is not then up to full speed, increase its speed to normal by gradually

weakening the field of the direct-current generator, now acting as a motor. Excite the synchronous motor by closing all the switches in its field circuit and synchronize the synchronous motor, now operating as a generator, using the methods for synchronizing an alternator.

When synchronized, open the armature switches of the direct-current end and reverse its series-field winding. If the shunt field is connected to the generator leads between the reversing switches and the main switches connecting to the bus-bars, opening the series-field reversing switches will also open the shunt-field circuit. In this case, care must be taken to open the first of these switches slowly, in order to avoid a quick opening of the shunt field and the possible puncturing of its insulation. The equalizer switch should then be closed, the pressure regulated by means of the generator rheostat, and the machine paralleled with the other direct-current units. In this case, because the speed relations of the generators are exactly maintained, the pressures of the incoming unit may be made equal to that of the busses instead of slightly higher. This is also proper if the generator is driven by an induction motor.

If the generator is shunt wound instead of compound wound, the procedure is the same as just described, except that no series-field reversing switches have to be operated, and no equalizer switch is to be closed.

4. Conversion of Direct to Alternating Current. The same motor-generator that is used for converting alternating to direct current can also be employed for changing direct to alternating. The methods of operation are practically the same as those for direct-current motors and alternating-current generators. For synchronizing, the speed of the alternator is regulated by means of the field rheostat of the direct-current motor, and after synchronizing, the distribution of load between alternators in parallel is controlled by the same means. By weakening the field of the direct-current motor, the alternator is given a tendency to advance in electric phase and to take a larger proportion of the energy load.

INDUCTION-MOTOR-DRIVEN FREQUENCY CHANGERS

5. The operation of the motor-generator frequency-changer sets is carried on in accordance with the methods for the operation of alternating-current motors and generators, but with some additions necessitated by special requirements. Since induction-motor-driven sets are not well adapted to inverse operation and do not run synchronously and therefore do not operate well together, frequency-changer sets are generally made with synchronous motors.

In the operation of induction-motor-driven sets, the motor is started in the usual manner, and the load is connected to the alternator after the motor is supplied with full running potential. Alternators driven by induction motors are not usually operated in parallel; but when such operation becomes desirable or necessary, the alternators are synchronized by varying the load on one of them, thus varying its speed by changing the slip of the induction motor. When the alternators are in phase, as indicated by the synchronizing devices, they are paralleled. There is no way of controlling the distribution of kilowatt load between two such units.

SYNCHRONOUS-MOTOR-DRIVEN FREQUENCY CHANGERS

FREQUENCY CHANGE IN SIMPLE RATIO

6. Ratio of One to Two.—The paralleling of synchronous-motor-driven frequency-changer sets is much more complicated than that of induction-motor-driven sets. The simplest case is that of sets for changing to double or half frequency.

If two such sets, unloaded, are started and brought up to synchronous speed by connecting their low-frequency ends, as motors, the high-frequency ends, on being excited, will generate electromotive forces that are in synchronism and in phase. But if the two units are unequally loaded before paralleling

them, the more heavily loaded unit will lag behind the other. Full load on a generator causes its low-frequency motor to lag about 25 electrical degrees behind the phase position it would have under no load, resulting in a lag of about 50 degrees in the generator electromotive force. The two generators of the synchronous-motor-generator sets may therefore run at the same frequency, but, before paralleling, be out of phase by an amount proportional to the difference in loads, the generator of a fully loaded unit being about 50 electrical degrees behind the generator of an incoming unit with no load. A phase difference of 50 degrees would be too great for paralleling steam-driven alternators; but with synchronous motors there is usually no way of controlling speed, and as the motors and generators will immediately equalize their loads as soon as connected together, the generators may be paralleled if their voltages are equalized. When they are connected in parallel, heavy cross-current and synchronizing current will exist for a few seconds, after which, if the units are similar, they will divide the load properly.

7. Ratio of Two to One.—If the same two units are started from the high-frequency ends, the electromotive forces of the low-frequency generators at no load may be in phase, or 180 electrical degrees out of phase.

If the unloaded generators are 180 degrees out of phase, the simplest means of correcting the phase difference is to reverse the direction of current in the field winding of one generator, which reverses the instantaneous polarity of the generator electromotive force. If no reversing switch is provided, one motor-armature switch may be opened, the motor-field circuit opened, and the rotating parts allowed to drop back slightly in speed, after which, first the armature switch and then the field switch may be closed, this process being repeated until, by chance, the machine comes up in correct phase relation. This operation, commonly known as *slipping poles*, is better performed if a synchronizer, or synchroscope, is installed for synchronizing the motor to the supply line. In this case, the procedure is as follows:

Having determined by the synchronizer on the generator that the generator electromotive force is 180 degrees out of phase with that of the running unit, connect the synchronizer of the motor, adjust the motor excitation for unity power factor, open the motor switch, and allow the motor to fall back in phase 360 electrical degrees, or 1 cycle, which will be indicated by one revolution of the needle of the synchronizer connected on the motor end. The motor switch must be closed at the exact instant of the in-phase position indicated by the vertical position of the synchronizer needle, and proper allowance must be made for the time element of the switch-operating mechanism.

In performing the operation of slipping poles when using a synchroscope, the motor, which is excited, after being disconnected acts as a generator, running by its own inertia, and must be synchronized very accurately. In order that its reduction in speed shall be small and its beat slow, the generator end of the unit should not be excited during the operation.

8. After the generator electromotive forces are thus brought into phase with one another, or approximately so, they should be equalized. The units may then be connected in parallel.

If the motor-generator already running is under load, the incoming machine will be out of phase, as in the preceding case, but by a different amount; full load on the running unit in this case causes displacement of the generator electromotive force by only about 12½ degrees.

SYNCHRONOUS FREQUENCY CHANGERS ON STANDARD SERVICE

9. Phase Relations.—Synchronous frequency changers more commonly work between 25-cycle and 60-cycle systems, in which case the higher frequency is 2.4 times the lower. Such units are usually constructed with ten poles on the 25-cycle end and twenty-four poles on the 60-cycle end; and there is but one position of the rotor correct for paralleling, although there are five possible positions of correct phase relation when the unit is operating as a 25-cycle motor only, that is, one-half

the number of motor poles. The cause of this complication of phase relations can be shown, arithmetically, as follows:

Two 25-cycle–60-cycle frequency-changer sets are assumed to be in operation as 25-cycle motors without load and with the 60-cycle generator electromotive forces in phase, though, in order that the following operations may be performed, the generators cannot be in parallel. If one machine is slipped back one pair of poles, or 360 electrical degrees, or 1 cycle, on the 25-cycle end, the 60-cycle generator will slip back $60 \div 25 = 2.4$ cycles, or 864 electrical degrees. The electromotive force of this generator will then be $864 - 720$, or $.4 \times 360 = 144$ degrees out of phase with the electromotive force of the other machine; the generator has been slipped back 144 degrees more than 2 complete cycles. If the motor is slipped back another cycle, the generator electromotive force will slip back 864 electrical degrees more, making the total slippage of the generator 1,728 degrees, or 4.8 cycles. The electromotive force of the generator is then .8 cycle, or $.8 \times 360 = 288$ degrees, behind that of the other machine, or .2 cycle = 72 degrees ahead; the total slip has been .8 cycle more than 4 complete cycles and .2 cycle less than 5 complete cycles. Another slip will cause the generator to be 72 degrees behind in phase; the next, 216 degrees behind, or 144 degrees ahead; and the fifth slip will bring the generators back into phase again. There is only one relation that the motors may hold to each other for proper paralleling of the generators.

10. If the operation is inverted, that is, if the 60-cycle machines are motors and the 25-cycle machines are generating, slipping the 60-cycle motor back 1 cycle, or 360 electrical degrees, will slip the 25-cycle end back $360 \div 2.4 = 150$ electrical degrees. It would require twelve slipping operations to bring the generators again into phase, and there would be twelve possible relative motor positions, only one of which would be correct for paralleling the 25-cycle generators.

The phase displacements of generator electromotive forces, due to load on the running units, may be such as to cause considerable confusion. If the 25-cycle end is running as a motor

and under full rated load, the generator electromotive force will lag about $2.4 \times 25 = 60$ electrical degrees. If the motor is 20 per cent. overloaded, the phase displacement of the generator will be about 72 degrees.

11. Paralleling by Special Synchroscopes.—In one method of paralleling frequency changers transforming 25-cycle energy into 60-cycle energy, two synchronism indicators are employed. The indicator on the 60-cycle, or generator, end is provided with a dial marked as shown in Fig. 1. When the incoming motor is up to synchronous speed and its 60-cycle generator is excited, the pointer of the synchronizer on the 60-cycle end will take a fixed position, showing the operator how many pairs of poles on the 25-cycle end must be slipped to bring the generators into phase.



FIG. 1

For example, assume that the running unit is without load and that the pointer of the 60-cycle synchronizer stops at the figure *2* when the incoming motor has reached synchronous speed. The operator then proceeds to slip poles on the 25-cycle end of the incoming unit. He follows the method in the third paragraph of Art. **7**, slipping only one pole at a time and synchronizing before slipping the next pole.

12. If the operating unit is about 20 per cent. overloaded and the incoming machine is without load, the needle of the 60-cycle synchronizer will come to rest in a position about 72 degrees ahead, in a clockwise direction, of its proper figure; that is, up to the next figure on the dial. Other relations between loads give other positions of the pointer. The indications thus given are easily misunderstood, and the resulting mistake of slipping the wrong number of pairs of poles can be avoided only by proper attention to the relative loads

on the two machines. The operator must always know the approximate percentages of full load that the units are carrying before attempting to parallel them.

Some synchronism indicators are provided with movable dials that can be set forwards by an amount depending on the load of the running machines.

13. If it is desired to parallel, by the pole-slipping method, two frequency changers in operation under separate loads, the generator synchronizer indications can be taken while the loads are connected, but the operator must give careful attention to the relative loads and interpret the synchronizer indications accordingly. The operator must also be familiar with the synchronizing connections. For example, if the more heavily loaded machine supplies current to the field winding of one type of synchronism indicator, the needle deflection will be clockwise from the figure indicating the number of slipping operations; if the more lightly loaded machine supplies current to the field winding of the synchronizer, the needle deflection will be counter-clockwise from the proper figure. After the correct synchronizer indication has been obtained, one of the machines is disconnected from its load, and the pole-slipping operation performed as previously described. Pole slipping cannot be performed on a frequency changer that is carrying a load.

14. The method of pole slipping described in Art. 7 is objectionable because of the necessity of using two synchronism indicators, and the necessity for extreme accuracy in synchronizing. In many frequency-changer installations, provision is made for slipping poles by inserting reversing switches in the field circuits of the motors. Each reversal of its field causes a synchronous motor to drop back in phase 180 electrical degrees. Each reversal of the field of the 25-cycle end of a motor generator changing 25-cycle energy into 60-cycle energy will therefore cause the 60-cycle generator to fall back in phase $2.4 \times 180 = 432$ degrees, or 1.2 cycles. A sufficient number of reversals will bring the generator electromotive force into the proper phase relation for paralleling. When this method of

pole slipping is used, the numbers on the 60-cycle synchronizer dial are arranged as shown in Fig. 2, no synchronism indicator being needed in connection with the 25-cycle, or motor, end.



FIG. 2

15. When a 25-cycle–60-cycle, synchronous-motor-generator is started from the 25-cycle end, there is one chance in five that the 60-cycle end will come up in phase with a running unit; whereas, if started from the 60-cycle end, there is only one chance in twelve that the 25-cycle end will come up in phase. Such a motor-generator is therefore preferably started from the 25-cycle end, even though it is normally the generator end. No complications will arise when starting from the generator end; the generator will at once automatically assume its proper load as a generator.

However, conditions may be such that the start must be made from the 60-cycle end. A synchronizer intended for use on the 25-cycle end of a frequency-changer set and marked for indicating pole-slipping operations of the 60-cycle motor by the method of Art. 7 would have twelve points numbered at 150-degree intervals from the zero, or in-phase, position, bringing adjacent points 30 degrees apart, as shown in Fig. 3. The 25-cycle generator displacement due to full load on the 60-cycle motor will be about $25 \div 2.4 = 10.4$ electrical degrees. In this case, there is less opportunity for error, as the displacement at full load is only about one-third the distance between the numerals on the dial.



FIG. 3

16. Synchronism Indicator Dials.—In Fig. 4 is illustrated a synchronism indicator dial specially marked for paralleling 25-cycle–60-cycle synchronous motor-generators started from the 60-cycle end, which is, in this case, the motor end. One element of the synchronism indicator is connected to the generator of the machine running, and the other to the generator of the machine starting. Although the pole slipping is performed by manipulating the motor switches, the dial is marked to show the necessary slip in pairs of poles on the generator end, and the numbering of the dial, therefore, differs from that shown in Fig. 3. The number indicated by the pointer when the motor reaches synchronous speed represents the number of times the pointer should reach zero when the poles are slipped. For example, assume that the pointer stands at *3* when synchronous speed is reached. The motor switch is then opened, the machine begins to slow down, and the pointer revolves. The pointer is allowed to pass the zero position twice, but at the instant that it reaches zero the third time, the motor switch is closed, as the phase relations are then correct.



FIG. 4

17. Special Type of Synchroscope.—One type of special synchroscope used to secure proper phase relations at both ends of a 25-cycle–60-cycle synchronous motor-generator has two pointers, or hands, rotatable over the same dial. One pointer is acted on by synchronizing currents from the 25-cycle end; the other, by currents from the 60-cycle end. The 25-cycle synchronous motor is started by applying to its windings alternating current at a reduced voltage. When synchronous speed is reached, the 25-cycle hand on the synchroscope will point to the zero mark on the dial, and the 60-cycle hand will have a position depending on the phase relation between the 60-cycle electromotive forces of the running and incoming units. If the phase relation of the 60-cycle end of the incoming unit is correct

for paralleling, both hands will point vertically to the zero mark. If incorrect, the motor switch must be opened and the rotor of the set allowed to slow down. The two hands of the synchroscope will then begin to revolve at different speeds, the 60-cycle hand making 2.4 revolutions for each revolution of the 25-cycle hand. If the running unit is not loaded, there will be an instant when both hands point to the top of the dial, zero mark, at the same time, and at this instant the operator closes either the generator switch or the motor switch. Then, as soon as the other switch is closed, the incoming machine is properly paralleled with those already in service, and auto-



FIG. 5

matically takes its proper share of the load. If the running unit is loaded, the indicating hand actuated by its generator current will be in a position at one side of the zero mark at the moment for synchronizing, the divergence depending on the load.

18. Paralleling by Voltmeter and Chart.—In case the generator synchronizer of a frequency-changer set is disabled or otherwise unavailable, an alternating-current voltmeter connected to show at one reading the difference in voltage between the incoming and running generators can be used. In Fig. 5, the voltmeter *a* is connected between the secondaries of potential transformers *b*, the primaries of which are connected between phase terminals of the three-phase Y-connected alternators

of the motor-generator sets. In this case, the neutral points of the alternator-armature windings are connected together through a grounded neutral bus. If the voltages of the two generators are adjusted separately to the same value, the reading of the voltmeter *a* will depend on the phase relation between the two electromotive forces.

19. In Fig. 6 is shown a chart prepared for use in paralleling 60-cycle, three-phase, 2,200-volt, star-pressure, alternators



FIG. 6

driven by 25-cycle synchronous motors. The chart shows the voltage differences between the 60-cycle alternators of the motor-generator sets at various loads and in different phase relations. The vertical scale represents volts difference between generators, and the horizontal scale, the percentage of rated load on the running unit. The curves marked *1*, *4*, *3*, *2*, and *0* represent the number of pairs of poles to be slipped on the

25-cycle motor when the operation is performed by the use of the motor switch and the 25-cycle synchronizer, as in Art. **7.**

20. To use the chart, the voltages of both generators, running and incoming, are adjusted to 2,200, and the reading of a voltmeter connected as in Fig. 5 is observed. The percentage of full load on the running machine is then determined by observation of the ammeter or wattmeter. The vertical line beginning at the number representing the observed per cent. rated load is then followed on the chart to the point of intersection with the horizontal line representing the reading obtained from the voltmeter. The curve *0*, *1*, *2*, *3*, or *4* that is nearest the intersection indicates the number of slipping operations necessary; and, owing to the manner in which the curves are prepared, the intersection will always be close to one of the curves.

If the intersection of the vertical line with the horizontal line falls within one of the rectangles at the curve intersections, the indication is uncertain and should not be relied on until one pair of poles has been slipped and another observation taken. The two observations together enable the operator to determine the proper number of slips to be made. For example, a running unit is assumed to be carrying 100 per cent. rated load. The voltages of the incoming and running generators are each regulated to 2,200, and the reading of the voltmeter, connected as shown in Fig. 5, is 58. The intersection of the vertical line at 100 with the horizontal line at 58 is near the curve *2*; hence, two pair of poles must be slipped. Again, the running unit is assumed to be carrying 80 per cent. of rated full load, and the voltmeter indication to be 70. Referring to the chart, the vertical line through *80* intersects the horizontal line through *70* at a point within the rectangle *a b c d*, and it is indeterminate whether the generators are in the correct phase relation for paralleling, or whether two pair of poles must be slipped. In order to get a definite observation, the motor is slipped one pair of poles. If the generators had at first been in proper position for paralleling, there will be four slips necessary and the voltmeter will indicate approximately 182 volts. If, however, the phase relation at first had been such that two slips were neces-

sary, only one will remain to be made, and the voltmeter would show in the neighborhood of 220 volts.

21. A chart similar to that shown in Fig. 6 can be made for use with other synchronous-motor-driven frequency changers converting 25-cycle energy into 60-cycle energy. One unit is run unloaded in each of the five possible phase positions successively. Another unit is run under various loads ranging from no load to 20 or 30 per cent. overload for each of the phase positions of the unloaded unit. The reading of a voltmeter connected as in Fig. 5 is observed and recorded for each condition, and the values of volts and per cent. rated load are laid off and curves plotted as in Fig. 6. The voltages of the generators must be kept constant and equal throughout the test. Afterwards, when using the chart, the generator voltages must be brought to this value, or the chart values must be multiplied by the proper correcting factor.

22. Conditions for Parallel Operation.—To be operated in parallel synchronous-motor-generators must be constructed alike, so that when the motors are rotating synchronously the generators will be exactly in phase with one another. The alinement of both the rotating and the stationary parts of the 25-cycle end with those of the 60-cycle end should therefore be precisely alike on all machines to be operated in parallel.

Even with correct alinement, an error in connections may cause an unsatisfactory division of load between units. Corresponding poles of all parallel connected motors and corresponding poles of all parallel connected generators of such sets must have like polarity. The relation of the connections of the motor armature leads is not important, but corresponding terminals of the generator armature windings must be connected to the same phase conductors of the busses.

23. Control of Power Factor and Current Load.—The power factor of the synchronous motor of a frequency-changer set is regulated in the same manner as though the motor carried a purely mechanical load. The current loads between paralleled generators of frequency changers are controlled in the same manner as for any alternators connected in parallel.

A unit to be disconnected should be relieved as much as possible of the current load by means of the generator rheostats before the armature switch is opened.

24. Control of Kilowatt Load.—The distribution of kilowatt load among synchronous frequency changers in parallel is ordinarily beyond the control of the operator. An incoming unit, on being connected in parallel with a running unit, at once takes a definite proportion of the load, and no manipulation of exciting currents will change this proportion more than 1 or 2 per cent.

In general, a synchronous-motor-generator that is to carry more or less than its proper proportion of the kilowatt load



FIG. 7

must be so manipulated as to cause it to lead or lag in phase relative to the machines in parallel with it. The manipulation consists in properly changing the connections of the generator armature leads, reversing the generator field leads, and slipping poles.

25. In Fig. 7 (*a*) are shown two generators *a* and *b* of synchronous-motor-generators properly connected for correct-load division; like terminals of the generators are connected to the same bus-bar, as indicated by the numerals. In (*b*) the leads of the generator *b* are shifted so as to change the phase relation of the machines by 120 degrees. Such a shift, or transposition, is called *spiraling* the leads, and is sometimes made in order to obtain a desired load division.

26. Assume that the leads of the 60-cycle generator of a synchronous-motor-generator converting 25-cycle energy into 60-cycle energy are spiraled at the generator terminals or somewhere between the synchroscope connections and the generator terminals so as to advance the phase position of the generator by 120 degrees. Slipping one pair of poles on the motor will cause that generator to lag 144 degrees behind its former phase position, the net result of the spiraling and pole slipping being to cause the generator to lag 144 − 120 = 24 degrees behind the others. A reversal of the generator field polarity will cause a further change of 180 degrees



FIG. 8

TABLE I

METHOD OF OBTAINING PHASE CHANGES IN SYNCHRONOUS-MOTOR-GENERATOR OPERATION

Generator Leads	Slip Generator Degrees	Generator Fields	Angle of Lead Degrees	Angle of Lag Degrees
Spiral forwards	288	Reverse	12	
Spiral backwards	216	No change	24	
No change	144	Reverse	36	
Spiral forwards	72	No change	48	
Spiral backwards	None	Reverse	60	
Spiral backwards	72	Reverse		12
Spiral forwards	144	No change		24
No change	216	Reverse		36
Spiral backwards	288	No change		48
Spiral forwards	None	Reverse		60

in its phase position, leaving it 180 − 24 = 156 degrees ahead of the others. By again slipping one pair of poles, 144 degrees of

this phase difference can be removed, leaving the generator 156 − 144 = 12 degrees ahead of the others.

In like manner, the phase relations can be changed by any desired multiple of 12; the procedure is as follows: The generator leads can be spiraled either forwards, as in Fig. 7 (*b*), or backwards, as in Fig. 8; the generator field can be reversed, and the generator can be slipped back by multiples of 72 degrees by slipping poles on the motor. The simplest method of securing a slip of 72 degrees on the generator end is to reverse the field on the motor end.

Table I shows the method of obtaining any desired phase difference in multiples of 12 degrees from a lag of 60 degrees to a lead of 60 degrees. In practice, it will seldom be necessary to use all the changes shown in the table.

27. Some synchronous-motor-generators are so constructed that the stationary, non-rotating member of either the 25-cycle end or the 60-cycle end is mounted in a cradle in which it may be rocked through a few degrees to obtain a phase displacement. This style of construction permits of a much finer adjustment than can possibly be obtained by the method previously described.

SYNCHRONOUS CONVERTERS

PRELIMINARY INSPECTION

28. Before starting a synchronous converter for service, the condition of the commutator and of the brush contact with the commutator and with the collector rings should be noted. Dirt, copper particles, dust, and all other foreign objects should be removed from the machine. Knife-blade switches should be examined for poor condition of contacts.

STARTING FROM SPECIAL TRANSFOMER TAPS

29. The simplest method of starting a synchronous converter is to apply to the armature a reduced voltage taken from portions of the secondary windings of the main transformers. Usually, about one-third normal alternating-current voltage is applied first, followed by two-thirds voltage, and then by full voltage. The field circuit is left open and the field winding is divided into open-circuited sections until the armature reaches synchronous speed. The reduced voltages for starting are usually obtained by means of two three-pole, double-throw switches connected as shown in Fig. 9.

30. Assuming that the machine is provided with a quick-break field switch, not shown in Fig. 9, the procedure for starting is as follows:

Open the field switch and also the field-break-up switch on the frame of the machine. See that the armature circuit is open on the direct-current end. Close the starting switch *a*, Fig. 9, to the upper position. Close the other starting switch *b* to the upper position. Close the primary switch (oil switch) connecting the transformers to the high-tension, alternating-current bus-bars. The armature will then begin rotation, and will reach synchronous speed in a few seconds, the time depending on the size of the armature and on the voltage applied.

When the armature has reached synchronous speed, observe the polarity of the machine by connecting the voltmeter (not shown) to the direct-current terminals, using, if possible, the switchboard instruments and connections. If the polarity is correct, close the field switch; then close the field-break-up switch into the running position, the upper position in Fig. 9. If the polarity is incorrect, as indicated by a reversed indication of the voltmeter, close the field switch, strengthen the field by cutting out resistance in the field rheostat, and close the field-break-up switch in the lower position. Carefully observe the voltmeter; the voltage will decrease to zero and reverse. At the instant that the voltmeter needle passes over the zero point, reverse the field-break-up switch, closing it into the running position.


A:C. Busses
Oil Switch
Step-Down Transformers
Positive D:C. Bus
Field Rheostat
Circuit-Breaker
Low-Voltage Release
Ammeter Shunt
Starting Box
To Fan Motor
Reactors
Rear View A:C. Starting Panel
1/3 and 2/3
a
b
D:C. Wattmeter
To open Oil Switch
To + Operating Bus
Shunt Field
Converter Armature
Series Field
Field Break-Up Switch
d
e
Speed Limit
To Current Transformer
Grounded on Machine Frame
c
Equalizer
Negative D:C. Bus

FIG. 9

When the polarity is correct and the field switches are closed, throw the starting switch *a*, Fig. 9, quickly to the two-thirds, or lower, position. In 4 or 5 seconds, increase the applied voltage to normal by throwing switch *b* quickly to the lower position.

STARTING BY INDUCTION MOTOR

31. A synchronous converter may be provided with an induction motor on an extension of the shaft. The motor is used exclusively for starting purposes and may be supplied either from a special set of transformers or from the main transformers that supply the converter. Assuming the latter condition, the procedure for starting is as follows:

See that the switch in the secondary circuit between the transformers and the armature of the synchronous converter is open. Close the field switch of the converter, the transformer primary switch, and the starting switch of the induction motor. The machine will then start; when it is running at a speed slightly greater than normal, connect the synchronizing circuit, and open the starting circuit of the induction motor. As the speed of the machine becomes slower, watch the synchronizing devices, and when synchronism is indicated close the switch connecting the armature of the converter to the transformer secondaries.

If no synchronism indicating circuits are provided, the procedure is changed. Start by means of the induction motor, as before; but leave the field and field-break-up switches of the synchronous converter open. When the machine is up to speed, open the induction-motor switch and close the switch connecting the converter armature to the transformer secondaries. Observe the polarity of the direct-current electromotive force and correct it, if necessary, as described in Art. **30.**

STARTING WITH DIRECT CURRENT

32. When started as a direct-current motor, a synchronous converter must be synchronized to the alternating-current supply in the same manner that one alternator is paralleled with another. The procedure varies somewhat according to the

system of connections. First will be considered the case of a synchronous converter excited from the direct-current busses and not provided with a switch between transformer secondaries and armature.

See that the field-break-up switch is closed in its running position and close the direct-current circuit-breaker. Cut out at least three-fourths of the rheostat resistance and test the fields for excitation by applying a piece of iron to one of the pole pieces. Close the starting switch to the first point, or clip, which places all the starting resistance in circuit. Close the armature switch having a polarity opposite that of the starting switch; this would be switch *c* in Fig. 9. The armature will begin to rotate. Observe the direct-current ammeter; when its needle has stopped, or nearly stopped, dropping back toward the zero position, cut out another section of a starting resistance, and proceed in this manner until this resistance is all out of circuit. Connect the synchronism indicating device, synchroscope, lamps, or voltmeter, and, by means of the field rheostat, regulate the speed of the machine until a good synchronizing beat is obtained. When the speed is correct, regulate the alternating voltage of the synchronous converter to a value that, multiplied by the step-up ratio of the transformers, will equal the line voltage. Close the transformer primary switch at the instant that the two alternating electromotive forces are in phase with each other, as indicated by the synchronizing device.

33. If provision is made for synchronizing with a secondary instead of a primary switch, proceed as follows: With the secondary switch open, close the transformer primary switch; start the synchronous converter, as described in the preceding article. Connect the synchronism indicating device; regulate the speed to obtain a proper beat; equalize the converter pressure to the transformer secondary pressure; and close the secondary switch when the electromotive forces are in phase.

34. In some installations, the converter field switch connects to the direct-current armature leads instead of to the bus. In this case, the switching procedure is the same as just described,

but the operator cannot test field excitation before connecting the armature circuit.

35. Split-pole synchronous converters, that is those having auxiliary regulating poles, require treatment slightly different from others. They are started with the main field excited to nearly full strength and no excitation of the auxiliary fields.

After the starting resistance is all cut out, regulate the alternating-current voltage of the machine to approximately that of the supply by adjusting the rheostats of the main and auxiliary fields. Strengthening the auxiliary field current in the same direction as the main field current reduces the alternating-current pressure, and reducing the auxiliary field current, or causing it to oppose the main field current, increases the alternating-current pressure. When the alternating electromotive force of the machine is approximately equal to that of the supply, regulate the speed of the machine by means of the main field rheostat as much as possible, and by means of the auxiliary fields when necessity demands it. When the speed is correct, adjust the auxiliary and regulating fields again to equalize the alternating electromotive forces. Considerable adjustment of both main and regulating field rheostats is sometimes required in order to regulate both speed and pressure. After this is done, the machine should be synchronized in the usual way.

COMBINATION METHOD OF STARTING

36. A synchronous converter can be started by combining the direct-current and alternating-current methods. The advantage of so doing is that no synchronizing operations are necessary.

Start the machine as a direct-current motor. When all the starting resistance is cut out, open the armature circuit and then open the field circuit by means of a quick-break field switch with a discharge resistance; immediately connect the alternating-current supply to the armature at the lowest available pressure. If secondary switches connected to different transformer taps are provided, proceed to increase the applied alternating-current pressure by the method explained in Art. **30.**

If no such switches are provided, connect the full supply potential to the armature when it is rotating at approximately full speed. If the field switch connects to the armature direct-current leads, correct the polarity, if it is incorrect. If the field circuit connects to the load direct-current busses, close the field switch and close the reversing field-break-up switch to the running position. If the polarity is reversed, it will be corrected when the fields are thus excited from the busses in the proper direction.

Another method of correcting polarity is available when paralleling a compound-wound synchronous converter to one or more similar units carrying considerable load. In this case, the shunt-field circuit of the incoming machine is left open, the equalizer switch and the armature switch of the same polarity are closed, and the armature switch of opposite polarity is left open. A part of the current of the other machines follows the path through the series winding of the incoming unit and corrects the polarity. The shunt-field circuit is then closed. This operation is best performed when the converter is running on the low-pressure connections.

SINGLE OPERATION

37. Synchronous converters employed in electric-lighting systems, especially if used in parallel with storage batteries, are usually shunt wound. To operate a shunt-wound machine separately, if the direct-current busses are dead, proceed as follows: Having started the machine and corrected the polarity, regulate the direct-current voltage to normal and close the armature switches to the direct-current busses. If these busses carry considerable load at the time the machine is connected in, the voltage will decrease a little but can be brought back to normal by whatever means is provided for voltage regulation.

The same procedure applies to the operation of a single compound-wound synchronous converter for railway service, except that the load, unless excessive, will not cause much, if any, drop in the direct-current voltage.

PARALLEL OPERATION

38. Assume that a shunt-wound synchronous converter is to be operated in parallel with other sources of direct current, as storage batteries, shunt generators, or other shunt-wound converters. After starting the machine regulate the direct-current voltage to equal that on the bus-bars, and close the main armature switches to the busses. Divide the load among the machines as desired. A synchronous converter is caused to take load by raising its terminal voltage and to drop load by the reverse process.

Compound-wound synchronous converters are connected in parallel in the same manner as compound generators; that is, by the use of equalizing connections for their series-field circuits. In paralleling such units, the equalizer switches are closed and then, on the incoming unit, the armature switch having the same polarity as the equalizer connections. After this is done, the converter pressure and that of the bus-bars, are equalized, after which the other armature switch should be closed.

Ordinarily, compound-wound rotary converters must not be connected in parallel with storage batteries, shunt-wound generators, or shunt-wound rotary converters. If, however, there is a long length of feeder between the compound machine and the battery, or the shunt machine, so that the drop in the feeder is equal to the compounding effect, they may be operated in parallel.

VOLTAGE REGULATION

39. The direct-current voltage regulation of synchronous converters is usually obtained by means of potential regulators connected in the alternating-current leads; by means of series synchronous boosters, sometimes called *synchronous booster converters;* and by means of regulating poles, or split-pole windings. Two other methods, by direct-current boosters and adjustment of field excitation, are not much used.

Voltage regulation by means of a potential regulator is produced by rotating the primary winding of the regulator into different positions with respect to the stationary secondary

winding. This is done either by the use of a hand wheel or an alternating-current motor geared to the rotating shaft of the regulator primary winding, the rotation of which in one direction lowers the alternating-current pressure applied to the armature and consequently lessens the direct-current pressure of the converter; rotation in the other direction raises the pressure.

Voltage regulation by means of series synchronous boosters is carried on by the use of the field rheostats in the main field circuits of the rotary converter and the booster. In this case, practically all the pressure regulation is done by means of the booster; but it is necessary to adjust the main field rheostat, also, in the regulation of the power factor.

Synchronous converters having regulating poles are regulated by varying the wave form of the alternating current in the armature. It is done entirely by adjusting the main and auxiliary field rheostats.

INTERRUPTION OF ALTERNATING-CURRENT SUPPLY

40. If the alternating-current supply to a synchronous converter operating alone is interrupted, the machine will stop. If, however, the synchronous converter is operating in parallel with direct-current generators, storage batteries, or synchronous converters having an uninterrupted supply, the converter on the interrupted circuit may run inverted, receiving energy from the direct-current bus, and may appear to be operating normally. A synchronous converter may also run inverted, because of too low transmission-line pressure. In either case, the inversion is indicated by a reversed reading of the direct-current ammeter.

To determine whether the inversion is due to interrupted supply or to low transmission-line pressure, strengthen the field of the inverted machine. If the amount of inversion, or back feed, is thereby reduced and the speed of the machine is not diminished, the indication is that the machine is still running synchronously and the supply is uninterrupted. If, however, strengthening the field causes a reduction in speed and the amount of back feed is reduced for only 2 or 3 seconds, the

transmission supply is probably interrupted. As long as a rotary converter is operating inverted, the alternating-current voltmeter indication is not a reliable means of determining whether the transmission-line supply is interrupted, because the alternating-current circuit is kept alive by the inversion.

If the test shows the supply to be interrupted, the synchronous converter should be disconnected from the alternating-current busses at once; because, if the transmission line were to be made alive with the inverted converter connected, the machine would probably be seriously damaged, having fallen out of step.

41. If a synchronous converter with very weak field excitation is operating in parallel with other sources of direct current, an interruption of the alternating-current supply may be followed by excessive speed of the machine, now motorized on the direct-current side. In such an emergency, the speed-limit device should immediately open the direct-current circuit-breaker; if it does not, the operator should at once either strengthen the fields or open the direct-current armature circuit.

If an inverted synchronous converter, even when normally operating with a strong field excitation, feeds back into a circuit taking lagging current, this current may weaken the converter field enough to cause the armature to speed up dangerously. For this reason, whenever it can be avoided, induction or even synchronous motors should not be operated on the same line with synchronous converters that feed to direct-current busses having other sources of supply.

Synchronous converters operating in parallel with some other source of direct current at a time when a severe short circuit occurs on the alternating-current line may invert or back feed from the direct-current bus and supply alternating current to the short circuit, even after the line oil switch at the generating station has opened. If, in such cases, reverse-current or overload relays do not automatically disconnect the inverted units, the oil switch of each rotary converter should be opened at once by the operator.

POWER FACTOR

42. The regulation of the power factor of a synchronous converter, like that of a synchronous motor, is effected by changing the exciting current. Machines built with regulating poles require regulation on both main and auxiliary fields, as do also converters with series synchronous boosters.

A synchronous converter operating with a low power factor may become fully loaded, or even overloaded, when the direct-current ammeter indicates less than the normal current rating, or when the output is less than the unit is rated for. If the synchronous converter is provided with an alternating-current ammeter, the operator should observe it frequently and carefully, as it indicates the actual load on the unit. If the power factor is low, the direct-current meters or the alternating-current wattmeter may lead the operator into serious error, if he relies on their indications alone. If no alternating-current ammeter is provided, the current can be calculated from readings of the alternating-current wattmeter and the power-factor indicator.

A synchronous converter should be operated, as near as possible, at unity power factor and at full load. Shunt-wound and compound-wound machines with the series-field cut out or short-circuited should take a leading current at no load, so as to give unity power factor with load. A compound-wound machine should take a lagging current at no load.

MISCELLANEOUS EQUIPMENT

STORAGE BATTERIES

FLOATING

43. In electric stations and substations, storage batteries are used in two distinct classes of service: *Peak-load service*, in which they are charged at times of light load and discharged during heavy-load periods; and *emergency*, or *stand-by*, *service*, for which they are kept charged and ready for immediate discharge in case of any interruption of the regular direct-current output from generators or synchronous converters.

When neither charging nor discharging, a storage battery can be disconnected from the bus-bars or it can be floated on them. In order that a battery may float on the busses its pressure must be regulated to equal the bus-bar voltage. Although a floating battery may charge and discharge in small amounts, taking care of the fluctuations in demand and supply, the battery remains available for practically its full rated duty. Under such conditions the battery performs a third service, that of steadying the bus voltage and the load on the station machinery.

44. Considerable care must be taken to see that floating is done properly. If the battery pressure is even slightly higher than the bus voltage, the discharge will be greater than the charge and the battery capacity immediately available will be gradually reduced. The usefulness of the battery for peak load or emergency service is thus diminished and the generating machinery is not materially relieved. Also, where end cells are used to regulate the battery voltage, some of the cells will be discharged less than the others. If the battery voltage is

too low for correct floating there will be a net charge, which, though harmless, is not economical.

45. Correct Floating Voltages.—The correct floating voltage per cell depends on the type of cell; the proper value for a given type is generally specified by the manufacturers,



FIG. 10

and may lie between 2.08 and 2.12 when the battery is fully charged. To keep a battery floating in the fully charged condition, its voltage must be changed to meet changes in the bus-bar voltage. When the battery voltage is regulated by means of end cells, equality of bus-bar and battery voltage cannot be maintained exactly without changing the bus-bar voltage.

If the battery is to float in a partly discharged condition, the floating voltage per cell must be determined from a discharge curve, because the voltage of a cell diminishes as the discharge progresses.

Lacking knowledge of the proper floating voltage, the operator must rely on the indications of an ammeter or ampere-hour meter in the battery circuit.

Precise floating can usually be obtained on lighting systems; on railway systems the load and bus voltages are generally so variable that the floating is only approximately correct.

46. Checking Floating Regulation.—The method of regulating the floating by cell pressures should be checked by observing the indications of the recording voltmeter and the ampere-hour meter, and by testing the specific gravity of the electrolyte in the pilot cell. The recording voltmeter should be so marked, or calibrated, as to indicate clearly the condition of correct floating, and it should be connected across a considerable number of cells, else its indication will be unreliable. The chart shown in Fig. 10 is printed with the correct floating voltage indicated by a heavy-line circle with which the wavy line traced by the voltmeter needle coincides when the battery is floating properly. On the actual chart, which is about twice as large as that shown in the illustration, the voltmeter indication is traced in red ink and the printed voltage circle is a black line heavier than the other circles.

DISCHARGE

47. A storage battery is caused to discharge by raising its voltage relative to that of the bus, and the amount of discharge is controlled by regulating the relative increase, as explained in *Storage Batteries*.

48. If, at any time, during discharge, the number of ampere-hours already delivered is known, the length of time during which the battery can be further discharged at a given rate can be determined by reference to a set of curves similar to those

shown in Fig. 11, which is drawn for a battery capable of delivering 1,060 amperes for 1 hour. The heavy-line curve is called the *capacity curve;* each of the broken-line curves represents the discharge, in ampere-hours, that has already taken place. For example, let it be assumed that the battery has been discharged for 30 minutes at a rate of 800 amperes and that the



FIG. 11

operator wishes to know how much longer the discharge can continue at a rate of 600 amperes. The number of ampere-hours already discharged is $\frac{800\times30}{60}=400$. The 400-ampere-hour discharge curve, marked *400*, is followed to its intersection with the horizontal line corresponding to the rate,

600 amperes, to be carried. The desired time interval is then found by measuring on the horizontal scale the distance between the intersection just found and the intersection of the rate line, 600, with the capacity curve. The first-named intersection is at a point corresponding to about 40 minutes on the horizontal scale, and the second-named intersection at a point corresponding to nearly 2 hours and 30 minutes. The battery can therefore carry a load of 600 amperes for 2 hours and 30 minutes less 40 minutes, or 1 hour and 50 minutes, approximately.

49. When a battery is subjected to a very long and heavy discharge, some of the cells may be completely discharged and reversed in polarity. When the battery is again charged, these cells will be again reversed, thus making their polarity correct; but when the remaining portion of the battery is fully charged, the cells that were reversed will be only partly charged. In order to complete their charge, the undercharged cells should be connected to a low-voltage supply and charged separately.

CHARGING

50. After a battery is discharged, it should be given the regular charge as soon as operating conditions will permit. This charge is usually given at the normal rate, which can be increased if the charge must be hastened.

In lighting, power, and railway service, the regular charge is usually carried on at constant current. The curve of the recording voltmeter should be watched during the charge, as it shows, in a general way, the state of the charge. There will be, first, a sharp rise in pressure, as at *a*, Fig. 12, followed by a long, steady rise until the voltage per cell reaches a maximum, at which point the cells, if in good condition, will begin to gas rather freely. The recording voltmeter curve will then take a steeper rise until the pressure required to maintain the constant charging rate becomes constant, as at *b*. The charge should be continued at this constant pressure for about 15 minutes and then stopped. End cells that were discharged a shorter time than the main battery will become fully charged

before the others, and should be cut out of circuit as soon as they have been gassing freely for 15 minutes.

The specific gravity of the acid increases during charge until it reaches a maximum and constant value when the cell is completely charged. Hydrometer readings of a cell in good condition, therefore, serve as indications of the state of charge.

51. Batteries that are not regularly discharged are subject to a reduction in capacity due to local action if kept on open



FIG. 12

circuit, or if floated at too low a voltage. When a battery has not been discharged and recharged for a considerable time, as 10 days or 2 weeks, it should be given a freshening charge to restore the cells to a normal and uniform condition. All the cells should be in circuit and the charge should be continued

until the cells gas freely and the charging voltage, with a constant current rate, remains constant for 15 minutes. If the battery is subject to a slight net discharge during floating, the freshening charge should be more frequent, once, or even twice, a week.

52. Formed-plate batteries should have an overcharge at intervals of 2 or 3 weeks if they have had no regular charge. In overcharging, the charging voltage is maintained constant for 1 or $1\frac{1}{4}$ hours.

53. Fig. 12 shows a recording voltmeter chart giving voltage records for floating a battery fully charged, a discharge at the 1-hour rate, floating after discharge, regular charge after a discharge, overcharge, and a freshening charge. The last two would not occur on the same day as a discharge and regular charge, but all are shown together for comparison.

SERIES BOOSTER GENERATORS

54. Direct-current generators used as boosters are connected in series between the direct-current supply (generator, synchronous converter, or storage battery) and the load. The method employed in putting a series booster generator into service varies according to the arrangement of the connections; the following is the common procedure for boosting feeders: Close the switches *a* and *b*, Fig. 13, connecting the booster generator to the bus and the feeder, respectively. The booster terminal connected to the bus must have a polarity opposite that of the bus. Open the feeder switch *c*, start the booster motor, not shown, and manipulate the field rheostat of the booster generator until the correct voltage on the feeder is obtained. When



FIG. 13

shutting down the booster, reverse the process; reduce the booster voltage, stop the motor, close the feeder switch, and disconnect the booster.

TRANSFORMERS

55. Large transformers in electric stations or substations are generally provided with primary and secondary switches and instruments. If properly adapted for multiple operation, they may be connected in parallel, either for transfer of load from one to the other, or for regular operation.

When putting large transformers into service, it is better to close, first, the switch connecting the transformer to the supply and then the one connecting the load to the transformer. In this way, the momentary rush of current is lessened.

Transformers cooled by air blast must not be operated without a continuous supply of air. If a transformer is under full load, an interruption of air blast for only a short time may result in overheating sufficient to damage the insulation to the breaking-down point or in permanently injuring the steel core. If the transformer is cooled by water circulating in coils of pipe submerged in oil, the same rule applies. Every effort should be made to put disabled cooling apparatus into condition as soon as possible.

POTENTIAL REGULATORS ON DISTRIBUTING CIRCUITS

56. The voltage regulation of an alternating-current circuit for local distribution from a generating station or a substation is accomplished by means of a potential regulator connected in series with the circuit. An automatically operated potential regulator should occasionally receive attention to see that it is maintaining the correct pressure on the circuit. If line-drop compensators are not used, the operator should have either a curve or a schedule showing the proper voltage for each load on each circuit, in order that he can check the performance of the regulators.

Non-automatically operated potential regulators require closer attention from the operator, who should be careful that the step-by-step action of a regulator of the variable-transformer type is positive and complete each time. Manipulation of the hand lever should be performed with a loose-wrist movement so as not to retard the quick-jump action of the dial switch.

CARE AND MAINTENANCE OF ELECTRICAL MACHINERY

GENERAL INSTRUCTIONS

INSTALLATION

57. Unpacking and Handling.—Large machines, too heavy to handle complete, are shipped in sections, which are assembled at their destination, usually by the erecting department of the manufacturer, and always according to the manufacturer's instructions. The following general remarks on installation apply more particularly to machines of small or moderate size shipped completely assembled.

During unpacking and handling, machines or parts should be carefully protected from severe shocks or blows. The eyebolts, or bails, when provided, should be used for lifting the machines, if possible. Great care should be exercised in handling castings during extremely cold weather, as they are then easily broken.

58. Location.—The location of an electrical machine cannot always be selected with a view to the best results in operation. The ideal location is clean, dry, well ventilated, easily accessible, and in plain sight. A machine should not be placed where it will be exposed to moisture; provision should be made for protection against drippings from steam or water pipes, or from the roof or wall of a tunnel or a mine. The atmosphere surrounding a machine should not be so warm

that the maximum temperature of the machine, while operating, will exceed the limit for normal running set by the manufacturers. Freedom of the atmosphere from acid fumes is essential.

59. Foundations.—Solid masonry foundations are best for electrical machines, but timber is often used for supporting machines of the smaller sizes. In any case, the foundation should be solid enough to prevent vibration. If it is desirable to insulate a machine frame from the ground, the slide rails or bedplate must be bolted to dry timbers, which are, in turn, firmly fastened to the masonry foundation. The timbers should be treated with some kind of moisture-repelling compound, and they should be countersunk where they receive the bolts that hold the machine bed. The heads of these bolts should be covered with insulating compound. The wood or iron uprights or stringers for mounting motors on ceilings or walls should be heavy and rigidly anchored to prevent vibration.

60. Erection.—Before a machine is firmly fastened to its foundation, the driving and driven shafts must be lined up. The pulleys of a belt drive must be in line, so that the belt will run true. The gears of a gear drive must mesh properly. Two shafts of a direct drive must be in line before the coupling is made. The alinement of pulleys can sometimes be tested by installing the belt temporarily and turning the pulleys by hand; if the alinement is poor, the belt will tend to run off.

Motors in industrial service are frequently mounted on a wall or a ceiling. If such mounting is intended, the manufacturers should be so informed when the order is placed. Some types of motors are provided with bearing brackets, or housings, that can be turned through an angle of 90° for wall mounting and through 180° for ceiling mounting. Sometimes the motor is fastened to its bedplate or its slide rails, as the case may be, before it is hoisted into position; in other cases, the slide rails are mounted in place before the motor is hoisted to its position on wall or ceiling; the method followed depends on the conditions.

Vertical motors must be mounted so that the shaft does not incline from the vertical by an angle greater than the limit set

by the manufacturers. Also, especial care must be taken that the driven shaft is properly alined with the motor shaft. Vertical motors should be very securely bolted to their foundations.

61. Removal of Moisture.—The windings of electrical machines must be dry before full voltage is applied. Machines that have been stored in unheated buildings or have been long in transit should have their windings thoroughly dried before they are put into service.

A machine can be conveniently dried by sending through its windings a current large enough to raise the temperature to about 70° C., but not over 85° C. The temperature should be raised gradually through several hours, the time depending on the size of the machine, and should be kept as nearly uniform as possible throughout the windings. At no time during the drying process should the temperature of the windings be allowed to drop to that of the surrounding air, because the moisture would then condense on the coils. A generator can be dried by its own current, the armature circuit being short-circuited beyond the ammeters and the field excitation being reduced. Field-exciting current from a separate source is preferable. Both the field and armature voltage should at first be kept low, because damp insulation is easily broken down. Some means must be provided for controlling the current, and the temperature of the machine should be watched closely, in order to prevent the interior of any winding from becoming too hot.

Small motors can be dried in ovens. If large machines must be dried by external heat, sheet-iron compartments can be built around them and the interiors heated by charcoal stoves or steam pipes; the latter must be free from leaks. The drying of electrical machinery by any process is very slow. It may take several days to dry a large machine.

BEARINGS

62. When first starting a machine, the bearings should be watched carefully to see that they are receiving proper lubrication. If possible, a new motor should be run for 1 or 2 hours

on light load to make sure that the bearings will work without undue heating.

Most bearing troubles are due to insufficient lubrication, caused by poor lubricant, lack of lubricant, dirty lubricant, failure of oil rings to revolve, clogged oil grooves, or poor grade of waste in waste-packed bearings. Oil that is too thin will not stick to the rings or chains of self-oiling bearings in sufficient quantity to be drawn up on to the shaft, and the bearing will heat due to lack of oil. In large bearings, where the distance that the oil must be lifted by ring or chain is considerable, the oil must be thicker than that used for small bearings. Sometimes oil rings, especially those of small bearings, do not revolve properly; this fault, though rare, should be remedied at once.

63. The first symptom of poor lubrication is heating of the bearing. A motor or generator bearing is usually safe if it operates at a constant temperature below the boiling point of water, but a rapid rise of temperature toward this limit is indicative of danger. An overheated bearing will be hot to the touch and will give off the odor, and perhaps the smoke, of burning oil.

Other causes of heated bearings are poor bearing surfaces, which may be caused by careless handling or by dirt in the lubricant, journal cap too tight, bent shaft, unbalanced rotating parts, bearing out of line, or excessive belt tension.

When an overheated bearing is observed, it should be given an abundant supply of fresh clean lubricant. If this treatment does not afford relief in a reasonable time, part or all of the load should be removed from the machine, which should be kept rotating slowly until the bearing cools; otherwise, the bearing will freeze, or set. When the bearing cools sufficiently, the machine can be stopped and a search made for the trouble. An inexperienced person should not attempt to repair bearings.

ROUTINE

64. The proper maintenance of electrical machinery requires that it be given regular attention to keep it clean and free from moisture, grit, and acid fumes. The operator

should at frequent and regular intervals, make careful inspections of all the apparatus, to note condition of contacts, wear, heating, and general conditions. To be on the alert to prevent trouble, systematic tests should be made to determine the condition of the electric circuits. The insulation resistance tests, described later, should be applied to armature and field windings, machine leads, etc. at frequent intervals.

In the event of any operating trouble or defect in performance, it is important to restore normal conditions as soon as possible. To do this, it is necessary to proceed systematically. Certain symptoms point to certain causes of trouble, and a thorough familiarity with both symptoms and causes is essential; haphazard guesswork may only complicate the trouble.

TROUBLES OF DIRECT-CURRENT MACHINES

POOR COMMUTATION

65. List of Causes.—Under *unsatisfactory performance* of direct-current machines may be included *poor commutation*, *excessive heating of electrical parts*, and *noisy operation*.

Poor commutation may result from overload, improper position (lag or lead) of brushes, hard or high-resistance brushes, rough commutator bars, high mica on the commutator, grounds, short circuits, or open circuits in the armature, high-resistance connections between the armature coils and the commutator, poor brush contact, inaccurate brush spacing, uneven air gap, or weak magnetic field.

66. Overload.—The symptom of overloading is general overheating of the armature and commutator accompanied by sparking, which can be reduced, but not stopped, by properly advancing the brush position. Overloading may also be recognized by comparing the ammeter reading with the nameplate rating of the machine.

67. Wrong Position of Brushes.—For satisfactory performance, the brushes of a direct-current machine must be at

the neutral points of commutation. On most standard machines without commutating, or regulating, poles, the no-load neutral points are in line with the centers of the poles, but the points change positions as the load varies. On generators, especially those that have large armature reaction, the brushes must be set forwards in the direction of rotation as the load increases; on motors, the brushes are set backwards. The amount of change must be determined by experiment for each machine. If the load on the machine is of a more or less fluctuating nature and attention cannot be given to the brush position, the brushes should be left in the position that gives the best average commutation for all loads at normal voltage.

68. Hard Brushes.—Brushes that are too hard or have too high a specific resistance may be unable to carry the current at the contact surface. Some generators require brushes that are harder and of higher resistance than can be used satisfactorily with others. In such cases, some experimenting is usually necessary to determine the proper kind of brushes to use. Brushes should not be changed, however, until it is certain that the cause of faulty commutation is not elsewhere.

69. Poor Commutator Surface.—Eccentricity of the commutator, high bars, low bars, flats, and high mica are all defects that necessitate resurfacing. Eccentricity may be detected by a regular rise and fall of the brushes in their holders, the frequency corresponding to the speed. The commutator should be put into a lathe and turned concentric to the shaft center, or, if preferable, the lathe tool may be carried on a portable holder mounted on the generator frame and the commutator turned in place.

High bars, if not too high, may sometimes be cut down by using carborundum. Sandpaper, or carborundum paper is best for cutting down projecting mica. Emery paper should not be used for this purpose. Low bars and flats are best treated by turning down the commutator with a tool.

70. Armature Defects.—Short circuits, grounds, reversed coils, open circuits, and high-resistance contacts in armatures cause firing, or sparking. If the commutator shows burning

or blackening on certain bars and inspection shows no high or low bars or flats some one of the foregoing troubles should be looked for. Short-circuited armature coils will be indicated by their excessive overheating. Open-circuited coils will not overheat, but will cause severe firing at the commutator bars, as will also high resistance in a coil or at the connection between the coil and the commutator. The commutator bar will usually be found to be burned more on one edge than on the other. The most probable place for the high resistance to occur is at the end joints or in the commutator connection.

71. Poor Brush Contact.—If the curvature of the brush does not properly fit that of the commutator, the effective brush surface is reduced, causing on the active surface a high current density accompanied by overheating and firing. This condition may be found by inspection. The brushes should be resurfaced with a strip of sandpaper drawn back and forth under the brush while in place. In sandpapering brushes, care must be taken to hold the smooth side of the sandpaper down on the surface of the commutator on both sides of the brush. If this is not done, one or both edges of the brush will be rounded off, and it will have contact only at the middle.

72. Inaccurate Spacing of Brushes.—If the brush-holder studs are not properly spaced around the commutator, when the brushes on one stud are set for a non-sparking position those on some other stud will spark because they are not in the neutral commutating plane. The remedy is to set the brushes in the positions, found by experiment, where the largest number of rows are not sparking and to mark the places. Having done this, the brushes are shifted forwards or back, as may be required, to positions where no sparking is obtained on other rows, thus experimenting to find how much it is necessary to move each row forwards or back to secure sparkless commutation. The generator should then be shut down and the brush-holder studs respaced accordingly.

Another method in considerable use for checking the spacing of brushes is to stop the machine and wrap a strip of paper close around the commutator under the brushes and to mark the

paper at the front edge of a brush in each stud. If these marks are not equidistant the brush-holder studs should be respaced.

73. Unequal Air Gaps.—Unequal air gaps between pole faces and armature will cause poor commutation, producing an effect similar to unequal brush spacing. The air gaps can be measured by a long tapering wedge, which is to be inserted into the gaps in a direction parallel to the armature slots. If the air gaps are found to be unequal, they should be corrected by recentering the armature among the field poles. On some machines, the bearing housings are specially arranged for centering the armature; on others, the bearings must be relined.

74. Weak Field.—As a cause of poor commutation a weak field is usually quickly recognized, as it also results in low voltage in a generator and high speed in a motor. If, however, the sparking is confined to one or two rows of brushes, the trouble may be caused by a local weak field due to a high reluctance in the magnetic circuit caused by the pole piece not being tightly secured to the field yoke.

EXCESSIVE HEATING

75. List of Causes.—Excessive heating, another form of poor performance of electrical machinery, may result from errors in design or construction, defective condition of the apparatus, or unfavorable conditions of operation.

76. Errors in Design or Construction.—Electrical machinery is usually subjected to severe test by the manufacturer so that it is very infrequent that defective apparatus is sold. Errors in design or construction include use of the wrong kind of steel for magnetic cores, copper conductors too small or with too low a specific resistance and faulty workmanship.

77. Defective Condition of Apparatus.—Excessive heating of armatures may be caused by poor insulation resulting either from dampness or from carbonization of the insulating fabric by previous overheating due to overloads. A test for low insulating resistance may be made with a high resistance voltmeter, as described later. There will usually be little

difficulty in determining whether or not low insulation results from dampness, as in this case the armature will steam slightly after being shut down. If due to carbonization of the insulating fabric, the insulation will be brittle and weak instead of tough and strong.

Excessive temperature rise in a magnetic core of an armature or a transformer may be a result of severe overheating due to an overload at some previous time. In such cases, the remedy is to rebuild or to replace the core. If large eddy currents are generated in the core, they may be due to the destruction of the coating of insulating japan on the laminations. If this is the case, it will be sufficient to disassemble the core and rejapan the laminations, after which they may be restacked and the winding replaced. This is a very expensive process, and can usually be done only by the manufacturers, or by repair men equipped for such work. Short-circuited armature coils may cause severe local heating which, if not stopped in time, will cause the coils to be burned out.

78. Unfavorable Operating Conditions.—The most common unfavorable condition causing overheating is overload. If it is not possible to reduce the load, every effort should be made to improve the surrounding conditions and to remove as much of the heat as possible by better ventilation. Doors and windows should be open to establish a good circulation of air, and if a fan is available, even of the ordinary desk variety, cool air should be blown on the overheated part.

Unfavorable surrounding conditions include closed doors or windows, close proximity of other heavily loaded machines, uncovered steam pipes, radiation from steam engines, and poor circulation of air. The operator should be on the alert for conditions of this nature and do whatever is possible to remove them.

NOISY OPERATION

79. Noisy operation may be caused by features of design and manufacture, such as high magnetic densities, form and number of armature teeth, etc., or it may be due to mechanical

defects that require attention. Imperfections of design are beyond remedy by the operator.

Brushes loose in their holders or working on a rough commutator are common sources of noise; they should be readjusted or the commutator resurfaced. Armature rubbing against field poles, rotating fields touching armature cores, and induction-motor rotors rubbing against their stators are also mechanical defects indicated by noise. In most of such cases, the noises are barely noticeable at first, as the rubbing is generally slight in the beginning. As it is important that they be found as quickly as possible, the operator should carefully investigate the cause of every unusual sound.

LOW VOLTAGE OF GENERATOR

80. List of Causes.—The service of a generator is unsatisfactory when its voltage is too low. The causes of low voltage are overload, low speed, improper setting of brushes, armature defects, and weak magnetic field. Overloading and wrong position of brushes are recognized by the symptoms given in Arts. **66** and **67**, respectively.

81. Armature Defects.—Armature defects, such as open-circuited, or reversed, coils, lower the generator voltage by reducing the effective number of conductors cutting the magnetic field. Such defects are easily recognized by the kind of sparking on the commutator. Sparking caused by improper brush position or overload is continuous; that due to armature defects is either confined to the commutator bars connected to the affected coils or, if continuous, is more severe on those bars.

82. Low Speed.—Low speed can be detected by means of a tachometer, or speed counter. If the generator is driven by a belt, the speed of the driving pulley and also that of the generator should be taken, in order to determine whether or not there is any slip of the belt. In most cases, belt slip can be recognized by a sharp screeching sound, which may be continuous or intermittent. In some cases, belt slipping is stopped by so moving the generator as to tighten the belt, but as this

increases the tendency to heat the bearings, it is not always the best procedure. If possible, the belt friction on the pulleys should be increased; and it sometimes occurs that this friction is reduced by oil getting on the working surface.

83. Weak Magnetic Field.—Weak magnetic field may be due to improper position of the rheostat contact-arm, causing too much resistance to be included in the field circuit; and it may be caused by a poor magnetic contact causing high reluctance in the magnetic circuit. In order to test the field circuit, turn the rheostat arm to the position for strong field excitation, that is, so as to cut the rheostat resistance out of circuit, and by means of a portable voltmeter measure the fall of potential across the entire field winding, making connections at the field-terminal lugs on the machine frame. If the potential drop across the field winding is less than the machine voltage indicated by the switchboard voltmeter, test each part of the field leads separately in order to locate the defect. If the potential drop in the winding is equal to the generated voltage, test each coil separately, taking care to include in each case the connection to the adjacent coil. If the fall of potential across any coil is found to be very much higher than it is on the others, the high resistance is between the points over which the large pressure drop occurs. The connection should be carefully examined, as it will be much more probable that the high resistance is in one of the connections between coils than inside the coil itself.

FAILURE OF MOTOR TO OPERATE

84. Mechanical Troubles.—The mechanical troubles that may cause a motor to stop or fail to start are severe overload, bent shaft, tight bearings, contact between armature and field poles, brush holders jammed, or excessive friction due to any cause.

A motor of small or moderate size that can be disconnected from its load can be examined for mechanical trouble by turning it by hand. If it turns harder than it should, mechanical trouble is indicated. If resistance to turning is greater at one

point than at others, it may be caused by a bent shaft or rubbing contact between armature and field or between rotor and stator. If the resistance to turning is uniform, or if the rotating parts cannot be turned at all, the bearings may be tight owing to the bearing cap having been screwed down too firmly or to seizing, or freezing, caused by overheating of the Babbitt, due to lack of oil.

Severe overload may cause the fuse in the supply circuit to blow and thus shut down the motor, or, if the load is heavy enough, may prevent the motor from starting. The remedy is, of course, to reduce the load to within proper limits.

85. Electrical Troubles.—The more common electrical troubles that cause failure of operation of a motor are open circuit in the supply, open-field circuit, and wrong connections.

An open circuit in the supply may be caused by a melted fuse, or by a broken wire or connection; the brushes may not be in contact with the commutator; or the current may be shut off at the generating station or at a break in the line.

86. If the field circuit is open, the motor will not start; and if very much of the starting resistance is cut out of circuit, the motor fuse will blow. If from any cause the field circuit is opened while the motor is in operation, the armature speed will increase and the current will become very great; the armature will probably be destroyed if the fuse does not blow. If the motor is under heavy load, the mechanical drag will prevent a rapid acceleration, a heavy current will result, and the fuse will blow or the circuit-breaker will open. A break in the field circuit is indicated by the failure of any pole piece to attract a small piece of soft iron when the field terminals are connected to the source of supply.

87. A break in a field circuit will usually be found, by inspection, to be in one of the leads or connections. If inspection fails to discover the break, the field coils should be tested with a voltmeter, as follows: Connect the field terminals to the source of supply, leaving the armature circuit open. Connect one terminal of the voltmeter to one of the field terminals, making

sure that the polarity is correct. To the other terminal of the instrument connect an insulated wire bared for a short distance from the free end, so as to make a contact point. Touch this point successively to the junctions between the field coils. When the voltmeter shows a deflection, the last coil included by the voltmeter connections is the defective one. The voltmeter must have a range at least equal to the full voltage of the supply.

An open-circuited field coil can also be located by the following method: Connect the field terminals to the source of supply, leaving the armature circuit open, as before. Short-circuit each field coil in succession, each time testing the field poles for magnetism with a small piece of soft iron. When the defective coil has been short-circuited, the field poles will strongly attract the iron. In this case the short circuit should be removed in a way to avoid severe inductive effect.

88. The foregoing has reference to a shunt-field circuit; a break in the conductors or connections of a series-field winding is equivalent to a break in the supply circuit.

89. Wrong connections on motors are uncommon, but among those to be looked for are: Motor armature in series with retaining magnetic coil of starting box; shunt field in series with armature; shunt field connected on wrong side of starting resistance; wrong terminal of the motor connected to the starting box; and part of the field coils reversed.

If the armature is in series with the coil of the retaining magnet, an attempt to start the motor will result in burning out the coil. This error will result from interchanging the field and armature leads at the connection to the starting box.

If the shunt field of a motor is connected in series with the armature, the current from the latter will be so limited as to prevent the motor from reaching any considerable speed.

If the shunt field is connected on the wrong side of the starting resistance, the motor will be weakly excited when starting current is applied and may start badly or not at all. If it starts, the field will be strengthened as starting resistance is cut out and the motor will run slower than normal.

If the armature connection of the starting box is made to the motor terminal to which the shunt field is connected, the fields will be practically unexcited, and the motor may not start, or, if it does, will not speed up, but the fuse will blow or the circuit-breaker will open.

If a part of the field coils are reversed, the error may be found by exciting the fields and using a pocket compass, holding it near the pole pieces in such position as to indicate the polarity of the magnets. If a pocket compass is not at hand, a piece of soft iron bar or a nail may be held so as to bridge across between two adjacent pole pieces. If the bar of iron or steel is held firmly to both pole pieces the poles are of opposite polarity; if it is repelled from one they are alike.

FAILURE OF GENERATOR TO OPERATE

90. A direct-current generator may fail to generate because of wrong connections, open-field circuit, too weak, residual magnetism, severe overload, reversed polarity, or poor brush contact.

Wrong connections include such errors as connecting shunt field in series with armature, or reversing part of the field coils. An open circuit in the field circuit will result in no excitation and consequently no generation.

A shunt generator will not build up its voltage if started under a heavy load. It builds up its voltage best on open circuit. Also, in operation, it drops its voltage if a certain critical load is exceeded.

If a generator fails to excite itself, the operator should examine all connections, try a temporarily increased pressure on the brushes, examine the field rheostat for a burn out or a broken coil, test the field coils for open circuit, and check up the position of the brushes. If nothing wrong is found with the connections or the windings, it may be necessary to excite the field from an outside source of energy in order to restore the residual magnetism.

91. If the residual magnetism is too weak or is completely destroyed, the poles will not attract pieces of soft iron held in such position as to bridge across two adjacent poles.

If the machine is compound wound and another machine is in operation, close the equalizer connections of both generators and close to the bus the armature switch of the same polarity as the equalizer connection of the unexcited generator. A part of the output of the running machine will then pass through the series-winding of the unit that will not generate. If the machine is then run at full speed, the generator will pick up.

If the machine is shunt wound and current from another machine or a storage battery is available, pass current from the running machine in proper direction through the fields but not through the armature. The procedure is as follows: Open the armature circuit by disconnecting one terminal of the armature leads between the shunt field tap and the armature; close the main armature switches to the busses to which the running machine or the storage battery is connected; first strengthen and then weaken the field excitation by means of the field rheostat; open the armature switches, taking care to open the first one slowly, drawing out a long arc, to avoid a high inductive electromotive force in the field winding; reconnect the armature terminal and start in the usual way.

92. If no other generator or storage battery is available, disconnect one terminal of the shunt-field circuit and connect it to one terminal of a few primary cells in series. Connect the other terminal of the battery to the remaining shunt-field terminal. Use cells with large current capacity and take care to connect the positive terminal of the battery to the positive end of the field circuit. Connect a portable voltmeter between the disconnected terminal of the shunt-field winding and the binding post from which it was disconnected. The instrument will then indicate the voltage of the batteries while exciting the fields. Cut out of circuit all resistance in the field rheostat, and start the machine. When the voltage of the generator is equal to that of the batteries, which will be indicated by the voltmeter reading being reduced to zero, reconnect the shunt-field terminal and immediately disconnect the battery. If the voltmeter reading cannot be reduced to zero,

it is an indication that more exciting current is required; either more cells should be connected in series to secure higher potential or additional cells should be connected in parallel with those already in circuit, in order to obtain a larger current capacity. High-voltage machines, 500 volts, require more cells than do those of lower potential.

93. Reversed polarity of a generator will be indicated by reversed readings of the main voltmeter. It may be corrected by either of the first two methods (Art. **91**) given for exciting a machine that has lost its residual magnetism. If no other generator or storage battery is available, the third method (Art. **92**) may be used, but in this case about twice as many cells will be needed as for mere excitation.

TROUBLES OF ALTERNATING-CURRENT MACHINES

INDUCTION-MOTOR TROUBLES

94. Alternating-current machines are free from troubles due to poor commutation, which is the chief cause of unsatisfactory operation of direct-current machines. Beyond routine inspection and cleaning, alternating-current machines require very little care. Most of the troubles of alternating-current motors are due to faults in the external, or supply, circuit. The effects of variations in the energy supply can be learned from a study of the performance, or operation, characteristics.

95. Shut-Down of Motor.—A shut-down of an induction motor may be caused by an overload or by any condition producing excessive friction. Especial attention should be given to inspection of the air gap of an induction motor that has been in operation for a considerable time. The air gaps of induction motors are made as small as is consistent with proper clearance; consequently, a comparatively small wear on the bearings may let the rotor rub against the stator, which

will eventually cause enough friction to shut down the machine, and, at the same time, may cause considerable damage to it.

A break in one leg of the supply circuit will cause a shut-down unless the motor is lightly loaded. Also, a low supply voltage may so reduce the torque that the motor is no longer able to carry its load.

96. Failure of Motor to Start.—The failure of an induction motor to start may be due to any of the troubles that cause a shut-down. If the starting voltage is too low, the motor will not start; if too high, it will start too rapidly and will take excessive current. Also, the torque will be greatly reduced when the switch is in the running position. An open circuit in the autostarter will, of course, prevent the motor from starting.

97. Winding Faults.—Winding faults in induction motors are very rare, but sometimes they exist in new motors, having escaped the notice of the factory inspectors. These faults may be looked for if examination fails to reveal any of the troubles previously given.

With one leg of a phase-wound rotor open, the motor pulls in at about half speed and continues to run at the same rate. The primary currents will be unbalanced, and the pull-out torque of the motor will be reduced. A reversed primary coil or a short-circuited primary coil will cause unbalanced primary currents and overheating. If one phase of the field is open-circuited, the motor will refuse to start.

Squirrel-cage rotors with soldered bars sometimes cause trouble, due to poor contacts at some of the joints. When some of the joints are bad, the motor will take unbalanced currents and may not come up to speed.

SYNCHRONOUS-MOTOR TROUBLES

98. The failure of a synchronous motor to start may be due to faulty connections in the motor leads or in the starting compensator. Inspection should be made for poor contacts or open circuits. An open circuit or a short circuit in one phase will prevent starting. Ammeters in the circuit will indicate

whether the trouble is an open circuit or a short circuit, giving zero reading for the former and abnormal reading for the latter.

Too much load or excessive friction will prevent a start. The ordinary synchronous motor will not start with more than one-third of its full-load torque. The field should be left unexcited until the motor reaches nearly synchronous speed; it will not start with excited fields.

99. Poor Torque.—If poor torque is developed by a synchronous motor, the trouble will generally be found in the field circuit. A glance at the exciter voltmeter or pilot lamp will tell whether the exciter is generating its proper voltage. An open circuit in the motor-field winding or rheostat will cause the motor armature to take excessive current; the motor will stop or develop excessive heat. A short-circuited or reversed field coil will manifest itself by causing the motor to require more than the normal field current for a given load.

100. Overheating.—Overheating of a synchronous motor is frequently due to an attempt to make the motor carry its rated load and at the same time to adjust the field to improve the power factor on the line. A short circuit in an armature coil usually burns out the coil completely.

DANGERS OF PHYSICAL INJURY

DANGERS FROM MECHANICAL SOURCES

101. The operator should be especially careful to avoid contact with moving belts, gears, rotating armatures, or fields, flywheels, etc. When working in the neighborhood of rotating machinery, he should avoid proximity to live circuits, or to static discharge from belts, either of which may cause an involuntary movement that may bring about a dangerous contact with the belt or with gears, or other rotating parts.

Bursting of rotating parts may cause pieces to be thrown about with great force. Such bursting may, in some cases, be caused by errors in operation, as, for example, the opening

of the field circuit of a direct-current motor while the armature is still connected, or the opening of the field circuit of a rotary converter while disconnected from the alternating-current supply and still connected to a source of direct current. Under these conditions the acceleration is generally very rapid, and only a few seconds may be required for the armatures to reach dangerous speeds.

DANGER FROM ELECTRICAL SOURCES

102. The extent of danger due to electric causes depends somewhat on the character of the apparatus, being greater when the voltage is high and when the safeguards are inadequate. It is not practicable to name any particular voltage as a safety limit, as a voltage that might be harmless to one individual might be fatal to another. Again, a pressure that would be harmless if applied across the hand, might cause instant death if so applied that the current would flow through the heart or the brain. In addition to the danger of injury due to electric shock is that due to electric burns, of which there are two kinds, flesh and contact burns. For these reasons two safe rules are: Never allow any part of the body to become a part of an electric circuit; and never expose any part of the body to even close proximity to an electrical arc.

103. In order to avoid accidentally causing a part of the body to become a part of a circuit, the operator should be careful, when obliged to touch live parts, to stand in such a manner that he touches them with only one part of the body. If any portion of the machine circuit is grounded, the ground is also a live part, and contact with it when handling the machine, is to be avoided. The last statement applies to street-railway systems having one side grounded, to alternators having one conductor or a neutral connection grounded, to grounded three-wire systems, or to any similar arrangement. Thus is indicated the advisability of using an insulated platform, stool, rubber mat, rubber shoes, or rubber gloves.

A dry wooden floor is ordinarily good insulation for potentials up to 250 volts; dry white pine is better than the hardwood.

A ¼-inch to ½-inch pure-rubber mat, if clean and dry, is good protection up to about 1,000 volts. For pressures exceeding 1,000 volts, nothing less safe than a stool with good glass or porcelain insulators should be used, and the safer practice is not to touch live parts carrying such voltages.

104. In order to avoid the possibility of current through some part of the body, it is advisable, whenever live circuits must be handled, to do as much as possible of the work with one hand. The other hand should be kept on the side of the body away from live parts, and care should be taken that the knees do not touch the machine frame while work is being done with the hands.

High-tension three-phase systems are now generally grounded at their neutral points, and therefore a person standing in electric contact with the ground and touching any one of the phase conductors would complete a circuit to the earth. When the voltage is very high, care must be taken not to come into even close proximity to the conductors on account of the possibility of a jump to the body. Such a jump is more liable to occur from a point or sharp angle on the conductor than from a flat or round surface.

No work on high-tension equipment should be done without permission from the person in charge of such matters, as it is nearly always necessary to disconnect the equipment from the system. The cleaning and inspection of high-tension equipment is usually done at regular intervals under the supervision of the chief operator, who takes the necessary precautions to render the work safe.

105. Electric burns may result from blowing fuses, accidental short circuits, breaking heavy currents with air-break switches, or causing current to flow through a part of the body. In breaking heavy currents with air-break switches, if the pressure tending to maintain the arc is high, the hands and face should be protected against the effects of the arc. Where there is a back feed, as in the case of a parallel system, this condition is not likely to be serious. When inserting or replacing potential transformer fuses, the operator should stand on a

sufficient insulator and use rubber gloves or a pair of insulating tongs, or both, if possible.

106. The operator should always remember that the source of danger is invisible, that it must be guarded against by continual vigilance, and that, as he becomes proficient in the operation of electrical machinery, there is danger of a growing tendency toward carelessness due to familiarity.

TESTS FOR FAULTS IN ELECTRICAL CIRCUITS

CLASSIFICATION

107. Tests for faults in electric circuits are of two kinds, qualitative and quantitative. *Qualitative tests* are made merely to detect the existence or nature of a fault; accurate measurements are not required. *Quantitative tests* are those requiring more careful use of measuring instruments. In practice, a circuit may be divided into parts, each of which is tested; then the series of qualitative tests combined form a location test. The most common forms of faults in electric circuits are *breaks*, *crosses*, and *grounds*.

QUALITATIVE TESTS

TESTING DEVICES

108. A **magneto-bell**, Fig. 14, is a small, hand-power, alternating-current generator connected to a bell similar to the call bell on a telephone. The armature is driven at high speed by means of gears g and p. The test leads are attached to terminals t and t'.

A magneto-bell is used by applying the test leads to the circuit to be tested and turning the crank of the generator. If

the circuit is complete and within the resistance through which the magneto is designed to ring, the bell will ring. The failure of the bell to ring indicates that the circuit between the magneto terminals is open, or of a resistance too great to pass enough current to ring the bell. If the generator turns very hard when the bell rings, the indication is that the resistance of the circuit is low.

A magneto-bell should not be used for an insulation test between the frame and armature of a large machine, between coil and core of a large transformer, between the sheath and the conductors of a long cable, or on any other circuit of considerable electrostatic capacity. Such a circuit may act as a condenser, receiving current enough to cause the bell to ring, and thus indicate a complete conducting circuit between the terminals of the magneto, even though the insulation is practically perfect.



FIG. 14

109. A test-lamp outfit consists simply of a long extension cord terminating at one end in an attachment plug or other device for connecting the outfit to a source of current supply and at the other end to an incandescent-lamp socket or a series of sockets. One of the conductors of the extension cord is cut and the ends thus made are bared for making electric connection to the circuit to be tested. Enough incandescent lamps must be connected in series to burn properly when supplied with the test voltage available.

In using the outfit, the test circuit is connected to the source of current supply and the two free ends of the test leads are

applied to the circuit to be tested. The lighting of the lamp indicates that the circuit is complete. If alternating current is supplied to the test circuit, the same limitations apply to the use of the lamp outfit as to the use of the magneto-bell.

110. Testing With Telephone Receiver.—A telephone receiver connected in series with one or two primary cells, dry cells, if in good condition, are preferable, serves as a convenient testing outfit. The terminals of the series combination are applied to the circuit to be tested. The telephone receiver is held to the ear and the contact of one of the test terminals with the circuit under test is made and broken repeatedly. If the circuit under test is complete, each make or break of the contact will cause a click in the telephone receiver; if the circuit is open, no click will be heard. The device is subject to the same limitations as the magneto-bell.

111. Testing With Voltmeter.—A voltmeter connected in series with the circuit to be tested and a source of electromotive force can be used for qualitative tests. The range of the voltmeter should be at least great enough to accommodate the total voltage impressed on the circuit. When properly connected, a deflection of the voltmeter needle indicates a complete circuit; no deflection shows an open circuit; a relatively small deflection indicates a high-resistance circuit. A direct-current voltmeter can be used in a wide field of testing work.

112. Detector Galvanometer.—A detector galvanometer is an inexpensive portable instrument that is designed for testing the condition of circuits. The instrument is connected in series with a battery, and the terminals of the series combination are applied to the circuit to be tested. If the needle remains at rest under these conditions, either no circuit or one of very high resistance exists. A deflection of the needle indicates a circuit, the amplitude of the deflection being, roughly, inversely proportional to the resistance. The galvanometer is not subject to the limitations encountered in the use of the magneto-bell, the telephone receiver, or a voltmeter on alternating current.

CONTINUITY TEST

113. A **continuity test** is made to determine whether or not there is a break in a conductor. The terminals of the test circuit are applied to the extremities of the conductor and the indications of the testing device are observed. In some cases, it may be necessary, in order to reach the remote end of a conductor under test, to use as part of the test circuit another conductor known to be continuous.

In order to test a transmission line for continuity, the line conductors must be connected together at the distant end. The test terminals are then applied to the station end of the line. If the transmission line is long, only direct current should be used for testing for continuity; in tests on short lines, a magneto-bell is convenient. The term *transmission line*, as used in this connection, includes underground cables.

114. If the line tested is found to be open-circuited, the faulty section is located by applying the continuity test to different parts of the circuit until the break is located. For example, assume that a test on an overhead line shows it to be open-circuited. The tester proceeds along the line, applying the test terminals at intervals. As soon as the tester has passed the break, the testing device will give indications of a closed circuit. The tester then knows that the fault is in the part of the line between the places where the last two tests were made and he proceeds to locate the break by inspection.

Sometimes the procedure is varied somewhat. The tester goes first to a point about midway between the ends of the line and applies the test terminals. If the test indicates an open circuit, he knows that the fault is in the half of the line beyond; if the test indicates continuity, the break is in the other half. The tester thus at once eliminates one-half the line as a possible container of the fault. A few more tests on the faulty half of the line will probably locate the break within reasonable limits.

TEST FOR CROSSES AND GROUNDS

115. A test for a cross or ground is made to determine whether or not a conducting path exists between two objects, two circuits, or two parts of circuits that should be insulated from each other. The test terminals are applied to the two objects or circuits, and the existence of the fault will be indicated by the action of the testing device. If the test lamp, when used, burns very dimly, the indication is that the cross or ground is of small current-carrying capacity and moderately high resistance.

In general, a test for a leak should be made with a device, such as a magneto, voltmeter, galvanometer, or telephone receiver, requiring only a small current to give an indication. In testing for a short circuit, a test lamp is generally more satisfactory.

DIFFERENTIAL TEST

116. It is sometimes necessary to locate, by a test at the station, a ground occurring several miles away on a series-arc-lamp circuit. For this purpose, a crude form of Wheatstone bridge is used. A series of incandescent lamps is connected across the terminals of the arc-lamp circuit, as shown, roughly, in Fig. 15. Generally, the arc lamps require about 50 volts each, and incandescent lamps rated at about 50 volts are therefore preferable; 110-volt lamps can be used, however, if 50-volt lamps are not available. In any case, the number of incandescent lamps in series should be equal to the number of arc lamps in circuit.

The electromotive force of the generator is consumed in sending currents through the parallel circuits of arc lamps and test lamps. From the positive terminal of the generator to the ground *a*, Fig. 15, on the arc circuit, there is a drop in potential of approximately 50 volts per lamp, or, in this case, $6 \times 50 = 300$ volts. If the movable arm *b* of the testing device is moved from contact *c* toward contact *d*, a point will be reached where the potential drop in the test-lamp circuit is the same as that between the positive terminal of the arc

circuit and the ground. There will then be no current through the detector galvanometer *e* and its needle will rest at the zero position. On further movement of the arm *b*, the galvanometer indication will be reversed. The number of test lamps between the positive terminal of the circuit and the test point at which the deflection of the galvanometer needle is zero is equal to the number of arc lamps between the positive terminal of the circuit and the ground. In this case, the number is six.



FIG. 15

A voltmeter can be used in place of the galvanometer, but it must be capable of indicating at least half the total voltage of the circuit, and the test must then begin with the arm *b* on the middle contact so that only half the voltage can be applied to the voltmeter. A double-throw voltmeter is preferable; if a single-throw instrument is used, care should be taken not to connect it so as to cause reversed deflection.

TESTS FOR DEFECTS IN DIRECT-CURRENT ARMATURES

117. Faults in direct-current armatures are conveniently located by what is known as the *bar-to-bar test*. Suitable contacts *A* and *B*, Fig. 16, are clamped to opposite sides of the commutator. Current from the mains, or bus-bars, *E* is led

to the commutator through a lamp bank *LB*. A movable contact piece, or *crab*, *C* provided with two spring contacts so spaced as to rest on adjacent bars, is connected to a galvanometer or a low-reading direct-current voltmeter *G*.

For the sake of illustration, it is assumed that in coil *N* there is a short circuit, that the commutator leads of coils *S*, *K*, and *W* have been mixed, as shown, and that there is an open circuit in coil *T*. The test is carried out as follows:



FIG. 16

118. Adjust the lamp bank until the galvanometer gives an easily readable deflection when the crab *C* is in contact with bars connected with what are supposed to be good coils. This serves as a standard deflection, with which to compare other deflections; all but defective coils will give this standard deflection.

When the test contacts rest on bars *3* and *4*, the deflection will be much larger, about double, than the standard deflection, because two coils, instead of one, are connected between these bars. When the contacts rest on bars *4* and *5*, the deflection will be reversed, because the leads are crossed, but will not be greater in amplitude than the standard. Between bars *5* and *6*, a large deflection will be obtained, for the same reason that a large deflection is obtained between bars *3* and *4*. Between bars *6* and *7* little or no deflection will be obtained, owing to the short circuit in coil *N*.

As the contact piece is moved around on the lower side of the commutator, no deflection will be obtained until bars *15* and *16* are bridged. There will then be a violent throw of the galvanometer needle, carrying it beyond the scale. When the contact piece is moved on to bars *16* and *17*, there will again be no deflection, thus locating the break in coil *T*. In order that the other coils connected to the bars in the lower half of the commutator can be tested, bars *15* and *16* must be connected together by a piece of wire.

If any of the coils has poor connections with the commutator bars, the effect will be the same as though the coil had a higher resistance than normal, and the galvanometer deflection will therefore be greater than the standard deflection.

QUANTITATIVE TESTS

MEASUREMENT OF INSULATION RESISTANCE

119. The insulation resistance of a circuit may be conveniently measured by means of a direct-current voltmeter.



FIG. 17

The instrument should have a known resistance of 90 to 200 ohms per volt of maximum scale reading, and the marks on the scale should be uniformly spaced. As an example of

the method of making the test, the measurement of the insulation resistance of a single-phase alternator is given; the method of applying the test to a transmission-line circuit is described in another Section.

The voltmeter *a*, Fig. 17, is connected to a double-pole double-throw switch *b* in such a manner that when the switch is in one position, upper position in this case, the instrument is connected directly across the source of voltage. With the switch in the other position, the voltmeter and the insulation of the machine are in series across the source of voltage. One of the test leads is connected to the frame of the machine; the other, to the windings.

If r = resistance of voltmeter;
e = reading obtained with voltmeter across source;
e_1 = reading with voltmeter in series with insulation;
R = insulation resistance.

Then,
$$R = \frac{r\,(e - e_1)}{e_1} \qquad (1)$$

The result will be expressed in ohms or megohms according as r is expressed in ohms or megohms. Some voltmeters for use in insulation tests are specially made with a resistance of 1 megohm. The preceding formula then becomes

$$R = \frac{e - e_1}{e_1} \qquad (2)$$

and the result is in megohms.

MURRAY LOOP TEST

120. The Murray loop test uses a Wheatstone bridge arrangement for locating a ground on one conductor of a line, the other conductor of which is continuous and ungrounded. The connections for the test are shown in Fig. 18, in which *a b* is a slide wire, *c* a galvanometer, *d* a battery, and *e* a flexible-cord connection between slide-wire terminals and line. The line wires are connected together at the distant end.

The manipulation consists in moving the contact maker *f* along the slide wire from point to point, care being taken not

to scrape the wire, until a point is found where a connection can be made without causing a deflection of the galvanometer needle. If the contact maker is moved very slightly to one side of this point, the galvanometer needle should deflect in one direction; if moved to the other side, the deflection should be reversed; thus the condition of a true balance of the bridge is verified.

121. In order to calculate the distance x to the ground, the length of the line must be known. The total length of line conductor in the loop is twice the length of the line, provided, of course, that the line conductors are of equal length, as they are in most parallel systems of distribution.

Let l = total length of line conductor;
x = distance to ground, Fig. 18;
m = distance $b\,f$ at balance;
n = length of slide wire $a\,b$;
$z = \frac{m}{n}$.

Then, $x = z\,l$

The value of z is the ratio between the length of the shorter arm of the slide wire, at balance, to the total length of the slide



FIG. 18

wire. Generally, the slide-wire scale has a total of 100 or 1,000 divisions, and the value of z can be written as a decimal fraction as soon as the balance point has been found. For example, if the total number of scale divisions in Fig. 18 is 1,000

and a balance is obtained with point $f=375$ divisions from point b, then $z=\frac{375}{1000}=.375$. As used here, the term *number of scale divisions* may include the equivalent, in divisions, of a fixed resistance.

After one balance is obtained, the battery terminals and the slide-wire connections should be reversed and the observations repeated. If the two sets of observations give unlike values of z, their average should be used in the calculations.

122. When applying the Murray loop test, the following considerations must be kept in mind: Connections should be carefully made, so that contact resistance will be inappreciable. If the line conductors are of different sizes, it is necessary to calculate the various lengths in equivalents of one chosen size of wire. The flexible leads e, Fig. 18, are generally so long that their lengths also must be reduced to an equivalent length of line conductor and included in the value of l in the formula of the preceding article.

EXAMPLE.—An underground line contains 20,000 feet, one way, of 211,600-circular-mil, twin-conductor cable and 25,000 feet of 250,000-circular-mil cable. The 211,600-circular-mil cable is at the station end of the line. The two flexible connections e, Fig. 18, are each 10 feet long and equivalent in cross-section to No. 14, B. & S. gauge, wire. The slide wire is 100 units in length, and when the balance is obtained, the contact maker is at a point 27.4 units from the zero end of the wire. How far from the station is the ground?

SOLUTION.—For convenience, all conductors in the line circuit are reduced to equivalent lengths of 250,000-cir.-mil cable. The equivalent length of 20,000 ft. of 211,600-cir.-mil cable is $\frac{20{,}000\times250{,}000}{211{,}600}=23{,}629$ ft. The equivalent length of 10 ft. of No. 14 wire, 4,106 cir. mils, is $\frac{10\times250{,}000}{4{,}106}$ $=608$ ft. The length of the line expressed in terms of 250,000-cir.-mil cable is then $608+23{,}629+25{,}000=49{,}237$ ft. As this length is taken one way, the total equivalent length of conductor in the line circuit during the test is $2\times49{,}237=98{,}474$ ft. The value of z is $\frac{27.4}{100}=.274$. The equivalent distance to the ground is therefore $.274\times98{,}474=26{,}981$ ft.

The equivalent distance must be reduced to actual length of line. The first 608 ft. of equivalent length is in the flexible connections, leaving

26,981 − 608 = 26,373 ft. of equivalent length in the line. Of this remainder, 23,629 equivalent feet are of 211,600-cir.-mil cable. The ground is therefore 26,373 − 23,629 = 2,744 ft. beyond the end of the 211,600-cir.-mil cable, or 20,000 + 2,744 = 22,744 ft. from the station. Ans.

123. The Murray loop method, when properly applied, will generally give good results, and the location of the fault as determined by the calculations will be within a short distance of the actual location. In general, the larger the size of the line conductors, the greater will be the liability of error and the greater must be the care exercised in taking the observations. The chief advantage of the method is that an inexpensive slide-wire bridge can be used and accurate resistance units are unnecessary.

VARLEY LOOP TEST

124. The Varley loop is another application of the principle of the Wheatstone bridge. It is more complicated than the Murray loop, but is capable of wider application, though with somewhat less reliable results.

The Varley loop method is especially useful in locating a ground when no good conductor is available as a return. The connections for the unit-resistance type of bridge are shown in Fig. 19 and those for the slide-wire type in Fig. 20. The flexible



FIG. 19

lead to the line conductor is shown at *a*. In each test in which the slide-wire bridge is used, the resistance *b*, Fig. 20, should have a value such as to cause a balance to be obtained when the contact maker is somewhere near the middle of the bridge wire.

The resistance of the line must be known either from previous measurement or from calculation. If the cross-section

of the line conductors is not the same throughout, the length of the line must be expressed in equivalents of one size of conductor. The resistance of the flexible lead *a* must also be taken into consideration, as in the Murray loop test.

125. With the bridge connected as shown in Figs. 19 or 20, obtain a balance and calculate the resistance, using the ordinary Wheatstone-bridge formula; call the result *n* ohms. Ground the distant end of the line and take a second measurement;



FIG. 20

call the result *p* ohms. Call the normal resistance of the line *m* ohms. Then the resistance from the bridge terminal to the fault is

$$r = p - \sqrt{(n-p)\,(m-p)}$$

From the value *r* subtract the resistance of the lead *b*. The remainder is the resistance of the line conductor from the station to the fault. If the conductors are not all the same size, calculate the resistance of each size and locate the ground as in the example of Art. **122.** The result thus found may be unreliable, and, in general, should serve only as a guide to the actual location of the fault.

126. If the fault is a cross to another conductor, the Varley loop test can be used as already explained, one conductor being considered as under test and the other as the ground.

INDEX

NOTE.—In this volume, each Section is complete in itself and has a number. This number is printed at the top of every page of the Section in the headline opposite the page number, and to distinguish the Section number from the page number, the Section number is preceded by a section mark (§). In order to find a reference, glance along the inside edges of the headlines until the desired Section number is found, then along the page numbers of that Section until the desired page is found. Thus, to find the reference "Acceleration, §17, p34," turn to the Section marked §17, then to page 34 of that Section.

A

Acceleration, §17, p34
  Causes of poor, §56, p12
  curves for electric trains, §17, p38
  Kilowatt input for, §17, p46
  Time required for, §56, pp5, 11
Adhesion, §17, p36
Adjustment of load, §56, p20
  of voltage, §56, p19
Air gaps, Unequal, §57, p44
  gongs, §22, p45
  supply for transformers, §55, p11
Alternating-current generators, Operation of, §56, p31
  -current lightning arresters, §53, p35
  -current machines, Tests for, §52, p28
  -current machines, Troubles of, §57, p52
  -current motors, §56, p10
  -current railway motors, §21, p12
  -current railway systems, §17, p23
  -current station, Medium-size, §54, p45
  -current stations, §54, p28
  -current stations, Large, §54, p50
  -current stations, Small, §54, p38
  -current substations, §55, p54
  -current switchboards, §53, p43
  -current switchgear, §53, p23
Alternator, Operation of single, §56, p32
  running-light test, §52, p28
  test with auxiliary motor, §52, p32
Alternators, Operating troubles of, §56, p43
  Parallel operation of, §54, p28; §56, p33
  Series operation of, §56, p33
  Speed control of, §56, p36
  Synchronizing, §56, p33
  Synchronizing circuits for polyphase, §54, p33
Aluminum-cell lightning arrester, §53, p39
Aluminum electrolytic lightning arrester, §22, p18
Amalgam bonds, §19, p31
Ammeter connections, §55, p19
Ammeters, §54, p8
Arc deflectors, §23, p5
  headlights, §22, p24
  welded rail joint, §19, p23
Armature defects, §57, p42
  loss, I^2R, §52, p2
Armatures, Tests for defects in direct-current, §57, p62
Arrangement of bus-bars, §53, p45
Autographic bond-testing car, §20, p29
Automatic control, Series-parallel, multiple-unit, §23, p20
  operation of oil switch, §53, p30
  sectionalizing switch, Feeder, §18, p8
  synchronous-converter substations, §55, p52
Auxiliary bus, §54, p11
  -motor connections, §55, p33
Axle bearings for trucks, §22, p52

B

Balancer set, §54, p18
Ballast of roadbed, §19, p1
Base of rail, §19, p13
Bearing-friction loss, §52, p2
Bearings, §57, p39
  for trucks, Axle, §22, p52
  of railway motor, Lubrication of, §21, p11
Bell circuits for railway car, §22, p36
Bench board, §53, p47
Bending rail to a given radius, §20, p36
Blacksmith shop, §22, p62
Blower drive, §55, p11
  systems for transformers, §55, p10

Blow-out fuse box, Magnetic, §22, p13
-out lightning arrester, Magnetic, §22, p17
Bond, Compressed stud terminal, §19, p28
Hammered stud terminal, §19, p29
test, §20, p26
test, Bridge method of, §20, p27
test, Differential voltmeter method of, §20, p27
-testing car, Autographic, §20, p29
Bonds, Amalgam, §19, p31
and rails, Data on, §20, pp5, 6, 7, 8
Copper-welded, §19, p31
Cross-, §19, p32
Electrically welded, §19, p30
Protected, §19, p28
Rail, §19, p26
Soldered, §19, p30
Unprotected, §19, p28
Booster connections, §17, p15
feeders, §54, p12
generators, Series, §57, p35
Location of, §17, p17
rating, §17, p11
The, §17, p10
voltage variations, Allowable, §17, p14
Boosters, Economy of, §17, p17
Installation of, §17, p10
Brace tie-plate, §19, p10
Bracket anchor, Catenary, §18, p39
construction, Catenary, §18, p32
Brakes, Motors used as, §23, p10
Braking by reversing, §23, p9
Branch-off curve, §19, p32
Breakers, Line, §18, p27
Breaks, Rail, §19, p41
Brush contact, Poor, §57, p43
Brushes, Inaccurate spacing of, §57, p43
I^2R loss in, §52, p3
Too hard, §57, p42
Wrong position of, §57, p41
Bus, Auxiliary, §54, p11
-bars, §53, p41
-bars, Arrangement of, §53, p45
-bars, High-voltage, §17, p9
system, High-tension, §55, p6
Busses, Air circulation between bars of, §53, p41
Current density in, §53, p42
in alternating-current stations, §54, p44
Joints in, §53, p42
of large alternating-current stations, §54, p53
of large stations, §54, p26
of medium-size alternating-current stations, §54, p49
of medium-size stations, §54, p24
of small direct-current plants, §54, p22
of unlike polarity, Separation of, §53, p42
Buzzer circuits for railway car, §22, p36

C

Cables, Leading out feeder, §54, p12
Calculation of track resistance, §20, p10
Calculations, Curve, §20, p34
Electric-railway, §20, p1
for single-phase alternating-current road, §20, p22
for third-rail road, §20, p23
Grade, §20, p38
Rail, §20, p33
relating to general engineering features, §20, p33
Capacity of transformers, §55, p9
Car, Autographic bond-testing, §20, p29
bodies, §22, p46
buzzer and bell circuits, Railway, §22, p36
devices, Auxiliary railway, §22, p34
Door-operating circuits for railway, §22, p37
equipment, Electric-, §22, p1
heating, Electric, §22, p27
house, §22, p56
lighting, Electric-, §22, p19
signs, Railway, §22, p39
Speed control for gasoline-electric, §23, p35
Speed control for storage-battery, §23, p34
speeds, Data on, §21, p3
wheels, §22, p54
wires, Installation of electric-, §22, p40
-wiring diagram for multiple-unit system with hand-operated control, §23, p17
-wiring diagram for series-parallel operation, §23, p6
-wiring diagram for single-phase speed control, §23, p30
-wiring diagram for unit-switch automatic control, §23, p24
Cars, Energy tests on electric, §17, p47
Gasoline-electric, §17, p23
Number of, required, §17, p29
Size of railway, §17, p30
Speed control of electric, §23, p1
Storage-battery, §17, p22
Weights of railway, §17, p31
Carborundum-block lightning arrester, §22, p16
Care of electrical machinery, §57, p37
of generators, §56, p30
Carpenter shop, §22, p60
Cartridge type fuse, §53, p8
Cast welded rail joint, §19, p24
Catenary bracket construction, §18, p32
bracket construction, Feeder tap for, §18, p35
bridge construction, §18, p40
construction, Anchorage on, §18, p39
construction, Double-, §18, p40
construction, Hints on installation of, §18, p44
construction, Installing the wires of, §18, p47

Catenary construction, Insulation of wires of, §18, p46
construction, Single-, §18, p31
construction, Size of wires of, §18, p46
construction, Tension of wires of, §18, p45
hangers, Length of, §18, p46
line construction, §18, p30
span-wire construction, §18, p39
Center of railway system, §17, p54
-pole railway construction, §18, p16
Channel plates, §19, p19
Characteristics of railway motors, §21, p17
Charging storage battery, §57, p33
Choke coils, §53, p39
Circuit-breaker, Hand-operated, §53, p9
-breaker, Low-voltage release on, §53, p12
-breaker, Remote-controlled, §53, p11
-breaker, Reverse-current release on, §53, p13
-breakers, §22, p9; §53, pp9, 24; §54, p9
-breakers, Automatically operated, §22, p11
-breakers, Hand-operated, §22, p9
-breakers, Speed-limiting, §53, p13
Circuits, Synchronizing, §54, p29
Tests for faults in electrical, §57, p57
Classification of direct-current substations, §55, p4
of switchgear, §53, p3
Clearances for track, §19, p38
Coefficient of adhesion, §17, p36
Commutating-pole railway motor, §21, p7
Commutation, Poor, §57, p41
Commutator room, §22, p60
surface, Poor, §57, p42
Comparison of methods of test, §52, p1
Compensation windings for alternating-current railway motors, §21, p13
Composition of rails, §19, p12
Compound generators, Operation of, §56, p22
generators, Paralleling of, §56, p22
generators with storage batteries, §56, p23
motors, §56, p8
track curve, §19, p38
Compressed stud terminal bond, §19, p28
Compression type joints for aluminum wires, §18, p12
Concrete poles, §18, p5
poles, Construction and installation of, §18, p5
Conduct of alternator running-light test, §52, p29
of direct-current motor test, §52, p21
Conductor-rail resistance, §20, p10
Conductors in a station, §54, p3
Conduit systems, §18, p57
systems, Construction of, §18, p57
systems, Operating features of, §18, p57
Conical tread, Rails with, §19, p16
Connection diagram of six-phase synchronous converter, §55, p27
diagram of three-phase synchronous converter, §55, p29
Equalizer, §55, p32
Connections at crossings on third-rail systems, §18, p52
Auxiliary-motor, §55, p33
Equalizing, §54, p6
for alternator running-light tests, §52, p28
for cars, Trunk, §22, p1
for loading-back test, §52, p19
for running-light test, §52, p9
for series-motor test, §52, p25
for synchronous-converter substations for light and power, §55, p38
for test for alternator with auxiliary motor, §52, p32
for transformer test, §52, p39
for transformers, §55, p9
Generator, §54, p4
Instrument and relay, §55, p34
Shunt-field, §54, p7; §55, pp8, 31
Single-phase, §54, p40
Synchroscope, §54, p36; §55, p51
Three-phase delta, §54, p43
Three-phase star, §54, p42
Two-phase, §54, p41
Construction of railway motors, §21, p7
of special trackwork, §19, p35
Track, §19, p1
Contact rail, The, §18, p49
Contactors, §23, p14
Continuity test, §57, p60
Continuous rail joints, §19, p20
Control and reset switch, §23, p16
-board panels for switchboards, §53, p47
of kilowatt load of frequency-changer sets, §57, p16
of power factor and current load of frequency-changer sets, §57, p15
switch, §53, p26
Controller, Master, §23, p12
Motor, §23, p12
regulators, §22, p34
Rheostatic, §23, p2
room, §22, p60
Series-parallel, §23, p4
steps, §23, p6
transition points, §23, p8
Conversion of direct to alternating current, §57, p3
Cooling methods for transformers, §55, p10
Copper cables, Data on stranded, §20, p20
-welded bonds, §19, p31
Core-loss test, Open-circuited, §52, p32
-loss test, Short-circuited, §52, p36

Correction of reversed polarity, §56, p18
Cross-bonds, §19, p32
-over, §18, p27; §19, p32
-sections of trolley wires, §18, p14
Crosses and grounds, Tests for, §57, p61
Crossings, §18, p27
Cupped track, §19, p40
Current-collection systems, §17, p2
densities in switches, §53, p4
density in busses, §53, p42
density of station conductors, §54, p3
transformers, §55, p18
Curvature tests of rails, §20, p38
Curve calculations, §20, p34
for railway construction, Typical, §18, p19
of efficiency, §52, p16
Curves, Elevation of rails on, §19, p38
Effect of railway, §17, p33
for tracks, §19, p37
Cut-out switches, §23, p15
-out switches, Action of, §23, p10

D

Danger from electrical sources, §57, p55
Dangers from mechanical sources, §57, p54
of physical injury, §57, p54
Data on car speeds, §21, p3
on composition of rails, §19, p12
on energy tests for electric cars, §17, pp48, 50
on messenger and trolley-wire tensions, §18, p45
on metal poles, §18, p3
on rail elevation, §19, p39
on rails and bonds, §20, pp5, 6, 7, 8
on railway costs, §17, pp58, 59
on standard T rails, §19, p15
on stranded copper cables, §20, p20
on wooden poles, §18, p2
Definite time-limit relay, §53, p32
Derived neutral with balancer set, §54, p18
neutral, Three-wire systems with, §55, p43
neutral with three-wire generator, §54, p20
Deriving neutral, Methods of, §55, p43
Designating curvature, Methods of, §20, p34
Desk board, §53, p47
Diamond turnout, §19, p32
Differential test for grounds, §57, p61
Direct-control switchboard, §53, p43
-current armatures, Tests for defects in, §57, p62
-current generating stations, §54, p4
-current generators, Field circuits of, §56, p26
-current generators, Operation of, §56, p16
-current generators, Tirrill regulators with, §56, p28
-current light and power stations, §54, p14
-current machine test, §52, p4
Direct-current machines, Troubles of, §57, p41
-current motor, Test-sheet data of, §52, p23
-current railway motors, §21, p4
-current railway systems, §17, p2
-current substations, §55, pp2, 4
-current switchboards, §53, p40
-current switchgear, §53, p3; §55, p7
Discharge of storage battery, §57, p31
Disconnecting switches, §53, p46
Distributing circuits of alternating-current stations, §54, p45
circuits of large alternating-current stations, §54, p54
circuits of medium-size alternating-current stations, §54, p49
Distribution of load, §56, p37
Division of load, Adjustment for proper, §54, p6
Door-operating circuits for railway car, §22, p37
-signal lamps for railway car, §22, p38
Double-catenary construction, §18, p40

E

Easement track curve, §19, p38
Eddy-current loss, §52, p3
Edison three-wire system, §56, p27
Efficiency curve, §52, p16
Electric-car equipment, §22, p1
car heating, §22, p27
-car lighting, §22, p19
cars, Speed control of, §23, p1
heater circuits, §22, p30
heaters, §22, p27
-railway calculations, §20, p1
railway systems, §17, p1
stations, §54, p1
substations, §55, p1
Electrical machinery, Care and maintenance of, §57, p37
machinery, Losses in, §52, p2
machinery, Measurements of resistance of, §52, p4
machines, Tests of direct-current, §52, p4
troubles of motor, §57, p48
Electrolysis, §20, p40
Cause of, §20, p41
Prevention of, §20, p41
Principles of, §20, p40
Electrolytic lightning arrester, §53, p39
lightning arrester, Aluminum, §22, p18
Elevation of rail on curves, §19, p38
Enclosed fuse, §22, p13; §53, p8
Energy calculations for railway systems, §17, p27
costs for railway systems, §17, p57
distribution systems for alternating-current operation, §17, p23

Energy distribution systems for direct-current operation, §17, p6
for railway systems, Independent, §17, p22
tests, Methods of making, §17, p51
tests on city roads, §17, p49
tests on electric cars, §17, p47
tests on interurban roads, §17, p47
Equalizer connection, §55, p32
set, §54, p18
Equalizing connections, §54, p6
Erection of electrical machinery, §57, p38
of trolley wire, §18, p18
Excitation from main generators, §55, p23
from separate unit, §55, p24
Exciter generators, §54, p38
system, §54, p51
Expansion rail joint, §19, p25
Expulsion fuse, §22, p14

F

Failure of generator to operate, §57, p50
of motor to operate, §57, p47
Fare box and register for electric car, Combined, §22, p43
Fastening rails and steel ties, §19, p8
Faults in electrical circuits, Tests for, §57, p57
Feeder and track-return tests, §20, p32
automatic sectionalizing switch, §18, p8
cables, Leading out, §54, p12
connections, Railway, §54, p10
formulas, §20, p3
insulators, §18, p12
layouts, Typical, §18, p7
problems, §20, p11
section switches, §18, p8
tap for catenary bracket construction, §18, p35
tap switch, §18, p8
Feeders, §17, p2
Booster, §54, p12
Calculations for aluminum, §20, p4
Calculations for copper, §20, p3
Conditions affecting the size of, §20, p1
of large stations, §54, p26
of medium-size stations, §54, p24
of small direct-current plants, §54, p22
Railway, §18, p6
Splicing, §18, p10
Tapping in, §18, p28
Field-break-up switch, §55, p31
circuits of direct-current generators, §56, p26
excitation of synchronous motors, §56, p12
-rheostat control, Methods of, §53, p17
rheostat, Motor-operated, §53, p18
rheostat, Potentiometer type of, §53, p16
rheostat, Series-resistance type of, §53, p15
rheostat, Shunt-resistance type of, §53, p16
Field rheostats, §53, p15
Weak, §57, p44
Fish-plates, §19, p19
Floating of storage battery, §57, p29
regulation, Checking of, §57, p31
voltages for storage battery, §57, p30
Formulas, Feeder, §20, p3
Power, §17, p43
Rail-resistance, §20, p9
Tractive-effort, §17, p31
Foundation for roadbed, §19, p1
Foundations for electrical machinery, §57, p38
Frequency-changer sets, Control of kilowatt load of, §57, p16
-changer sets, Control of power factor and current load of, §57, p15
-changer substation, §55, pp2, 54
changers by special synchroscopes, Paralleling, §57, p8
changers by voltmeter and chart, Paralleling, §57, p12
changers, Conditions for parallel operation of, §57, p15
changers, Induction-motor-driven, §55, p54
changers, Synchronous-motor-driven, §55, p54
Frogs, §18, p26
Locating of, §18, p26
Fuse box, Magnetic blow-out, §22, p13
Cartridge type, §53, p8
Enclosed, §22, p13
Expulsion, §22, p14
Fuses, §22, p13; §53, p7
Enclosed, §53, p8
High-tension, §53, p33
Open, §53, p7

G

Galvanometer, Testing with detector, §57, p59
Gasoline-electric car, Speed control for, §23, p35
-electric cars, §17, p23
Gauges for track and wheel, §19, p16
Gauging track, §19, p40
Gauntlet track, §19, p36
Gear ratio, §21, p2
reduction, §21, p2
Generating stations, Direct-current, §54, p4
Generator, Causes of low voltage of, §57, p46
connections, §54, p4
panel, §54, p5
test, §52, p8
to operate, Failure of, §57, p50
Generators, Care of, §56, p30
Excitation from main, §55, p23
Exciter, §54, p38
Inspection of, §56, p30
Motor-driven, §55, p7
Operation of alternating-current, §56, p31

Generators, Operation of direct-current, §56, p16
Self-excited, §56, p26
Separately excited, §56, p26
Series booster, §57, p35
Girder rail, §19, pp13, 14
Gongs, Air, §22, p45
Grade calculations, §20, p38
Grades and train resistance, Total kilowatt input for, §17, p44
Effect of railway, §17, p33
Limiting railway, §17, p37
Grinding room, §22, p62
Groove of rail, §19, p13
rail, §19, pp13, 14
Ground connection for lightning arrester, §53, p22
-return system, §17, p3
Grounds and crosses, Tests for, §57, p61
Grounding belt-driven machinery, §55, p8
Guard-rails, §19, p17
wires, §18, p22

H

Hammered stud terminal bond, §19, p29
Hand control, Series-parallel multiple-unit, §23, p12
Hanger ears, §18, p24
Hangers for railway line, §18, p23
Headlights, §22, p22
Arc, §22, p24
Incandescent, §22, p23
Head of rail, §19, p13
Heat regulation for cars, §22, p32
Heater circuits, §22, p30
Heaters, Electric, §22, p27
Heating cars by hot air, §22, p32
Electric car, §22, p27
of machines, Causes of excessive, §57, p44
High-tension bus system, §55, p6
-tension construction, §55, p27
-tension fuses, §53, p33
-voltage bus-bars, §17, p9
Horn-gap lightning arrester, §53, p21
Hysteresis loss, §52, p3

I

Inaccurate synchronizing, Effects of, §56, p36
Incandescent headlights, §22, p23
Induction-motor-driven frequency changers, §55, p54
-motor-driven frequency changers, Operation of, §57, p4
-motor-driven sets, Starting, §57, p1
motor, Slip of an, §56, p15
-motor test, §52, p37
-motor troubles, §57, p52
Injuries, Dangers of, §57, p54
Inspection of generators, §56, p30
of railway motors, Overhauling, §21, p24
of railway motors, Quick, §21, p22
Routine, §57, p40
Installation of boosters, §17, p10
of catenary construction, Hints on, §18, p44
of electric-car wires, §22, p40
of electrical machinery, §57, p37
of metal poles, §18, p6
of railway motors, §21, p20
of wooden poles, §18, p2
Installing the wires of catenary construction §18, p47
Instantaneous relays, §53, p31
Instrument and relay connections, §55, p34
equipment for motor-generator substations, with induction motors, §55, p17
equipment of railway station, §54, p8
Insulation resistance, Measurement of, §57, p64
Insulators, Feeder, §18, p12
Section, §18, p27
Span-wire, §18, p22
Third-rail, §18, p50
Integrating wattmeters, §54, p8
Inverse time-limit relays, §53, p31
I^2R armature loss, §52, p2
loss in shunt field, §52, p2
loss in the brushes, §52, p3
series-field loss, §52, p2

J

Joint, McIntyre, §18, p11
plates, §19, p19
Joints in busses, §53, p42
of the compression type, Aluminum, §18, p12
Rail, §19, p18
Welded, §19, p21

K

Knife-blade switches, §53, pp3, 23

L

Lamp outfit, Testing with, §57, p58
Large alternating-current stations, §54, p50
alternating-current stations, Switches, busses, and distributing circuits of, §54, p52
direct-current central stations, §54, p25
stations, Busses and feeders of, §54, p26
Layouts for feeders, §18, p7
Leakage of current from third rail, §18, p56
Length of air break for switches, §53, p5
of railway track, §17, p28
Light and power stations, Direct-current, §54, p14
Lighting-circuit diagram for cars, §22, p19
Electric-car, §22, p19
Lightning arrester, Aluminum-cell, §53, p39
arrester, Aluminum electrolytic, §22, p18

Lightning arrester, Carborundum-block, §22, p16
arrester, Electrolytic, §53, p39
arrester, Ground connections for, §53, p22
arrester, Horn-gap, §53, p21
arrester, Magnetic blow-out, §22, p17
arrester, Multigap, §53, p35
arrester, Opening the ground circuit of a, §22, p17
arresters, §22, p16
arresters for alternating-current circuits, §53, p35
arresters for direct-current circuit, §53, p20
arresters for railway line, §18, p30
arresters, Theory of, §53, p20
protection, §55, p37
Limit of adhesion in railway work, §17, p36
Limiting railway grades, §17, p37
Line breakers, §18, p27
calculations, Railway, §20, p1
construction, Electric-railway, §18, p1
poles, §18, p1
tests, Railway, §20, p26
Lining track, §19, p40
Lip of rail, §19, p13
Load, Adjustment for proper division of, §54, p6
Adjustment of, §56, p20
center of railway system, §17, p54
Distribution of, §56, p37
regulation, §56, p21
Loading-back test, §52, p19
Location of electrical machinery, §57, p37
of power house, §17, p54
of railway motors on cars, §21, p21
of third rail, §18, p49
Loop test, Murray, §57, p65
test, Varley, §57, p68
Lorain welded rail joint, §19, p21
Loss, Armature I^2R, §52, p2
Bearing-friction, §52, p2
Eddy-current, §52, p3
Hysteresis, §52, p3
in the brushes, I^2R, §52, p3
Series-field I^2R, §52, p2
Shunt-field I^2R, §52, p2
Windage, §52, p2
Losses in electrical machinery, §52, p2
Low-voltage drop for railway system, Importance of, §20, p25
voltage of generator, Causes of, §57, p46
Lubrication for railway motors, §21, p31
of bearings of railway motor, §21, p11

M

Machine shop, §22, p58
Magnetic blow-out fuse box, §22, p13
blow-out lightning arrester, §22, p17
Magneto-bell, Testing with, §57, p57
Maintenance of electrical machinery, §57, p37
of railway motors, §21, p22
of track, §19, p39
Manually operated oil switch, §53, p26
Master controller, §23, p12
McIntyre joint, §18, p11
Measurement of insulation resistance, §57, p64
Measurements of resistances of electrical machinery, §52, p4
Mechanical troubles of motor, §57, p47
Medium-size alternating-current station, §54, p45
-size alternating-current station, Busses and distributing circuits of, §54, p49
-size direct-current lighting and power stations, §54, p23
-size stations, Busses and feeders of, §54, p24
Messenger and trolley-wire tension, Data on, §18, p45
Metal poles, §18, p3
poles, Construction of, §18, p3
poles, Data on, §18, p3
poles, Installation of, §18, p5
Mill and carpenter shop, §22, p60
Moisture, Removal of, §57, p39
Motor controller, §23, p12
-driven generators, §55, p7
Electrical troubles of, §57, p48
-generator substations with induction motors, §55, p15
-generator substations with synchronous motors, §55, p23
-generators and synchronous converters, Choice between, §55, p13
-generators and synchronous converters, Operation of, §57, p1
-generators for current conversion, §57, p1
Mechanical troubles of, §57, p47
-operated rheostat, §53, p17
-operated oil-switch mechanism, §53, p27
suspension, §21, p20
test, Direct-current, §52, p17
to operate, Failure of, §57, p47
Motors, Alternating-current, §56, p10
Compound, §56, p8
Operation of direct-current, §56, p4
Operation of electric, §56, p4
Railway, §21, p1
Reversing, §56, p8
Running, §56, p6
Series, §56, p10
Stopping, §56, p7
used as brakes, §23, p10
Mounting knife-blade switches, §53, p7
Multigap lightning arrester, §53, p35

Multiple-unit automatic control, Series-parallel, §23, p20
-unit hand control, Series-parallel, §23, p12
Murray loop test, §57, p65

N

Neck of rail, §19, p13
Neutral, Methods of deriving, §55, p43
with balancer set, Derived, §54, p18
with three-wire generator, Derived, §54, p20
Noisy operation of machines, §57, p45
Nose suspension, §21, p20

O

Oil-and-water-cooled transformers, §55, p12
-cooled transformers, §55, p10
switch, Automatic operation of, §53, p30
switch, Control switch for an, §53, p26
switch, Manually operated, §53, p26
-switch mechanism, Motor-operated, §53, p27
-switch mechanism, Solenoid-operated, §53, p29
switch, Pneumatic operation of, §53, p30
switches, §53, p24; §55, p7
Open-conduit system, §17, p5
fuses, §53, p7
Operating-bus supply, §55, p35
requirements of railway motors, §21, p1
temperatures for insulation, §56, p2
temperatures of bare copper, §56, p3
temperatures of knife-blade switches, §56, p2
temperatures of magnetic cores, §56, p2
temperatures of the bearings, §56, p3
temperatures of transformer oil, §56, p4
temperatures, Safe, §56, p1
troubles of alternators, §56, p43
Operation of alternating-current generators, §56, p31
of alternating-current railway motor, §21, p14
of alternators, Parallel, §54, p28
of compound generators, §56, p22
of compound motors, §56, p8
of direct-current generators, §56, p16
of direct-current motors, §56, p4
of electrical machinery, §56, p1
of electric motors, §56, p4
of induction-motor-driven frequency changers, §57, p4
of machines, Noisy, §57, p45
of miscellaneous station equipment, §57, p29
of motor-generators and synchronous converters, §57, p1
of potential regulators on distributing circuits, §57, p36
of series generators, §56, p24
of single alternator, §56, p32
Operation of storage battery, §57, p29
of synchronous converters, §57, p18
of synchronous converters, Parallel, §57, p25
of synchronous converters, Single, §57, p24
of synchronous frequency changers on standard service, §57, p6
of synchronous-motor-driven sets, §57, p1
of transformers, §57, p36
Outdoor substations, §55, p59
Output curves, Tractive effort and horsepower-, §17, p46
Overhead systems of railway construction, §18, p1
Overload, Effect of excessive, §56, p22
relay, §23, p16
-relay connections, §55, p19
relay, Example of, §53, p31
Symptoms of, §57, p41
trip, §23, p23

P

Paint shop, §22, p61
Panel, Generator, §54, p5
Panels, Arrangement of switchboard, §54, p13
Parallel operation of alternators, §54, p28; §56, p33
operation of synchronous converters, §57, p25
Paralleling compound generators, §56, p22
Correct voltage for, §56, p19
frequency changers by special synchroscopes, §57, p8
frequency changers by voltmeter and chart, §57, p12
Passenger factor, §17, p28
Performance curve, §21, p17
Physical injury, Dangers of, §57, p54
Pit room, §22, p57
Plain curve, §19, p32
V curve, §19, p32
Plow for slot system, §17, p6
Pneumatic operation of oil switch, §53, p30
Polarity, Correction of reversed, §56, p18
Tests for, §56, p17
tests of compound motors, §56, p8
Poles, Concrete, §18, p5
Line, §18, p1
Metal, §18, p3
Repairs and renewals of, §18, p6
Wooden, §18, p1
Portable substation, §17, p21
substations, §55, p38
Position of brushes in running-light test, §52, p10
Potential regulators on distributing circuits, Operation of, §57, p36
transformers, §55, p17
Power factor of synchronous converter, Regulation of, §57, p28

Power formulas, §17, p43
house, Location of, §17, p54
Preparations for generator test, §52, p8
for loading-back test, §52, p19
Preservation of wooden ties, §19, p6
Pressure wiring, §53, p40
Protected bonds, §19, p28
Protection for third-rail systems, §18, p51
from overload, §54, p46
Lightning, §55, p37
Reverse-current, §55, p37
Protective devices, §54, p46; §55, p41
Preventive-reactance coils, §23, p29

Q

Quantitative tests, §57, p64
Quick-break switches, §53, p6

R

Rail and tie accessories, §19, p9
bonds, §19, p26
breaks, §19, p41
calculations, §20, p33
chairs, §19, p10
elevation, Data on, §19, p39
elevation on curves, §19, p38
Girder, §19, pp13, 14
Groove, §19, pp13, 14
joint, Arc welded, §19, p23
joint, Cast welded, §19, p24
joint, Expansion, §19, p25
joint, Lorain welded, §19, p21
joint, Thermit, §19, p24
joint, Zinc, §19, p25
joints, §19, p18
joints, Continuous, §19, p20
joints, Disposition of, §19, p25
joints, Standard channel-plate, §19, p19
joints, Welded, §19, p21
-resistance formulas, §20, p9
sections, §19, p13
to a given radius, Bending, §20, p36
weight, §19, p13
weight to sectional area, Relation of, §20, p33
Rails and bonds, Data on, §20, pp5, 6, 7, 8
Composition of, §19, p12
Curvature tests of, §20, p38
Data on composition of, §19, p12
Data on standard T, §19, p15
Drop test for, §19, p12
Guard-, §19, p17
per mile, Weight of, §20, p34
with conical tread, §19, p16
Railway calculations, Electric-, §20, p1
car, Air gongs for, §22, p45
car bodies, §22, p46
Railway car buzzer and bell circuits, §22, p36,
car, Combined fare box and register for §22, p43
car, Combined hot-air and ventilating systems for, §22, p32
car devices, Auxiliary, §22, p34
car, Door-operating circuits for, §22, p37
car, Door-signal lamps for, §22, p38
car, Heat regulation for, §22, p32
car heating, Electric, §22, p27
car lighting, Electric-, §22, p19
car, Register-ringing device for, §22, p39
car, Sand boxes for, §22, p44
car signs, §22, p39
cars, Energy tests on electric, §17, p47
cars, Number required, §17, p29
cars, Relation of maximum and average currents for, §17, p53
cars, Size of, §17, p30
cars, Trunk connections for, §22, p1
cars, Weights of, §17, p31
construction, Catenary, §18, p30
construction, Center-pole, §18, p16
construction, Overhead systems of, §18, p1
construction, Side-bracket, §18, p18
construction, Span-wire, §18, p15
construction, Typical curve, §18, p19
construction, Typical tangent, §18, p18
costs, Data on, §17, pp58, 59
curve calculations, §20, p34
feeders, §18, p6
grade, Calculations of, §20, p38
grades, Limiting, §17, p37
line calculations, §20, p1
line construction, Electric-, §18, p1
line lightning arresters, §18, p30
line tests, §20, p26
motor, Armature coils for, §21, p9
motor, Armature spider for, §21, p8
motor, Brush holders for, §21, p10
-motor characteristics, §21, p17
motor, Commutating-pole, §21, p7
motor, Commutating pole for, §21, p8
motor, Commutator for, §21, p9
motor, Compensation windings for alternating-current, §21, p13
motor, Gears for, §21, p11
-motor installation, §21, p20
motor, Lubrication of bearings of, §21, p11
motor, Operation of alternating-current, §21, p14
motor, Pinions for, §21, p10
-motor ratings, §21, p4
-motor rheostats, §22, p15
motors, §21, p1
motors, Alternating-current, §21, p12
motors, Construction of, §21, p7

Railway motors, Direct-current, §21, p4
motors, Lubrication for, §21, p31
motors, Maintenance of, §21, p22
motors on cars, Location of, §21, p21
motors, Operating requirements of, §21, p1
motors, Overhauling inspection of, §21, p24
motors, Quick inspection of, §21, p22
power formulas, §17, p43
power house, Location of, §17, p54
stations, §54, p4
supply, 600-volt, §17, p19
supply, 1,500-volt, §17, p19
supply, 2,400-volt, §17, p21
system, Alternating-current generation and direct-current supply for, §17, p18
system, Center of, §17, p54
system, Direct-current generation and supply for, §17, p6
system, Energy distribution for direct-current, §17, p6
system, Single-phase generation and supply for, §17, p23
system, Three-phase generation and supply for, §17, p25
systems, Alternating-current, §17, p23
systems, Conduit, §18, p57
systems, Direct-current, §17, p2
systems, Electric, §17, p1
systems, Energy costs for, §17, p57
systems, Energy distribution for alternating-current, §17, p23
systems, Independent energy for, §17, p22
systems, Third-rail, §18, p49
track construction, §19, p1
track, Length of, §17, p28
train, Acceleration of, §17, p34
train, Limit of adhesion of, §17, p36
train resistance curves, §17, p42
train, Total tractive effort of, §17, p35
train, Tractive effort per ton of, §17, p35
trains, Acceleration curves for electric, §17, p38
trains, Tractive effort for, §17, p40
transmission circuit, Distribution of voltage in, §20, p11
Railways, Effect of curves on, §17, p33
Effect of grade on, §17, p33
Train resistance on, §17, p32
Ratings of railway motors, §21, p4
Ratio, Gear, §21, p2
Register and fare box for electric car, Combined, §22, p43
-ringing device for railway car, §22, p39
Regulation of compound generators, Voltage, §56, p23
of heat for cars, §22, p32
of load, §56, p21
Regulation of power factor of synchronous converter, §57, p28
of synchronous converters, Voltage, §57, p25
Regulators, Controller, §22, p34
Tirrill, §54, p46
with alternators, Tirrill, §56, p39
with direct-current generators, Tirrill, §56, p28
Relay and instrument connections, §55, p34
Definite time-limit, §53, p32
Overload, §23, p16
Relays, Instantaneous, §53, p31
Inverse time-limit, §53, p31
Reverse-current, §53, p32
Release on circuit-breaker, Low-voltage, §53, p12
on circuit-breaker, Reverse-current, §53, p13
Remote-control circuit, §54, p47
-control switchboards, §53, p43
-controlled circuit-breaker, §53, p11
Renewals of poles, §18, p6
Repair shop, §22, p58
Repairs of poles, §18, p6
Reset switch, §23, p16
Resistance, Conductor-rail, §20, p10
measurement of electrical machinery, §52, p4
measurement, Temperature corrections for, §52, p7
-measurement test, §52, p4
of track, §20, p5
Track-rail, §20, p9
Reverse-current protection, §55, p37
-current relays, §53, p32
-current release on circuit-breaker, §53, p13
curve, §19, p32
switch, Action of, §23, p9
Reverser, §23, p15
Reversing motors, §56, p8
Rheostatic controller, §23, p2
control of car speed, §23, p2
Rheostat, Motor-operated, §53, p17
Rheostats, Field, §53, p15
Railway-motor, §22, p15
Starting, §53, p14
Roadbeds, §19, p1
for city roads, §19, p3
for interurban roads, §19, p3
Typical, §19, p3
Roller bearings, Wheel, §22, p52
Routine inspection, §57, p40
Running-light test, Conduct of alternator during, §52, p29
-light test, Connections for, §52, p9
-light test for alternator, §52, p28
-light test for synchronous motor, §52, p31
-light test of electrical machinery, §52, p8

Running-light test, Position of brushes in, §52, p10
motors, §56, p6

S

Sand boxes, §22, p44
boxes, Air-operated, §22, p45
boxes, Lever-operated, §22, p44
Scrapers, Track, §22, p46
Sectionalizing switch, Feeder automatic, §18, p8
Section insulators, §18, p27
of rails, §19, p13
switches, Feeder, §18, p8
Self-excited generators, §56, p26
Separately excited generators, §56, p26
Series booster generators, §57, p35
field, I^2R loss in, §52, p2
generators, Operation of, §56, p24
-motor test, §52, p25
motors, §56, p10
operation of alternators, §56, p33
-parallel controller, §23, p4
-parallel cylinder control of car speed, §23, p3
-parallel multiple-unit automatic control, §23, p20
-parallel multiple-unit hand control, §23, p12
-parallel operation, Car-wiring diagram for, §23, p6
Setting the Tirrill regulator, §56, p39
Shoe fuse, §17, p5
shunt, §17, p4
Third-rail, §17, p3
Shops in car house, §22, p56
Short-circuited core-loss test, §52, p36
Shunt-field connections, §54, p7; §55, pp8, 31
field, I^2R loss in, §52, p2
Side-bracket railway construction, §18, p18
Siding, §19, p33
Signs, Railway car, §22, p39
Simple track curve, §19, p37
Single-catenary construction, §18, p31
-phase alternating-current road, Calculations for, §20, p22
-phase connections, §54, p40
-phase speed control, §23, p28
Six-phase synchronous converter, Connection diagram of, §55, p27
Sleet troubles of the third-rail system, §18, p54
Slip of an induction motor, §56, p15
Slot system, §17, p5
system, Plow for, §17, p6
Small alternating-current stations, §54, p38
three-wire systems, §54, p16
two-wire stations, §54, p14
Soldered bonds, §19, p30
Solenoid-operated oil-switch mechanism, §53, p29
Span-wire insulators, §18, p22
-wire railway construction, §18, p15
wires, §18, p21
Special trackwork, §19, p32
trackwork, Construction of, §19, p35
Speed control for gasoline-electric car, §23, p35
control for storage-battery car, §23, p34
control of alternators, §56, p36
control of electric cars, §23, p1
control, Rheostatic, §23, p2
control, Single-phase, §23, p28
-limit device, §55, p37
-limiting circuit-breakers, §53, p13
Splice bars, §19, p19
Splicing aluminum wire, §18, p11
copper wire, §18, p10
feeders, §18, p10
trolley wires, §18, p14
Starting alternating-current motors, §56, p10
a six-phase synchronous converter, §55, p29
a synchronous converter by an induction motor, §57, p21
induction-motor-driven sets, §57, p1
methods for motor-generators equipped with induction motors, §55, p15
rheostats, §53, p14
shunt generators, §56, p16
shunt motors, §56, p4
synchronous converters by combination method, §57, p23
synchronous converters from special transformer taps, §57, p19
synchronous converters with alternating current, §55, p47
synchronous converters with direct current, §55, p49; §57, p21
synchronous-motor-driven generator sets, §55, p25
synchronous-motor-driven sets, §57, p1
Station conductors, §54, p3
conductors, Current density of, §54, p3
equipment, Operation of miscellaneous, §57, p29
generating units, Number of, §54, p1
generating units, Similarity of, §54, p2
Medium-size alternating-current, §54, p45
voltmeter, §54, p9
Stations, Alternating-current, §54, p28
Capacity of, §54, p1
Direct-current generating, §54, p4
Direct-current light and power, §54, p14
Electric, §54, p1
Large alternating-current, §54, p50
Large direct-current, §54, p25
Location of electric, §54, p1
Medium-size direct-current lighting and power, §54, p23

Stations, Railway, §54, p4
Small alternating-current, §54, p38
Small two-wire, §54, p14
Steel ties, §19, p7
ties, Methods of fastening rails and, §19, p8
Stopping motors, §56, p7
Storage-battery auxiliary, §17, p18
-battery car, Speed control for, §23, p34
-battery cars, §17, p22
battery, Charging, §57, p33
battery, Discharge of, §57, p31
batteries, Operation of, §57, p29
Subgrade, §19, p1
Substation, General arrangement of, §55, p4
Portable, §17, p21
Substations, Alternating-current, §55, p54
and generating stations, Similarity between, §55, p3
Automatic synchronous-converter, §55, p52
Classification of direct-current, §55, p4
Direct-current, §55, pp2, 4
Electric, §55, p1
for light and power, Synchronous-converter, §55, p38
for light and power, Transformer, §55, p58
for railways, Synchronous-converter, §55, p26
for railways, Transformer, §55, p57
Frequency-changer, §55, pp2, 54
Miscellaneous equipment of, §55, p6
Number and capacity of units of, §55, p5
Outdoor, §55, p59
Portable, §55, p38
Purpose of, §55, p1
Transformer, §55, pp3, 57
Transformers for, §55, p9
with induction motors, Motor-generator, §55, p15
with synchronous motors, Motor-generator, §55, p23
Surfacing track, §19, p40
Suspensions for railway line, §18, p23
Switch closing, Time element in, §56, p36
Control, §53, p26
Control and reset, §23, p16
Field-break-up, §55, p31
Switches, §54, p9
Current densities in, §53, p4
Cut-out, §23, p15
Disconnecting, §53, p46
in alternating-current stations, §54, p44
Knife-blade, §53, pp3, 23
Length of air break for, §53, p5
Mounting knife-blade, §53, p7
of large alternating-current stations, §54, p52
Oil, §53, p24
Quick-break, §53, p6
Unit, §23, p20
Switchboard panels, Arrangement of, §54, p13
The, §53, p39
Switchboards, Alternating-current, §53, p43
Control-board panels for, §53, p47
Direct-control, §53, p43
Direct-current, §53, p40
Electric control of, §53, p44
General requirements for, §53, p39
Mechanical arrangement of remote-control for, §53, p44
Remote-control, §53, p43
Switchgear, §53, p1
Alternating-current, §53, p23
Classification of, §53, p3
Direct-controlled, §53, p1
Direct-current, §53, p3; §55, p7
Remote-controlled, §53, p1
Synchronism indicator dials, §57, p11
Synchronizing alternators, §56, p33
circuits, §54, p29
circuits for polyphase alternators, §54, p33
circuits for synchronous converters, §55, p50
Effects of inaccurate, §56, p36
with lamps, §54, p29; §56, p34
with voltmeter or synchroscope, §56, p35
with voltmeters, §54, p35
Synchronous converter, Connection diagram of six-phase, §55, p27
converter, Connection diagram of three-phase, §55, p29
converter, Effect of an interruption of the alternating-current supply to a, §57, p26
converter, Regulation of power factor of a, §57, p28
-converter substations for light and power, §55, p38
-converter substations for railways, §55, p26
converters and motor-generators, Choice between, §55, p13
converters, Operation of, §57, p18
converters, Parallel operation of, §57, p25
converters, Synchronizing circuits for, §55, p50
converters, Voltage regulation of, §57, p25
converters with alternating current, Starting, §55, p47
converters with direct current, Starting, §55, p49
-motor-driven frequency changers, §55, p54
-motor-driven sets, Starting, §57, p1
motor, Effect of interrupted circuit of, §56, p14
-motor running-light test, §52, p31
-motor troubles, §57, p53
motors, Field excitation of, §56, p12
Synchroscope connections, §54, p36; §55, p51
Special type of, §57, p11

Synchroscopes, Paralleling frequency changers by special, §57, p8

T

Tangent railway construction, Typical, §18, p18
Tap for catenary bracket construction, Feeder, §18, p35
Tapping aluminum feeders, §18, p30
copper feeders, §18, p28
in feeders, §18, p28
Telephone receiver, Testing with, §57, p59
Temperature corrections for resistance measurements, §52, p7
Temperatures, Safe operating, §56, p1
Tension of trolley wire, §18, p20
Test, Alternator running-light, §52, p28
Conduct of alternator running-light, §52, p29
Conduct of induction-motor, §52, p37
Conduct of running-light, §52, p11
Conduct of series-motor, §52, p25
connections, Alternator running-light, §52, p28
connections for alternator with auxiliary motor, §52, p32
Connections for induction-motor, §52, p37
Connections for loading-back, §52, p19
Connections for running-light, §52, p9
Connections for transformer, §52, p39
for alternators with auxiliary motors, §52, p32
for bonds, §20, p26
for grounds, Differential, §57, p61
for rails, Drop, §19, p12
Induction-motor, §52, p37
Loading-back, §52, p19
Murray loop, §57, p65
of alternating-current machines, §52, p28
of direct-current machine, §52, p4
of direct-current motor, §52, p17
of direct-current motor, Conduct of, §52, p21
of generator, §52, p8
of generator, Preparations for, §52, p8
of resistance of electrical machinery, §52, p4
of series-motor, §52, p25
Open-circuited core-loss, §52, p32
Position of brushes in running-light, §52, p10
Preparations for induction-motor, §52, p37
Preparations for loading-back, §52, p19
Preparations for series-motor, §52, p25
Running-light, §52, p8
Series-motor, §52, p25
-sheet data for direct-current motor, §52, p23
-sheet data for induction motor, §52, p38
-sheet data, Running-light, §52, p11
sheet for alternator with auxiliary motor, §52, p33
sheet for loading-back test, §52, p24
Test sheet for running-light test, §52, p12
sheet for series-motor test, §52, p26
sheet for transformer, §52, p40
Short-circuited core-loss, §52, p36
Synchronous-motor running-light, §52, p31
Transformer, §52, p40
Varley loop, §57, p68
Tests, Comparison of methods of, §52, p1
for continuity, §57, p60
for crosses and grounds, §57, p61
for defects in direct-current armatures, §57, p62
for faults in electrical circuits, §57, p57
for feeder and track return, §20, p32
for polarity, §56, p17
for railway lines, §20, p26
of compound motors, Polarity, §56, p8
of electric railway cars, Energy, §17, p47
Quantitative, §57, p64
Track, §20, p38
Testing devices, §57, p57
with a lamp outfit, §57, p58
with detector galvanometer, §57, p59
with magneto-bell, §57, p57
with telephone receiver, §57, p59
with voltmeter, §57, p59
Theory of lightning arrester, §53, p20
Thermit rail joint, §19, p24
Third-rail insulators, §18, p50
-rail leakage, §18, p56
rail, Location of, §18, p49
-rail road, Calculations for, §20, p23
-rail shoe, §17, p3
-rail system, §17, p3
-rail systems, §18, p49
-rail systems, Connections at crossings for, §18, p52
-rail systems, Protection for, §18, p51
-rail systems, Sleet troubles of, §18, p54
rail, The, §18, p49
rail, Weights of, §18, p50
Three-part V curve, §19, p32
-phase delta connections, §54, p43
-phase star connections, §54, p42
-phase synchronous converter, Connection diagram of, §55, p29
-wire system, Edison, §56, p27
-wire systems, Small, §54, p16
-wire systems with derived neutral, §55, p43
Through V curve, §19, p32
Thrown-over turnout, §19, p33
Tie and rail accessories, §19, p9
-plate, Brace for, §19, p10
-plates, §19, p9
-rods, §19, p9
Ties, §19, p6
Steel, §19, p7

Ties, Wooden, §19, p6
Time element in switch closing, §56, p36
  required for acceleration, §55, p5
Tirrill regulator, Setting the, §56, p39
  regulators, §54, p46
  regulators with alternators, §56, p39
  regulators with direct-current generators, §56, p28
Track clearances, §19, p38
  construction, §19, p1
  Cupped, §19, p40
  curve, Compound, §19, p38
  curve, Easement, §19, p38
  curve, Simple, §19, p37
  curve, Transition, §19, p38
  gauges, §19, p16
  Gauging, §19, p40
  Gauntlet, §19, p36
  Lining, §19, p40
  Maintenance of, §19, p39
  -rail resistance, §20, p9
  resistance, §20, p5
  resistance, Calculation of, §20, p10
  scrapers, §22, p46
  Surfacing, §19, p40
  tests, §20, p38
  The, §19, p6
  Weeds on, §19, p41
Trackwork, Construction of special, §19, p35
  Special, §19, p32
Tractive effort, §17, p32
  effort and horsepower-output curves, §17, p46
  -effort formulas, §17, p31
  effort for trains, §17, p40
  effort per ton, §17, p35
  effort, Total, §17, p35
  force, §17, p32
T rail, §19, pp13, 14
Train resistance, §17, p32
  resistance and grades, Total kilowatt input for, §17, p44
  resistance curves, Railway, §17, p42
  resistance, Kilowatt input for, §17, p43
Tram of rail, §19, p13
Transformer substations, §55, pp3, 57
  substations for light and power, §55, p58
  substations for railways, §55, p57
  test, §52, p40
  test, Connections for, §52, p39
Transformers, Air supply for, §55, p11
  Blower systems for, §55, p10
  Capacity of, §55, p9
  Connections for, §55, p9
  Cooling methods for, §55, p10
  for substations, §55, p9
  Number of, §55, p9
  Oil-and-water-cooled, §55, p12
Transformers, Oil-cooled, §55, p10
  Operation of, §57, p36
Transition points, Controller, §23, p8
  track curve, §19, p38
Trip, Overload, §23, p23
Trolley, §17, p2
  catchers, §22, p7
  fittings, §22, p4
  fork, §22, p4
  guards, §22, p8
  harp, §22, pp4, 5
  pole, §22, p5
  retriever, §22, p8
  stand, §22, p4
  system, §17, p2
  The, §22, p4
  Underground, §17, p5
  wheel, §22, pp4, 5
  wire, §17, p2
  wire at curves, Offset in, §18, p20
  -wire devices, Auxiliary, §18, p22
  -wire erection, §18, p18
  -wire tension, §18, p20
  wires, §18, p13
  wires, Cross-sections of, §18, p14
  wires, Material of, §18, p13
  wires, Splicing, §18, p14
  wires, Suspension, §18, p15
Troubles of alternating-current machines, §57, p52
  of alternators, Operating, §56, p43
  of direct-current machines, §57, p41
  of induction motors, §57, p52
  of synchronous motor, §57, p53
Trucks, §22, p49
  Axle bearings for, §22, p52
  Classification of, §22, p49
  Roller-wheel bearings for, §22, p52
  Types of, §22, p50
  Wheel base of, §22, p54
  Wheels for, §22, p54
Trunk connections for cars, §22, p1
  wire, §22, p1
Two-phase connections, §54, p41

U

Underground trolley, §17, p5
Unit switches, §23, p20
Unprotected bonds, §19, p28

V

Varley loop test, §57, p68
Voltage, Adjustment of, §56, p19
  for paralleling, Correct, §56, p19
  regulation of compound generators, §56, p23
  regulation of synchronous converters, §57, p25

Voltages between trolley and rail, Alternating-current, §17, p25
Voltmeter connections, Alternating-current, §55, p52
Station, §54, p9
Testing with, §57, p59

W

Wall-type control-board panel, §53, p47
Watt-hour meter connections, §55, p20
-hour meters, §54, p8
Wattmeter connections, §55, p19
Wattmeters, Integrating, §54, p8
Web of rail, §19, p13
Weeds on track, §19, p41
Weight of rails, §19, p13
of rails per mile, §20, p34
Weights of third rail, §18, p50
Welded bonds, Electrically, §19, p30
rail joint, Arc, §19, p23
rail joint, Cast, §19, p24
rail joints, §19, p21
Wheel bearings, §22, p52
gauges, §19, p16
Wheels for trucks, §22, p54
Windage loss, §52, p2
Winding room, §22, p59
Wire table, Stranded, §20, p20
Trunk, §22, p1
Wires, Guard, §18, p22
Span, §18, p21
Trolley, §18, p13
Wiring diagrams, §55, p22
Pressure, §53, p40
Wooden poles, §18, p1
poles, Data on, §18, p2
poles, Installation of, §18, p2
poles, Selection of, §18, p1
ties, §19, p6
ties, Preservation of, §19, p6

Z

Zinc rail joint, §19, p25